



**BUILDING CODE COMPLIANCE OFFICE (BCCO)  
PRODUCT CONTROL DIVISION**

**MIAMI-DADE COUNTY, FLORIDA  
METRO-DADE FLAGLER BUILDING  
140 WEST FLAGLER STREET, SUITE 1603  
MIAMI, FLORIDA 33130-1563  
(305) 375-2901 FAX (305) 375-2908**

**NOTICE OF ACCEPTANCE (NOA)**

---

**W.R. Bonsal Company  
8201 Arrowbridge Boulevard  
P.O. Box 241148  
Charlotte, NC 28224-1148**

**SCOPE:**

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed by Miami-Dade County Product Control Division and accepted by the Board of Rules and Appeals (BORA) to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Division (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. BORA reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Division that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the High Velocity Hurricane Zone of the Florida Building Code.

**DESCRIPTION: Bonsal Roof Tile Mortar**

**LABELING:** Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA revises NOA # 01-0302.03 and consists of pages 1 through 3.  
The submitted documentation was reviewed by Frank Zuloaga, RRC.



**NOA No 03-0407.01  
Expiration Date: 02/01/06  
Approval Date: 09/18/03  
Page 1 of 3**

## ROOFING COMPONENT APPROVAL

**Category:** Roofing  
**Sub-Category:** Roof Tile Mortar  
**Material:** Cement

### 1. SCOPE

This revises "Bonsal" Roof Tile Mortar, as manufactured W.R. Bonsal Company as described in Section 2 of this Notice of Acceptance, designed to comply with the Florida Building Code for use with approved Roof Tile Systems.

### 2. PRODUCT DESCRIPTION:

<u>Product</u>	<u>Dimensions</u>	<u>Product Description</u>
BONSAL Roof Tile Mortar Mix	80 lb bag	Premixed, prebagged roof tile mortar for used with approved roof tile in accordance with RAS 120.

### 3. EVIDENCE SUBMITTED:

<u>Test Agency</u>	<u>Test Identifier</u>	<u>Test Specification</u>	<u>Date</u>
ATEC Associates, Inc.	70-02-94-00228	ASTM C 270 Type M/ TAS 123	May 1994
Law Engineering, Inc.	LAW Job No. CHG 8192	Physical Property Testing TAS 123 (ASTM C 270)	Nov 1990

### 4. LIMITATIONS:

- 4.1 Fire classification is not part of this acceptance.
- 4.2 Field uplift testing shall be performed, in compliance with the test procedure set forth in Testing Application Standard TAS 106. Testing shall be performed not prior to 30 days after installation.
- 4.3 W.R. Bonsal Roof Tile Mortar shall be placed in a 5" x 12" minimum pad at time of application. The mortar pad placement shall be in accordance with the 'Placement Details' provided RAS 120.
- 4.4 W.R. Bonsal Roof Tile Mortar shall be applied in accordance with W.R. Bonsal Construction Products Specifications.
- 4.5 Tile must be applied within 5 minutes of the application of W.R. Bonsal Roof Tile Mortar.
- 4.6 Refer to Roofing Application Standards RAS 120, for penetrations and terminations.
- 4.7 Refer to Tile manufacturer's Product Control Notice of Acceptance for system approvals.
- 4.8 All products listed herein shall have a quality assurance audit in accordance with the Florida Building Code and Rule 9B-72 of the Florida Administrative Code.

### 5. INSTALLATION:

W.R. Bonsal Roof Tile Mortar and its components shall be installed in strict compliance with Roofing Application Standard RAS 120.



NOA No 03-0407.01  
Expiration Date: 02/01/06  
Approval Date: 09/18/03  
Page 2 of 3

**6. BUILDING PERMIT REQUIREMENTS:**

As required by the Building Official or the applicable Building Code in order to properly evaluate the installation of this system. This Notice of Acceptance on its own cannot be used to obtain a building permit.

**END OF THIS ACCEPTANCE**



NOA No 03-0407.01  
Expiration Date: 02/01/06  
Approval Date:09/18/03  
Page 3 of 3