



BUILDING CODE COMPLIANCE OFFICE (BCCO)  
PRODUCT CONTROL DIVISION

MIAMI-DADE COUNTY, FLORIDA  
METRO-DADE FLAGLER BUILDING  
140 WEST FLAGLER STREET, SUITE 1603  
MIAMI, FLORIDA 33130-1563  
(305) 375-2901 FAX (305) 375-2908  
[www.buildingcodeonline.com](http://www.buildingcodeonline.com)

**NOTICE OF ACCEPTANCE (NOA)**

**PGT Industries**  
1070 Technology Drive  
Nokomis, FL 34275

**SCOPE:**

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed by Miami-Dade County Product Control Division and accepted by the Board of Rules and Appeals (BORA) to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Division (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. BORA reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Division that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

**DESCRIPTION: Series 2"x Heavy Wall Aluminum Tube Clipped Mullion - L.M.I.**

**APPROVAL DOCUMENT:** Drawing No. 6223, titled "2" Heavy Wall, Elevations Aluminum Tube Clipped Mullion", sheets 1 through 5 of 5, dated 04/28/00, with revision "C" dated 05/03/06, prepared by PGT Industries, signed and sealed by Robert L.Clark, P.E., bearing the Miami-Dade County Product Control Renewal Stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Division.

**MISSILE IMPACT RATING: Large and Small Missile Impact**

**LABELING:** Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA **renews NOA # 04-0528.06** and consists of this page 1 and evidence pages E-1 and E-2, as well as approval document mentioned above.

The submitted documentation was reviewed by **Jaime D. Gascon, P.E.**



J. Gascon  
5/16/06

NOA No 06-0125.08  
Expiration Date: June 28, 2011  
Approval Date: June 08, 2006  
Page 1

PGT Industries

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

**A. DRAWINGS**

1. Manufacturer's die drawings and sections.
2. Drawing No **6223**, titled 2" Heavy Wall, Elevations Aluminum Tube Clipped Mullion, Sheets 1 through 5 of 5, dated 04/28/00, with revision "C" on 05/03/06, prepared by PGT Industries, signed and sealed by Robert L. Clark, P.E.

**B. TESTS**

1. Test reports on 1) Uniform Load Static Air Pressure Test, per FBC, TAS 202-94  
2) Large Missile Impact Test, FBC, TAS 201-94  
3) Cyclic Loading Test, per FBC, TAS 203-94  
along with installation diagram of a pair of fixed aluminum windows (OO configuration) 60" x 54" mullied together with a 1x 2 x std. wall mullion, prepared by Fenestration Testing Laboratory, Inc., Test Report No. **FTL-2902**, dated 01/05/01, signed and sealed by Antonio Acevedo, P.E.  
**"Submitted under NOA# 04-0528.06"**
2. Test reports on 1) Uniform Load Static Air Pressure Test, per FBC, TAS 202-94  
2) Large Missile Impact Test, FBC, TAS 201-94  
3) Cyclic Loading Test, per FBC, TAS 203-94  
along with installation diagram of a pair of fixed aluminum windows (OO configuration) 80" x 76" mullied together with a 1x 4 x std. wall mullion, prepared by Fenestration Testing Laboratory, Inc., Test Report No. **FTL-2903**, dated 01/05/01, signed and sealed by Antonio Acevedo, P.E.  
**"Submitted under NOA# 04-0528.06"**
3. Test reports on 1) Uniform Load Static Air Pressure Test, per FBC, TAS 202-94  
2) Large Missile Impact Test, FBC, TAS 201-94  
3) Cyclic Loading Test, per FBC, TAS 203-94 discussed  
along with installation diagram of a pair of fixed aluminum windows with a transom lite (O/OO configuration) mullied together with a 1x 2 x 3/4" wall vertical and a 2 x 6" x 1/4" wall horizontal mullion, prepared by Fenestration Testing Laboratory, Inc., Test Report No. **FTL-2975**, dated 01/23/01, signed and sealed by Antonio Acevedo, P.E.  
**"Submitted under NOA# 04-0528.06"**

**C. CALCULATIONS**

1. Revised Anchor Calculations and structural analysis, complying with FBC-2004, prepared by PGT Industries, dated 01/23/06, signed and sealed by Robert L. Clark, P.E.



Jaime D. Gascon, P.E.  
Chief, Product Control Division  
NOA No 06-0125.08  
Expiration Date: June 28, 2011  
Approval Date: June 08, 2006

**PGT Industries**

**NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED**

**D. QUALITY ASSURANCE**

1. Miami Dade Building Code Compliance Office (BCCO).

**E. MATERIAL CERTIFICATIONS**

1. None.

**F. STATEMENTS**


1. Statement letter of conformance, dated 01/23/06, signed and sealed by Robert L. Clark, P.E.
2. Statement letter of no financial interest, dated 01/23/06 and sealed by Robert L. Clark, P.E.

**G. OTHER**

1. Notice of Acceptance No. **04-0528.06**, issued to PGT Industries for their 2" x Heavy Wall-Aluminum Tube Clipped Mullion, approved on 07/15/04 and expiring on 06/28/06.
2. Letter from consultant dated 04/21/06, stating that the product is in compliance with the Florida Building Code (FBC).




Jaime D. Gascon, P.E.  
Chief, Product Control Division  
NOA No 06-0125.08  
Expiration Date: June 28, 2011  
Approval Date: June 08, 2006



**(2) WINDOWS MULLED  
W/ONE ABOVE**

FOR DETERMINING MAX ALLOWABLE  
DESIGN PRESSURE SEE TABLES  
ON PAGE 5


- M1) MAX OPENING = H OR H1+H2  
MULL LENGTH = W OR W1+W2
- M2) MAX OPENING = W OR W1+W2  
MULL LENGTH = H1



**MULTIPLE WINDOWS MULLED  
W/ONE ABOVE**

FOR DETERMINING MAX ALLOWABLE  
DESIGN PRESSURE SEE TABLES  
ON PAGE 5


- M3) MAX OPENING = H OR H1+H2  
MULL LENGTH = W OR W1+W2+W3
- M4) MAX OPENING = W1+W2 OR W2+W3  
MULL LENGTH = H1



**(2) WINDOWS MULLED TOGETHER**

FOR DETERMINING MAX ALLOWABLE  
DESIGN PRESSURE SEE TABLES  
ON PAGE 5

- MAX OPENING = W OR W1+W2
- MULL LENGTH = H



$H = H1 + H2$

**(1) WINDOW MULLED  
W/ONE ABOVE**

FOR DETERMINING MAX ALLOWABLE  
DESIGN PRESSURE SEE TABLES  
ON PAGE 5

- MAX OPENING = H OR H1+H2
- MULL LENGTH = W


**NOTES:**

1. THE 33 1/3% STRESS INCREASE HAS NOT BEEN USED IN THE DESIGN OF THIS PRODUCT. FOR ANCHORAGE TYPE, QUANTITY AND LOCATION, REFER TO SHEETS 2, 3 AND 5.
2. WINDOWS AND DOORS OR COMBINATIONS THEREOF MAY BE MULLED TO A MAXIMUM OF (7) UNITS.
3. MULLIONS ARE APPROVED FOR IMPACT AND NON-IMPACT APPLICATIONS.
4. REFERENCE TEST REPORTS: FTL-2902, 2903 AND 2975.


*P.J.P.*  
5/5/06  
Robert L. Clark, P.E.  
PE #39712  
Structural

TO BE USED ONLY WITH PGT INDUSTRIES PRODUCTS					
<b>PGT INDUSTRIES</b>		Revsd By: F.K.	Date: 1/9/06	Revisions: B-REVISE ANCHORAGE	
		Revsd By: F.K.	Date: 5/3/06	Revisions: C-NO CHG THIS SHT	
		Drawn By: P.J.P.	Date: 4/28/00		
Description: 2" HEAVY WALL, ELEVATIONS					
Title: ALUMINUM TUBE CLIPPED MULLION					
Series/Model: MULLS	Scale: NTS	Sheet: 1 of 5	Drawing No. 6223	Rev: C	


**PRODUCT REVIEWED**  
as complying with the Florida  
Building Code  
Acceptance No. 06-0125-08  
Expiration Date 06/28/11  
By: *[Signature]*  
Miami-Dade Product Control  
Division




TYPICAL MULLION TO MULLION INSTALLATION, DETAIL "A"



TYPICAL MULLION TO STRUCTURE WITH WOOD BUCK REMOVED FROM CONC., DETAIL "C"



TYPICAL MULLION TO STRUCTURE WITH WOOD BUCK, DETAIL "B"



TYPICAL MULLION TO STRUCTURE WITH WOOD BUCK AND CONC., DETAIL "D"

NOTES:

1. FOR CONCRETE APPLICATIONS IN MIAMI-DADE COUNTY, USE ONLY MIAMI-DADE COUNTY APPROVED MASONRY ANCHORS. MINIMUM DISTANCE FROM CENTER OF ANCHORS TO CONCRETE EDGE IS 2 1/2". ELCO 1/4" SS4 CRETE-FLEX ANCHORS MAY BE USED INSTEAD OF 1/4" TAPCONS PROVIDED EMBEDMENT IS INCREASED TO 1 3/4".
2. 1/4" TAPCONS OR ELCO 1/4" SS4 CRETE-FLEX MASONRY ANCHORS MAY BE USED INSTEAD OF #12 SCREWS FOR WOOD APPLICATIONS.
3. FOR MULL SIZE AND QUANTITY OF ANCHORS SEE SHEET 5. FOR ANCHOR LOCATIONS SEE SHEET 3. QUANTITY OF PINNING SCREWS FOR MULL-TO-CLIP TO BE HALF THE QUANTITY OF ANCHORS FROM CLIP-TO-OPENING. (MINIMUM OF 2 SCREWS PER CLIP)
4. IMPORTANT: QUANTITY OF ANCHORS SHOWN ABOVE ARE FOR PICTORIAL REPRESENTATION ONLY. FOR CORRECT QUANTITY OF ANCHORS, REFER TO CHARTS 1 AND 2 ON SHEET 5. FIND THE APPLICABLE MULL SIZE AND PRESSURE REQUIRED FOR YOUR SPECIFIC APPLICATION.
5. REFERENCE TEST REPORTS: FTL-2902, 2903 AND 2975.


PRODUCT REVISED  
 as complying with the Florida  
 Building Code  
 Acceptance No. 06-0125.08  
 Expiration Date 06/28/11  
 By: *[Signature]*  
 Miami Dade Product Control  
 Division

TO BE USED ONLY WITH PGT INDUSTRIES PRODUCTS


 Robert L. Clark, P.E. PE #39712 Structural 5/5/06		Revsd By: F.K. Date: 1/9/06 Revisions: B-REVISE ANCHORAGE
	Revsd By: F.K. Date: 5/3/04 Revisions: C-NO CHG THIS SHT	Drawn By: P.J.P. Date: 4/28/00
Description: <b>2" HEAVY WALL, CLIP INSTALLATION DETAIL</b>		Title: <b>ALUMINUM TUBE CLIPPED MULLION</b>
Series/Model: MULLS	Scale: NTS	Sheet: 2 of 5
Drawing No. 6223		Rev: C

1070 TECHNOLOGY DRIVE  
 NOKOMIS, FL 34275


P.O. BOX 1529  
 NOKOMIS, FL 34274




2" MULL CLIP  
EXTRUSION DWG #513




(3) ANCHOR LOCATIONS




(4) ANCHOR LOCATIONS




(6) ANCHOR LOCATIONS




(8) ANCHOR LOCATIONS




2" MULL CLIP  
W/TABS REMOVED  
EXTRUSION DWG #513




(3) ANCHOR LOCATIONS



(4) ANCHOR LOCATIONS



(6) ANCHOR LOCATIONS



(8) ANCHOR LOCATIONS

PRODUCT REVISED  
in compliance with the Florida  
Building Code  
Acceptance No. 06-0125.08  
Expiration Date 06/28/11  
By: *[Signature]*  
Metal/Steel Product Control  
Division

CLIP LENGTH CHART FOR 1x MULL	
MULL SIZE	'A'
2 x 4 x 1/4	3 7/16
2 x 6 x 1/4	5 7/16

**NOTES:**

- IMPORTANT: QUANTITY OF ANCHORS SHOWN ARE FOR PICTORIAL REPRESENTATION ONLY. FOR CORRECT QUANTITY OF ANCHORS, PLEASE REFER TO CHARTS 1 AND 2 ON SHEET 5. FIND THE CORRECT MULL SIZE AND PRESSURE REQUIRED FOR YOUR SPECIFIC APPLICATION.
- REFERENCE TEST REPORTS: FTL-2902, 2903 AND 2975.

*[Signature]*  
5/5/06  
Robert L. Clark, P.E.  
PE #38712  
Structural

TO BE USED ONLY WITH PGT INDUSTRIES PRODUCTS





1070 TECHNOLOGY DRIVE  
NOKOMIS, FL 34275  
P.O. BOX 1529  
NOKOMIS, FL 34274

Revsd By: F.K.	Date: 1/9/06	Revisions: B-ADD 3-4 HOLE APP.
Revsd By: F.K.	Date: 5/3/06	Revisions: C-ADD MISSING DIM.
Drawn By: P.J.P.	Date: 4/28/00	

Description:  
2" HEAVY WALL, ANCHOR LOCATIONS

Title:  
ALUMINUM TUBE CLIPPED MULLION

Series/Model: MULLS	Scale: NTS	Sheet: 3 of 5	Drawing No. 6223	Rev: C
------------------------	---------------	------------------	---------------------	-----------



2x HEAVY WALL MULLS  
 MAT'L: 6063-T6

PROJECT REVISED  
 as complying with the Florida  
 Building Code  
 Acceptance No. 06-0125-08  
 Expiration Date 06/28/11  
 By: *[Signature]*  
 Product Control  
 Division

TO BE USED ONLY WITH PGT INDUSTRIES PRODUCTS

*[Signature]*  
 5/5/06  
 Robert L. Clark, P.E.  
 PE #39712  
 Structural



1070 TECHNOLOGY DRIVE  
 NOKOMIS, FL 34275  
 P.O. BOX 1529  
 NOKOMIS, FL 34274

Revsd By: F.K.	Date: 1/9/06	Revisions: B-NO CHG. THIS SHT.
Revsd By: F.K.	Date: 5/3/06	Revisions: C-NO CHG THIS SHT
Drawn By: P.J.P.	Date: 4/28/00	

Description:  
 2" HEAVY WALL, MULLION PROFILES



Title:  
 ALUMINUM TUBE CLIPPED MULLION

Series/Model: MULLS	Scale: 1X	Sheet: 4 of 5	Drawing No. 6223	Rev: C
------------------------	--------------	------------------	---------------------	-----------

NOTE:  
 1. REFERENCE TEST REPORT FTL-2902, 2903 AND 2975

**CHART 2. - 2x6x.250**

		OPENING WIDTH IN INCHES																				
		50		60		70		80		90		100		110		120		130		160		
ANCHOR TYPE & QTY.		(3) A	(4) A	(3) A	(4) A	(3) A	(4) A	(3) A	(4) A	(3) A	(4) A	(3) A	(4) A	(3) A	(4) A	(3) A	(4) A	(3) A	(4) A	(3) A	(4) A	
		(6) B	(8) B	(6) B	(8) B	(6) B	(8) B	(6) B	(8) B	(6) B	(8) B	(6) B	(8) B	(6) B	(8) B	(6) B	(8) B	(6) B	(8) B	(6) B	(8) B	
MULL LENGTH IN INCHES	42	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	
	48	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	
	50.625	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	
	54	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	
	60	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	
	63	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170	170
	66	170	170	170	170	170	170	170	170	170	170	170	168	170	162	170	159	170	158	170	158	170
	72	170	170	170	170	170	170	165	170	154	170	146	170	140	170	136	170	134	170	133	170	
	76	170	170	170	170	168	170	154	170	143	170	135	170	129	170	125	166	122	162	119	159	
	78	170	170	170	170	162	170	148	170	138	170	130	170	124	165	119	159	116	155	113	151	
	84	170	170	166	170	148	170	134	170	124	166	117	155	111	148	106	142	103	137	98	130	
	90	170	170	153	170	136	170	123	164	113	151	106	141	100	133	96	127	92	123	86	116	
	96	165	170	142	170	125	167	113	151	104	139	97	129	91	123	87	115	83	109	77	98	
	108	144	170	123	163	109	141	98	125	89	112	83	102	78	95	73	88	70	83	63	73	
111	140	170	119	154	105	133	94	118	86	106	80	97	75	89	71	83	67	78	61	68		
144	105	108	89	90	78	78	69	69	61	61	56	56	51	51	47	47	44	44	37	37		



**CHART 1. - 2x4x.250**

		OPENING WIDTH IN INCHES									
		50	60	70	80	90	100	110	120	130	160
ANCHOR TYPE & QTY.		(3) A	(3) A	(3) A	(3) A	(3) A	(3) A	(3) A	(3) A	(3) A	(3) A
		(6) B	(6) B	(6) B	(6) B	(6) B	(6) B	(6) B	(6) B	(6) B	(6) B
MULL LENGTH IN INCHES	42	170	170	170	170	170	170	170	170	170	170
	48	170	170	170	170	170	170	170	170	170	170
	50.625	170	170	170	170	170	170	170	170	170	170
	54	170	170	170	170	170	170	170	170	170	170
	60	170	170	170	170	170	170	170	170	170	170
	63	170	170	170	170	170	166	162	160	159	159
	66	170	170	170	170	170	154	149	146	145	145
	72	170	170	166	152	142	135	129	125	123	122
	76	170	170	154	141	131	124	119	115	112	109
	78	170	167	149	136	127	119	114	110	107	104
	84	177	153	136	124	114	107	102	98	94	90
90	163	141	125	113	104	97	92	88	85	79	
96	151	129	112	100	91	83	78	73	69	63	
108	107	90	78	69	62	57	53	49	47	41	
111	98	83	72	63	57	52	48	45	43	37	
144	45	37	32	28	26	23	21	20	18	16	

**NOTES:**

1. MAXIMUM ALLOWABLE PRESSURE IN PSF.
2. DESIGN IS BASED ON OPENING WIDTH. FOR MULTIPLE UNITS, CONSIDER ONLY TWO ADJACENT UNITS AT A TIME. SEE SHEET 1.
3. REFERENCE TEST REPORT FTL-2902, 2903 AND 2975
4. ANCHOR TYPES: A. 1/4" TAPCON  
B. #12 SCREW

**PRODUCT REVISED**  
as complying with the Florida  
Building Code  
Acceptance No 06-0125.08  
Expiration Date 06/28/11  
By [Signature]  
Miami-Dade Product Control  
Division

TO BE USED ONLY WITH PGT INDUSTRIES PRODUCTS

[Signature]  
5/5/06  
Robert L. Clark, P.E.  
PE #39712  
Structural



1070 TECHNOLOGY DRIVE  
NOKOMIS, FL 34275

P.O. BOX 1529  
NOKOMIS, FL 34274

Revsd By: F.K.	Date: 1/9/06	Revisions: B-REVISE ANCHORAGE
Revsd By: F.K.	Date: 5/3/06	Revisions: C-NO CHG THIS SHT
Drawn By: P.J.P.	Date: 4/28/00	
Description: 2" HEAVY WALL, PRESSURE CHARTS 1 & 2		
Title: ALUMINUM TUBE CLIPPED MULLION		
Series/Model: MULLS	Scale: NTS	Sheet: 5 of 5
Drawing No. 6223		Rev: C