MIAMI-DADE

BUILDING CODE COMPLIANCE OFFICE (BCCO)
PRODUCT CONTROL DIVISION

MIAMI-DADE COUNTY, FLORIDA
METRO-DADE FLAGLER BUILDING
140 WEST FLAGLER STREET, SUITE 1603
MIAMI, FLORIDA 33130-1563
(305) 375-2901 FAX (305) 375-2908

NOTICE OF ACCEPTANCE (NOA)

Henry Company
3802 Miller Park Drive
Garland Texas 75042

SCOPE:
This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed by Miami-Dade County Product Control Division and accepted by the Board of Rules and Appeals (BORA) to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Division (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. BORA reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Division that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Henry 280 DC Premium Elastomeric White Roof Maintenance Coating

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA revises NOA No. 04-1027.01 and consists of pages 1 through 12.
The submitted documentation was reviewed by Jorge L. Acebo.

PRODUCT CONTROL ACCEPTED

ROOFING SYSTEM APPROVAL

Category:	Roofing
Subcategory:	Cements, Coatings and Adhesives
Deck Type:	Roof Maintenance Coating
Materials:	Acrylic Elastomeric

SCOPE:

This approves a roofing maintenance coating system using Henry Company 280DC Premium Elastomeric White Roof Coating as described in this Notice of Acceptance. This product has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

TRADE NAMES OF PRODUCTS MANUFACTURED OR LABELED BY APPLICANT:

PHYSICAL PROPERTIES OF COMPONENTS:

Trade name: **Henry 280 DC**

Thickness: See Systems Approvals Below.

Specification: ASTM D 6083

Description: A premium white elastomeric roof coating water-based acrylic latex coating. All installation details in accordance with the Henry Company's recommended application procedures.

Container Size: 1 and 5 and 275 (Totes) gallons. Note all cautions on container label.

Trade Name: **Henry 107 Un-fibered asphalt emulsion coating**

Thickness: See Systems Approvals Below.

Specifications: ASTM D 1266 type III

Description: Asphalt base, unfibered clay emulsion. Apply with soft bristle brush or spray equipment at a rate of 3 gal./sq. in two coats.

Container Size: 1 and 5 and 275 (Totes) gallons. Note all precautions on container.

EVIDENCE SUBMITTED:

Test Agency	Test Identifier	Description	Date
PRI Asphalt Technologies	HGC-023-02-01	ASTM D 6083	07/17/03
	HGC-023-02-01	ASTM D 6083	06/26/06

EXISTING SUBSTRATES:

Substrate: **Existing Metal Roof Panel System**

All General Limitations apply.

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions. For rust or corrosion, refer the HENRY 112 Rust Inhibiting Rubber Based Primer.

Foundation Coat: On all exposed fasteners encapsulate with Henry 295 Metal Seam Sealer or alternately embed a 6 inch by 6 inch piece of Henry Tietex 196 fabric into Henry 280 DC White Elastomeric Roof Coating or HENRY 291 Premium Gray Elastomeric Base Coating then fully saturated in HENRY 280 DC White Elastomeric Roof Coating or HENRY 291 Premium Gray Elastomeric Base Coating. All seams, joints, or laps should be sealed with H 295 Metal Seam Sealer or alternately embed strips of Henry Tietex 196 overlapping fabric joints 4" in the Henry 280 DC or Henry 291 and fully saturate. Follow with one coat of HENRY 280 DC White Elastomeric Roof Coating or HENRY 291 Premium Gray Elastomeric Base Coating at a rate of 1 gal/sq (70ft^2/gal) by brush or spray. Allow to thoroughly dry before application of the finish coat.

Finish Coat: Apply Henry 280DC White Elastomeric Roof Coating finish coat at right angles to the foundation coat at a rate of 1 gal/sq. (70ft^2/gal) by brush or spray.

Maximum Design Pressure: N/A

Substrate: **New or Existing Spray Applied Polyurethane Foam**

All General Limitations apply.

System 1

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply one coat of HENRY 280 DC White Elastomeric Roof Coating at a rate of 1 gal/sq (70ft^2/gal) by brush or spray. Allow to thoroughly dry before application of the finish coats.

(Optional) Apply Henry 280 DC by brush or spray to fully saturate existing substrate at a maximum rate of 2 gal/sq (50 ft^2/gal) providing a minimum of 18 mils dry film thickness. Fully embed Henry 196 Tietex polyester fabric while coating is still wet, keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 280 DC and allowed to dry.

Finish Coat (Required) Apply two coats of Henry 280DC White Elastomeric Roof Coating in two equal coats at right angles with a combined rate of 2 gal/sq. (70ft^2/gal/coat) by brush or spray.

Maximum Design Pressure: N/A

System 2

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply one coat of HENRY 107 Unfibered Asphalt Emulsion at a rate of 4 gal/sq (64 mils) by brush or spray. Allow to thoroughly dry before application of the finish coats. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 107 and allowed to dry.

Finish Coat: (Required) Apply two coats of Henry 280DC White Elastomeric Roof Coating in two equal coats at right angles with a combined rate of 2 gal/sq. (70ft^2/gal/coat) by brush or spray.

Maximum Design Pressure: N/A

System 3

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply one coat of Henry 280DC White Elastomeric Roof Coating or HENRY 291 Premium Elastomeric Base Coating at a rate of 1 gal/sq (70ft^2/gal) by brush or spray. Allow to thoroughly dry before application of the finish coats.

Finish Coat: Apply Henry 280DC White Elastomeric Roof Coating finish coat at right angles to the foundation coat at a rate of 1 gal/sq. (70ft^2/gal) by brush or spray.

Maximum Design Pressure: N/A

Substrate: **Existing SBS Smooth Surface Modified Bituminous Roof System**

All General Limitations apply.

System 1

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply Henry 280 DC to fully saturate existing substrate at a maximum rate of 2 gal/sq (50 ft^2/gal) providing a minimum of 18 mils dry film thickness. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 280 DC and allowed to dry.

Finish Coat: Apply two coats of Henry 280DC White Elastomeric Roof Coating in two equal coats at a combined rate of 2 gal/sq. (70ft^2/gal/coat) by brush or spray.

Maximum Design Pressure: N/A

System 2

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply one coat of HENRY 107 Unfibered Asphalt Emulsion at a rate of 4 gal/sq (64 mils) by brush or spray. Allow to thoroughly dry before application of the finish coats. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 107 and allowed to dry.

Finish Coat: Apply two coats of Henry 280DC White Elastomeric Roof Coating in two equal coats at a combined rate of 2 gal/sq. (70ft^2/gal/coat) by brush or spray.

Maximum Design Pressure: N/A

System 3

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply one coat of HENRY 107 Unfibered Asphalt Emulsion at a rate of 4 gal/sq (64 mils) by brush or spray. Allow to thoroughly dry before application of the finish coats. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 107 and allowed to dry.

Intermediate Coat: Apply a second coat of HENRY 107 Unfibered Asphalt Emulsion at a rate of 3 gal/sq (48 mils) by brush or spray. Allow to thoroughly dry before application of the finish coats. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 107 and allowed to dry.

Finish Coat: Apply two coats of Henry 280DC White Elastomeric Roof Coating in two equal coats at a combined rate of 2 gal/sq. (70ft^2/gal/coat) by brush or spray.

Maximum Design Pressure: N/A

System 4

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply one coat of Henry 280DC White Elastomeric Roof Coating or HENRY 291 Premium Elastomeric Base Coating at a rate of 1 gal/sq (70ft^2/gal) by brush or spray. Allow to thoroughly dry before application of the finish coats.

Finish Coat: Apply Henry 280DC White Elastomeric Roof Coating finish coat at right angles to the foundation coat at a rate of 1 gal/sq. (70ft^2/gal) by brush or spray.

Maximum Design Pressure: N/A

Substrate: **Existing SBS Granulated Cap Sheet Modified Bituminous Roof System**

All General Limitations apply.

System 1

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply Henry 280 DC to fully saturate existing substrate at a maximum rate of 2 gal/sq (50 ft^2/gal) providing a minimum of 18 mils dry film thickness. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 280 DC and allowed to dry.

Finish Coat: Apply two coats of Henry 280DC White Elastomeric Roof Coating in two equal coats at a combined rate of 2 gal/sq. (70ft^2/gal/coat) by brush or spray.

Maximum Design Pressure: N/A

System 2

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply one coat of HENRY 107 Unfibered Asphalt Emulsion at a rate of 4 gal/sq (64 mils) by brush or spray. Allow to thoroughly dry before application of the finish coats. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 107 and allowed to dry.

Finish Coat: Apply two coats of Henry 280DC White Elastomeric Roof Coating in two equal coats at a combined rate of 2 gal/sq. (70ft^2/gal/coat) by brush or spray.

Maximum Design Pressure: N/A

System 3

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply one coat of HENRY 107 Unfibered Asphalt Emulsion at a rate of 4 gal/sq (64 mils) by brush or spray. Allow to thoroughly dry before application of the finish coats. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 107 and allowed to dry.

Intermediate Coat: Apply a second coat of HENRY 107 Unfibered Asphalt Emulsion at a rate of 3 gal/sq (48 mils) by brush or spray. Allow to thoroughly dry before application of the finish coats. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 107 and allowed to dry.

Finish Coat: Apply two coats of Henry 280DC White Elastomeric Roof Coating in two equal coats at a combined rate of 2 gal/sq. (70ft^2/gal/coat) by brush or spray.

Maximum Design Pressure: N/A

System 4

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply one coat of Henry 280DC White Elastomeric Roof Coating or HENRY 291 Premium Elastomeric Base Coating at a rate of 1 gal/sq (70ft^2/gal) by brush or spray. Allow to thoroughly dry before application of the finish coats.

Finish Coat: Apply Henry 280DC White Elastomeric Roof Coating finish coat at right angles to the foundation coat at a rate of 1 gal/sq. (70ft^2/gal) by brush or spray.

Maximum Design Pressure: N/A

Substrate: **Existing APP Modified**

All General Limitations apply.

System 1

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply Henry 280 DC to fully saturate existing substrate at a maximum rate of 2 gal/sq (50 ft^2/gal) providing a minimum of 18 mils dry film thickness. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 280 DC and allowed to dry.

Finish Coat: Apply two coats of Henry 280DC White Elastomeric Roof Coating in two equal coats at a combined rate of 2 gal/sq. (70ft^2/gal/coat) by brush or spray.

Maximum Design Pressure: N/A

System 2

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply one coat of HENRY 107 Unfibered Asphalt Emulsion at a rate of 4 gal/sq (64 mils) by brush or spray. Allow to thoroughly dry before application of the finish coats. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 107 and allowed to dry.

Finish Coat: Apply two coats of Henry 280DC White Elastomeric Roof Coating in two equal coats at a combined rate of 2 gal/sq. (70ft^2/gal/coat) by brush or spray.

Maximum Design Pressure: N/A

System 3

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply one coat of HENRY 107 Unfibered Asphalt Emulsion at a rate of 4 gal/sq (64 mils) by brush or spray. Allow to thoroughly dry before application of the finish coats. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 107 and allowed to dry.

Intermediate Coat: Apply a second coat of HENRY 107 Unfibered Asphalt Emulsion at a rate of 3 gal/sq (48 mils) by brush or spray. Allow to thoroughly dry before application of the finish coats. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 107 and allowed to dry.

Finish Coat: Apply two coats of Henry 280DC White Elastomeric Roof Coating in two equal coats at a combined rate of 2 gal/sq. (70ft^2/gal/coat) by brush or spray.

Maximum Design Pressure: N/A

System 4

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply one coat of Henry 280DC White Elastomeric Roof Coating or HENRY 291 Premium Elastomeric Base Coating at a rate of 1 gal/sq (70ft^2/gal) by brush or spray. Allow to thoroughly dry before application of the finish coats.

Finish Coat: Apply Henry 280DC White Elastomeric Roof Coating finish coat at right angles to the foundation coat at a rate of 1 gal/sq. (70ft^2/gal) by brush or spray.

Maximum Design Pressure: N/A

Substrate: **Existing Built-Up Roofing System**

All General Limitations apply.

System 1

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply Henry 280 DC to fully saturate existing substrate at a maximum rate of 2 gal/sq (50 ft^2/gal) providing a minimum of 18 mils dry film thickness. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 280 DC and allowed to dry.

Finish Coat: Apply two coats of Henry 280DC White Elastomeric Roof Coating in two equal coats at a combined rate of 2 gal/sq. (70ft^2/gal/coat) by brush or spray.

Maximum Design Pressure: N/A

System 2

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply one coat of HENRY 107 Unfibered Asphalt Emulsion at a rate of 4 gal/sq (64 mils) by brush or spray. Allow to thoroughly dry before application of the finish coats. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 107 and allowed to dry.

Finish Coat: Apply two coats of Henry 280DC White Elastomeric Roof Coating in two equal coats at a combined rate of 2 gal/sq. ($70ft^2$/gal/coat) by brush or spray.

Maximum Design Pressure: N/A

System 3

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply one coat of HENRY 107 Unfibered Asphalt Emulsion at a rate of 4 gal/sq (64 mils) by brush or spray. Allow to thoroughly dry before application of the finish coats. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 107 and allowed to dry.

Intermediate Coat: Apply a second coat of HENRY 107 Unfibered Asphalt Emulsion at a rate of 3 gal/sq (64 mils) by brush or spray. Allow to thoroughly dry before application of the finish coats. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 107 and allowed to dry.

Finish Coat: Apply two coats of Henry 280DC White Elastomeric Roof Coating in two equal coats at a combined rate of 2 gal/sq. ($70ft^2$/gal/coat) by brush or spray.

Maximum Design Pressure: N/A

System 4

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply one coat of Henry 280DC White Elastomeric Roof Coating or HENRY 291 Premium Elastomeric Base Coating at a rate of 1 gal/sq ($70ft^2$/gal) by brush or spray. Allow to thoroughly dry before application of the finish coats.

Finish Coat: Apply Henry 280DC White Elastomeric Roof Coating finish coat at right angles to the foundation coat at a rate of 1 gal/sq. ($70ft^2$/gal) by brush or spray.

Maximum Design Pressure: N/A

Substrate: **Existing PVC Membrane Roof Systems**

All General Limitations apply.

Preparation: The existing surface should be smooth, clean (using a 10% TSP/water solution), sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply one coat of Henry 280DC White Elastomeric Roof Coating or HENRY 291 Premium Elastomeric Base Coating at a rate of 1 gal/sq (70ft^2/gal) by brush or spray . Allow to thoroughly dry before application of the finish coats.

(Optional) Apply Henry 280 DC or Henry 291 HENRY 291 Premium Elastomeric Base Coating by brush or spray to fully saturate existing substrate at a maximum rate of 2 gal/sq (50 ft^2/gal) providing a minimum of 18 mils dry film thickness. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 280 DC or Henry 291 HENRY 291 Premium Elastomeric Base Coating and allowed to dry.

Finish Coat: Apply Henry 280DC White Elastomeric Roof Coating finish coat at right angles to the foundation coat at a rate of 1 gal/sq. (70ft^2/gal) by brush or spray.

Maximum Design Pressure: N/A

Substrate: **Existing EPDM Membrane Roof System**

All General Limitations apply.

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Primer: Apply Henry 825 Rubberkote Primer™ with a hand spray unit the rate of 0.2 gal/sq. Rinse thoroughly with water and allow to completely dry before applying the foundation coat

Foundation Coat: Apply one coat of Henry 280DC White Elastomeric Roof Coating or HENRY 291 Premium Elastomeric Base Coating at a rate of 1 gal/sq (70ft^2/gal) by brush or spray. Let thoroughly dry before application of the finish coats.

(Optional) Apply Henry 280 DC or HENRY 291 Premium Elastomeric Base Coating by brush or spray to fully saturate existing substrate at a maximum rate of 2 gal/sq (50 ft^2/gal) providing a minimum of 18 mils dry film thickness. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 280 DC or HENRY 291 Premium Elastomeric Base Coating and allowed to dry.

Finish Coat: Apply Henry 280DC White Elastomeric Roof Coating finish coat at right angles to the foundation coat at a rate of 1 gal/sq. (70ft^2/gal) by brush or spray.

Maximum Design Pressure: N/A

Substrate: **Existing HYPALON Membrane Roof System**

All General Limitations apply.

Preparation: The existing surface should be smooth, clean, sound and dry prior to the application of the Henry coating. All surface preparation shall be in compliance with the coating manufacture's current published application instructions.

Foundation Coat: Apply one coat of Henry 280DC White Elastomeric Roof Coating or HENRY 291 Premium Elastomeric Base Coating at a rate of 1 gal/sq (70ft^2/gal) by brush or spray. Allow to thoroughly dry before application of the finish coats.

(Optional) Apply Henry 280 DC or Henry 291 HENRY 291 Premium Elastomeric Base Coating to by brush or spray, fully saturate existing substrate at a maximum rate of 2 gal/sq (50 ft^2/gal) providing a minimum of 18 mils dry film thickness. Fully embed Henry 196 Tietex polyester fabric while coating is still wet keeping a minimum 4 inch fabric overlap. Fabric must be completely embedded in Henry 280 DC or Henry 291 HENRY 291 Premium Elastomeric Base Coating and allowed to dry.

Finish Coat: Apply Henry 280DC White Elastomeric Roof Coating finish coat at right angles to the foundation coat at a rate of 1 gal/sq. (70ft^2/gal) by brush or spray.

Maximum Design Pressure: N/A

LIMITATIONS:

1. Fire classification is not part of this acceptance; refer to a current Approved Roofing Materials Directory for fire ratings of this product.
2. Henry Company products shall not be applied in inclement weather conditions.
3. All products listed herein shall have an unannounced follow-up quality control program from an approved listing agency. Follow up test results shall be made available to BCCO upon request. All products listed herein shall have a quality assurance audit in accordance with the Florida Building Code and Rule 9B-72 of the Florida Administrative Code.
4. All approved products listed herein shall be labeled in compliance with TAS 121.
5. Change in materials, use, or manufacture of any of the products listed herein shall be cause for termination of this Notice of Acceptance.
6. This NOA is for the sole use as a roof maintenance coating system in accordance with applicable Building Code.
7. Henry 280DC shall not be covered with stone chips, screeds, tiles or soil.
8. Approved primer is required on all unprotected iron and steel.
9. The products listed herein are components of roof assemblies and are approved for use with roof assemblies that list any of the products listed herein as part of their roof assemblies Notice of Acceptance.
10. Contractor shall be a Henry Company trained and approved applicator familiar with the details and specifications published by the manufacturer.

BUILDING PERMIT REQUIREMENTS:

1. This Notice of Acceptance.
2. Any other documents required by the Building Official or applicable Building Code in order to properly evaluate the installation of this system.

END OF THIS ACCEPTANCE