



MIAMI-DADE COUNTY, FLORIDA
 METRO-DADE FLAGLER BUILDING
 140 WEST FLAGLER STREET, SUITE 1603
 MIAMI, FLORIDA 33130-1563
 (305) 375-2901 FAX (305) 372-6339
www.miamidadecounty.gov/buildingcode

BUILDING CODE COMPLIANCE OFFICE (BCCO)
 PRODUCT CONTROL DIVISION
NOTICE OF ACCEPTANCE (NOA)

Jeld-Wen, Inc (OR)
3737 Lakeport Blvd.
Klamath Falls, OR 97601

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed by Miami-Dade County Product Control Division and accepted by the Board of Rules and Appeals (BORA) to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Division (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. BORA reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Division that this product or material fails to meet the requirements of the applicable building code. This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Series "Custom Collection In - Sash" Aluminum Clad Wood Casement Window – L.M.I.

APPROVAL DOCUMENT: Drawing No. **07-JWN-0007**, titled "Custom Collection In-Sash Casement Window - Large Missile Impact Resistant", sheets 1 through 8 of 8, dated 11/09/07 with revision, dated 11/09/07, prepared by Engineering Express, signed and sealed by Frank L. Bennardo, P.E., bearing the Miami-Dade County Product Control Approval stamp with the Notice of Acceptance number and Approval date by the Miami-Dade County Product Control Division.

MISSILE IMPACT RATING: Large and Small Missile Impact Resistant

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official. This NOA consists of this page 1 and evidence pages E-1 and E-2, as well as approval document mentioned above.

The submitted documentation was reviewed by **Manuel Perez, P.E.**



NOA No. 08-0117.05
 Expiration Date: September 18, 2013
 Approval Date: September 18, 2008
 Page 1

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

A. DRAWINGS

1. Manufacturer's die drawings and sections.
2. Drawing No **07-JWN-0007**, titled "Custom Collection In-Sash Casement Window - Large Missile Impact Resistant", sheets 1 through 8 of 8, dated 11/09/07 with revision dated 04/18/08, prepared by Engineering Express, signed and sealed by Frank L. Bennardo, P.E.

B. TESTS

1. Test reports on:
 - 1) Air Infiltration Test, per FBC, TAS 202-94
 - 2) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
 - 3) Water Resistance Test, per FBC, TAS 202-94
 - 4) Large Missile Impact Test per FBC, TAS 201-94
 - 5) Cyclic Wind Pressure Loading per FBC, TAS 203-94
 - 6) Forced Entry Test, per FBC 2411 3.2.1, TAS 202-94

Along with marked-up drawings and installation diagram of a custom collection casement window, prepared by National Certified Testing Laboratories, Test Report No. **NCTL-110-10770-1**, dated 07/12/07, signed and sealed by Harold E. Rupp, P.E.

C. CALCULATIONS

1. Anchor verification calculations and structural analysis, complying with FBC-2004, prepared by Engineering Express, dated 11/29/07, with revision dated 03/27/08, signed and sealed by Frank L. Bennardo, P.E.
Complies with ASTM E1300- 02

D. QUALITY ASSURANCE

1. Miami Dade Building Code Compliance Office (BCCO).

E. MATERIAL CERTIFICATIONS

1. Notice of Acceptance No. **07-1116.04** issued to E.I. DuPont DeNemours & CO., Inc. for "**DuPont Sentry Glass Plus**" dated January 03, 2008, expiring on January 14, 2012.

F. STATEMENTS

1. Statement letter of conformance, dated January 9, 2008, signed and sealed by Frank L. Bennardo, P.E.
2. Statement letter of no financial interest, dated January 9, 2008, signed and sealed by Frank L. Bennardo, P.E.
3. Laboratory compliance statement for Test Report no. **NCTL-110-10770-1**, issued by National Certified Testing Laboratories, dated July 12, 2007, signed and sealed by Harold E. Rupp, P.E.


Manuel Perez, P.E.
Product Control Examiner
NOA No. 08-0117.05

Expiration Date: September 18, 2013
Approval Date: September 18, 2008

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

F. STATEMENTS (CONTINUED)

4. Addendum letter of Acrylic Sealant for Test Report no. **NCTL-110-10770-1**, issued by National Certified Testing Laboratories, dated June 25, 2008, signed and sealed by Gerard J. Ferrara, P.E.
5. Addendum letter of the Silicone Sealant for Test Report no. **NCTL-110-10770-1**, issued by National Certified Testing Laboratories, dated July 01, 2008, signed and sealed by Harold E. Rupp, P.E.

G. OTHERS

1. None


Manuel Perez, P.E.
Product Control Examiner

NOA No. 08-0117.05

Expiration Date: September 18, 2013


Approval Date: September 18, 2008

CUSTOM COLLECTION IN-SASH CASEMENT WINDOW

LARGE MISSILE IMPACT RESISTANT


FRANK L. BENNARDO, P.E.
PE0046549

08/18/2008




NOTE: MAXIMUM FRAME DIMENSIONS DO NOT INCLUDE INTEGRAL NAILING FIN.

1 TYPICAL ELEVATION
1 N.T.S. EXTERIOR ELEV



NOTE: MAXIMUM FRAME DIMENSIONS DO NOT INCLUDE INTEGRAL NAILING FIN.

2 36"x72" EXTENDED CIRCLE SEGMENT ELEVATION
1 N.T.S. EXTERIOR ELEV



NOTE: MAXIMUM FRAME DIMENSIONS DO NOT INCLUDE INTEGRAL NAILING FIN.

3 32"x54" EXTENDED CIRCLE SEGMENT ELEVATION
1 N.T.S. EXTERIOR ELEV

GENERAL NOTES

1. THE SYSTEM DESCRIBED HEREIN HAS BEEN DESIGNED AND TESTED IN ACCORDANCE WITH THE 2004 FLORIDA BUILDING CODE WITH 2006 SUPPLEMENTS, FOR USE WITHIN AND OUTSIDE THE HIGH VELOCITY HURRICANE ZONE, PER TAS 201 / 202 / 203 & ASTM E1300-02 STANDARDS.
2. NO 33-1/3% INCREASE IN ALLOWABLE STRESS HAS BEEN USED IN THE DESIGN OF THIS SYSTEM. WIND LOAD DURATION FACTOR Cd=1.6 HAS BEEN USED FOR WOOD ANCHOR DESIGN.
3. POSITIVE AND NEGATIVE DESIGN PRESSURES CALCULATED FOR USE WITH THIS SYSTEM SHALL BE DETERMINED BY OTHERS ON A JOB-SPECIFIC BASIS IN ACCORDANCE WITH THE GOVERNING CODE.
4. THE SYSTEM DETAILED HEREIN IS GENERIC AND DOES NOT PROVIDE INFORMATION FOR A SPECIFIC SITE. FOR SITE CONDITIONS DIFFERENT FROM THE CONDITIONS DETAILED HEREIN, A LICENSED ENGINEER OR REGISTERED ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE IN CONJUNCTION WITH THIS DOCUMENT.
5. PERMIT HOLDER SHALL VERIFY THE ADEQUACY OF THE EXISTING STRUCTURE TO WITHSTAND SUPERIMPOSED LOADS. WOOD BUCKS (BY OTHERS) SHALL BE ANCHORED PROPERLY TO TRANSFER LOADS TO THE EXISTING STRUCTURE.
6. ALL WOOD COMPONENTS OF THIS PRODUCT SHALL BE

PRESSURE TREATED WESTERN PINE OR WESTERN WOODS WITH G=0.36 OR GREATER DENSITY, UNLESS NOTED OTHERWISE.

7. UNITS GLAZED WITH 5/16" LAMINATED GLASS (5/32" ANNEALED / 0.090" SGP INTERLAYER / 5/32" ANNEALED, LAMINATED BY CARDINAL) ARE IMPACT RESISTANT AND DO NOT REQUIRE IMPACT RESISTANT SHUTTERS.

8. UNITS GLAZED WITH 1" INSULATED LAMINATED GLASS (1/8" TEMPERED + 1/2" GAP + 5/32" ANNEALED / 0.090" SGP INTERLAYER / 5/32" ANNEALED, LAMINATED BY CARDINAL) ARE LARGE MISSILE IMPACT RESISTANT AND DO NOT REQUIRE IMPACT RESISTANT SHUTTERS.

9. UNITS GLAZED WITH 1" INSULATED LAMINATED GLASS (1/8" ANNEALED + 1/2" GAP + 5/32" ANNEALED / 0.090" SGP INTERLAYER / 5/32" ANNEALED, LAMINATED BY CARDINAL) ARE LARGE MISSILE IMPACT RESISTANT AND DO NOT REQUIRE IMPACT RESISTANT SHUTTERS.

10. PLASTIC COMPONENTS USED WITHIN THE HVHZ MUST MEET ALL APPLICABLE FIRE/SMOKE/UV PERFORMANCE REQUIREMENTS AS SET FORTH IN THE ABOVE-NOTED BUILDING CODE.

11. ALL STEEL IN CONTACT WITH ALUMINUM SHALL BE PAINTED OR PLATED AS PRESCRIBED IN THE ABOVE-NOTED BUILDING CODE.

SHAPED UNIT NOTES:

1. FOR EXTENDED CIRCLE SEGMENT SHAPED UNITS WITH DIMENSIONS OTHER THAN THOSE SHOWN ABOVE, JAMB HEIGHT SHALL BE A MINIMUM OF 85% OF FRAME HEIGHT.
2. ALL SHAPED UNITS SHALL FIT WITHIN THE RECTANGULAR DIMENSIONS SHOWN IN THE DESIGN SCHEDULE.

Approved as complying with the Florida Building Code
Date 08/18/2008
NOA# 08-0117-05
Miami-Dade Product Control
Division
By *[Signature]*

ENGINEERING EXPRESS

160 SW 12th AVENUE, #106
DEERFIELD BEACH, FL 33442
Ph: (954) 354-0660 Fax: (954) 354-0443
WWW.ENGEXP.COM

CERT OF AUTH #985
A FRANK L. BENNARDO, P.E., INC. INNOVATION

JELBOWEN

3737 LAKEPORT BOULEVARD
KLAMATH FALLS, OREGON 97601
PHONE: (541) 850 - 2606

CUSTOM COLLECTION IN-SASH CASEMENT WINDOW
LARGE MISSILE IMPACT RESISTANT
MIAMI-DADE NOTICE OF ACCEPTANCE

REMARKS	DRWN	CHKD	DATE
INIT ISSUE	KL	CL	11/09/07

07-JWN-0007

SCALE: 1/16" = 1'-0"

PAGE DESCRIPTION: 01

1

F:\01 Project Files\Jeld-Wen (JWN)\2007\07-JWN-0007 Custom Wood - In-Sash Casement, Operable, LMI (NOA).dwg

08/18/2008 - 3:17pm keithl

FRANK L. BENNARDO, P.E.
PE0046549

08/18/2008

ENGINEERING EXPRESS

160 SW 12th AVENUE, #106
DEERFIELD BEACH, FL 33442
Ph: (954) 354-0660 Fax: (954) 354-0443
WWW.ENGEXP.COM


A FRANK L. BENNARDO, P.E., INC. INNOVATION
CERT OF AUTH #9885

DESIGN SCHEDULE

FRAME HEIGHT	SASH HEIGHT	D.L.O. HEIGHT	18"	20"	24"	28"	30"	32"	36"	FRAME WIDTH
			16-1/8"	18-1/8"	22-1/8"	26-1/8"	28-1/8"	30-1/8"	34-1/8"	SASH WIDTH
			13"	15"	19"	23"	25"	27"	31"	D.L.O. WIDTH
18"	16"	12-1/2"	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-75	MAXIMUM ALLOWABLE DESIGN PRESSURES (PSF)
20"	18"	14-1/2"	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-75	
24"	22"	18-1/2"	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-75	
30"	28"	24-1/2"	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-75	
32"	30"	26-1/2"	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-75	
36"	34"	30-1/2"	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-75	
40"	38"	34-1/2"	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-75	
42"	40"	36-1/2"	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-75	
48"	46"	42-1/2"	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-75	
54"	52"	48-1/2"	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-90	+60/-75	
56"	54"	50-1/2"	+60/-75	+60/-75	+60/-75	+60/-75	+60/-75	+60/-75	+60/-75	
60"	58"	54-1/2"	+60/-75	+60/-75	+60/-75	+60/-75	+60/-75	+60/-75	+60/-75	
64"	62"	58-1/2"	+60/-75	+60/-75	+60/-75	+60/-75	+60/-75	+60/-75	+60/-75	
66"	64"	60-1/2"	+60/-75	+60/-75	+60/-75	+60/-75	+60/-75	+60/-75	+60/-75	
72"	70"	66-1/2"	+60/-75	+60/-75	+60/-75	+60/-75	+60/-75	+60/-75	+60/-75	


GLAZING TYPE A

5/16" LAMINATED, LMI




GLAZING TYPE B

1" INSULATED LAMINATED, LMI



GLAZING TYPE C

1" INSULATED LAMINATED, LMI



2 GLAZING DETAILS

1 N.T.S. VERT SECTION

JELD-WEN
3737 LAKEPORT BOULEVARD
KLAMATH FALLS, OREGON 97601
PHONE: (541) 850 - 2606

CUSTOM COLLECTION IN-SASH CASEMENT WINDOW
LARGE MISSILE IMPACT RESISTANT
MIAMI-DADE NOTICE OF ACCEPTANCE

REMARKS	DRWN	CHKD	DATE
INIT ISSUE	KL	CL	11/09/07

07-JWN-0007



SCALE: 01

PAGE DESCRIPTION:

Approved as complying with the
Florida Building Code
Date 09/18/2008
NOA# 08-117.05
Miami Dade Product Control
Division
By *Wanuel Perez*

08/18/2008

A
3 TYPICAL HEAD ASSEMBLY
N.T.S. VERT SECTION



C
3 TYPICAL JAMB ASSEMBLY AT HINGE
N.T.S. HORIZ SECTION

D
3 TYPICAL JAMB ASSEMBLY AT LOCK
N.T.S. HORIZ SECTION

ENGINEERING EXPRESS
160 SW 12th AVENUE, #106
DEERFIELD BEACH, FL 33442
Ph: (954) 354-0660 FAX: (954) 354-0443
WWW.ENGEXP.COM
CERT OF AUTH #9885
A FRANK L. BENNARDO, P.E., INC. INNOVATION

JELD-WEN
3737 LAKEPORT BOULEVARD
KLAMATH FALLS, OREGON 97601
PHONE: (541) 850 - 2606
CUSTOM COLLECTION IN-SASH CASEMENT WINDOW
LARGE MISSILE IMPACT RESISTANT
MIAMI-DADE NOTICE OF ACCEPTANCE

DRWN	CHKD	DATE
KL	CL	11/09/07

REMARKS

INIT ISSUE


07-JWN-0007
SCALE: 01
PAGE DESCRIPTION:

Approved as complying with the Florida Building Code
Date 09/10/2008
NOA# 68-0117.05
Miami Dade Product Control Division
By *Manuel Perez*


F:\01 Project Files\Jeld-Wen (JWN)\2007\07 - Insash Casement, Operable, LMI (NOA)\07-JWN-0007 - In-Sash Casement, Operable, LMI (NOA).dwg
08/18/2008 - 3:17pm
keith

F:\01 Project Files\Jeld-Wen (JWN)\2007\07-JWN-0007 Custom Wood - In-Sash Casement, Operable, LMI (NOA).dwg


08/18/2008 - 3:17pm keithl



1
ANCHOR ELEVATION FOR
INSTALLATION WITH NAIL FIN
N.T.S. EXTERIOR ELEV



2
ANCHOR ELEVATION FOR
INSTALLATION THROUGH FRAME
N.T.S. EXTERIOR ELEV



3
ANCHOR ELEVATION FOR
INSTALLATION WITH STRAP
N.T.S. EXTERIOR ELEV

ANCHOR SCHEDULE:

TO HOLLOW BLOCK OR 3192 PSI MIN CONCRETE HOST STRUCTURE:

- 1/4" TAPCONS (ELCO OR ITW) THRU 1X OR 2X WOOD BUCKS OR DIRECTLY INTO MASONRY / CONCRETE WITH 1-3/4" MIN. EMBEDMENT.

TO WOOD BUCK OR HOST STRUCTURE (G=0.55 MIN WOOD):

- 1/4" TAPCONS (ELCO OR ITW) WITH 1-1/2" MIN. THREAD PENETRATION.
- #14 WOOD SCREWS WITH 1-1/2" MIN. THREAD PENETRATION.
- 1/4" LAG SCREWS WITH 1-1/2" MIN. THREAD PENETRATION.

ANCHOR NOTES:

- SEE ANCHOR ELEVATIONS FOR ANCHOR LOCATIONS AND/OR SPACING.
- ANCHORAGE METHODS, INCLUDING ANCHOR TYPES AND MAXIMUM SPACING, ARE APPLICABLE TO ALL SHAPED UNITS SHOWN ON SHEET 1.
- ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS' RECOMMENDATIONS.
- TAPCONS MAY BE MANUFACTURED BY ELCO OR ITW.
- ENSURE MINIMUM 2-1/2" EDGE DISTANCE FOR ALL ANCHORS INTO CONCRETE AND INTO HOLLOW BLOCK.
- WHERE ANCHORS FASTEN TO NARROW FACE OF STUD FRAMING, ANCHOR SHALL BE LOCATED IN CENTER OF NOMINAL 2x (MIN) WOOD STUD (i.e. 3/4" EDGE DISTANCE IS ACCEPTABLE FOR ANCHORS TO WOOD FRAMING).
- WOOD HOST STRUCTURE SHALL BE "SOUTHERN PINE" G=0.55 OR GREATER DENSITY.
- MINIMUM EMBEDMENT SHALL BE AS NOTED IN ANCHOR SCHEDULE. MINIMUM EMBEDMENT AND EDGE DISTANCE EXCLUDES STUCCO, FOAM, BRICK, AND OTHER WALL FINISHES.
- ANCHOR SCHEDULE APPLIES TO ALL PRODUCTS CERTIFIED HEREIN.
- WHERE EXISTING STRUCTURE IS WOOD FRAMING, EXISTING CONDITIONS MAY VARY. FIELD VERIFY THAT FASTENERS ARE INTO ADEQUATE WOOD FRAMING MEMBERS, NOT INTO PLYWOOD.
- WOOD BUCKS (BY OTHERS) SHALL BE ANCHORED PROPERLY TO TRANSFER LOADS TO THE EXISTING STRUCTURE.

Approved as complying with the
Florida Building Code
Date 09/18/2008
NOA 68-017.05
Miami Dade Product Control
Division
By *Mauro Perez*

FRANK L. BENNARDO, P.E.
PE0046549

08/18/2008

ENGINEERING EXPRESS

160 SW 12th AVENUE, # 106
DEERFIELD BEACH, FL 33442
Ph: (954) 354-0660 Fax: (954) 354-0443
WWW.ENGEXP.COM
CERT OF AUTH #9885
A FRANK L. BENNARDO, P.E., INC. INNOVATION

JELD-WEN

3737 LAKEPORT BOULEVARD
KLAMATH FALLS, OREGON 97601
PHONE: (541) 850 - 2606

CUSTOM COLLECTION IN-SASH CASEMENT WINDOW
LARGE MISSILE IMPACT RESISTANT
MIAMI-DADE NOTICE OF ACCEPTANCE

REMARKS	DRWN	CHKD	DATE
INIT ISSUE	KL	CL	11/09/07

07-JWN-0007

SCALE: 1/8" = 1'-0" 01

PAGE DESCRIPTION:

4

08/18/2008



160 SW 12th AVENUE, # 106
DEERFIELD BEACH, FL 33442
PH: (954) 354-0660 FAX: (954) 354-0443
WWW.ENGEXP.COM
CERT OF AUTH #9885
A. FRANK L. BENNARDO, P.E., INC. INNOVATION



3737 LAKEPORT BOULEVARD
KLAMATH FALLS, OREGON 97601
PHONE: (541) 850 - 2606
CUSTOM COLLECTION IN-SASH CASEMENT WINDOW
LARGE MISSILE IMPACT RESISTANT
MIAMI-DADE NOTICE OF ACCEPTANCE

REMARKS	DRWN	CHKD	DATE
INIT ISSUE	KL	CL	11/09/07


07-JWN-0007
SCALE: 1/8" = 1'-0"
PAGE DESCRIPTION: 01

Approved as complying with the Florida Building Code
Date 09/18/2008
NOAH 08-0117-05
Miami Dade Product Control Division
By: *Manuel Perez*


5

INSTALLATION WITH FIN AT FRAME HEAD

A
5 N.T.S. VERT SECTION




NOTE: NAIL FIN INSTALLATION REQUIRES MINIMUM 2X OR GREATER PRESSURE TREATED WOOD BUCK (BY OTHERS) IN CONCRETE AND MASONRY HOST STRUCTURE.



INSTALLATION WITH FIN AT FRAME JAMB

C
5 N.T.S. HORIZ SECTION

NOTE: NAIL FIN INSTALLATION REQUIRES MINIMUM 2X OR GREATER PRESSURE TREATED WOOD BUCK (BY OTHERS) IN CONCRETE AND MASONRY HOST STRUCTURE.




INSTALLATION WITH FIN AT FRAME JAMB

D
5 N.T.S. HORIZ SECTION

NOTE: SEE ANCHOR SCHEDULE AND ANCHOR NOTES FOR REQUIRED EDGE DISTANCES AND EMBEDMENTS.

INSTALLATION WITH FIN AT FRAME SILL

B
5 N.T.S. VERT SECTION



NOTE: NAIL FIN INSTALLATION REQUIRES MINIMUM 2X OR GREATER PRESSURE TREATED WOOD BUCK (BY OTHERS) IN CONCRETE AND MASONRY HOST STRUCTURE.




F:\01 Project Files\Jeld-Wen (JWN)\2007\07-JWN-0007 Custom Wood - Insash Casement, Operable, LMI (NOA).dwg
08/18/2008 - 3:17pm keith

08/18/2008

A 6

INSTALLATION THROUGH FRAME HEAD

N.T.S. VERT SECTION



C 6

INSTALLATION THROUGH FRAME JAMB


N.T.S. HORIZ SECTION

D 6

INSTALLATION THROUGH FRAME JAMB

N.T.S. HORIZ SECTION

NOTE: SEE ANCHOR SCHEDULE AND ANCHOR NOTES FOR REQUIRED EDGE DISTANCES AND EMBEDMENTS.



B 6

INSTALLATION THROUGH FRAME SILL

N.T.S. VERT SECTION

ENGINEERING EXPRESS

160 SW 12th AVENUE, # 106
DEERFIELD BEACH, FL 33442
Ph: (954) 354-0660 FAX: (954) 354-0443
WWW.ENGEXP.COM

CERT OF AUTH #9885
A FRANK L. BENNARDO, P.E., INC. INNOVATION

JELD-WEN

5737 LAKEPORT BOULEVARD
KLAMATH FALLS, OREGON 97601
PHONE: (541) 850 - 2606

CUSTOM COLLECTION IN-SASH CASEMENT WINDOW
LARGE MISSILE IMPACT RESISTANT
MIAMI-DADE NOTICE OF ACCEPTANCE

REMARKS	DRWN	CHKD	DATE
INIT ISSUE	KL	CL	11/09/07

07-JWN-0007

SCALE: 1/8" = 1'-0"

PAGE DESCRIPTION:

Approved as complying with the
Florida Building Code
Date 09/18/2008
NOA# 08-0117.05
Miami Dade Product Control
Division
By *Manuel Perez*

6

08/18/2008

EX ENGINEERING EXPRESS
160 SW 12th AVENUE, # 106
DEERFIELD BEACH, FL 33442
Ph: (954) 354-0660 Fax: (954) 354-0443
WWW.ENGEXP.COM
CERT OF AUTH #988
A FRANK L. BENNARDO, P.E., INC. INNOVATION

JELD-WEN
3737 LAKEPORT BOULEVARD
KLAMATH FALLS, OREGON 97601
PHONE: (541) 850 - 2606
CUSTOM COLLECTION IN-SASH CASEMENT WINDOW
LARGE MISSILE IMPACT RESISTANT
MIAMI-DADE NOTICE OF ACCEPTANCE



DRWN	CHKD	DATE
KL	CL	11/09/07

07-JWN-0007
SCALE: 1/8" = 1'-0"
PAGE DESCRIPTION: 01

Approved as complying with the Florida Building Code
Date 09/18/2008
NOA# 68-0117.05
Miami Dade Product Control
Division
By *Manuel Diaz*


INSTALLATION WITH STRAP AT FRAME HEAD

A
7 N.T.S. VERT SECTION



INSTALLATION WITH STRAP AT FRAME JAMB

C
7 N.T.S. HORIZ SECTION




INSTALLATION WITH STRAP AT FRAME JAMB

D
7 N.T.S. HORIZ SECTION

NOTE: SEE ANCHOR SCHEDULE AND ANCHOR NOTES FOR REQUIRED EDGE DISTANCES AND EMBEDMENTS.

INSTALLATION WITH STRAP AT FRAME SILL


B
7 N.T.S. VERT SECTION




F:\01 Project Files\Jeld-Wen (JWN)\2007\07-JWN-0007 Custom Wood - In-sash Casement, Operable, LMI (NOA).dwg
08/18/2008 - 3:17pm Keith

F:\01 Project Files\Jeld-Wen (JWN)\2007-07-JWN-0007 Custom Wood - Insash Casement, Operable, LMI (NOA)\07-JWN-0007 Custom Wood - In-Sash Casement, Operable, LMI (NOA).dwg


08/18/2008 - 3:17pm keith




1 NAIL FIN
6" = 1'-0" 6063-T5 ALUM.




2 SASH BOTTOM RAIL
6" = 1'-0" WOOD




3 BOTTOM RAIL CLADDING
6" = 1'-0" 6063-T5 ALUM.




4 GLAZING STOP
6" = 1'-0" WOOD




5 OPERATOR COVER
6" = 1'-0" WOOD




6 JAMB EXTENDER
6" = 1'-0" WOOD




7 FRAME HEAD AND SILL
6" = 1'-0" WOOD




10 FRAME JAMB
6" = 1'-0" WOOD




12 SASH STILE AND TOP RAIL
6" = 1'-0" WOOD




13 STILE AND TOP RAIL CLADDING
6" = 1'-0" 6063-T5 ALUM.



14 HEAD STOP
6" = 1'-0" WOOD



17 SIDE STOP
6" = 1'-0" WOOD



22 13GA GALVANIZED INSTALLATION STRIP
6" = 1'-0" STEEL

BILL OF MATERIALS

ITEM	PART #	DESCRIPTION	MATERIAL	REMARKS
1	VH-53639	NAIL FIN EXTRUSION	6063-T5	
2	CA0151RA	SASH BOTTOM RAIL	WOOD	PRESSURE TREATED AURALAST®
3	VH-50333	EXTRUDED BOTTOM RAIL CLADDING	6063-T5	
4	CA0278SP	GLAZING STOP	WOOD	PRESSURE TREATED AURALAST®
5	CA01420C	OPERATOR COVER	WOOD	PRESSURE TREATED AURALAST®
6	CA260AJE	JAMB EXTENDER	WOOD	PRESSURE TREATED AURALAST®
7	CA0153HJ	FRAME SILL & HEAD	WOOD	PRESSURE TREATED AURALAST®
8	12261	FRAME WEATHERSTRIP	PVC	BY AMESBURY
9	50468A	SASH WEATHERSTRIP	PVC	BY INTEK
10	CA0177SJ	FRAME JAMB	WOOD	PRESSURE TREATED AURALAST®
11		ROTO OPERATOR TRACK	STEEL	BY TRUTH
12	CA0152RA	SASH STILE AND TOP RAIL	WOOD	PRESSURE TREATED AURALAST®
13	VH-49545	STILE AND TOP RAIL CLADDING	6063-T5	
14	CA0282SP	HEAD STOP	WOOD	PRESSURE TREATED AURALAST®
15		SINGLE ARM ROTO OPERATOR	STEEL	BY TRUTH
16	30263B	OPERATOR COVER FASTENING STRIP	PVC	BY INTEK
17	CA0274SP	SIDE STOP	WOOD	PRESSURE TREATED AURALAST®
18		BUTT HINGE	STEEL	BY TRUTH
19		LOCK KEEPERS	STEEL	BY AMEROCK
20		CONCEALED LOCK	STEEL	BY AMEROCK
21		SILICONE SEALANT	SILICONE	DOW CORNING 899
22		GALVANIZED INSTALLATION STRAP	STEEL	13 GA

Approved as complying with the Florida Building Code
 Date 09/18/2008
 NOA# 08-0117-05
 Miami Dade Product Control Division
 By *Maurice Perry*

FRANK L. BENNARDO, P.E.
PE0046549

08/18/2008

ENGINEERING EXPRESS®
 160 SW 12th AVENUE, # 106
 DEERFIELD BEACH, FL 33442
 Ph: (954) 354-0660 Fax: (954) 354-0443
 WWW.ENGEXP.COM
 CERT. OF AUTH. #9885
 A FRANK L. BENNARDO, P.E., INC. INNOVATION

JELD-WEN
 3737 LAKEPORT BOULEVARD
 KLAMATH FALLS, OREGON 97601
 PHONE: (541) 850 - 2606
 CUSTOM COLLECTION IN-SASH CASEMENT WINDOW
 LARGE MISSILE IMPACT RESISTANT
 MIAMI-DADE NOTICE OF ACCEPTANCE

DRWN	CHKD	DATE
KL	CL	11/09/07

07-JWN-0007
SCALE: 1/8" = 1'-0"

PAGE DESCRIPTION:

8