



BUILDING CODE COMPLIANCE OFFICE (BCCO)
PRODUCT CONTROL DIVISION

MIAMI-DADE COUNTY, FLORIDA
METRO-DADE FLAGLER BUILDING
140 WEST FLAGLER STREET, SUITE 1603
MIAMI, FLORIDA 33130-1563
(305) 375-2901 FAX (305) 375-2908

www.buldingcodeonline.com

NOTICE OF ACCEPTANCE (NOA)

Innovative Window Concepts, LLC
1801 Corporate Drive
Boynton Beach, FL 33426

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed by Miami-Dade County Product Control Division and accepted by the Board of Rules and Appeals (BORA) to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Division (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. BORA reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Division that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Series 1072 Aluminum Single Hung Window – S.M.I.

APPROVAL DOCUMENT: Drawing No. **W03-95**, titled "Series 1072 Alum. Single Hung Window (S.M.I.)", sheets 1 through 5 of 5, dated 10/20/03 with revision E dated 10/24/08, prepared by Al-Farooq Corporation, signed and sealed by Humayoun Farooq, P.E., bearing the Miami-Dade County Product Control Revision stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Division.

MISSILE IMPACT RATING: Small Missile Impact Resistant

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official. This NOA **revises and renews** NOA # **06-1129.05** and consists of this page 1 and evidence pages E-1 and E-2, as well as approval document mentioned above.

The submitted documentation was reviewed by **Fitz A. Harris, P.E.**



Fitz A. Harris
01/14/09

NOA No. 08-1210.02
Expiration Date: February 19, 2014
Approval Date: February 4, 2009
Page 1

Innovative Window Concepts, LLC

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

A. DRAWINGS

1. Manufacturer's die drawings and sections.
2. Drawing No **W03-95**, Sheets 1 through 5 of 5, titled "Series 1072 Alum. Single Hung Window (S.M.I.)", dated 10/20/03 with revision E dated 10/24/08, prepared by Al-Farooq Corporation, signed and sealed by Humayoun Farooq, P.E.

B. TESTS

1. Test reports on
 - 1) Air Infiltration Test, per FBC, TAS 202-94
 - 2) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94
 - 3) Water Resistance Test, per FBC, TAS 202-94
 - 4) Small Missile Impact Test, per FBC, TAS 201-94
 - 5) Cyclic Wind Pressure Loading, per FBC, TAS 203-94
 - 6) Force Entry Test, per FBC 2411 3.2.1 and TAS 202-94

along with marked-up drawings and installation diagram of an aluminum single hung window, prepared by American Test Lab of South Florida, Test Report No. **ATL-0422.02-03**, dated 07/24/03, signed and sealed by Henry Hattem, P.E.

"Submitted under NOA# 03-1201.04"

C. CALCULATIONS

1. Revised Anchor verification calculations and structural analysis, complying with FBS-2007, prepared by Al-Farooq Corporation, dated 10/20/08, signed and sealed by Humayoun Farooq, P.E.
2. Revised Anchor verification calculations and structural analysis, complying with FBC-2004, prepared by Al-Farooq Corporation, dated 10/23/06, signed and sealed by Humayoun Farooq, P.E.

Complies with ASTM E1300/02

3. Anchor calculations, and structural analysis, complying with FBC-2004, prepared by Al-Farooq Corporation on 09/03/05, signed and sealed by Humayoun Farooq, P.E.


"Submitted under NOA# 05-1004.01"

D. QUALITY ASSURANCE

1. Miami Dade Building Code Compliance Office (BCCO).

E. MATERIAL CERTIFICATIONS

1. Notice of Acceptance No. **03-0827.08** issued to Solutia Inc. for "Solutia Interlayers", dated 03/04/04, expiring on 03/04/09.


Fitz A. Harris, P.E.

Product Control Examiner

NOA No. 08-1210.02

Expiration Date: February 19, 2014

Approval Date: February 4, 2009

Innovative Window Concepts, LLC

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

F. STATEMENTS

1. Statement letter of compliance, dated October 20, 2008, signed and sealed by Humayoun Farooq, P.E.
2. Statement letter of conformance, dated September 3, 2005, signed and sealed by Humayoun Farooq, P.E.
3. Statement letter of no financial interest, dated September 3, 2005, signed and sealed by Humayoun Farooq, P.E.
4. Laboratory compliance letter for Test Report no. **ATLSF- 0422.02-03**, issued by American Test Lab of South Florida, dated 07/24/03, signed and sealed by William R. Mehner, P.E. and Henry Hattem, P.E.

G. OTHER

1. Notice of Acceptance No. **06-1129.05** issued to Innovative Window Concepts, LLC for their Series 1072 Aluminum Single Hung Window – S.M.I. approved on 03/ 29/ 2007 and expiring on 02/19/09
2. Notice of Acceptance No. **05-1004.01**, issued to Innovative Window Concepts, LLC for their Series 1072 Aluminum Single Hung Window – S.M.I., approved on 03/23/06 and expiring on 02/19/09.


Fitz A. Harris, P.E.

Product Control Examiner
NOA No. 08-1210.02

Expiration Date: February 19, 2014

Approval Date: February 4, 2009

UNEQUAL LITES WINDOWS			
DESIGN LOAD CAPACITY - PSF			
FLANGE DIMS.		STD. ANCHOR SPACING	
WIDTH	HEIGHT	EXT.(+)	INT.(-)
19-1/8"	50-5/8" (4)	90.0	160.0
24"		90.0	160.0
26-1/2"		90.0	160.0
32"		90.0	160.0
37"		90.0	138.4
40"		90.0	128.0
48"	90.0	106.7	
53-1/8"	90.0	96.4	
19-1/8"	63" (5)	90.0	160.0
24"		90.0	160.0
26-1/2"		90.0	160.0
32"		90.0	160.0
37"		90.0	139.0
40"		90.0	128.6
48"	90.0	107.1	
53-1/8"	90.0	96.8	
19-1/8"	76" (6)	90.0	160.0
24"		90.0	160.0
26-1/2"		90.0	160.0
32"		90.0	159.9
37"		90.0	138.3
40"		90.0	127.9
48"	90.0	106.6	
53-1/8"	90.0	96.3	
19-1/8"	84" (7)	90.0	160.0
24"		90.0	160.0
26-1/2"		90.0	160.0
32"		90.0	140.0
37"	90.0	140.0	
40"	90.0	135.0	
19-1/8"	96" (8)	90.0	160.0
24"		90.0	160.0
26-1/2"		90.0	160.0
32"		90.0	140.0
37"	90.0	140.0	

* NO. IN PARENTHESIS INDICATE NO. OF ANCHORS PER JAMB.

UNEQUAL LITES WINDOWS			
DESIGN LOAD CAPACITY - PSF			
FLANGE DIMS.		EXTRA JAMB ANCHORS	
WIDTH	HEIGHT	EXT.(+)	INT.(-)
19-1/8"	50-5/8" (6)	90.0	160.0
24"		90.0	160.0
26-1/2"		90.0	160.0
32"		90.0	160.0
37"		90.0	160.0
40"		90.0	160.0
48"	90.0	158.8	
53-1/8"	90.0	137.0	
19-1/8"	63" (7)	90.0	160.0
24"		90.0	160.0
26-1/2"		90.0	160.0
32"		90.0	160.0
37"		90.0	160.0
40"		90.0	160.0
48"	90.0	140.0	
53-1/8"	90.0	125.6	
19-1/8"	76" (8)	90.0	160.0
24"		90.0	160.0
26-1/2"		90.0	160.0
32"		90.0	140.0
37"		90.0	140.0
40"		90.0	140.0
48"	90.0	140.0	
53-1/8"	90.0	123.8	

* NO. IN PARENTHESIS INDICATE NO. OF ANCHORS PER JAMB.

SERIES 1072 ALUMINUM SINGLE HUNG WINDOW

DESIGN LOAD RATINGS FOR THESE WINDOWS TO BE AS PER CHARTS SHOWN ON SHEETS 1 & 2.

APPROVAL APPLIES TO SINGLE UNITS OR SIDE BY SIDE COMBINATIONS OF S.H./S.H. OR SINGLE HUNG WITH OTHER WINDOW TYPES IN MODULES OF TWO OR MORE WINDOWS USING MIAMI-DADE COUNTY APPROVED MULLIONS IN BETWEEN. LOWER DESIGN PRESSURE FROM WINDOWS OR MULLION APPROVAL WILL APPLY TO ENTIRE SYSTEM.

THIS PRODUCT HAS BEEN DESIGNED AND TESTED TO COMPLY WITH THE REQUIREMENTS OF THE FLORIDA BUILDING CODE 2004/2007 EDITION INCLUDING HIGH VELOCITY HURRICANE ZONE (HVHZ).


WOOD BUCKS BY OTHERS, MUST BE ANCHORED PROPERLY TO TRANSFER LOADS TO THE STRUCTURE.

ANCHORS SHALL BE AS LISTED, SPACED AS SHOWN ON DETAILS, ANCHORS EMBEDMENT TO BASE MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO. ANCHORING OR LOADING CONDITIONS NOT SHOWN IN THESE DETAILS ARE NOT PART OF THIS APPROVAL.

A LOAD DURATION INCREASE IS USED IN DESIGN OF ANCHORS INTO WOOD ONLY.

MATERIALS INCLUDING BUT NOT LIMITED TO STEEL/METAL SCREWS, THAT COME INTO CONTACT WITH OTHER DISSIMILAR MATERIALS SHALL MEET THE REQUIREMENTS OF 2004/2007 FLORIDA BLDG. CODE SECTION 2003.8.4.

NOTE:
GLASS CAPACITIES ON THIS SHEET ARE
BASED ON ASTM E1300-02/04 (3 SEC. GUSTS)
AND FLORIDA BUILDING COMMISSION
DECLARATORY STATEMENT DCA05-DEC-219



UNEQUAL LITES (ORIEL TYPE)

TYPICAL ELEVATION
TESTED UNIT

WINDOWS RATED FOR SMALL MISSILE IMPACT.
SHUTTERS REQUIRED FOR INSTALLATIONS UP TO 30 FT. OF GRADE
SHUTTERS NOT REQUIRED FOR INSTALLATIONS ABOVE 30 FT.

Engr. DR. HUMAYOUN FAROOQ
STRUCTURES
FLA. PE # 16557
C.A.N. 3538

NOV 06 2008

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. **08-1210-02**
Expiration Date **08-19-2014**
[Signature]
Florida Code Product Control
Division

SERIES 1072 ALUM SINGLE HUNG WINDOW (S.M.I.)
INNOVATIVE WINDOW CONCEPTS, LLC
1801 CORPORATE DRIVE
BOYNTON BEACH, FL. 33426
TEL. (561) 493-2303 FAX. (561) 493-2302

no.	date	description
A	01.13.04	NO CHANGE THIS SHEET
B	08.06.05	UPDATED FOR 2004 FBC
C	02.01.06	REV. PER BCCO COMMENTS
D	10.19.06	GLAZING TAPE OPTION ADDED
E	10.24.08	UPDATED FOR 2007 FBC

date: 10-20-03
scale: 1/2"=1'-0"
dr. by: HAMID
chk. by:


drawing no.
W03-95
sheet 1 of 5

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP-ANL\W03-95IWS

EQUAL LITES WINDOWS				
DESIGN LOAD CAPACITY - PSF				
FLANGE DIMS.		STD. ANCHOR SPACING		
WIDTH	HEIGHT	EXT.(+)	INT.(-)	
19-1/8"	26"	90.0	160.0	
24"		90.0	160.0	
26-1/2"		90.0	160.0	
32"		(2)	90.0	155.8
37"		90.0	134.7	
40"		90.0	124.6	
48"		90.0	103.8	
53-1/8"		90.0	93.8	
19-1/8"	38-3/8"	90.0	160.0	
24"		90.0	160.0	
26-1/2"		90.0	160.0	
32"		(3)	90.0	158.3
37"		90.0	136.9	
40"		90.0	126.6	
48"		90.0	105.5	
53-1/8"		90.0	95.4	
19-1/8"	50-5/8"	90.0	160.0	
24"		90.0	160.0	
26-1/2"		90.0	160.0	
32"		(4)	90.0	160.0
37"		90.0	138.4	
40"		90.0	128.0	
48"		90.0	106.7	
53-1/8"		90.0	96.4	
19-1/8"	63"	90.0	160.0	
24"		90.0	160.0	
26-1/2"		90.0	160.0	
32"		(5)	90.0	160.0
37"		90.0	139.0	
40"		90.0	128.6	
48"		90.0	107.1	
53-1/8"		90.0	96.8	
19-1/8"	76"	90.0	160.0	
24"		90.0	160.0	
26-1/2"		90.0	160.0	
32"		(6)	90.0	159.9
37"		90.0	138.3	
40"		90.0	127.9	
48"		90.0	106.6	
53-1/8"		90.0	96.3	
19-1/8"	84"	90.0	160.0	
24"		90.0	160.0	
26-1/2"		90.0	160.0	
32"		(7)	90.0	160.0
37"		90.0	145.9	
40"		90.0	135.0	
48"		90.0	112.5	
19-1/8"	96"	90.0	160.0	
24"		90.0	160.0	
26-1/2"		90.0	160.0	
32"		(8)	90.0	160.0
37"		90.0	145.9	
40"		90.0	135.0	
48"		90.0	112.5	


EQUAL LITES WINDOWS				
DESIGN LOAD CAPACITY - PSF				
FLANGE DIMS.		EXTRA JAMB ANCHORS		
WIDTH	HEIGHT	EXT.(+)	INT.(-)	
19-1/8"	26"	90.0	160.0	
24"		90.0	160.0	
26-1/2"		90.0	160.0	
32"		(3)	90.0	160.0
37"		90.0	160.0	
40"		90.0	160.0	
48"		90.0	155.8	
53-1/8"		90.0	140.7	
19-1/8"	38-3/8"	90.0	160.0	
24"		90.0	160.0	
26-1/2"		90.0	160.0	
32"		(5)	90.0	160.0
37"		90.0	160.0	
40"		90.0	160.0	
48"		90.0	160.0	
53-1/8"		90.0	158.9	
19-1/8"	50-5/8"	90.0	160.0	
24"		90.0	160.0	
26-1/2"		90.0	160.0	
32"		(6)	90.0	160.0
37"		90.0	160.0	
40"		90.0	160.0	
48"		90.0	156.3	
53-1/8"		90.0	135.2	
19-1/8"	63"	90.0	160.0	
24"		90.0	160.0	
26-1/2"		90.0	160.0	
32"		(7)	90.0	160.0
37"		90.0	160.0	
40"		90.0	160.0	
48"		90.0	138.7	
53-1/8"		90.0	118.3	
19-1/8"	76"	90.0	160.0	
24"		90.0	160.0	
26-1/2"		90.0	160.0	
32"		(8)	90.0	160.0
37"		90.0	160.0	
40"		90.0	160.0	
48"		90.0	129.1	
53-1/8"		90.0	108.2	
19-1/8"	84"	90.0	160.0	
24"		90.0	160.0	
26-1/2"		90.0	160.0	
32"		(8)	90.0	160.0
37"		90.0	160.0	
40"		90.0	154.3	
48"		90.0	126.4	
19-1/8"	96"	90.0	160.0	
24"		90.0	160.0	
26-1/2"		90.0	160.0	
32"		(9)	90.0	160.0
37"		90.0	160.0	
40"		90.0	160.0	
48"		90.0	151.9	

NOTE:
GLASS CAPACITIES ON THIS SHEET ARE
BASED ON ASTM E1300-02/04 (3 SEC. GUSTS)
AND FLORIDA BUILDING COMMISSION
DECLARATORY STATEMENT DCA05-DEC-219



GLAZING OPTIONS

* NO. IN PARENTHESIS INDICATE
NO. OF ANCHORS PER JAMB.



TYPICAL ELEVATION
TESTED UNIT

Engr. DR. HUMAYOUN FAROOQ
STRUCTURES
FLA. PE # 116557
C.A.N. 3538

NOV 06 2008

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 08-1210-02
Expiration Date 02-19-2014
By *[Signature]*
Miami Dade Product Control
Division


af c
AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP-ANL W03-95IWS

SERIES 1072 ALUM SINGLE HUNG WINDOW (S.M.I.)
INNOVATIVE WINDOW CONCEPTS, LLC
1801 CORPORATE DRIVE
BOYNTON BEACH, FL. 33426
TEL (561) 493-2303 FAX (561) 493-2302

no	date	description
A	01.13.04	NO CHANGE THIS SHEET
B	09.06.05	CHARTS REV.
C	02.01.06	REV. PER BCCO COMMENTS
D	10.19.06	NOTE REV.
E	10.24.08	UPDATED FOR 2007 FBC

date: 10-20-03
scale: 1/2"=1'-0"
dr. by: HAMID
chk. by:

drawing no. **W03-95**
sheet 2 of 5



WOOD BUCKS AND METAL STRUCTURE NOT BY I.W.C. MUST SUSTAIN LOADS IMPOSED BY GLAZING SYSTEM AND TRANSFER THEM TO THE BUILDING STRUCTURE.

TYPICAL ANCHORS: SEE ELEV. FOR SPACING

1/4" DIA. ULTRACON BY 'ELCO' ($F_u=177$ KSI, $F_y=155$ KSI)

INTO 2BY WOOD BUCKS OR WOOD STRUCTURES

1-1/2" MIN. PENETRATION INTO WOOD

THRU 1BY BUCKS INTO CONC. OR MASONRY

1-1/4" MIN. EMBED INTO CONC. OR MASONRY

DIRECTLY INTO CONC. OR MASONRY

1-1/4" MIN. EMBED INTO CONC. OR MASONRY

#14 SMS OR SELF DRILLING SCREWS (GRADE 2 CRS)

INTO METAL STRUCTURES

STEEL : 12 GA. MIN. ($F_y = 36$ KSI MIN.)

ALUMINUM : 1/8" THK. MIN. (6063-T5 MIN.)

(STEEL IN CONTACT WITH ALUMINUM TO BE PLATED OR PAINTED)

#12 SMS OR SELF DRILLING SCREWS

INTO MIAMI-DADE COUNTY APPROVED MULLIONS (MIN. THK. = .090")
(NO SHIM SPACE)

TYPICAL EDGE DISTANCE

INTO CONCRETE AND MASONRY = 2-1/2" MIN.

INTO WOOD STRUCTURE = 1" MIN.

INTO METAL STRUCTURE = 3/4" MIN.

CONCRETE $f'_c = 3000$ PSI MIN.

MASONRY $f'_m = 1500$ PSI MIN.

SEALANT:

ALL JOINTS AND FRAME CONNECTIONS SEALED WITH SCHNEE MOREHEAD SEAM SEALER SM5504.

Engr. DR. HUMAYUN, FAROOQ
STRUCTURES
FLA. PE # 10557
C.A.N. 3538

NOV 06 2008

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 08-1210-02
Registration Date 02-19-2014

By *Jim Harris*
Miami Dade Product Control
Division




af c
AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP-ANL\W03-95IWS

SERIES 1072 ALUM SINGLE HUNG WINDOW (S.M.I.)
INNOVATIVE WINDOW CONCEPTS, LLC
1801 CORPORATE DRIVE
BOYNTON BEACH, FL. 33426
TEL. (561) 493-2303 FAX. (561) 493-2302

no	date	by	description
A	01.13.04		NO CHANGE THIS SHEET
B	09.06.05		ANCHORS REV.
C	02.01.06		REV. PER BCCO COMMENTS
D	10.19.06		EDGE DIST. ADDED
E	10.24.08		UPDATED FOR 2007 FBC

date: 10-20-03
scale: 1/2" = 1"
dr. by: HAMID
chk. by:

drawing no.
W03-95
sheet 3 of 5



ITEM NO.	PART NO.	QUANTITY	DESCRIPTION	MATERIAL	MANF./SUPPLIER/REMARKS
1	021-029	1	FRAME HEAD	6063-T5	ARCH ALUM.
2	021-002	1	FRAME SILL	6063-T5	ARCH ALUM.
3	021-005	2	FRAME JAMB	6063-T6	ARCH ALUM.
4	022-007	1	MTG. RAIL	6063-T5	ARCH ALUM.
6	022-004	1	VENT TOP RAIL	6063-T5	ARCH ALUM.
7	022-001	1	VENT BOTTTOM RAIL	6063-T5	ARCH ALUM.
8	021-003	2	VENT SIDE RAIL	6063-T5	ARCH ALUM.
18	021-011	4/ LITE	GLAZING BEAD	6063-T5	ARCH ALUM.
23	021-008	2/ VENT	SNAP LATCH (2 @ 3" LG)	6063-T5	ARCH ALUM.
24	025-000	2	ULTRA LIFT BALANCE		CALOWELL MFG
24A	024-000	2	BLOCK & TACKLE BALANCE		BSI
25	006-001	2	SPRING	ST/ST	IND. SPRING
26	004-005	-	UEK BRACKET	STEEL	CALOWELL MFG
27	010-001	-	SASH STOP	RIGID VINYL	MASTER TOOL
28	004-002	-	SWEEP LOCK @ 7" FROM ENDS	METAL	SULLIVAN & ASSOC.
29	016-001	AS REQD.	FIN SEAL	WOOL PILE	ULTRA FAB
30	023-001	-	FILLED BULB VINYL		AMESBURY
31	015-009	-	CHIMNEY PLUG	CLOSED CELL	FRANK LOWE RUBBR
33	008-014	AS REQD.	#8X1 PPH SMS	ST/ST	
34	008-031	2/ END	#10X1 PPH SMS	ST/ST	
37	012-001	-	SEAM SEALER SM5504	ACRYLIC	SCHNEE MOREHEAD
39	008-010	-	#8X1/2 UCFPH SMS	ST/ST	
40	008-017	-	#8X1 1/4 FHPH SMS	ST/ST	
42	015-001	AS REQD.	BULB VYNIL	VINYL	MASTER TOOL
45	015-006	-	0.150 SPACER	VINYL	FRANK LOWE RUBBR
46	012-004	-	DOW 1199	SILICONE	DOW CORNING
49	010-010	-	SASH GUIDE TOP	RIGID PVB	M & M PLASTICS
50	010-011	-	SASH GUIDE BOT	RIGID PVB	M & M PLASTICS
51	008-002	-	#6X1/2 FHPH SMS	ST/ST	
55	003-001	AS REQD.	ROLL FORM SCREEN FRAME	ALUMINUM	FLORIDA SCREEN

Engr. DR. HUMAYOUN FAROOQ
STRUCTURES
FLA. PE # 18567
C.A.N. 3538

NOV 06 2008

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 08-1210-02
Expiration Date 02-19-2014

Dr. by: HAVID
chk. by:

afC

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP-ANL W03-95IWS


SERIES 1072 ALUM SINGLE HUNG WINDOW (S.M.I.)

INNOVATIVE WINDOW CONCEPTS, LLC
1801 CORPORATE DRIVE
BOYNTON BEACH, FL. 33426
TEL. (561) 493-2303 FAX. (561) 493-2302


revisions:	no.	date	by	description
	A	01.13.04		NO CHANGE THIS SHEET
	B	09.06.05		NO CHANGE THIS SHEET
	C	02.01.06		REV. PER BCCO COMMENTS
	D	10.19.06		NO CHANGE THIS SHEET
	E	10.24.08		UPDATED FOR 2007 FBC

date: 10-20-03
scale: 1/2" = 1"
dr. by: HAVID
chk. by:


drawing no.
W03-95
sheet 4 of 5




① FRAME HEAD




④ FIXED MEETING RAIL




③ FRAME JAMB




⑥ VENT TOP RAIL




② FRAME SILL




⑦ VENT BOTTOM RAIL




②③ LATCH



⑧ VENT SIDE RAIL



⑱ GLAZING BEAD



VENT TOP CORNER

VENT BOTTOM CORNER

FRAME CORNERS

Engr. DR. HUMAYOUN FAROOQ
STRUCTURES
FLA. PE # 16567
C.A.N. 3538

NOV 06 2008

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 08-1210-02
Expiration Date 02-19-2014
By *Jim Harris*
Miami Dade Product Control
Division

af c
AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP-ANL \ W03-95IWS

SERIES 1072 ALUM SINGLE HUNG WINDOW (S.M.I.)
INNOVATIVE WINDOW CONCEPTS, LLC
1801 CORPORATE DRIVE
BOYNTON BEACH, FL. 33426
TEL (561) 493-2303 FAX. (561) 493-2302

NO	DATE	BY	DESCRIPTION
A	01.13.04	REV. PER BCCO COMMENTS	
B	09.06.05	NO CHANGE THIS SHEET	
C	02.01.06	NO CHANGE THIS SHEET	
D	10.19.06	NO CHANGE THIS SHEET	
E	10.24.08	UPDATED FOR 2007 FBC	

date: 10-20-03
scale: 1/2" = 1"
dr. by: HAMID
chk. by:

drawing no.
W03-95
sheet 5 of 5