



MIAMI-DADE COUNTY
BUILDING CODE COMPLIANCE OFFICE (BCCO)
PRODUCT CONTROL DIVISION

MIAMI-DADE COUNTY, FLORIDA
METRO-DADE FLAGLER BUILDING
140 WEST FLAGLER STREET, SUITE 1603
MIAMI, FLORIDA 33130-1563
(305) 375-2901 FAX (305) 372-6339

NOTICE OF ACCEPTANCE (NOA)

www.miamidade.gov/buildingcode

AWP, LLC
8130 NW 74th Avenue
Miami, FL 33166

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed by Miami-Dade County Product Control Division and accepted by the Board of Rules and Appeals (BORA) to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Division (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. BORA reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Division that this product or material fails to meet the requirements of the applicable building code. This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Series 800 Aluminum Awning Window

APPROVAL DOCUMENT: Drawing No. **W98-21**, titled "Series 800 Alum. Awning Window (ND)", sheets 1 through 4 of 4, dated 03/03/98 with revision E dated 02/20/09, prepared by Al-Farooq Corporation, signed and sealed by Humayoun Farooq, P.E., bearing the Miami-Dade County Product Control Revision stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Division.

MISSILE IMPACT RATING: None

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official. This NOA revises **NOA # 07-0205.10** and consists of this page 1 and evidence pages E-1 and E-2, as well as approval document mentioned above.

The submitted documentation was reviewed by **Fitz A. Harris, P.E.**

Fitz A. Harris
 4/15/09



NOA No. 09-0316.07
Expiration Date: September 17, 2011
Approval Date: May 6, 2009
 Page 1

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

A. DRAWINGS

1. Manufacturer's die drawings and sections.
2. Drawing No **W98-21**, Sheets 1 through 4 of 4, titled "Series 800 Aluminum Awning Window (NI)", prepared by Al-Farooq Corporation, dated 03/03/98 with revision E dated 02/20/09, signed and sealed by Humayoun Farooq, P.E.

B. TESTS

1. Test reports on 1) Air Infiltration Test, per FBC, TAS 202-94
2) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
3) Water Resistance Test, per FBC, TAS 202-94
4) Large Missile Impact Test per FBC, TAS 201-94
5) Cyclic Wind Pressure Loading per FBC, TAS 203-94
6) Forced Entry Test, per FBC 2411 3.2.1, TAS 202-94
along with marked-up drawings and installation diagram of a series 800 aluminum awning window, prepared by Fenestration Testing Laboratory, Inc., Test Report No. **FTL-5099**, dated 11/24/06, signed and sealed by Edmundo Largaespada, P.E.
2. Addendum letter for test report **FTL-5099** referenced above dated December 22, 2006, signed by Carlos S. Rionda, P.E.
3. Test report on: 1) Air Infiltration Test, per PA 202-94
2) Uniform Static Air Pressure Test, Loading per PA 202-94
3) Water Resistance Test, per PA 202-94
4) Forced Entry Test, per SFBC 3603.2 (b) and PA 202-94
along with marked-up drawings and installation diagram of an aluminum awning window, prepared by Fenestration Testing Laboratory, Inc., Test Report No. **FTL-1827**, dated 12/30/97, signed and sealed by Gilbert Diamond, P.E.
4. Addendum letter for test report **FTL-1827** referenced above dated August 17, 1998, signed by Mr. Manny Sanchez.
5. Addendum letter for test report **FTL-1827** referenced above dated August 25, 1998, signed and sealed by Mr. Gilbert Diamond, P.E..

C. CALCULATIONS

1. Revised anchor calculations and structural analysis, complying with FBC-2007, prepared by Al-Farooq Corporation, dated February 24, 2009, signed and sealed by Humayoun Farooq, P.E.
2. Anchor verification calculations and structural analysis, complying with FBC-2004, prepared by Al-Farooq Corporation, dated June 24, 2006, signed and sealed by Humayoun Farooq, P.E.

Complies with ASTM E1300-98/02



Fitz A. Harris, P.E.

Product Control Examiner

NOA No. 09-0316-07

Expiration Date: September 17, 2011

Approval Date: May 6, 2009

AWP,LLC

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

3. Comparative analysis and anchor calculations, prepared by Al-Farooq Corporation, dated March 11, 1998, revised on August 23 and 26, 1998, signed and sealed by Humayoun Farooq, P.E.

D. QUALITY ASSURANCE

1. Miami Dade Building Code Compliance Office (BCCO).

E. MATERIAL CERTIFICATIONS

1. None.

F. STATEMENTS

1. Statement letter of conformance, dated February 24, 2009, signed by Dr. Humayoun Farooq, P.E.
2. Letter of Compliance, dated February 24, 2009, signed by Dr. Humayoun Farooq, P.E.
3. Letter from AWP, LLC, dated 03/10/09, requesting a revision to update to the FBC2007 and company name, signed by Mr. Roberto Perez, AWP, LLC.
4. Laboratory compliance letter for Test Report no. FTL- 5099 issued by Fenestration Testing Laboratory, Inc., dated May 10, 2007, signed and sealed by Carlos Rionda, P.E.

G. OTHERS

1. None.



Fitz A. Harris, P.E.


Product Control Examiner

NOA No. 09-0316.07

Expiration Date: September 17, 2011

Approval Date: May 6, 2009

DESIGN LOAD CAPACITY - PSF							
WINDOW DIMS.		NUMBER OF VENTS	NUMBER OF ANCHORS/JAMB	1/8" DSB ANN. GLASS		3/16" ANN. GLASS	
WIDTH	HEIGHT			EXT.(+)	1NT.(-)	EXT.(+)	1NT.(-)
19-1/8"	26"	2	2	63.3	75.0	-	-
26-1/2"		2	2	63.3	75.0	-	-
37"		2	2	63.3	71.3	-	-
53-1/8"		2	2	37.0	37.0	49.6	49.6
19-1/8"	38-3/8"	3	3	63.3	75.0	-	-
26-1/2"		3	3	63.3	75.0	-	-
37"		3	3	63.3	72.4	-	-
53-1/8"		3	3	37.0	37.0	50.1	50.1
19-1/8"	50-5/8"	4	4	63.3	75.0	-	-
26-1/2"		4	4	63.3	75.0	-	-
37"		4	4	63.3	73.2	-	-
53-1/8"		4	4	37.0	37.0	49.8	49.8
19-1/8"	63"	5	5	63.3	75.0	-	-
26-1/2"		5	5	63.3	75.0	-	-
37"		5	5	63.3	73.5	-	-
53-1/8"		5	5	37.0	37.0	49.5	49.5
19-1/8"	74-1/4"	6	5	63.3	75.0	-	-
26-1/2"		6	5	63.3	75.0	-	-
37"		6	5	63.3	74.9	-	-
53-1/8"		6	5	37.0	37.0	50.1	50.0



SERIES-800 ALUMINUM AWNING WINDOW

DESIGN LOAD RATINGS FOR THESE WINDOWS TO BE AS PER CHARTS SHOWN ABOVE.

APPROVAL APPLIES TO SINGLE AWNING WINDOWS, ALSO COMBINATIONS OF AWNING/AWNING OR AWNING WITH OTHER WINDOW TYPES IN MODULES OF TWO OR MORE WINDOWS USING MIAMI-DADE COUNTY APPROVED MULLIONS IN BETWEEN. LOWER DESIGN PRESSURE FROM WINDOWS OR MULLION APPROVAL WILL APPLY TO ENTIRE SYSTEM.

THIS PRODUCT HAS BEEN DESIGNED AND TESTED TO COMPLY WITH THE REQUIREMENTS OF THE FLORIDA BUILDING CODE 2004/2007 EDITION INCLUDING HIGH VELOCITY HURRICANE ZONE (HVHZ).


WOOD BUCKS BY OTHERS, MUST BE ANCHORED PROPERLY TO TRANSFER LOADS TO THE STRUCTURE.

ANCHORS SHALL BE AS LISTED, SPACED AS SHOWN ON DETAILS, ANCHORS EMBEDMENT TO BASE MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO.

ANCHORING OR LOADING CONDITIONS NOT SHOWN IN THESE DETAILS ARE NOT PART OF THIS APPROVAL.

A LOAD DURATION INCREASE IS USED IN DESIGN OF ANCHORS INTO WOOD ONLY.

MATERIALS INCLUDING BUT NOT LIMITED TO STEEL/METAL SCREWS, THAT COME INTO CONTACT WITH OTHER DISSIMILAR MATERIALS SHALL MEET THE REQUIREMENTS OF 2004/2007 FLORIDA BLDG. CODE SECTION 2003.8.4.



VENT TOP/BOTTOM

VENT JAMB

EXTERIOR GLAZED WITH ROLL FORMED ALUMINUM GLAZING BEAD AND 'GE 1000 SILICONE'. ('SCHNEE MOREHEAD 5555' GLAZING COMPOUND OPTIONAL)

GLAZING DETAIL

NOTE: GLASS CAPACITIES ON THIS SHEET ARE BASED ON ASTM E1300-02/04 (3 SEC. GUSTS) AND FLORIDA BUILDING COMMISSION DECLARATORY STATEMENT DCA05-DEC-219

WINDOWS NOT RATED FOR IMPACT. INSTALLATION OF THIS PRODUCT IN THE HVHZ AREA REQUIRES THE USE OF APPROVED SHUTTERS OR EXTERNAL PROTECTION DEVICES COMPLYING WITH HVHZ REQUIREMENTS. INSTALLATION OF THIS SYSTEM OUTSIDE THE HVHZ AREA SHALL MEET THE APPLICABLE REQUIREMENTS FOR WIND BORNE DEBRIS PROTECTION.

**MONOLITHIC GLASS
NON IMPACT**

Engr: DR. HUMAYQUN FAROOQ
STRUCTURES
FLA. PE # 16557
C.A.N. 3538
MAR 05 2009

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 09-0316.09
Expiration Date 9-17-2011

By *John Harris*
Miami Dade Product Control
Division

af c
AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP - ANL \ W98 - 21AMP

SERIES-800 ALUM AWNING WINDOW (N.I.)
AWP, LLC.
8130 N.W. 74TH AVE.
MEDLEY, FL. 33166
TEL. (305) 887-2646 FAX (305) 883-1309



no	date	description
A	8.25.98	GENERAL REVISION
B	05.31.01	UPGRADED TO CODE REQUIREMENTS
C	06.24.06	UPDATED FOR 2004 FBC
D	05.15.07	REV. PER BCC COMMENTS
E	02.20.09	UPDATED FOR 2007 FBC

date: 03-03-98
scale: 1/2" = 1'-0"
dr. by: HAMID
chk. by:

drawing no.
W98-21
sheet 1 of 4

revisions:	no	date	by	description
	C	06.24.06		UPDATED FOR 2004 FBC
	D	05.15.07		NO CHANGE THIS SHEET
	E	02.20.09		UPDATED FOR 2007 FBC

date:	03-03-98
scale:	1/2" = 1"
dr. by:	HAMID
chk. by:	



TYPICAL ANCHORS: SEE ELEV. FOR SPACING

1/4" DIA. TAPCONS BY 'ITW'

1/4" DIA. ULTRACON BY 'ELCO' (Fu=177 KSI, Fy=155 KSI)

INTO 2BY WOOD BUCKS OR WOOD STRUCTURES
 1-3/8" MIN. PENETRATION INTO WOOD

THRU 1BY BUCKS INTO CONC. OR MASONRY
 1-1/4" MIN. EMBED INTO CONC. OR MASONRY

DIRECTLY INTO CONC. OR MASONRY
 1-1/4" MIN. EMBED INTO CONC. OR MASONRY

#14 SMS OR SELF DRILLING SCREWS (GRADE 2 CRS)

INTO METAL STRUCTURES
 STEEL : 12 GA. MIN. (Fy = 36 KSI MIN.)
 ALUMINUM : 1/8" THK. MIN. (6063-T5 MIN.)
 (STEEL IN CONTACT WITH ALUMINUM TO BE PLATED OR PAINTED)

#10 SMS OR SELF DRILLING SCREWS

INTO MIAMI-DADE COUNTY APPROVED MULLIONS (MIN. THK. = .090")
 (NO SHIM SPACE)

TYPICAL EDGE DISTANCE

INTO CONCRETE AND MASONRY = 1-1/4" MIN.
 INTO WOOD STRUCTURE = 1/2" MIN.
 INTO METAL STRUCTURE = 1/2" MIN.

CONCRETE f'c = 3000 PSI MIN.
 MASONRY f'm = 2000 PSI MIN.

SEALANTS:




FRAME CORNERS AND VENT CORNER SEAMS TO BE SEALED WITH 'SCHNEE MOREHEAD 5504' SEALANT.

Engr. DR. HUMAYOON FAROOQ
 STRUCTURES
 FLA. PE # 16557
 C.A.N. 3538

MAR 05 2009

PRODUCT REVISED
 as complying with the Florida
 Building Code
 Acceptance No. 09-0316-07
 Expiration Date 9-17-2011



By *[Signature]*
 Miami Dade Product Control
 Division



VENT CORNER ASSEMBLY

FRAME CORNER ASSEMBLY

FRAME AND VENTS ARE ASSEMBLED USING STAKED MORTISE AND TENON FABRICATION



Engr: DR. HUMAYOON FAROOQ
STRUCTURES
FLA. PE # 18557
C.A.N. 3538

MAR 05 2009

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 09-0316-07
Expiration Date 9-17-2011

By *Jim Harris*
Miami Dade Product Control
Division

af c
AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP - ANL \ W98 - 21AWP


SERIES-800 ALUM AWNING WINDOW (N.I.)
AWP, LLC.
8130 N.W. 74TH AVE.
MEDLEY, FL. 33166
TEL. (305) 887-2646 FAX (305) 883-1309

revisions:	no	date	by	description
	C	06.24.06		UPDATED FOR 2004 FBC
	D	05.15.07		NO CHANGE THIS SHEET
	E	02.20.09		UPDATED FOR 2007 FBC


date: 03-03-98
scale: 1/2" = 1"
dr. by: HAMID
chk. by:

drawing no.
W98-21


sheet 3 of 4




FRAME HEAD




VENT TOP




CENTER & TOP VENT BOTTOM




BOTTOM VENT BOTTOM



FRAME SILL



FRAME JAMB



VENT JAMB

ITEM #	PART #	QUANTITY	DESCRIPTION	MATERIAL	MANF./SUPPLIER
1	YE-5	1	FRAME HEAD	ALUM. (6063-T5)	TIFTON OR EQUAL
2	YE-1	1/VENT	VENT TOP	ALUM. (6063-T5)	TIFTON OR EQUAL
3	YH-818	1/VENT	BULB WEATHERSTRIPPING (.155 X .265)	VINYL	WIBORG OR EQUAL
4	YH-817	1	FRAME HEAD WEATHERSTRIPPING (.150 X .200)	VINYL	WIBORG OR EQUAL
5	-	AS REQD.	GLAZING BEAD	ROLL FORMED ALUM.	FLORIDA SCREEN
6	YE-2	1/VENT	CENTER & TOP VENT BOTTOM	ALUM. (6063-T5)	TIFTON OR EQUAL
7	YE-14	1	BOTTOM VENT BOTTOM	ALUM. (6063-T5)	TIFTON OR EQUAL
8	YE-4	1	FRAME SILL	ALUM. (6063-T5)	TIFTON OR EQUAL
9	YE-3	2/VENT	VENT JAMB	ALUM. (6063-T5)	TIFTON OR EQUAL
10	YE-18	2/VENT	VENT HINGE	ALUM. (6063-T5)	YALE OGRON FAB.
11	YH-819	2/VENT	VENT LOCKING PIN	ALUM.	PAN-AMERICAN
12	YE-8	2/VENT	HINGE LINK	ALUM. (6063-T6)	YALE OGRON FAB.
13	YH-811	1/HINGE	HINGE LINK RIVET	ALUM.	PAN-AMERICAN
14	YH-809	2/VENT	SLIDE BAR RETAINER	NYLON	M & M PLASTICS
15	YE-10	2	FRAME JAMB	ALUM. (6063-T5)	TIFTON OR EQUAL
16	YE-6	1/JAMB	SLIDE BAR	ALUM. (6063-T6)	YALE OGRON FAB.
17	YH-806	2/WINDOW	CONNECTING LINK RIVET	ALUMINUM	PAN-AMERICAN
18	YH-805	AS REQD.	'E' RING	ARC STEEL	INTERSTATE SCREW
19	YH-810	2/VENT	CAM LOCK	ZINC DIE CAST	SOUTHERN DIE CAST
20	YE-59	1/BAR	CONNECTING LINK ARM	ALUM. (6063-T5)	YALE OGRON FAB.
21	YH-808	1/BAR	SLIDE BAR BOTTOM PIN	ALUMINUM	PAN-AMERICAN
22	YH-815	1	ATW OFFSET ANGLE OPERATOR (LH OR RH)	ZINC DIE CAST	SOUTHERN DIE CAST
23	YH-803	2	CROSS SHAFT ARM	ZINC DIE CAST	SOUTHERN DIE CAST
24	YH-801	2	CROSS SHAFT BEARING	NYLON	M & M PLASTICS
25	YH-826	1	CROSS SHAFT	STEEL	GALVANIZED
26	YF-6	AS REQD.	SCREW # 10 X 5/16"	PLATED STEEL	INTERSTATE SCREW
27	YH-804	1/ARM	CROSS SHAFT ARM PIN	ALUMINUM	PAN-AMERICAN
28	YH-820	2/VENT	SLIDE BAR PIN-UPPER	ALUMINUM	PAN-AMERICAN
29	YH-807	2/VENT	SLIDE BAR RIVET	ALUMINUM	PAN-AMERICAN
30	YH-821	-	SCREEN SWIVEL CLIP	ALUMINUM	-
31	YH-816	-	SCREEN CLIP RIVET	ALUMINUM	-
32	YH-814	1/LOCK	CAM LOCK RIVET	ALUMINUM	PAN-AMERICAN
33	YH-813	2/HINGE	VENT HINGE RIVET	ALUMINUM	PAN-AMERICAN
34	YH-812	AS REQD.	HINGE LINK RIVET BUSHING	NYLON	M & M PLASTICS

af c
AL-FAROOQ CORPORATION
 ENGINEERS & PRODUCT DEVELOPMENT
 1235 S.W. 87 AVE
 MIAMI, FLORIDA 33174
 TEL. (305) 264-8100 FAX. (305) 262-6978
 COMP-ANL W98-21 AWP

SERIES-800 ALUM AWNING WINDOW (N.I.)
 AWP, LLC.
 8130 N.W. 74TH AVE.
 MEDLEY, FL. 33166
 TEL. (305) 887-2646 FAX (305) 883-1309

no	date	by	description
C	06.24.06		UPDATED FOR 2004 FBC
D	05.15.07		NO CHANGE THIS SHEET
E	02.20.09		UPDATED FOR 2007 FBC

Engr: DR. HUMAYOON FAROOQ
 STRUCTURES
 FLA. PE # 16557
 C.A.N. 3538
 MAR 05 2009

PRODUCT REVISED
 as complying with the Florida
 Building Code
 Acceptance No 09-0316-07
 Expiration Date 9-17-2011
 By: *[Signature]*
 Miami Dade Product Contr.

date: 03-03-98
 scale: 1/2" = 1"
 dr. by: HAMID
 chk. by:
 drawing no.
W98-21
 sheet 4 of 4