MIAMI-DADE

BUILDING CODE COMPLIANCE OFFICE (BCCO)
PRODUCT CONTROL DIVISION

MIAMI-DADE COUNTY, FLORIDA
METRO-DADE FLAGLER BUILDING
140 WEST FLAGLER STREET, SUITE 1603
MIAMI, FLORIDA 33130-1563
(305) 375-2901 FAX (305) 375-2908

NOTICE OF ACCEPTANCE (NOA)

Siplast, Inc.
1111 Highway 67 South
Arkadelphia, AR 71923

SCOPE:
This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed by Miami-Dade County Product Control Division and accepted by the Board of Rules and Appeals (BORA) to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Division (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. BORA reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Division that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone of the Florida Building Code.

DESCRIPTION: Siplast Liquid Applied Roofing Systems over Concrete Decks

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA consists of pages 1 through 15.
The submitted documentation was reviewed by Jorge L. Acebo

MIAMI-DADE COUNTY APPROVED

ROOFING ASSEMBLY APPROVAL

Category:	Roofing
Sub-Category:	Liquid Applied Roof Sytems
Deck Type:	Concrete
Material:	PMMA
Maximum Design Pressure	**-495 psf**

TABLE 1
TRADE NAMES OF PRODUCTS MANUFACTURED OR LABELED BY APPLICANT:

Product	Dimensions	Test Specification	Product Description
Parapro Liquid Applied Membrane	20-kg Drums	Proprietary	A liquid applied reinforced PMMA membrane system.
Parapro Roof Membrane Resin	20-kg Drums	Proprietary	Multi-component PMMA resin.
Pro Fleece	12"x 16.5' roll 12"x 82' roll 25"x 164' roll 41"x 164' roll	Proprietary	Non-woven, needle punched, polyester fabric reinforcement.
Pro Primer R Resin	5-kg & 10-kg Drums	Proprietary	PMMA primer component for use over BUR, modified bitumen or other soft substrates.
Pro Primer W Resin	5-kg & 10-kg Drums	Proprietary	PMMA primer component for use over wood, concrete or other hard substrates.
Pro Primer T Resin	5-kg & 10-kg Drums	Proprietary	PMMA primer component for use over wood, concrete or other hard substrates.
Pro Catalyst Powder	Box of 10 3.2oz bags	Proprietary	Reactive agent for use during priming and membrane application.
Pro Clear Finish Resin	5-kg & 10-kg Drums	Proprietary	Clear, multi-component, flexible PMMA resin.
Pro Color Finish Resin	5-kg & 10-kg Drums	Proprietary	Color pigmented, multi component, flexible PMMA.
Paradiene 20	3.28' x 50'	ASTM D6163	Asphalt elastomer sheet with random fiberglass mat reinforcement for use as a base ply.
Paradiene 20 HT	3.28' x 50'	ASTM D6163	Asphalt elastomer sheet with fiberglass scrim reinforcement for use as a base ply.
Paradiene 20 TS	3.28' x 33.5'	ASTM D6163	High performance, semi-adhered SBS modified bitumen with random fiberglass mat reinforcement used as a base ply.
Paradiene 20 EG	3.28' x 33.5'	ASTM D6163	Heavy duty asphalt elastomer sheet with fiberglass scrim reinforcement for use as a base ply.

Product	Dimensions	Test Specification	Product Description
Paradiene 20 HV	3.28' x 33.5'	ASTM D6163	Heavy duty asphalt elastomer sheet with random fiberglass mat reinforcement for use as a base ply.
Paradiene 20 P	3.28' x 50'	ASTM D6163	Modified bitumen base ply for use in Parapro roof membrane systems.
Paradiene 20 TS P	3.28' x 33.5'	ASTM D 6163	Semi-adhered modified bitumen base ply for use in Parapro systems with heat-activated adhesive strips on the underside.
Paradiene 20 TG	3.28' x 33.5'	ASTM D 6163	Asphalt elastomer sheet with random fiberglass reinforcement for use as a base ply.
Paradiene 20 HT TG	3.28' x 33.5'	ASTM D 6163	Asphalt elastomer sheet with fiberglass scrim reinforcement for use as a base ply.
Paradiene 20 EG TG	3.28' x 33.5';	ASTM D 6163	Heavy duty asphalt elastomer sheet with fiberglass scrim reinforced for use as a base ply.
Paradiene 20 TG P	3.28' x 50'	ASTM D6163	Asphalt elastomer sheet with random fiberglass mat reinforcement for use as a base ply in torch.
Paradiene 20 PR	3.28' x 33.5'	ASTM D6164	Heavy duty asphalt elastomer sheet with fiberglass scrim reinforcement for use as a base ply.
Paradiene 20 SA	3.28' x 33.5'	ASTM D6163	High performance, self adhering SBS modified bitumen with random fiberglass mat reinforcement for use as a base sheet.
Paradiene 20 TS SA	3.28' x 33.5'	ASTM D6163	High performance, self-adhering SBS modified bitumen with random fiberglass mat reinforcement used as a base ply.
Paradiene 20 SA P	3.28' x 33.5'	ASTM D6163	High performance, self adhering SBS modified bitumen with random fiberglass mat reinforcement for use as a base sheet.
Paradiene 20 TS SA P	3.28' x 33.5'	ASTM D6163	High performance, self-adhering SBS modified bitumen with random fiberglass mat reinforcement used as a base ply.
Siplast PA-1125 Primer	5 or 55 gal.	ASTM D 41	Asphaltic primer.
PA-311,311M,311LS Adhesive	5 or 55 gallon	ASTM D4479	Blend of adhesives asphalts and quick drying solvents.
Para-Stik Insulation Adhesive	30 lb pressurized cylinders	N/A	A single component moisture curing urethane foam adhesive.

TABLE 2

APPROVED INSULATIONS:

Product	Description	Manufacturer (With Current NOA)
Paratherm W, Paratherm H	Isocyanurate insulation	Siplast
ACFoam II	Isocyanurate insulation	Atlas Roofing
H-Shield	Isocyanurate insulation	Hunter Panels
Multi-Max 3, FA-3	Polyisocyanurate foam insulation	Rmax
DensDeck, DensDeck DuraGuard	Water resistant gypsum	G-P Gypsum Corp.
Securock	Water resistant recycled cellulose and synthetic gypsum	USG
DuraBoard	High-density perlite roof insulation	Johns Manville

TABLE 3

APPROVED FASTENERS:

Fastener Number	Product	Description	Dimension	Manufacturer (With Current NOA)
1.	N/A	N/A	N/A	N/A

EVIDENCE SUBMITTED:

Test Agency	Test Identifier	Description	Date
Factory Mutual	3029275 3027962	FM 4470 FM 4470	03/24/08 10/03/06
Trinity|ERD	C8500SC.11.07 S9000.03.09-R1	TAS 117-B / ASTM D6862 Physical Properties G155/D638 ASTM D1929/D2843/D635 TAS 114-D/ TAS 114-J	11/30/07 05/06/09
Momentum Technologies, Inc.	TX31G6A	Physical Properties	08/19/09

APPROVED ASSEMBLIES:

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete or concrete plank

System Type A(1): Insulation adhered with approved asphalt. Subsequent system fully adhered.

All General and System Limitations apply.

One or more layers of any of the following insulations:

Insulation Base Layer:	**Insulation Fasteners Table 3**	**Fastener Density/ft²**
AC Foam II, Paratherm W Minimum: 1.5" thick	N/A	N/A

Insulation Top Layer:	**Insulation Fasteners Table 3**	**Fastener Density/ft²**
Dens-Deck, Securock Minimum ½" thick	N/A	N/A

Note: Concrete deck shall be primed with ASTM D 41 asphalt primer and allowed to dry prior to application of base insulation. All insulation shall be adhered in full mopping of approved asphalt within the EVT range and applied at a rate of 20-40 lbs/100 ft^2. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the polyisocyanurate side facing down.

Primer: Apply Pro Primer W Resin to DensDeck at a minimum rate of 0.082 lb/ft^2.

Membrane: Base coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.42 lb/ft² onto the primer; followed by one ply of Pro Fleece laid in the wet base coat; followed by a top coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.27 lb/ft² onto the embedded Pro Fleece.

Maximum Design Pressure: **-262.5 psf.** (See General Limitation #9)

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete or concrete plank

System Type A(2): Insulation adhered with approved adhesive. Subsequent system fully adhered.

All General and System Limitations apply.

(Optional) One or more layers of any of the following insulations:

Insulation Base Layer:	**Insulation Fasteners Table 3**	**Fastener Density/ft²**
AC Foam II, Paratherm W Minimum: 1.5" thick	N/A	N/A

Insulation Top Layer:	**Insulation Fasteners Table 3**	**Fastener Density/ft²**
DensDeck Minimum ½" thick	N/A	N/A

Note: All insulation shall be adhered with Para-Stik Roofing Adhesive or Olybond 500 Adhesive Fastener applied in continuous ¾ to 1 in. ribbons spaced 12 in. o.c. or with Olybond Adhesive Fastener spray applied at a rate of 1.0 gal/square. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the polyisocyanurate side facing down.

Primer: Apply Pro Primer W Resin to DensDeck at a minimum rate of 0.082 lb/ft^2.

Membrane: Base coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.42 lb/ft^2 onto the primer; followed by one ply of Pro Fleece laid in the wet base coat; followed by a top coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.27 lb/ft^2 onto the embedded Pro Fleece.

Maximum Design Pressure: **-120 psf.** (See General Limitation #9)

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete or concrete plank

System Type A(3): Insulation adhered with approved adhesive. Subsequent system fully adhered.

All General and System Limitations apply.

Insulation Base Layer:	**Insulation Fasteners Table 3**	**Fastener Density/ft²**
AC Foam II, Paratherm W Minimum: 1.5" thick	N/A	N/A

Insulation Top Layer:	**Insulation Fasteners Table 3**	**Fastener Density/ft²**
Securock Minimum ¼" thick	N/A	N/A

Note: All insulation shall be adhered with Olybond 500 Adhesive Fastener applied in continuous ¾ to 1 in. ribbons spaced 12 in. o.c. or Olybond Adhesive Fastener spray applied at an application rate of 1 gal/sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the polyisocyanurate side facing down.

Base Sheet: Paradiene 20 TG, Paradiene 20 HT TG or Paradiene 20 EG TG torch adhered to the cover board or Paradiene 20, Paradiene 20 HT, Paradiene 20 P, Paradiene 20 EG or Paradiene 20 HV applied to the cover board in full mopping of approved asphalt within the EVT range and applied at a rate of 20-25 lbs/100 ft2.

Membrane: Base coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.42 lb/ft² onto the base sheet; followed by one ply of Pro Fleece laid in the wet base coat; followed by a top coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.27 lb/ft² onto the embedded Pro Fleece.

Maximum Design Pressure: **-225 psf.** (See General Limitation #9)

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete or concrete plank

System Type A(4): Insulation adhered with approved adhesive. Subsequent system fully adhered.

All General and System Limitations apply.

Insulation Base Layer:	**Insulation Fasteners Table 3**	**Fastener Density/ft²**
AC Foam II, Paratherm W Minimum: 1.5" thick	N/A	N/A

Insulation Top Layer:	**Insulation Fasteners Table 3**	**Fastener Density/ft²**
Securock Minimum ¼" thick	N/A	N/A

Note: All insulation shall be adhered with Para-Stik Roofing Adhesive applied in continuous ¾ to 1 in. ribbons spaced 12 in. o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the polyisocyanurate side facing down.

Base Sheet: Paradiene 20 TG, Paradiene 20 HT TG or Paradiene 20 EG TG torch adhered to the cover board or Paradiene 20, Paradiene 20 HT, Paradiene 20 P, Paradiene 20 EG or Paradiene 20 HV applied to the cover board in full mopping of approved asphalt within the EVT range and applied at a rate of 20-25 lbs/100 ft2.

Membrane: Base coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.42 lb/ft² onto the base sheet; followed by one ply of Pro Fleece laid in the wet base coat; followed by a top coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.27 lb/ft² onto the embedded Pro Fleece.

Maximum Design Pressure: **-285 psf.** (See General Limitation #9)

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete or concrete plank

System Type A(5): Insulation adhered with approved adhesive. Subsequent system fully adhered.

All General and System Limitations apply.

Insulation Base Layer:	**Insulation Fasteners Table 3**	**Fastener Density/ft²**
AC Foam II, Paratherm W Minimum: 1.5" thick	N/A	N/A

Insulation Top Layer:	**Insulation Fasteners Table 3**	**Fastener Density/ft²**
Dens Deck Minimum ¼" thick	N/A	N/A

Note: Concrete deck shall be primed with Siplast PA-1125 Primer, or any ASTM D 41 asphalt primer and allowed to dry prior to application of base insulation. All insulation shall be adhered with Para-Stik Roofing Adhesive or Olybond 500 Adhesive Fastener applied in continuous ¾ to 1 in. ribbons spaced 12 in. o.c. or Olybond Adhesive Fastener spray applied at an application rate of 1 gal/sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the polyisocyanurate side facing down.

Base Sheet: Paradiene 20 TS SA self-adhered to the insulation coverboard.

Membrane: Base coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.42 lb/ft² onto the base sheet; followed by one ply of Pro Fleece laid in the wet base coat; followed by a top coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.27 lb/ft² onto the embedded Pro Fleece.

Maximum Design Pressure: **-112.5 psf** (See General Limitation #9)

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete or concrete plank

System Type A(6): Insulation adhered with approved adhesive. Subsequent system fully adhered.

All General and System Limitations apply.

Insulation Base Layer:	**Insulation Fasteners Table 3**	**Fastener Density/ft²**
H-Shield, Paratherm H Minimum: 1.5" thick	N/A	N/A

Note: Concrete deck shall be primed with Siplast PA-1125 Primer, or any ASTM D 41 asphalt primer and allowed to dry prior to application of base insulation. All insulation shall be adhered with Para-Stik Roofing Adhesive or Olybond 500 Adhesive Fastener applied in continuous ¾ to 1 in. ribbons spaced 12 in. o.c. or Olybond Adhesive Fastener spray applied at an application rate of 1 gal/sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the polyisocyanurate side facing down.

Base Sheet: Paradiene 20 TS SA self-adhered to the insulation coverboard.

Membrane: Base coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.42 lb/ft² onto the base sheet; followed by one ply of Pro Fleece laid in the wet base coat; followed by a top coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.27 lb/ft² onto the embedded Pro Fleece.

Maximum Design Pressure:
-157.5 psf using Para-Stik Roofing Adhesive (See General Limitation #9)
-150 psf using Olybond 500 & Olybond Adhesive (See General Limitation #9)

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete or concrete plank

System Type A(7): Insulation adhered with approved adhesive. Subsequent system fully adhered.

All General and System Limitations apply.

Insulation Base Layer (Optional):	**Insulation Fasteners Table 3**	**Fastener Density/ft²**
Multi-Max 3, Multi-Max FA-3, H-Shield, Paratherm H Minimum: 1.5" thick	N/A	N/A

Insulation Top Layer:	**Insulation Fasteners Table 3**	**Fastener Density/ft²**
DuraBoard Minimum ¾" thick	N/A	N/A

Note: All insulation shall be adhered with Para-Stik Roofing Adhesive or OlyBond 500 Adhesive Fastener applied in continuous ¾ to 1 in. ribbons spaced 12 in. o.c. or OlyBond Adhesive Fastener applied at a rate of 1.0 gal/sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the polyisocyanurate side facing down.

Base Sheet: Paradiene 20, Paradiene 20 HT, Paradiene 20 P, Paradiene 20 EG or Paradiene 20 HV applied to either cover board in full mopping of approved asphalt within the EVT range and applied at a rate of 20-25 lbs/100 ft2.

Membrane: Base coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.42 lb/ft² onto the base sheet; followed by one ply of Pro Fleece laid in the wet base coat; followed by a top coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.27 lb/ft² onto the embedded Pro Fleece.

Maximum Design Pressure: **-112.5 psf** (See General Limitation #9)

Deck Type 3I: Concrete Decks, Insulated

Deck Description: 2500 psi structural concrete or concrete plank

System Type A(8): Insulation adhered with approved adhesive. Subsequent system fully adhered.

All General and System Limitations apply.

Insulation Base Layer (Optional):	**Insulation Fasteners Table 3**	**Fastener Density/ft²**
Multi-Max 3, Multi-Max FA-3, H-Shield, Paratherm H Minimum: 1.5" thick	N/A	N/A

Insulation Top Layer:	**Insulation Fasteners Table 3**	**Fastener Density/ft²**
Dens Deck Minimum ¼" thick	N/A	N/A

Note: All insulation shall be adhered with Para-Stik Roofing Adhesive or OlyBond 500 Adhesive Fastener applied in continuous ¾ to 1 in. ribbons spaced 12 in. o.c. or OlyBond Adhesive Fastener applied at a rate of 1.0 gal/sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate. Composite insulation panels used as a top layer shall be placed with the polyisocyanurate side facing down.

Base Sheet: Paradiene 20 TG, Paradiene 20 HT TG, Paradiene 20 TS, Paradiene 20 TS P or Paradiene 20 EG TG torch adhered to the cover board or Paradiene 20, Paradiene 20 HT, Paradiene 20 P, Paradiene 20 EG or Paradiene 20 HV applied to cover board in full mopping of approved asphalt within the EVT range and applied at a rate of 20-25 lbs/100 ft2.

Membrane: Base coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.42 lb/ft² onto the base sheet; followed by one ply of Pro Fleece laid in the wet base coat; followed by a top coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.27 lb/ft² onto the embedded Pro Fleece.

Maximum Design Pressure: **-157.5 psf** (See General Limitation #9)

Deck Type 3I:	Concrete Decks, Non-Insulated
Deck Description:	2500 psi structural concrete or concrete plank
System Type F(1):	Siplast system applied directly to substrate.

All General and System Limitations apply.

Primer:	(Optional) Apply Pro Primer W Resin to the deck at a minimum rate of 0.082 lb/ft^2.
Membrane:	Base coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.42 lb/ft^2 onto the primer or deck; followed by one ply of Pro Fleece laid in the wet base coat; followed by a top coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.27 lb/ft^2 onto the embedded Pro Fleece.
Maximum Design Pressure:	**-52.5 psf** without primer application. (See General Limitation #9) **-322.5 psf** with primer application. (See General Limitation #9)

Deck Type 3I:	Concrete Decks, Non-Insulated
Deck Description:	2500 psi structural concrete or concrete plank
System Type F(2):	Siplast system applied directly to substrate

All General and System Limitations apply.

Primer:	Concrete deck is primed with Siplast PA-1125 Primer, or any ASTM D41 asphaltic primer, followed by a flood coat of hot asphalt applied at a rate of 20-25 lb/sq.
Base Sheet:	Paradiene 20 base membrane is fully adhered in hot asphalt applied at a rate of 20-25 lb/sq onto the primed deck.
Primer:	Apply Pro Primer R Resin to the base sheet at a minimum rate of 0.082 lb/ft^2.
Membrane:	Base coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.42 lb/ft^2 onto the primer; followed by one ply of Pro Fleece laid in the wet base coat; followed by a top coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.27 lb/ft^2 onto the embedded Pro Fleece.
Maximum Design Pressure:	**-202.5 psf.** (See General Limitation #9)

Deck Type 3I:	Concrete Decks, Non-Insulated
Deck Description:	2500 psi structural concrete or concrete plank
System Type F(3):	Siplast system applied directly to substrate

All General and System Limitations apply.

Primer:	Concrete deck is primed with Siplast PA-1125 Primer, or any ASTM D41 asphaltic primer, followed by a flood coat of hot asphalt applied at a rate of 20-25 lb/sq.
Base Sheet:	Paradiene 20 P base membrane is fully adhered in hot asphalt applied at a rate of 20-25 lb/sq onto the primed deck.
Membrane:	Base coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.42 lb/ft^2 onto the base sheet; followed by one ply of Pro Fleece laid in the wet base coat; followed by a top coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.27 lb/ft^2 onto the embedded Pro Fleece.
Maximum Design Pressure:	**-495 psf.** (See General Limitation #9)

Deck Type 3I:	Concrete Decks, Non-Insulated
Deck Description:	2500 psi structural concrete or concrete plank
System Type F(4):	Siplast system applied directly to substrate

All General and System Limitations apply.

Primer:	Concrete deck is primed with Siplast PA-1125 Primer, or any ASTM D41 asphaltic primer, followed by a flood coat of hot asphalt applied at a rate of 20-25 lb/sq.
Base Sheet:	Paradiene 20 TS P base membrane is torch adhered to primed concrete deck.
Membrane:	Base coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.42 lb/ft^2 onto the base sheet; followed by one ply of Pro Fleece laid in the wet base coat; followed by a top coat of Parapro Roof Membrane Resin roller applied at a minimum rate of 0.27 lb/ft^2 onto the embedded Pro Fleece.
Maximum Design Pressure:	**-442.5 psf.** (See General Limitation #9)

CONCRETE DECK SYSTEM LIMITATIONS:

1. If mechanical attachment to the structural deck through the lightweight insulating concrete is proposed, a field withdrawal resistance testing shall be performed to determine fastener patterns and density. All testing and fastening design shall be in compliance with Testing Application Standard TAS 105 and Roofing Application Standard RAS 117, calculations shall be signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant.

GENERAL LIMITATIONS:

1. Fire classification is not part of this acceptance, refer to a current Approved Roofing Materials Directory for fire ratings of this product.
2. Insulation may be installed in multiple layers. The first layer shall be attached in compliance with Product Control Approval guidelines. All other layers shall be adhered in a full mopping of approved asphalt applied within the EVT range and at a rate of 20-40 lbs./sq., or mechanically attached using the fastening pattern of the top layer
3. All standard panel sizes are acceptable for mechanical attachment. When applied in approved asphalt, panel size shall be 4' x 4' maximum.
4. An overlay and/or recovery board insulation panel is required on all applications over closed cell foam insulations when the base sheet is fully mopped. If no recovery board is used the base sheet shall be applied using spot mopping with approved asphalt, 12" diameter circles, 24" o.c.; or strip mopped 8" ribbons in three rows, one at each sidelap and one down the center of the sheet allowing a continuous area of ventilation. Encircling of the strips is not acceptable. A 6" break shall be placed every 12' in each ribbon to allow cross ventilation. Asphalt application of either system shall be at a minimum rate of 12 lbs./sq. **Note: Spot attached systems shall be limited to a maximum design pressure of -45 psf.**
5. Fastener spacing for insulation attachment is based on a Minimum Characteristic Force (F') value of 275 lbf., as tested in compliance with Testing Application Standard TAS 105. If the fastener value, as field-tested, are below 275 lbf. insulation attachment shall not be acceptable.
6. Fastener spacing for mechanical attachment of anchor/base sheet or membrane attachment is based on a minimum fastener resistance value in conjunction with the maximum design value listed within a specific system. Should the fastener resistance be less than that required, as determined by the Building Official, a revised fastener spacing, prepared, signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant may be submitted. Said revised fastener spacing shall utilize the withdrawal resistance value taken from Testing Application Standards TAS 105 and calculations in compliance with Roofing Application Standard RAS 117.
7. Perimeter and corner areas shall comply with the enhanced uplift pressure requirements of these areas. Fastener densities shall be increased for both insulation and base sheet as calculated in compliance with Roofing Application Standard RAS 117. Calculations prepared, signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant **(When this limitation is specifically referred within this NOA, General Limitation #9 will not be applicable.)**
8. All attachment and sizing of perimeter nailers, metal profile, and/or flashing termination designs shall conform with Roofing Application Standard RAS 111 and applicable wind load requirements.
9. The maximum designed pressure limitation listed shall be applicable to all roof pressure zones (i.e. field, perimeters, and corners). Neither rational analysis, nor extrapolation shall be permitted for enhanced fastening at enhanced pressure zones (i.e. perimeters, extended corners and corners). **(When this limitation is specifically referred within this NOA, General Limitation #7 will not be applicable.)**

END OF THIS ACCEPTANCE