



**BUILDING CODE COMPLIANCE OFFICE (BCCO)  
PRODUCT CONTROL DIVISION**

**MIAMI-DADE COUNTY, FLORIDA  
METRO-DADE FLAGLER BUILDING  
140 WEST FLAGLER STREET, SUITE 1603  
MIAMI, FLORIDA 33130-1563  
(305) 375-2901 FAX (305) 375-2908**

[www.miamiadade.gov/buildingcode](http://www.miamiadade.gov/buildingcode)

**NOTICE OF ACCEPTANCE (NOA)**

**E.S. Windows, LLC  
10653 NE Quaybridge Ct.  
Miami, Fl.33138**

**SCOPE:**

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed by Miami-Dade County Product Control Division and accepted by the Board of Rules and Appeals (BORA) to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Division (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. BORA reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Division that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code, including High Velocity Hurricane Zone of the Florida Building Code.

**DESCRIPTION:** ES Series "V2000" PVC Horizontal Sliding Window

**APPROVAL DOCUMENT:** Drawing No. **W10-27**, titled "Series V2000 PVC Horiz. Sliding WDW (LMI)", sheets 1 through 8 of 8, prepared by Al-Farooq Corporation, dated 04-27-10 and last revised on Nov 11, 2010, signed and sealed by Javad Ahmad, P.E., bearing the Miami-Dade County Product Control approval stamp with the Notice of Acceptance number and approval date by the Miami-Dade County Product Control Division.

**MISSILE IMPACT RATING:** Large and Small Missile Impact

**Limitation:** 1. Fin Frame mount is applicable to wood substrate only.

**LABELING:** Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA consists of this page 1 and evidence page E-1, as well as approval document mentioned above.

The submitted documentation was reviewed by **Ishaq I. Chanda, P.E.**

**NOA No 10-0623.04  
Expiration Date: December 23, 2015  
Approval Date: December 23, 2010**



A  
12/21/10

**NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED**

**A. DRAWINGS**

1. Manufacturer's die drawings and sections.
2. Drawing No. **W10-27**, titled "Series V2000 PVC Horiz. Sliding WDW (LMI)", sheets 1 through 8 of 8, prepared by Al-Farooq Corporation, dated 04-27-10 and last revised on Nov 11, 2010, signed & sealed by Javad Ahmad, P.E.

**B. TESTS** Test reports on

- 1) Air Infiltration Test, per FBC, TAS 202-94
- 2) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94
- 3) Water Resistance Test, per FBC, TAS 202-94
- 4) Large Missile Impact Test, per FBC, TAS 201-94
- 5) Cyclic Wind Pressure Loading, per FBC, TAS 203-94
- 6) Forced Entry Test, per FBC 2411 3.2.1 and TAS 202-94

along with marked-up drawing and installation diagram of Vinyl Horizontal Sliders, prepared by National Certified Testing Laboratory, Inc., No. **NCTL-110-12834-1**, dated 05/09/07 and last revised on 01/25/10, signed and sealed by Harold E. Rupp, P.E.

**C. CALCULATIONS**

1. Anchor verification calculations and structural analysis, prepared by Al Farooq Corporation, dated 06/01/10 and last revised on 11/08/10, signed and sealed by Javad Ahmad, P.E.
2. Glazing complies w/ ASTM E-1300-02 & -04

**D. QUALITY ASSURANCE BY:**

1. Miami-Dade County Building Code Compliance Office (BCCO)

**E. MATERIAL CERTIFICATIONS**

1. Notice of Acceptance No. **05-1208.02** issued to E.I. DuPont DeNemours for "Butacite PVB Interlayer", expiring on 12-11-2010
2. Notice of Acceptance No. **08-0620.09** issued to Thermoplast, Inc. for their "White Rigid PVC", expiring on 07/05/12.

**F. STATEMENTS**

1. Statement letter of conformance and "No financial interest" issued by Al-Farooq Corp., dated 05/27/10, signed and sealed by Javad Ahmad, P.E.
2. Laboratory compliance statements, part of the above referenced test reports.

**G. OTHER**

1. Distribution agreement ES Windows-Energia Solar, S.A. and ES Windows, LLC, dated 10/20/10, signed by Ms Carla G. Torrente and Andres Chamorro respectively.




Ishaq I. Chanda, P.E.

Product Control Examiner


NOA No 10-0623.04

Expiration Date: December 23, 2015


Approval Date: December 23, 2010



**FLANGE FRAMES**



**FLUSH FRAMES**



**FIN FRAMES**

(WOOD SUBSTRATE INSTALLATION ONLY)

**TYPICAL ELEVATIONS**

THESE WINDOWS ARE RATED FOR LARGE & SMALL MISSILE IMPACT. SHUTTERS ARE NOT REQUIRED.

**SERIES V2000 PVC HORIZONTAL SLIDING WINDOW**

DESIGN LOAD RATINGS FOR THESE WINDOWS TO BE AS PER CHARTS SHOWN ON SHEET 2.

APPROVAL APPLIES TO SINGLE UNITS OR SIDE BY SIDE COMBINATIONS OF H.R./H.R. OR HORIZONTAL ROLLING WITH OTHER WINDOW TYPES IN MODULES OF TWO OR MORE WINDOWS USING MIAMI-DADE COUNTY APPROVED CLIPPED MULLIONS IN BETWEEN. LOWER DESIGN PRESSURE FROM WINDOWS OR MULLION APPROVAL WILL APPLY TO ENTIRE SYSTEM.

THIS PRODUCT HAS BEEN DESIGNED AND TESTED TO COMPLY WITH THE REQUIREMENTS OF THE FLORIDA BUILDING CODE 2007 EDITION INCLUDING HIGH VELOCITY HURRICANE ZONE (HVHZ).

WOOD BUCKS BY OTHERS, MUST BE ANCHORED PROPERLY TO TRANSFER LOADS TO THE STRUCTURE.

ANCHORS SHALL BE AS LISTED, SPACED AS SHOWN ON DETAILS, ANCHORS EMBEDMENT TO BASE MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO.

ANCHORING OR LOADING CONDITIONS NOT SHOWN IN THESE DETAILS ARE NOT PART OF THIS APPROVAL.

A LOAD DURATION INCREASE IS USED IN DESIGN OF ANCHORS INTO WOOD ONLY.

MATERIALS INCLUDING BUT NOT LIMITED TO STEEL/METAL SCREWS, THAT COME INTO CONTACT WITH OTHER DISSIMILAR MATERIALS SHALL MEET THE REQUIREMENTS OF 2007 FLORIDA BLDG. CODE SECTION 2003.8.4.

**D.L. OPENING**  
 D.L.O WIDTH = VENT WIDTH - 3.000"  
 D.L.O. HEIGHT = VENT HEIGHT - 2.813"  
 VENT  
 VENT WIDTH = INTERIOR FRAME WIDTH/2 - .750"  
 VENT HEIGHT = INTERIOR FRAME HEIGHT - 3.000"

WINDOWS MUST MEET EGRESS REQUIREMENTS PER FBC AND TO BE REVIEWED BY BLDG OFFICIAL (IF SO REQUIRED).

Approved as complying with the Florida Building Code  
 Date DEC 23, 2010  
 NOA# 10-0623-04  
 Miami Dade Product Control  
 Division  
 By Shag I. Uhande

Engr: JAVAD AHMAD  
 CIVIL  
 FLA. PE # 70592  
 C.A.N. 3538  
 NOV 08 2010

LAMINATED INSULATING GLASS  
 LARGE & SMALL MISSILE IMPACT

**af c**  
**AL-FAROOQ CORPORATION**  
 ENGINEERS & PRODUCT DEVELOPMENT  
 1235 S.W. 87 AVE  
 MIAMI, FLORIDA 33174  
 TEL. (305) 264-8100 FAX. (305) 262-6978  
 COMP-ANL\W10-27ES

SERIES V2000 PVC HORIZ. SLIDING WDW. (L.M.I.)  
**E.S. WINDOWS, LLC**  
 5220 N.W. 72 AVE. BAY #4  
 MIAMI, FL. 33166  
 TEL. (305) 624-7775 FAX. (305) 624-7777

no	date	by	description
A	09.24.10		REV. PER BCCO COMMENTS

date: 04-27-10  
 scale: 1/2" = 1"  
 dr. by: HAMID  
 chk. by:

drawing no.  
**W10-27**

sheet 1 of 8





DESIGN LOAD CAPACITY - PSF (XO OR OX SIZES)				
INTERIOR FRAME DIMENSIONS		A	7/8" OVERALL LAM. INSUL. GLASS	
WIDTH	HEIGHT		EXT.(+)	INT.(-)
26-1/2"	26"	4	50.0	50.0
37"		4	50.0	50.0
53-1/8"		6	50.0	50.0
74"		6	50.0	50.0
26-1/2"	38-3/8"	4	50.0	50.0
37"		4	50.0	50.0
53-1/8"		6	50.0	50.0
74"		6	50.0	50.0
26-1/2"	50-5/8"	4	50.0	50.0
37"		4	50.0	50.0
53-1/8"		6	50.0	50.0
74"		6	50.0	50.0
26-1/2"	63"	4	50.0	50.0
37"		4	50.0	50.0
53-1/8"		6	50.0	50.0
74"		6	45.7	45.7
74"	63"	7	50.0	50.0 *

A = NO. OF ANCHORS PER HEAD & SILL

\* ADDL. ANCHOR REQD. AT MTG. STILE ENDS

DESIGN LOAD CAPACITY - PSF (XO OR OX SIZES)				
INTERIOR FRAME DIMENSIONS		A	7/8" OVERALL LAM. INSUL. GLASS	
WIDTH	HEIGHT		EXT.(+)	INT.(-)
24"	24"	4	50.0	50.0
36"		4	50.0	50.0
48"		5	50.0	50.0
60"		6	50.0	50.0
72"		6	50.0	50.0
24"		36"	4	50.0
36"	4		50.0	50.0
48"	5		50.0	50.0
60"	6		50.0	50.0
72"	6		50.0	50.0
24"	48"		4	50.0
36"		4	50.0	50.0
48"		5	50.0	50.0
60"		6	50.0	50.0
72"		6	50.0	50.0
24"		60"	4	50.0
36"	4		50.0	50.0
48"	5		50.0	50.0
60"	6		50.0	50.0
72"	6		50.0	50.0

A = NO. OF ANCHORS PER HEAD & SILL



Approved as complying with the Florida Building Code  
Date DEC 23, 2010  
NOA# 10-0623-04  
Miami Dade Product Control  
Division  
By J. S. Chan

NOTE:  
GLASS CAPACITIES ON THIS SHEET ARE  
BASED ON ASTM E1300-04 (3 SEC. GUSTS)  
AND FLORIDA BUILDING COMMISSION  
DECLARATORY STATEMENT DCA05-DEC-219

Engr: JAVAD AHMAD  
CIVIL  
FLA. PE # 70592  
C.A.N. 3538  
NOV 08 2010  
*JA*





**af c**  
**AL-FAROOQ CORPORATION**  
ENGINEERS & PRODUCT DEVELOPMENT  
1235 S.W. 87 AVE  
MIAMI, FLORIDA 33174  
TEL. (305) 264-8100 FAX. (305) 262-6978  
COMP-ANL\W10-27ES

SERIES V2000 PVC HORIZ. SLIDING WDW. (L.M.I.)  
**E.S. WINDOWS, LLC**  
5220 N.W. 72 AVE. BAY #4  
MIAMI, FL. 33166  
TEL. (305) 624-7775 FAX. (305) 624-7777

no	date	description	REV. PER BCCO COMMENTS
A	09.24.10		

date: 04-27-10  
scale: 1/2" = 1"  
dr. by: HAMID  
chk. by:

drawing no.  
**W10-27**  
sheet 2 of 8



WOOD BUCKS AND METAL STRUCTURE NOT BY ES WINDOWS MUST SUSTAIN LOADS IMPOSED BY GLAZING SYSTEM AND TRANSFER THEM TO THE BUILDING STRUCTURE.

**WEEPHOLES:**

- W1 = 1/4" X 1" WEEP SLOT AT 3-1/2" FROM EACH END WITH PLASTIC BAFFLE.
- W2 = 3/16" X 1" WEEP SLOT AT 1" FROM EACH END
- W3 = 3/16" X 3/4" WEEP SLOT AT 1-3/4" FROM EACH END

**SEALANT:**

ALL JOINTS AND FRAME CONNECTIONS SEALED WITH SILICONE SEALANT.

**TYPICAL ANCHORS:**

**FLANGE AND FLUSH FRAMES:** SEE ELEV. FOR SPACING

1/4" DIA. TAPCON BY 'ITW' (Fu=120 KSI, Fy=92 KSI)

1/4" DIA. ULTRACON BY 'ELCO' (Fu=177 KSI, Fy=155 KSI)

INTO 2BY WOOD BUCKS OR WOOD STRUCTURES

1-3/8" MIN. PENETRATION INTO WOOD

THRU 1BY BUCKS INTO CONC. OR MASONRY

1-1/4" MIN. EMBED INTO CONC. OR MASONRY

DIRECTLY INTO CONC. OR MASONRY

1-1/4" MIN. EMBED INTO CONC. OR MASONRY

#12 SMS OR SELF DRILLING SCREWS (GRADE 2 CRS)

INTO MIAMI-DADE COUNTY APPROVED MULLIONS (MIN. THK. = 1/8")

INTO METAL STRUCTURES

STEEL : 12 GA. MIN. (Fy = 36 KSI MIN.)

ALUMINUM : 1/8" THK. MIN. (6063-T5 MIN.)

(STEEL IN CONTACT WITH ALUMINUM TO BE PLATED OR PAINTED)

**TYPICAL EDGE DISTANCE**


INTO CONCRETE AND MASONRY = 2" MIN.

INTO WOOD STRUCTURE = 1" MIN.

INTO METAL STRUCTURE = 3/4" MIN.

CONCRETE AT HEAD, SILL OR JAMBS f'c = 3000 PSI MIN.

C-90 HOLLOW/FILLED BLOCK AT JAMBS f'm = 2000 PSI MIN.



Approved as complying with the Florida Building Code  
 Date: DEC 23, 2010  
 NOA# 10-0622.04  
 Miami Dade Product Control  
 Division  
 By: *[Signature]*

Engr: JAVAD AHMAD  
 CIVIL  
 FL PE # 70560  
 NOV 09 2010  
*[Signature]*

**FLANGE FRAMES**


**af c**  
**AL-FAROOQ CORPORATION**  
 ENGINEERS & PRODUCT DEVELOPMENT  
 1235 S.W. 87 AVE  
 MIAMI, FLORIDA 33174  
 TEL. (305) 264-8100 FAX. (305) 262-6978  
 COMP-ANL\W10-27ES

SERIES V2000 PVC HORIZ. SLIDING WDW. (L.M.I.)  
**E.S. WINDOWS, LLC**  
 5220 N.W. 72 AVE. BAY #4  
 MIAMI, FL. 33166  
 TEL. (305) 624-7775 FAX. (305) 624-7777



no	date	description
A	09.24.10	REV. PER BCCO COMMENTS

date: 04-27-10  
 scale: 1/2" = 1"  
 dr. by: HAMID  
 chk. by:


drawing no.  
**W10-27**  
 sheet 3 of 8



FIX. MTG. RAIL INSTALLATION AT HEAD/SILL



Approved as complying with the  
 Florida Building Code  
 Date Dec 23, 2010  
 NOA# 10-0623-04  
 Miami Dade Product Control  
 Division  
 By Chas. L. Han



Engr: JAVAD AHMAD  
 CIVIL  
 FLA. PE # 70592  
 CA # 35776  
 NOV 08 2010

FLANGE FRAMES


**af c**  
**AL-FAROOQ CORPORATION**  
 ENGINEERS & PRODUCT DEVELOPMENT  
 1235 S.W. 87 AVE  
 MIAMI, FLORIDA 33174  
 TEL. (305) 264-8100 FAX. (305) 262-6978  
 COMP - ANL \ W10-27ES

SERIES V2000 PVC HORIZ. SLIDING WDW. (L.M.I.)  
**E.S. WINDOWS, LLC**  
 5220 N.W. 72 AVE. BAY #4  
 MIAMI, FL. 33166  
 TEL. (305) 624-7775 FAX. (305) 624-7777


no	date	by	description
A	09.24.10		REV. PER BCCO COMMENTS

date: 04-27-10  
 scale: 1/2" = 1"  
 dr. by: HAMID  
 chk. by:



drawing no.  
**W10-27**  
 sheet 4 of 8



FLANGE AND FLUSH FRAMES CAN BE USED AT ALL ANCHORAGE CONDITIONS.



MEETING STILES DETAIL  
SEE SHEET 4



MIAMI-DADE COUNTY  
APPROVED CLIPPED MULLION  
& MULLION ANCHORS  
SEE SEPARATE NOA

Approved as complying with the  
Florida Building Code  
Date DEC 23, 2010  
NOA# 10-0623-04  
Miami Dade Product Control  
Division  
By Shag I. Khan

**FLUSH FRAMES**

Engr: JAVAD AHMAD  
CIVIL  
FLA. PE # 70592  
C.A.N. 3538  
  
NOV 08 2010

**af c**  
**AL-FAROOQ CORPORATION**  
ENGINEERS & PRODUCT DEVELOPMENT  
1235 S.W. 87 AVE  
MIAMI, FLORIDA 33174  
TEL. (305) 264-8100 FAX. (305) 262-6978  
COMP-ANL\W10-27ES


SERIES V2000 PVC HORIZ. SLIDING WDW. (L.M.I.)  
**E.S. WINDOWS, LLC**  
5220 N.W. 72 AVE. BAY #4  
MIAMI, FL. 33166  
TEL. (305) 624-7775 FAX. (305) 624-7777

no	date	by	description
A	09.24.10		REV. PER BCCO COMMENTS


date: 04-27-10	scale: 1/2" = 1"	dr. by: HAMID	chk. by:
drawing no. <b>W10-27</b>			
sheet 5 of 8			

ILLUSTRATIVE DTLS. ONLY  
EXT. OR INT. FINISHES  
NOT BY ES WDW.




**TYPICAL ANCHORS:**  
**FIN FRAMES:** SEE ELEV. FOR SPACING

#8 SMS (GRADE 2 CRS)  
INTO 2BY WOOD BUCKS OR WOOD STRUCTURES  
1-3/8" MIN. PENETRATION INTO WOOD  
3/4" MIN. EDGE DISTANCE



(D)  
MEETING STILES DETAIL  
SEE SHEET 4



Approved as complying with the  
Florida Building Code  
Date Dec 23, 2010  
NOA# 10-0623-07  
Miami Dade Product Control  
Division  
By Chas. Chan

Engr: JAVAD AHMAD  
CIVIL  
FLA. PE # 70592  
C.A.N. 3538  
  
NOV 08 2010

FIN FRAMES

**af c**  
**AL-FAROOQ CORPORATION**  
ENGINEERS & PRODUCT DEVELOPMENT  
1235 S.W. 87 AVE  
MIAMI, FLORIDA 33174  
TEL. (305) 264-8100 FAX. (305) 262-6978  
COMP-ANL\W10-27ES

SERIES V2000 PVC HORIZ. SLIDING WDW. (L.M.I.)  
**E.S. WINDOWS, LLC**  
5220 N.W. 72 AVE. BAY #4  
MIAMI, FL. 33166  
TEL. (305) 624-7775 FAX. (305) 624-7777


no.	date	description
A	09.24.10	REV. PER BCCO COMMENTS


date:	04-27-10
scale:	1/2" = 1"
dr. by:	HAMID
chk. by:	


drawing no.	W10-27
sheet	6 of 8




② FLANGE FRAME




②A FLUSH FRAME




②B FIN FRAME




⑦ SILL ADAPTER




① VENT TOP/BOTTOM/SIDE RAIL




③③ VENT REINFORCEMENT




③ SILL COVER




⑨ SASH STOP




④ VENT INTERLOCK STILE




③⑥ VENT INTERLOCK REINF.




① FIXED INTERLOCK STILE




③⑩ FIX. INTERLOCK REINF.



③⑦ EXTENSION BLOCK



⑩ GLAZING BEAD



⑧ GLAZING BEAD

Approved as complying with the  
Florida Building Code  
Date DEC 23, 2010  
NOA# 10-0623-04  
Miami Dade Product Control  
Division  
By [Signature]

Engr: JAVAD AHMAD  
CIVIL  
FLA. PE # 70592  
C.A.N. 3538  
[Signature]  
NOV 09 2010


**af c**  
**AL-FAROOQ CORPORATION**  
ENGINEERS & PRODUCT DEVELOPMENT  
1235 S.W. 87 AVE  
MIAMI, FLORIDA 33174  
TEL. (305) 264-8100 FAX. (305) 262-6978  
COMP-ANL W10-27ES

SERIES V2000 PVC HORIZ. SLIDING WDW. (L.M.I.)  
**E.S. WINDOWS, LLC**  
5220 N.W. 72 AVE. BAY #4  
MIAMI, FL. 33166  
TEL. (305) 624-7775 FAX. (305) 624-7777


no	date	by	description
A	09.24.10		REV. PER BCCO COMMENTS

date: 04-27-10  
scale: 1/2" = 1"  
dr. by: HAMID  
chk. by:

drawing no.  
**W10-27**  
sheet 7 of 8



FRAME CORNERS



VENT CORNERS

ITEM	PART #	QUANTITY	DESCRIPTION	MATERIAL	MANF./SUPPLIER/REMARKS
1	4254	1	FIXED MEETING RAIL	WHITE RIGID PVC	THERMOPLAST
2	4252E	4/ WDW.	FLANGE FRAME HEAD/SILL/JAMB	WHITE RIGID PVC	THERMOPLAST
2A	4202	4/ WDW.	FLUSH FRAME HEAD/SILL/JAMB	WHITE RIGID PVC	THERMOPLAST
2B	4252	4/ WDW.	FIN FRAME HEAD/SILL/JAMB	WHITE RIGID PVC	THERMOPLAST
3	4008	1	SILL COVER	WHITE RIGID PVC	THERMOPLAST
4	4084A	1	SASH INTERLOCK	WHITE RIGID PVC	THERMOPLAST
5	4027A	1	SASH FRAME	WHITE RIGID PVC	THERMOPLAST
7	4219	1	SILL ADAPTER	WHITE RIGID PVC	THERMOPLAST
8	4022	AS REQD.	7/8" GLAZING BEAD	WHITE RIGID PVC	THERMOPLAST
9	4010	1	SASH STOP	WHITE RIGID PVC	THERMOPLAST
10	4013	AS REQD.	7/8" GLAZING BEAD	WHITE RIGID PVC	THERMOPLAST
11	-	AS REQD.	SCREEN FRAME (OPTIONAL)	WHITE RIGID PVC	THERMOPLAST
12	HF-7320-187	AS REQD.	WEATHERSTRIPPING	-	SCHLEGEL
13	PB-8830-187	AS REQD.	WEATHERSTRIPPING	-	SCHLEGEL
14	DPAB-1.062-200	AS REQD.	FIN WEATHERSTRIPPING	-	SCHLEGEL
15	-	AS REQD.	SETTING BLOCK ( .90" X 1" X 1/8" )	-	-
16	Q4060	-	TILT LATCH	-	THERMOPLAST
17	4076	-	ROLLERS	-	THERMOPLAST
19	Q4080	2/ VENT	LOCK, AT 8" FROM EACH END	-	THERMOPLAST
20	Q4082	-	KEEPER	-	THERMOPLAST
21	-	AS REQD.	SCREEN SPRING	-	-
23	4052	2	MULLION CONNECTOR	-	-
24	4053	AS REQD.	SCREEN SUPPORT	-	-
25	#6 X 1"	-	LOCK SCREWS	-	FH
26	#6 X 1-1/2"	-	KEEPER SCREWS	-	FH
27	7/16" X 5/8"	2/ CONNECTOR	FIX. RAIL CONNECTOR SCREWS	-	-
28	#8 X 1/2"	AS REQD.	SCREEN SUPPORT SCREWS	-	FH
29	97-03-00-00	2/ WDW.	VALVE	-	GEARMOLD
30	A112-02P096	1	FIX. INTERLOCK REINFORCEMENT	6063-T6	-
31	#10 X 2"	-	RECEPTACLE SCREWS	-	FH
32	#8 X 1"	-	TILT LATCH SCREWS	-	FH
33	A110-02P096	-	SASH REINFORCEMENT	6063-T6	-
34	#8 X 1/2"	-	REINFORCEMENT SCREWS	ST. STEEL	-
35	#10 X 3"	-	FIXED RAIL SCREWS	-	PH
36	A111-02P096	-	MTG. RAIL REINFORCEMENT	6063-T6	-
37	4020	-	EXTENSION BLOCK	-	-

WHITE PVC EXTRUSIONS TO BE LABELED WITH AAMA EXTRUDER CODE, EXTRUDER NAME, CITY, STATE AND 'MCCA'.

Approved as complying with the  
 Florida Building Code  
 Date: DEC 23, 2010  
 NOA# 10-0623-04  
 Miami Dade Product Control  
 Division  
 By: Chas L. Khan

Engr: JAVAD AHMAD  
 CIVIL  
 FLA. PE # 70592  
 C.A.N. 3538  
  
 NOV 08 2010

**afC**  
**AL-FAROOQ CORPORATION**  
 ENGINEERS & PRODUCT DEVELOPMENT  
 1235 S.W. 87 AVE  
 MIAMI, FLORIDA 33174  
 TEL. (305) 264-8100 FAX. (305) 262-6978  
 COMP-ANL\W10-27ES

SERIES V2000 PVC HORIZ. SLIDING WDW. (L.M.I.)  
**E.S. WINDOWS, LLC**  
 5220 N.W. 72 AVE. BAY #4  
 MIAMI, FL. 33166  
 TEL. (305) 624-7775 FAX. (305) 624-7777

date: 04-27-10	scale: 1/2" = 1"	dr. by: HAMID	chk. by:
drawing no. <b>W10-27</b>			
sheet 8 of 8			

no	date	description
A	09.24.10	REV. PER BCCO COMMENTS