



DEPARTMENT OF PERMITTING, ENVIRONMENT, AND REGULATORY
AFFAIRS (PERA)
BOARD AND CODE ADMINISTRATION DIVISION

MIAMI-DADE COUNTY
PRODUCT CONTROL SECTION
11805 SW 26 Street, Room 208
Miami, Florida 33175-2474
T (786) 315-2590 F (786) 315-2599

www.miamidade.gov/pera

NOTICE OF ACCEPTANCE (NOA)

Innovative Window Concepts, LLC
1801 Corporate Drive
Boynton Beach, FL 33426

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County PERA - Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. PERA reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Series "3072" Aluminum Fixed Window – S.M.I.

APPROVAL DOCUMENT: Drawing No. **W04-05**, titled "S-3072 Aluminum Fixed Window (S.M.I.)", sheets 1 through 4 of 4, dated 01/14/04, with revision E dated 01/13/12, prepared by Al-Farooq Corporation, signed and sealed by Javad Ahmad, P.E., bearing the Miami-Dade County Product Control Revision stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Section.

MISSILE IMPACT RATING: Small Missile Impact Resistant

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state, model/series, and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official. This NOA revises NOA # 09-0527.08 and consists of this page 1 and evidence page E-1, as well as approval document mentioned above.

The submitted documentation was reviewed by **Manuel Perez, P.E.**



MP
4/12/12

NOA No. 12-0216.02
Expiration Date: August 26, 2014
Approval Date: April 19, 2012
Page 1

Innovative Window Concepts, L.L.C.

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

A. DRAWINGS

1. Manufacturer's die drawings and sections.
2. Drawing No. **W04-05**, titled "S-3072 Aluminum Fixed Window (S.M.I.)", sheets 1 through 4 of 4, dated 01-14-04, with revision E dated 01/13/12, prepared by Al Farooq Corporation, signed and sealed by Javad Ahmad, P.E.

B. TESTS (transferred from file # **07-1018.02**)

1. Test reports on:
 - 1) Air Infiltration Test, per FBC, TAS 202-94
 - 2) Water Infiltration Resistant Test per FBC TAS 202-94
 - 3) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
 - 4) Small Missile Impact Test per FBC, TAS 201-94
 - 5) Cyclic Wind Pressure Loading per FBC, TAS 203-94along with marked-up drawings and installation diagram of a series 3040 and 3062 aluminum fixed "picture" window, prepared by American Test Lab of South Florida, Test Report No. **ATL-0428.01-03**, dated 09/30/03, signed and sealed by William R. Mehner, P.E. and Henry Hattem, P. E.
(Submitted under previous NOA#07-1018.02)

C. CALCULATIONS

1. Anchor verification calculations, comparative and structural analysis, complying with FBC-2007, prepared by Al-Farooq Corporation, dated 07/17/09, signed and sealed by Arshad Viqar, P.E.
(Submitted under previous NOA#09-0527.08)
2. Glazing complies with ASTM E1300-04

D. QUALITY ASSURANCE

1. Miami-Dade Department of Permitting, Environment, and Regulatory Affairs (PERA)

E. MATERIAL CERTIFICATIONS

1. Notice of Acceptance No. **11-0325.05** issued to Solutia, Inc. for their "**Saflex and Vanceva clear and color interlayers**" dated 05/05/11, expiring on 05/21/16


F. STATEMENTS

1. Statement letter of conformance, complying with FBC-2010, and of no financial interest, dated January 13, 2012, signed and sealed by Javad Ahmad, P.E.

G. OTHER

1. Notice of Acceptance No. **09-0527.08**, issued to Innovative Window Concepts, LLC for their Series 3072 Aluminum Fixed Window – S.M.I., approved on 08/26/09 and expiring on 08/26/14


Manuel Perez, P.E.
Product Control Examiner
NOA No. 12-0216.02
Expiration Date: August 26, 2014
Approval Date: April 19, 2012



TYPICAL ELEVATION
TESTED UNIT

DAYLITE OPENINGS:
D.L.O. HEIGHT = WINDOW HEIGHT - 4.062"
D.L.O. WIDTH = WINDOW WIDTH - 4.062"

THESE WINDOWS ARE RATED FOR SMALL MISSILE IMPACT.
MIAMI-DADE COUNTY APPROVED IMPACT RESISTANT SHUTTERS
REQUIRED FOR INSTALLATIONS UP TO 30 FT. OF GRADE.
SHUTTERS NOT REQD. FOR INSTALLATIONS ABOVE 30 FT. OF GRADE.

S-3072 ALUMINUM FIXED WINDOW

DESIGN LOAD RATINGS FOR THESE WINDOWS TO BE AS PER
CHARTS SHOWN ON SHEET 2.

APPROVAL APPLIES TO SINGLE UNITS OR SIDE BY SIDE
COMBINATIONS OF FIX./FIX. OR FIXED WITH OTHER
WINDOW TYPES IN MODULES OF TWO OR MORE WINDOWS USING
MIAMI-DADE COUNTY APPROVED MULLIONS IN BETWEEN.
LOWER DESIGN PRESSURE FROM WINDOWS OR MULLION APPROVAL
WILL APPLY TO ENTIRE SYSTEM.

THIS PRODUCT HAS BEEN DESIGNED AND TESTED TO COMPLY WITH THE
REQUIREMENTS OF THE FLORIDA BUILDING CODE INCLUDING HIGH VELOCITY
HURRICANE ZONE (HVHZ).


1BY OR 2BY WOOD BUCKS BY OTHERS, MUST BE ANCHORED PROPERLY
TO TRANSFER LOADS TO THE STRUCTURE.

ANCHORS SHALL BE AS LISTED, SPACED AS SHOWN ON DETAILS, ANCHORS
EMBEDMENT TO BASE MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO.

ANCHORING OR LOADING CONDITIONS NOT SHOWN IN THESE DETAILS ARE
NOT PART OF THIS APPROVAL.

A LOAD DURATION INCREASE IS USED IN DESIGN OF ANCHORS INTO WOOD ONLY.

MATERIALS INCLUDING BUT NOT LIMITED TO STEEL/METAL SCREWS, THAT
COME INTO CONTACT WITH OTHER DISSIMILAR MATERIALS SHALL MEET THE
REQUIREMENTS OF THE FLORIDA BLDG. CODE SECTION 2003.8.4.



GLAZING OPTIONS

Engr. JAVAD AHMAD
CIVIL
FLA. PE. # 70592
C.A.N. 3538
JAN 17 2012

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 12-0216-02
Expiration Date AUG. 26, 2014
By *Youssef Jara*
Miami Dade Product Control

af c
AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP-ANL\W04-05IWS

S-3072 ALUMINUM FIXED WINDOW (S.M.I.)
INNOVATIVE WINDOW CONCEPTS, LLC
1801 CORPORATE DRIVE
BOYNTON BEACH, FL. 33426
TEL. (561) 493-2303 FAX. (561) 493-2302

no.	date	description
A	05.31.05	NOTES REV.
B	09.24.07	GENERAL REVISION
C	04.23.09	UPDATED FOR 2007 FBC
D	07.23.09	REV. PER BCCO COMMENTS
E	01.13.12	UPDATED TO 2010 FBC

date: 01-14-04
scale: 1/2" = 1'-0"
dr. by: HAMID
chk. by:

drawing no.
W04-05
sheet 1 of 4


DESIGN LOAD CAPACITY - PSF							
WINDOW DIMS.		GLASS TYPE 'A'		GLASS TYPE 'B'			
		ANCHORS 'A'		ANCHORS 'A'		ANCHORS 'B'	
WIDTH	LENGTH	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)
19-1/8"	26" (3)	90.0	155.0	90.0	155.0	90.0	155.0
24"		90.0	155.0	90.0	155.0	90.0	155.0
26-1/2"		90.0	155.0	90.0	155.0	90.0	155.0
32"		90.0	155.0	90.0	155.0	90.0	155.0
37"		90.0	155.0	90.0	155.0	90.0	155.0
40"		90.0	155.0	90.0	155.0	90.0	155.0
48"		90.0	155.0	90.0	155.0	90.0	155.0
53-1/8"		90.0	155.0	90.0	155.0	90.0	155.0
60"		90.0	150.8	90.0	150.8	90.0	155.0
76"		90.0	155.0	90.0	155.0	90.0	155.0
19-1/8"	38-3/8" (4)	90.0	155.0	90.0	155.0	90.0	155.0
24"		90.0	155.0	90.0	155.0	90.0	155.0
26-1/2"		90.0	155.0	90.0	155.0	90.0	155.0
32"		90.0	155.0	90.0	155.0	90.0	155.0
37"		90.0	155.0	90.0	155.0	90.0	155.0
40"		90.0	155.0	90.0	155.0	90.0	155.0
48"		90.0	130.7	90.0	133.4	90.0	155.0
53-1/8"		90.0	119.4	90.0	141.5	90.0	155.0
60"		90.0	106.6	90.0	117.7	90.0	153.5
76"		84.5	84.5	90.0	118.4	90.0	154.4
19-1/8"	50-5/8" (5)	90.0	155.0	90.0	155.0	90.0	155.0
24"		90.0	155.0	90.0	155.0	90.0	155.0
26-1/2"		90.0	155.0	90.0	155.0	90.0	155.0
32"		90.0	155.0	90.0	155.0	90.0	155.0
37"		90.0	128.8	90.0	155.0	90.0	155.0
40"		90.0	120.6	90.0	150.5	90.0	155.0
48"		90.0	105.1	90.0	128.0	90.0	155.0
53-1/8"		90.0	97.9	90.0	130.9	90.0	155.0
60"		87.3	87.3	90.0	105.0	90.0	136.9
66"		78.3	78.3	88.6	107.4	88.6	140.1
76"	67.4	67.4	90.0	100.6	90.0	131.2	
19-1/8"	63" (6)	90.0	155.0	90.0	155.0	90.0	155.0
24"		90.0	155.0	90.0	155.0	90.0	155.0
26-1/2"		90.0	155.0	90.0	155.0	90.0	155.0
32"		90.0	126.9	90.0	147.1	90.0	155.0
37"		90.0	105.6	90.0	134.3	90.0	155.0
40"		90.0	97.9	90.0	128.6	90.0	155.0
48"		85.9	85.9	90.0	118.2	90.0	154.2
53-1/8"		80.5	80.5	90.0	114.3	90.0	149.1
60"		75.1	75.1	90.0	102.4	90.0	133.6
76"		62.7	62.7	87.8	92.0	87.8	120.1
19-1/8"	76" (7)	90.0	155.0	90.0	155.0	90.0	155.0
24"		90.0	155.0	90.0	155.0	90.0	155.0
26-1/2"		90.0	155.0	90.0	155.0	90.0	155.0
32"		90.0	111.0	90.0	134.4	90.0	155.0
37"		88.6	88.6	90.0	121.3	90.0	155.0
40"		80.3	80.3	90.0	115.2	90.0	150.3
44"		74.1	74.1	88.5	108.6	88.5	141.7
48"		68.5	68.5	90.0	103.4	90.0	134.9
53-1/8"		66.4	66.4	90.0	98.3	90.0	128.2
60"		64.6	64.6	89.2	93.5	89.2	122.0
68"	60.4	60.4	86.2	90.4	86.2	117.9	

() INDICATE NO. OF ANCHORS FOR SHOWN DIMENSION

DESIGN LOAD CAPACITY - PSF								
WINDOW DIMS.		GLASS TYPE 'A'		GLASS TYPE 'B'				
		ANCHORS 'A'		ANCHORS 'A'		ANCHORS 'B'		
WIDTH	LENGTH	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)	
24"	24" (2)	90.0	155.0	90.0	155.0	90.0	155.0	
30"		90.0	155.0	90.0	155.0	90.0	155.0	
36"		90.0	155.0	90.0	155.0	90.0	155.0	
42"		90.0	155.0	90.0	155.0	90.0	155.0	
48"		90.0	155.0	90.0	155.0	90.0	155.0	
54"		90.0	155.0	90.0	155.0	90.0	155.0	
60"		90.0	155.0	90.0	155.0	90.0	155.0	
66"		90.0	155.0	90.0	155.0	90.0	155.0	
72"		90.0	153.6	90.0	153.6	90.0	155.0	
78"		90.0	155.0	90.0	155.0	90.0	155.0	
84"		90.0	149.3	90.0	149.3	90.0	155.0	
24"		36" (3)	90.0	155.0	90.0	155.0	90.0	155.0
30"			90.0	155.0	90.0	155.0	90.0	155.0
36"			90.0	155.0	90.0	155.0	90.0	155.0
42"	90.0		155.0	90.0	155.0	90.0	155.0	
48"	90.0		136.5	90.0	136.5	90.0	155.0	
54"	90.0		125.0	90.0	142.2	90.0	155.0	
60"	90.0		113.8	90.0	121.9	90.0	155.0	
66"	90.0		104.1	90.0	128.0	90.0	155.0	
72"	90.0		96.3	90.0	113.8	90.0	148.4	
78"	90.0		90.2	90.0	119.5	90.0	155.0	
84"	84.9		84.9	90.0	108.6	90.0	141.7	
24"	48" (4)		90.0	155.0	90.0	155.0	90.0	155.0
30"			90.0	148.9	90.0	148.9	90.0	155.0
36"			90.0	136.5	90.0	136.5	90.0	155.0
42"		90.0	121.8	90.0	130.0	90.0	155.0	
48"		90.0	110.2	90.0	128.0	90.0	155.0	
54"		90.0	100.2	90.0	128.0	90.0	155.0	
60"		90.0	90.4	90.0	106.7	90.0	139.2	
66"		81.9	81.9	90.0	109.7	90.0	143.1	
69"		78.0	78.0	88.3	102.4	88.3	133.6	
72"		72.7	72.7	90.0	96.0	90.0	125.3	
78"		66.6	66.6	90.0	99.6	90.0	129.9	
84"		61.8	61.8	89.6	89.6	90.0	116.9	
24"		60" (5)	90.0	155.0	90.0	155.0	90.0	155.0
30"			90.0	136.5	90.0	136.5	90.0	155.0
36"	90.0		113.8	90.0	121.9	90.0	155.0	
42"	90.0		98.7	90.0	112.5	90.0	146.8	
48"	90.0		90.4	90.0	106.7	90.0	139.2	
54"	83.7		83.7	88.5	103.4	88.5	134.9	
55"	82.7		82.7	86.9	103.1	86.9	134.5	
60"	78.3		78.3	90.0	102.4	90.0	133.6	
66"	72.1		72.1	90.0	102.4	90.0	133.6	
72"	68.2		68.2	87.8	87.8	90.0	114.5	
78"	62.9		62.9	87.8	89.6	87.8	116.9	
84"	58.7		58.7	79.6	79.6	84.0	103.9	

DESIGN LOAD CAPACITY - PSF							
WINDOW DIMS.		GLASS TYPE 'A'		GLASS TYPE 'B'			
		ANCHORS 'A'		ANCHORS 'A'		ANCHORS 'B'	
WIDTH	LENGTH	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)
24"	72" (6)	90.0	153.6	90.0	153.6	90.0	155.0
30"		90.0	128.8	90.0	129.3	90.0	155.0
36"		90.0	96.3	90.0	113.8	90.0	148.4
42"		81.6	81.6	90.0	103.3	90.0	134.7
46"		76.3	76.3	88.3	98.1	88.3	128.0
48"		72.7	72.7	90.0	96.0	90.0	125.3
54"		69.7	69.7	90.0	91.0	90.0	118.8
60"		68.2	68.2	87.8	87.8	90.0	114.5
66"		63.9	63.9	85.9	85.9	90.0	112.1
72"		60.2	60.2	85.3	85.3	90.0	111.3
24"	84" (7)	90.0	149.3	90.0	149.3	90.0	155.0
30"		90.0	117.1	90.0	124.7	90.0	155.0
36"		84.9	84.9	90.0	108.6	90.0	141.7
39"		75.8	75.8	90.0	102.6	90.0	133.8
42"		65.7	65.7	90.0	97.5	90.0	127.2
48"		61.8	61.8	89.6	89.6	90.0	116.9
54"		61.0	61.0	83.8	83.8	88.4	109.4
60"		58.7	58.7	79.6	79.6	84.0	103.9
61"		58.1	58.1	79.1	79.1	83.4	103.2
24"		96" (8)	90.0	146.3	90.0	146.3	90.0
30"	90.0		115.1	90.0	121.4	90.0	155.0
34"	84.9		84.9	90.0	109.8	90.0	143.2
36"	71.7		71.7	90.0	105.0	90.0	137.0
42"	60.5		60.5	90.0	93.6	90.0	122.1
48"	56.5		56.5	85.3	85.3	90.0	111.3
54"	52.5		52.5	79.1	79.1	83.5	103.3

() INDICATE NO. OF ANCHORS FOR SHOWN DIMENSION



NOTE:
WIDTH AND LENGTH DIMENSIONS CAN BE ORIENTED
VERTICALLY OR HORIZONTALLY AS SHOWN ABOVE.

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538
JAN 17 2012





PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 12-0216-02
Expiration Date 06-26-2014
By *Mamun Joz*
Miami Dade Product Control

af c
AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP-ANL\W04-05IWS

S-3072 ALUMINUM FIXED WINDOW (S.M.I.)
INNOVATIVE WINDOW CONCEPTS, LLC
1801 CORPORATE DRIVE
BOYNTON BEACH, FL. 33426
TEL. (561) 493-2303 FAX. (561) 493-2302

no	date	description
A	05.31.05	LOAD CAPACITY CHART REV.
B	09.24.07	GENERAL REVISION
C	04.23.09	UPDATED FOR 2007 FBC
D	07.23.09	REV. PER BCCO COMMENTS
E	10.13.12	NO CHANGE THIS SHEET

date: 01-14-04
scale: 1/2" = 1'-0"
dr. by: HAMID
chk. by:
drawing no.
W04-05
sheet 2 of 4



TYPICAL ANCHORS: SEE ELEV. FOR SPACING

TYPE 'A'

3/16" DIA. ULTRACON BY 'ELCO' (Fu=177 KSI, Fy=155 KSI)
 INTO 2BY WOOD BUCKS OR WOOD STRUCTURES
 1-3/8" MIN. PENETRATION INTO WOOD
 THRU 1BY BUCKS INTO CONC. OR MASONRY
 1-1/4" MIN. EMBED INTO CONC. OR MASONRY
 DIRECTLY INTO CONC. OR MASONRY
 1-1/4" MIN. EMBED INTO CONC. OR MASONRY

3/16" TEKS OR SELF DRILLING SCREWS (GRADE 5 CRS)
 INTO METAL STRUCTURES
 STEEL : 12 GA. MIN. (Fy = 36 KSI MIN.)
 ALUMINUM : 1/8" THK. MIN. (6063-T5 MIN.)
 (STEEL IN CONTACT WITH ALUMINUM TO BE PLATED OR PAINTED)

#10 SMS OR SELF DRILLING SCREWS
 INTO MIAMI-DADE COUNTY APPROVED CLIPPED MULLIONS (MIN. THK. = 1/8")
 (NO SHIM SPACE)

TYPE 'B'

1/4" DIA. ULTRACON BY 'ELCO' (Fu=177 KSI, Fy=155 KSI)
 INTO 2BY WOOD BUCKS OR WOOD STRUCTURES
 1-3/8" MIN. PENETRATION INTO WOOD
 THRU 1BY BUCKS INTO CONC. OR MASONRY
 1-1/4" MIN. EMBED INTO CONC. OR MASONRY
 DIRECTLY INTO CONC. OR MASONRY
 1-1/4" MIN. EMBED INTO CONC. OR MASONRY

#14 SMS OR SELF DRILLING SCREWS (GRADE 2 CRS)
 INTO METAL STRUCTURES
 STEEL : 12 GA. MIN. (Fy = 36 KSI MIN.)
 ALUMINUM : 1/8" THK. MIN. (6063-T5 MIN.)
 (STEEL IN CONTACT WITH ALUMINUM TO BE PLATED OR PAINTED)

#10 SMS OR SELF DRILLING SCREWS
 INTO MIAMI-DADE COUNTY APPROVED CLIPPED MULLIONS (MIN. THK. = 1/8")
 (NO SHIM SPACE)

WOOD BUCKS AND METAL STRUCTURE NOT BY I.W.C.
 MUST SUSTAIN LOADS IMPOSED BY GLAZING SYSTEM
 AND TRANSFER THEM TO THE BUILDING STRUCTURE.


TYPICAL EDGE DISTANCE

INTO CONCRETE AND MASONRY = 1-1/2" MIN.
 INTO WOOD STRUCTURE = 1" MIN.
 INTO METAL STRUCTURE = 3/4" MIN.

CONCRETE f'c = 3000 PSI MIN.
 C-90 HOLLOW/FILLED BLOCK f'm = 2000 PSI MIN.

SEALANT:

ALL JOINTS AND FRAME CONNECTIONS SEALED WITH
 SCHNEE MOREHEAD SEAM SEALER SM5504.



Engr: JAVAD AHMAD
 CIVIL
 FLA. PE # 70592
 C.A.N. 3538
 JAN 17 2012


PRODUCT REVISED
 as complying with the Florida
 Building Code
 Acceptance No 12-0216-02
 Expiration Date 12.26.2014
 By *Muhammed*
 Miami Dade Product Control

af c
AL-FAROOQ CORPORATION
 ENGINEERS & PRODUCT DEVELOPMENT
 1235 S.W. 87 AVE
 MIAMI, FLORIDA 33174
 TEL. (305) 264-8100 FAX. (305) 262-6978
 COMP-ANL\W04-05IWS


S-3072 ALUMINUM FIXED WINDOW (S.M.I.)
INNOVATIVE WINDOW CONCEPTS, LLC
 1801 CORPORATE DRIVE
 BOYNTON BEACH, FL. 33426
 TEL. (561) 493-2303 FAX. (561) 493-2302

no	date	by	description
			NO CHANGE THIS SHEET
A	05.31.05		GENERAL REVISION
B	09.24.07		UPDATED FOR 2007 FBC
C	04.23.09		REV. PER BCCO COMMENTS
D	07.23.09		NO CHANGE THIS SHEET
E	01.13.12		NO CHANGE THIS SHEET


date: 01-14-04
 scale: 1/2" = 1"
 dr. by: HAMID
 chk. by:
 drawing no.
W04-05
 sheet 3 of 4



FRAME




GLAZING STOP




WEDGE GASKET


ITEM	PART #	QUANTITY	DESCRIPTION	MATERIAL	MANF./SUPPLIER/REMARKS
1	021-024	4	WINDOW FRAME	6063-T6	-
2	021-020	4	GLAZING STOP	6063-T5	-
4	#8 X 1"	2/ CORNER	ASSEMBLY SCREWS	CRS	PH SMS
5	-	2/ LITE	SETTING BLOCK, 1/2" X 1/4" X 1" LONG	NEOPRENE	FRANK LOWE
6	015-007	AS REQD.	GLAZING GASKET	RIGID VINYL	MASTER TOOL
7	015-006	AS REQD.	.105 SPACER	POLYURETHANE	FRANK LOWE



EXTERIOR
D.L. OPG.
WINDOW WIDTH



FRAME CORNERS



Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538
JAN 17 2012

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No _____
Expiration Date _____
By _____
Miami Dade Product Control

afC
AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP-ANL\W04-05IWS

S-3072 ALUMINUM FIXED WINDOW (S.M.I.)
INNOVATIVE WINDOW CONCEPTS, LLC
1801 CORPORATE DRIVE
BOYNTON BEACH, FL. 33426
TEL. (561) 493-2303 FAX. (561) 493-2302

no	date	by	description
A	05.31.05		NO CHANGE THIS SHEET
B	09.24.07		GENERAL REVISION
C	04.23.09		UPDATED FOR 2007 FBC
D	07.23.09		REV. PER BCCO COMMENTS
E	01.13.12		UPDATED TO 2010 FBC

date: 01-14-04
scale: 1/2" = 1"
dr. by: HAMID
chk. by:

drawing no.
W04-05
sheet 4 of 4