

MIAMI-DADE COUNTY PRODUCT CONTROL SECTION

11805 SW 26 Street, Room 208 Miami, Florida 33175–2474 T (786) 315–2590 F (786) 315–2599 www.miamidade.gov/pera

DEPARTMENT OF PERMITTING, ENVIRONMENT, AND REGULATORY AFFAIRS (PERA) BOARD AND CODE ADMINISTRATION DIVISION NOTICE OF ACCEPTANCE (NOA)

Sika Sarnafil Inc. 100 Dan Road Canton, MA 02021

Scope:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami–Dade County PERA – Product Control Section to be used in Miami–Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami-Dade County) and/or the AHJ (in areas other than Miami-Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. PERA reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code including the High Velocity Hurricane Zone of the Florida Building Code.

DESCRIPTION: Sika Sarnafil PVC Single Ply Roofing over Steel Deck.

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state, and following statement: "Miami–Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/ or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami–Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA renews and revises NOA No. 11-0526.03 and consists of pages 1 through 32. The submitted documentation was reviewed by Jorge L. Acebo.



And W

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 1 of 32

ROOFING SYSTEM APPROVAL

Category:RoofingSub-Category:Single PlyMaterial:PVCDeck Type:SteelMaximum Design Pressure-112.5 psf

TRADE NAMES OF PRODUCTS MANUFACTURED OR LABELED BY APPLICANT:

TABLE 1

		Test	Product
Product	Dimensions	Specification	<u>Description</u>
G410	Various	ASTM D 4434	Fiberglass reinforced PVC roofing membrane.
G410 Felt	Various	ASTM D 4434	Fiberglass reinforced PVC roofing membrane with a non-woven felt backing.
G410 PS	Various	ASTM D 4434	Fiberglass reinforced PVC roofing membrane with a peel & stick self-adhering backing.
S327	Various	ASTM D 4434	Polyester reinforced PVC roofing membrane.
S327 Felt	Various	ASTM D 4434	Polyester reinforced PVC roofing membrane.
Sikaplan 45	45 mil thick	ASTM D 4434	White polyester reinforced PVC roofing membrane.
G459	Various	ASTM D 4434	Fiberglass reinforced PVC Alloy asphalt compatible flashing membrane.
Sarnatape	Various		Air flow barrier tape
Sarnacol 2170	5 gallons		Solvent based bonding adhesive.
Sarnacol 2121	5 gallons		Water based bonding adhesive.
Sarnacol 2163			Insulation adhesive.
Sarnacol 2164			Insulation adhesive.
Sarnacorner	5", 6", 8.5"		Prefabricated inside and outside corner flashing.
Sarnaflash	18" x 40"		Prefabricated expansion joints.
Sarnatred	3.25' x 32.8'		PVC walkway protection sheet.
SarnaWalkways	Various		PVC walkway protection sheet.
Sarnastack	Various		Prefabricated cone flashing.
Sarnadrain RAC	Various		Aluminum drain insert.
Sarnaclad	Various		Heat weldable PVC/galvanized steel flashing



NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 2 of 32

APPROVED INSULATIONS:

TABLE 2

Product Name	Product Description	Manufacturer (With Current NOA)
Sarnatherm	Isocyanurate Insulation	Sarnafil, Inc.
Sarnatherm 25 PSI	Polyisocyanurate insulation board.	Sarnafil, Inc.
ACFoam Composite	Isocyanurate Insulation with perlite facer	Atlas Roofing Corp.
ACFoam II, ACFoam III	Isocyanurate Insulation	Atlas Roofing Corp.
ACFoam Supreme	Isocyanurate Insulation	Atlas Roofing Corp.
DensDeck, DensDeck Prime, DensDeck DuraGuard	Silicon treated gypsum	G-P Products
ENRGY 3	Isocyanurate Insulation	Johns Manville
ENRGY 3 Plus	Isocyanurate Insulation with wood fiberboard facer	Johns Manville
ENRGY 3 PSI-25	Isocyanurate Insulation	Johns Manville
High Density Wood Fiberboard	Wood fiber insulation	Generic
H-Shield, H-Shield CG	Isocyanurate Insulation	Hunter Panels
ISO 95+ GL	Isocyanurate Insulation	Firestone
Multi-Max FA-3	Isocyanurate Insulation	Rmax, Inc.
Perlite Insulation Board	Perlite Insulation	Generic
Thermaroof-3	Isocyanurate Insulation	Rmax, Inc.
Thermaroof Composite-3	Isocyanurate Insulation with perlite facer	Rmax, Inc.
Type X Gypsum	Gypsum Wallboard	Generic



NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 3 of 32

APPROVED FASTENERS:

TABLE 3

<u>Fastener</u> <u>Number</u>	<u>Product</u> <u>Name</u>	Product <u>Description</u>	<u>Dimensions</u>	Manufacturer (With Current NOA)
1.	OMG Fasteners	Insulation and membrane fastener	Various	OMG, Inc.
2.	SFS Fasteners	Insulation and membrane fastener	Various	SFS Intec, Inc.
3.	Tru-Fast Fasteners	Insulation and membrane fastener	Various	The Tru-Fast Corp.
4.	Sarnafil Fasteners	Insulation and membrane fastener	Various	Sarnafil, Inc.
5.	PVC Rhino Plates	Insulation fastener	Various	OMG, Inc.
6.	Sarnabar	Galvanized or stainless steel membrane fastening bar.	Various	Sarnafil, Inc.
7.	Sarnadisc	Membrane fastening stress plate.	2" Round	Sarnafil, Inc.
8.	Sarnaplate	Insulation fastening plate.	3" Round	Sarnafil, Inc.
9.	Sarnarail Polymer Batten Strip	Polymer Batten Bar	1" x 250'	Sarnafil, Inc.
10.	Sarnafastener-XP	Membrane and insulation fastener.	Various	Sarnafil, Inc.
11.	Sarnafastener MAXLoad	Membrane fastener	Various	Sarnafil, Inc.
12.	Sarnadisc MAXLoad Plate	AZ50 galvalume coated steel plate	3.5" Round	Sarnafil, Inc.
13.	Sarnadisc-XPN	Membrane and insulation fastening plate.	1.5" x 3.75"	Sarnafil, Inc.
14.	PVC Rhino Plates	Insulation fastening plate	Various	Sarnafil, Inc.
15.	OMG Super XHD	Insulation fastener for steel, wood and concrete decks	Various	OMG, Inc.



NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 4 of 32

EVIDENCE SUBMITTED:

Test Agency	Test Identifier	Description	Date
Celotex Technical Center	MTS Job No. 258215	Wind Uplift	09/09/97
Factory Mutual Research	0P6A6.AM	FM 4470	03/03/94
Corporation	0X3A3.AM	FM 4470	07/31/94
•	2X2A5.AM	FM 4470	07/31/94
	0B9A0.AM	FM 4470	10/22/96
	1Z5A6.AM	FM 4470	07/18/97
	4B3A2.AM	FM 4470	06/19/97
	3012964	FM 4470	06/11/02
	3015643	FM 4470	12/06/02
	3016201	FM 4470	01/28/03
	3006785	FM 4470	05/06/04
	3017292	FM 4470	09/03/04
	3021131	FM 4470	07/07.05
	3024229	FM 4470	11/16/05
	3030053	FM 4470	09-12/07
	3028309	FM 4470	03/30/07
Underwriters Laboratories, Inc.	R8992	Fire Classification	1994



NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 5 of 32

APPROVED ASSEMBLIES:

Membrane Type: Single Ply, Thermoplastic, PVC

Deck Type 2I: Steel, Insulated **Deck Description:** 18 – 22ga. steel

System Type B(1): Base Layer of insulation mechanically attached, optional top insulation layer fully

adhered with approved asphalt.

All General and System Limitations apply:

Vapor Retarder: (Optional) An FM approved vapor barrier approved for use with hot asphalt may

be applied to the deck or perlite base layer.

Barrier: (Optional) Minimum ⁵/₈ "Type X Gypsum or ¹/₄ "DensDeck.

Base Insulation Layer	Insulation Fasteners (Table 3)	<u>Fastener</u> <u>Density/ft²</u>
ACFoam II, ACFoam Composite (bottom layer only), H-S	Shield	
Minimum 1.3" thick or tapered	1, 2, 3, or 4	1:2 ft ²
Minimum 2" thick or tapered	1, 2, 3, or 4	1:4 ft ²
Sarnatherm, Sarnatherm-25 PSI, ENRGY 3, ENRGY 3 P	Plus, ENRGY 3 PSI-25	
Minimum 1.4" thick or tapered	1, 2, 3, or 4	1:3 ft ²
Minimum 2" thick or tapered	1, 2, 3, or 4	1:4 ft ²
DensDeck, DensDeck Prime		
Minimum 1/4" thick	1, 2, 3, or 4	1:1.2 ft ²
Minimum 1/2" thick	1, 2, 3, or 4	1:1.7 ft ²
Multi-Max FA-3, Thermaroof Composite-3 (bottom layer	only)	
Minimum 1.25" thick	1, 2, 3, or 4	1:2 ft²
Minimum 2" thick	1, 2, 3, or 4	1:4 ft ²
Approved High Density Wood Fiber (base layer only)		
Minimum 1" thick or tapered	1, 2, 3, or 4	1:2 ft²
Minimum 1.4" thick or tapered	1, 2, 3, or 4	1:2 ft ²
Approved Perlite		
Minimum 3/4" thick	1, 2, 3, or 4	1:1 ft²

Note: Base layer shall be mechanically attached with fasteners and density described. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).



NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 6 of 32

Top Insulation Layer	Insulation Fasteners (Table 3)	<u>Fastener</u> Density/ft2
ACFoam II Minimum 1.3" thick or tapered	N/A	N/A
Sarnatherm, Sarnatherm-25 PSI, ENRGY 3, ENRGY 3 Minimum 1.4" thick or tapered	Plus, ENRGY 3 PSI-25 N/A	N/A
DensDeck, DensDeck Prime Minimum 1/4" thick	N/A	N/A
Multi-Max FA-3 Minimum 1.25" thick or tapered	N/A	N/A

Note: Optional top layer of insulation shall be adhered with approved asphalt within the EVT range and at a rate of 20-40 lbs/100 ft². Please refer to Roofing Application Standard RAS 117 for insulation attachment. Composite insulation boards used as a top layer shall be installed with the polyisocyanurate face down.

Membrane: Sarnafil G410 or S327, smooth backed, adhered with Sarnacol 2170 applied at a

> rate of 1.25gal/sq. to the substrate and 0.5 gal/sq. to the back of the Membrane, or Sarnacol 2121 adhesive applied at a rate of 1.75 to substrate. Sarnafil G410 Felt or S327 Felt, adhered with Sarnacol 2170 applied at a rate of 1.25gal/sq. to the substrate followed by a second coat at a rate of 1.0gal/sq to the substrate.

Maximum Design

-45 psf. (See General Limitation #9)

Pressures:



NOA No.: 12-0313.16 **Expiration Date: 07/08/13** Approval Date: 06/28/12 Page 7 of 32

Deck Type 2I: Steel, Insulated **Deck Description:** 18 – 22ga. steel

System Type B(2): Base Layer of insulation mechanically attached, optional top insulation layer fully

adhered with approved asphalt or adhesive.

All General and System Limitations apply.

Vapor Retarder: (Optional) Any UL or FM approved vapor barrier approved for use with hot

asphalt may be applied to the deck or perlite base layer.

Barrier: (Optional) Minimum ¼ "Type X Gypsum or DensDeck

Base Insulation Layer	Insulation Fasteners	Fastener
	<u>(Table 3)</u>	Density/ft ²
ACFoam II, ACFoam III, H-Shield, ISO 95+GL, ENRG	Y 3, Sarnatherm	
Minimum 1.4" thick or tapered	1	1:2 ft ²

Note: Base layer shall be mechanically attached with fasteners and density described. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Insulation for Top Layer</u> (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft ²
ACFoam II, ACFoam III, H-Shield, ISO 95+C Minimum 1.4" thick or tapered	GL, ENRGY 3, Sarnatherm N/A	N/A
DensDeck, DensDeck Prime Minimum 1/4" thick or tapered	N/A	N/A

Note: Optional top layer of insulation shall be adhered to the deck in full coating of OlyBond Adhesive Fastener at a rate of 1 gal/sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate

Membrane: Sarnafil G410, G410 Felt, S327 or S327 Felt adhered with Sarnacol 2170 adhesive.

Adhesive rolled applied as a primer at a rate 1.0-1.25 gal/sq. to the insulation allowed to dry. Following a second coat roller applied of adhesive at 0.5 gal/sq. The roof cover is immediately placed into the adhesive and the top surface rolled

with a weighted roller.

Maximum Design -45 psf. (See General Limitation #9)

Pressures:

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12

Page 8 of 32



Deck Type 2I: Steel, Insulated

Deck Description: Min. 18-22 ga. steel

System Type B(3): Base Layer of insulation mechanically attached, optional top insulation layer

adhered with approved adhesive.

All General and System Limitations apply:

Vapor Retarder: (Optional) Any UL or FM approved vapor barrier approved for use with hot asphalt

may be applied to the deck or perlite base layer.

Barrier: (Optional) Minimum ½ "Type X Gypsum or DensDeck

Base Insulation Layer	Insulation Fasteners	Fastener
	<u>(Table 3)</u>	Density/ft ²
ACFoam Supreme, H-Shield, Sarnatherm or H-Shield CG		
Minimum 1.5" thick or tapered	1, 2, 3, or 4	1:4 ft ²

Note: Base layer shall be mechanically attached with fasteners and density described. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Insulation for Top Layer</u> (Optional)	Insulation Fasteners (Table 3)	<u>Fastener</u> <u>Density/ft²</u>
ACFoam Supreme, H-Shield, Sarnatherm or H-Shield CG Minimum 1.5" thick or tapered	N/A	N/A
DensDeck Prime, DensDeck DuraGuard Minimum 1/4" thick or tapered	N/A	N/A

Note: Optional top layer of insulation shall be adhered with approved asphalt within the EVT range and at a rate of 25 lbs/sq. or 0.75" wide beads of OlyBond 500 or Spot Shot spaced 12" o.c.

Membrane: Sarnafil G410 PS, self-adhered to insulation and installed with a 3" wide heat

welded seam. Membrane is rolled into insulation with a weighted roller.

Maximum Design -45 psf. (See General Limitation #9)

Pressure:

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 9 of 32



Deck Type 2I: Steel, Insulated **Deck Description:** 18 – 22ga. steel

System Type C(1): All layers of insulation simultaneously fastened; membrane fully adhered.

All General and System Limitations apply.

Vapor Retarder: (Optional) An FM approved vapor barrier approved for use with hot asphalt may

be applied to the deck or perlite base layer.

Barrier: (Optional) Minimum ⁵/₈ " Type X Gypsum or ¹/₄ "DensDeck

Insulation for Base Layer	Fastener Type	Fastener Density/ft ²		
ACFoam II, ACFoam Composite (bottom layer only), ACFoam Supreme, H-Shield				
Minimum 1.3" thick or tapered	N/A	N/A		
Sarnatherm, Sarnatherm-25 PSI, ENRGY 3, E	NRGY 3 Plus, ENRGY	3 PSI-25, ISO 95+ GL		
Minimum 1.4" thick or tapered	N/A	N/A		
Approved High Density Wood Fiberboard (bas Minimum 1" thick	e layer only) N/A	N/A		
Multi-Max FA-3, Thermaroof-3 Minimum 1.25" thick or tapered	N/A	N/A		
DensDeck, DensDeck Prime Minimum 1/4" thick	N/A	N/A		
Approved Perlite (base layer only) Minimum ¾" thick	N/A	N/A		

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Insulation for Top Layer	Insulation Fasteners	<u>Fastener</u>
	<u>(Table 3)</u>	Density/ft ²
ACFoam II		
Minimum 1.3" thick or tapered	1, 2, 3, or 4	1:2 ft ²
Minimum 2" thick or tapered	1, 2, 3, or 4	1:4 ft ²
Sarnatherm, Sarnatherm-25 PSI, ENRGY 3, ENRGY 3 Pl	us, ENRGY 3 PSI-25	
Minimum 1.4" thick or tapered	1, 2, 3, or 4	1:3 ft ²
Minimum 2" thick or tapered	1, 2, 3, or 4	1:4 ft ²
DensDeck, DensDeck Prime		
Minimum 1/4" thick	1, 2, 3, or 4	1:1.2 ft ²
Minimum 1/2" thick	1, 2, 3, or 4	1:1.7 ft ²

MIAMI-DADE COUNTY
APPROVED

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 10 of 32

Insulation for Top Layer (Continued)	Insulation Fasteners	Fastener Density/ft ²
Multi-Max FA-3	<u>(Table 3)</u>	Density/it_
Minimum 1.25" thick	1, 2, 3, or 4	1:3 ft ²
Minimum 2" thick	1, 2, 3, or 4	1:4 ft ²

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sarnafil G410 or S327, smooth backed, adhered with Sarnacol 2170 applied at a

rate of 1.25gal/sq. to the substrate and 0.5 gal/sq. to the back of the Membrane, or Sarnacol 2121 adhesive applied at a rate of 1.75 to substrate. Sarnafil G410 Felt or S327 Felt, adhered with Sarnacol 2170 applied at a rate of 1.25gal/sq. to the substrate followed by a second coat at a rate of 1.0gal/sq to the substrate.

Maximum Design

-45 psf. (See General Limitation #9)

Pressures:



NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 11 of 32

Deck Type 2I: Steel, Insulated

Deck Description: 18 – 22ga. steel deck fastened to supports spaced maximum 6 ft. o.c. with Traxx 5

fasteners spaced 6 in. o.c. and with side laps fastened with Traxx 1 fasteners

spaced maximum 24 in. o.c.

System Type C(2): All layers of insulation simultaneously fastened; membrane bonded.

All General and System Limitations apply.

<u>Insulation for Base Layer</u> <u>Fastener Density/ft²</u> <u>Fastener Type</u>

Any approved insulation listed in Table 2

Minimum 0.25" thick N/A N/A

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Insulation for Top Layer (Optional)

Any approved cover board listed in Table 2

Minimum 0.25" thick

See Design Pressure

OMG Super XHD and PVC Rhino Plates

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sarnafil S327, S327 Felt Backed or Sikaplan 45 bonded to PVC Rhino Plates with

Rhino Plate bonding tool at 6 seconds per plate so the tool reaches 400°F. Side lap

is sealed with minimum 3/4" wide heat weld.

Maximum Design
Pressures:

Maximum Pressure

-45 psf
(See General Limitation #7)

Fastener Spacing
2 ft.

3 ft.



NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 12 of 32

Deck Type 2I: Steel, Insulated

Deck Description: 18 – 22ga., Grade 80 steel deck fastened to supports spaced maximum 6 ft. o.c.

with Traxx 5 fasteners spaced 6 in. o.c. and with side laps fastened with Traxx 1

fasteners spaced maximum 24 in. o.c.

System Type C(3): All layers of insulation simultaneously fastened; membrane bonded.

All General and System Limitations apply.

Insulation for Base Layer	Fastener Density/ft ²	Fastener Type
Any approved insulation listed in Table 2		
Minimum 0.25" thick	N/A	N/A

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Insulation for Top Layer	Fastener Density/ft ²	Fastener Type		
(Optional) Any approved cover board listed in Table 2				
Minimum 0.25" thick	See Design Pressure	OMG Super XHD or		
	-	Sarnafastener-XP and		
		PVC Rhino Plates		

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sarnafil S327, S327 Felt Backed or Sikaplan 45 bonded to PVC Rhino Plates with Rhino Plate bonding tool at 6 seconds per plate so the tool reaches 400°F. Side

lap is sealed with minimum 3/4" wide heat weld.

	Maximum Pressure	Fastener Spacing	Fastener Row Spacing
Maximum Design Pressures:	-45 psf (See General Limitation #7	2 ft.	3 ft.
i i visui vi	-60 psf (See General Limitation #7)	2 ft.	2 ft.



NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 13 of 32

Deck Type 2I: Steel, Insulated

Deck Description: 18 ga. steel deck fastened to supports spaced maximum 6 ft. o.c. with Traxx 5

fasteners spaced 6 in. o.c. and with side laps fastened with two Traxx 1 fasteners

spaced maximum 24 in. o.c.

System Type C(4): All layers of insulation simultaneously fastened; membrane bonded.

All General and System Limitations apply.

Insulation for Base Layer	Fastener Type	Fastener Density/ft ²
Any approved insulation listed in Table 2		
Minimum 0.25" thick	N/A	N/A

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Insulation for Top Layer	Fastener Density/ft ²	Fastener Type		
(Optional) Any approved cover board listed in Table 2				
Minimum 0.25" thick	See Design Pressure	Sarnafastener-XP and PVC Rhino Plates		

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sarnafil S327, S327 Felt Backed or Sikaplan 45 bonded to PVC Rhino Plates with

Rhino Plate bonding tool at 6 seconds per plate so the tool reaches 400°F. Side

lap is sealed with minimum ³/₄" wide heat weld.

	Maximum Pressure	Fastener Spacing	Fastener Row Spacing
Maximum Design Pressures:	-45 psf (See General Limitation #7)	12 in.	6 ft.
	-52.5 psf (See General Limitation #7)	12 in.	5 ft.
	-90 psf (See General Limitation #7)	6 in.	6 ft.
	-105 psf (See General Limitation #7)	6 in.	5 ft.

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 14 of 32

MIAMI-DADE COUNTY
APPROVED

Deck Type 2I: Steel, Insulated **Deck Description:** 18 – 22ga. steel

System Type C(5): All layers of insulation simultaneously fastened; membrane fully adhered.

All General and System Limitations apply.

Insulation for Base Layer Fastener Type Fastener Density/ft²

Any approved polyisocyanurate listed in Table 2

Minimum 1.5" thick N/A N/A

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Insulation for Top Layer	<u>Insulation Fasteners</u> (Table 3)	Fastener Density/ft ²
DensDeck Prime		
Minimum 5/8" thick	4	1:2 ft ²

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sarnafil G410 Felt or S327 Felt, adhered with Sarnacol 2121 adhesive applied at a

rate of 2.0 - 2.5 gal/sq to substrate. Minimum 3" wide side lap is sealed with a 1.5"

wide heat weld.

Maximum Design -52.5 psf. (See General Limitation #7)

Pressures:

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12

Page 15 of 32



Deck Type 2I: Steel, Insulated **Deck Description:** 18 – 22ga. steel

System Type C(6): All layers of insulation simultaneously fastened; membrane fully adhered.

All General and System Limitations apply.

Insulation for Base Layer Fastener Type Fastener Density/ft²

Any approved polyisocyanurate listed in Table 2

Minimum 1.5" thick N/A N/A

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Insulation for Top Layer	<u>Insulation Fasteners</u> (Table 3)	Fastener Density/ft ²
DensDeck Prime		
Minimum 5/8" thick	4	1:2 ft ²

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sarnafil G410 or S327, adhered with Sarnacol 2170 applied at a rate of 0.75 – 2

gal/sq. to the substrate and 0.5 gal/sq. to the back of the membrane. Minimum 3"

wide side lap is sealed with a 1.5" wide heat weld.

Maximum Design -60.0 psf. (See General Limitation #7)

Pressures:

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 16 of 32



Deck Type 2I: Steel, Insulated

Deck Description: 18 – 22ga. steel deck fastened to supports spaced maximum 6 ft. o.c. with Traxx 5

fasteners spaced 6 in. o.c. and with side laps fastened with Traxx 1 fasteners

spaced maximum 24 in. o.c.

System Type C(7): All layers of insulation simultaneously fastened; membrane bonded.

All General and System Limitations apply.

<u>Insulation for Base Layer</u> <u>Fastener Type</u> <u>Fastener Density/ft²</u>

Any approved insulation listed in Table 2

Minimum 0.25" thick N/A N/A

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Insulation for Top Layer (Optional)

Any approved cover board listed in Table 2

Minimum 0.25" thick

See Design Pressure

OMG Super XHD and PVC Rhino Plates

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sarnafil S327, S327 Felt Backed or Sikaplan 45 bonded to PVC Rhino Plates with

Rhino Plate bonding tool at 6 seconds per plate so the tool reaches 400°F. Side

lap is sealed with minimum 3/4" wide heat weld.

Maximum Design
Pressures:

Maximum Pressure

-60 psf
(See General Limitation #7)

Fastener Spacing
2 ft.

2 ft.



NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 17 of 32

Deck Type 2I: Steel, Insulated

Deck Description: Minimum 18-22 ga. Steel with supports at maximum 6' o.c.

System Type D(1): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply.

Vapor Retarders: (Optional) a FM approved vapor barrier applied directly to the deck or over the

base insulation layer.

Barrier: (Optional) Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade

County approved insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4' and not less than four fasteners for any board with

any greater dimension than 4'.

One or more layers of any approved insulation listed in Table 2.

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Minimum 45 mil thick Sarnafil S327 or Sikaplan 45 attached to deck as specified

below.

Fastening #1: Sarnafastener-XP fasteners and Sarnadisc XPN plates spaced 6" o.c. within 5.5"

wide side laps spaced maximum 114.5" o.c. Laps are sealed with a minimum

0.5" wide outside edge heat weld.

Maximum Design Pressure -45.0 psf. (See General Limitation #7)

Fastening #2: Sarnafastener MAXLoad fasteners and Sarnadisc MAXLoad plates spaced 6" o.c.

within 7" wide side laps spaced maximum 113" o.c. Laps are sealed with a

minimum 0.875" wide outside edge heat weld.

Maximum Design Pressure -60.0 psf (See General Limitation #7)

Maximum Design

Pressures:

See Fastening Pattern. (See General Limitation #7)

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 18 of 32



Deck Type 2I: Steel, Insulated

Deck Description: Minimum 18-22 ga. Steel with supports at maximum 6' o.c.

System Type D(2): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply.

Vapor Retarders: (Optional) a FM approved vapor barrier applied directly to the deck or over the

base insulation layer.

Barrier: (Optional) Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade

County approved insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4' and not less than four fasteners for any board with

any greater dimension than 4'.

One or more layers of any approved insulation listed in Table 2.

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Minimum 45 mil thick Sarnafil S327 or Sikaplan 45 attached to deck as specified

below with Sarnarail Polymer Batten Strips.

Fastening #1: Sarnafastener MAXLoad fasteners spaced 18" o.c. through batten strip spaced

maximum 73.25" o.c. within the 5.5" wide side lap. Batten strip splice joints are made by overlapping the batten 24" and securing with two Sarnafastener

MAXLoad screws spaced 18" o.c. Laps are sealed with at 1.5" wide heat weld on

the outside edge and 1.0" wide heat weld on the inside edge.

Maximum Design Pressure -45.0 psf. (See General Limitation #7)

Fastening #2: Sarnafastener-XP fasteners spaced 12" o.c. through batten strip spaced maximum

73.25" o.c. within the 5.5" wide side lap. Batten strip splice joints are made by overlapping the batten 18" and securing with two Sarnafastener XP screws spaced 12" o.c. Laps are sealed with at 1.5" wide heat weld on the outside edge and 1.0"

wide heat weld on the inside edge.

Maximum Design Pressure -45.0 psf. (See General Limitation #7)

Fastening #3: Sarnafastener-XP fasteners spaced 6" o.c. through batten strip spaced maximum

144" o.c. within the 5.5" wide side lap. Batten strip splice joints are made by overlapping the batten 12" and securing with two Sarnafastener XP screws spaced 6" o.c. Laps are sealed with at 1.5" wide heat weld on the outside edge and 1.0"

wide heat weld on the inside edge.

Maximum Design Pressure -52.5 psf. (See General Limitation #7)

Fastening #4: Sarnafastener-XP fasteners spaced 6" o.c. through batten strip spaced maximum

73.25" o.c. within the 5.5" wide side lap. Batten strip splice joints are made by overlapping the batten 12" and securing with two Sarnafastener XP screws spaced 6" o.c. Laps are sealed with at 1.5" wide heat weld on the outside edge and 1.0"

wide heat weld on the inside edge.

Maximum Design Pressure -75.0 psf. (See General Limitation #7)

Maximum Design

Pressures: See Fastening Pattern. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 19 of 32

Deck Type 2I: Steel, Insulated

Deck Description: Minimum 18-22 ga. Steel with supports at maximum 6' o.c.

System Type D(3): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply.

Vapor Retarders: (Optional) a FM approved vapor barrier applied directly to the deck or over the

base insulation layer.

Barrier: (Optional) Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade

County approved insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4' and not less than four fasteners for any board with

any greater dimension than 4'.

One or more layers of any approved insulation listed in Table 2.

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Minimum 45 mil thick Sarnafil S327 or Sikaplan 45 attached to deck as specified

below.

Fastening #1: Sarnafastener MAXLoad fasteners and ³/₄" wide Sarnarail Polymer Batten Strip

spaced 12" o.c. within 5.5" wide side laps spaced maximum 114.5" o.c. Batten Strip is lapped 14" within lap to provide a minimum 2 screw securement in lap. Laps are sealed with a minimum 1.25" wide outside edge heat weld and minimum

0.75" wide inside edge heat weld.

Maximum Design Pressure -45.0 psf (See General Limitation #7)

Fastening #2: Sarnafastener-XP fasteners or OMG Large Head #15 Roofgrip fasteners and ³/₄"

wide Sarnarail Polymer Batten Strip spaced 6" o.c. within 5.5" wide side laps spaced maximum 114.5" o.c. Batten Strip is lapped 8" within lap to provide a minimum 2 screw securement in lap. Laps are sealed with a minimum 1.25" wide

outside edge heat weld and minimum 0.75" wide inside edge heat weld.

Maximum Design Pressure -60.0 psf. (See General Limitation #7)

Fastening #3: Sarnafastener MAXLoad fasteners and ³/₄" wide Sarnarail Polymer Batten Strip

spaced 6" o.c. within 5.5" wide side laps spaced maximum 114.5" o.c. Batten Strip is lapped 8" within lap to provide a minimum 2 screw securement in lap. Laps are sealed with a minimum 1.25" wide outside edge heat weld and minimum

0.75" wide inside edge heat weld.

Maximum Design Pressure -67.5 psf (See General Limitation #7)

Maximum Design

Pressures:

See Fastening Pattern. (See General Limitation #7)

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 20 of 32



Deck Type 2I: Steel, Insulated

Deck Description: 18-22 ga. steel

System Type D(4): Membrane attached over preliminary fastened insulation.

The following assembly is approved to a maximum design pressure listed with specific fastening patterns. No substitutions shall be made. All General and System Limitations apply.

Deck: Minimum 18-22 ga Grade E steel deck shall be secured to ¹/₄" thick structural

supports spaced a maximum of 6 ft on centers with ITW Buildex Traxx/5 at the

bottom of each rib (6" o/c.)

All General and System Limitations apply.

Vapor Retarders: (Optional) a FM approved vapor barrier applied directly to the deck or over the

base insulation layer.

Barrier: (Optional) Minimum 5/8" Type X Gypsum or ½ " DensDeck.

One or more of the following.

Insulation for Base Layer Fastener Type Fastener Density/ft²

ACFoam II, ACFoam Composite (bottom layer only), ACFoam Supreme, H-Shield

Minimum 1.3" thick or tapered N/A N/A

Sarnatherm, Sarnatherm-25 PSI, ENRGY 3, ENRGY 3 Plus, ENRGY 3 PSI-25, ISO 95+ GL

Minimum 1.4" thick or tapered N/A N/A

Approved High Density Wood Fiberboard (base layer only)

Minimum 1" thick N/A N/A

Multi-Max FA-3, Thermaroof-3

Minimum 1.25" thick or tapered N/A N/A

DensDeck, DensDeck Prime

Minimum ¹/₄" thick N/A N/A

Approved Perlite (base layer only)

Minimum ³/₄" thick N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sarnafil S327 or Sikaplan 45 attached to deck as specified below.

Fastening #1: Sarnafastener-XP screws and plates spaced 12 in. o.c. within 5.5 in. wide side laps.

Laps spaced 73 in. o.c. and sealed with a 1.5 in. wide heat weld.

Maximum Design Pressure -45 psf. (See General Limitations # 7)



NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 21 of 32 **Fastening # 2:** Sarnafastener-XP screws with 2" Sarnadisc- plates spaced 12 in. o.c. within 6 in.

wide side laps. Laps spaced 72.5 in. and sealed with a 0.75 in. wide heat weld on

the inside and a 1.5 in. heat weld on the outside.

Maximum Design Pressure -45 psf. (See General Limitations # 7)

Fastening #3: Sarnafastener-XP screws and plates spaced 6 in. o.c. within 5.5 in. wide side laps.

Laps spaced 73.5 in. o.c. and sealed with a 1.5 in. wide heat weld. Maximum Design Pressure -75 psf. (See General Limitations # 7)

Fastening #4: Sarnafastener-XP screws with 2" Sarnadisc plates spaced 6 in. o.c. within the 6 in.

wide side laps. Laps spaced 72.5 in. and sealed with a 0.75 in. wide heat weld on

the inside and a 1.5 in. heat weld on the outside.

Maximum Design Pressure -82.5 psf. (See General Limitations # 7)

Fastening # 5: Sarnabars spaced 3' o.c. maximum fastened with Sarnafastener-XP spaced 6 in.

o.c. through the field of the membrane and covered with a 7" minimum width

cover strip with 1.5" welds on each side.

Maximum Design Pressure -112.5 psf. (See General Limitations # 7)

Maximum Design

Pressures:

See Fastening Pattern. (See General Limitations # 7)



NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 22 of 32

Deck Type 2I: Steel, Insulated

Deck Description: Minimum 18-22 ga. Steel with supports at maximum 6' o.c.

System Type D(5): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply.

Vapor Retarders: (Optional) a FM approved vapor barrier applied directly to the deck or over the

base insulation layer.

Barrier: (Optional) Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade

County approved insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4' and not less than four fasteners for any board with

any greater dimension than 4'.

One or more layers of any approved insulation.

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Minimum 45 mil thick Sarnafil S327 or Sikaplan 45 attached to deck as specified

below.

Fastening #1: Sarnafastener MAXLoad fasteners and Sarnarail Polymer Batten Strip spaced 24"

o.c. within 5.5" wide side laps spaced maximum 54" o.c. Laps are sealed with a minimum 1" wide outside heat weld and a minimum 5/8" wide inside heat weld.

Maximum Design Pressure -45.0 psf. (See General Limitation #7)

Fastening #2: Sarnafastener MAXLoad fasteners and Sarnadisc MAXLoad plates spaced 24" o.c.

within 6.5" wide side laps spaced maximum 53" o.c. Laps are sealed with a

minimum 1.6"" wide outside heat weld.

Maximum Design Pressure -45.0 psf. (See General Limitation #7)

Fastening #3: Sarnafastener MAXLoad fasteners and Sarnadisc MAXLoad plates spaced 12" o.c.

within 7" wide side laps spaced maximum 113" o.c. Laps are sealed with a

minimum 1.5"" wide outside heat weld.

Maximum Design Pressure -45.0 psf. (See General Limitation #7)

Fastening #4: Sarnafastener-XP fasteners and Sarnarail Polymer Batten Strip spaced 12" o.c.

within 5.5" wide side laps spaced maximum 54" o.c. Laps are sealed with a minimum 1" wide outside heat weld and a minimum 5/8" wide inside heat weld.

Maximum Design Pressure -52.5 psf. (See General Limitation #7)

Fastening #5: Sarnafastener MAXLoad fasteners and Sarnarail Polymer Batten Strip spaced 18"

o.c. within 5.5" wide side laps spaced maximum 54" o.c. Laps are sealed with a minimum 1" wide outside heat weld and a minimum 5/8" wide inside heat weld.

Maximum Design Pressure -52.5 psf. (See General Limitation #7)

Fastening #6: Sarnafastener MAXLoad fasteners and Sarnadisc MAXLoad plates spaced 18" o.c.

within 6.5" wide side laps spaced maximum 53" o.c. Laps are sealed with a

minimum 1.6"" wide outside heat weld.

Maximum Design Pressure -52.5 psf. (See General Limitation #7)

(MIAMI-DADE COUNTY APPROVED

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 23 of 32 **Fastening #7:** Sarnafastener-XP fasteners and Sarnadisc XPN plates spaced 12" o.c. within 5.5"

wide side laps spaced maximum 54" o.c. Laps are sealed with a minimum 1.6"

wide outside heat weld.

Maximum Design Pressure -60.0 psf. (See General Limitation #7)

Fastening #8: Sarnafastener MAXLoad fasteners and Sarnadisc MAXLoad plates spaced 12" o.c.

within 6.5" wide side laps spaced maximum 53" o.c. Laps are sealed with a

minimum 1.6" wide outside heat weld.

Maximum Design Pressure -60.0 psf. (See General Limitation #7)

Fastening #9: Sarnafastener MAXLoad fasteners and Sarnarail Polymer Batten Strip spaced 12"

o.c. within 5.5" wide side laps spaced maximum 54" o.c. Laps are sealed with a minimum 1" wide outside heat weld and a minimum 5/8" wide inside heat weld.

Maximum Design Pressure -67.5 psf. (See General Limitation #7)

Fastening #10: Sarnafastener-XP fasteners and Sarnadisc XPN plates spaced 6" o.c. within 5.5"

wide side laps spaced maximum 54" o.c. Laps are sealed with a minimum 1.6"

wide outside heat weld.

Maximum Design Pressure -90.0 psf. (See General Limitation #7)

Fastening #11: Sarnafastener MAXLoad fasteners and Sarnadisc MAXLoad plates spaced 6" o.c.

within 6.5" wide side laps spaced maximum 53" o.c. Laps are sealed with a

minimum 1.6"" wide outside heat weld.

Maximum Design Pressure -105.0 psf. (See General Limitation #7)

Fastening #12: Sarnafastener MAXLoad fasteners and Sarnarail Polymer Batten Strip spaced 6"

o.c. within 5.5" wide side laps spaced maximum 54" o.c. Laps are sealed with a minimum 1" wide outside heat weld and a minimum 5/8" wide inside heat weld.

Maximum Design Pressure -112.5 psf. (See General Limitation #7)

Maximum Design

Pressures: See Fastening Pattern. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 24 of 32

Deck Type 2I: Steel, Insulated

Deck Description: Minimum 18-22 ga. steel

System Type D(6): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply.

Barrier: (Optional) Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade

County approved insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4' and not less than four fasteners for any board

with any greater dimension than 4'.

One or more layers of the following.

Insulation Layer Fastener Type Fastener Density/ft²

ACFoam II, ACFoam Composite (bottom layer only), ACFoam Supreme

Minimum 1.3" thick or tapered N/A N/A

Sarnatherm, Sarnatherm-25 PSI, ENRGY 3, ENRGY 3 Plus, ENRGY 3 PSI-25, ISO 95+ GL

Minimum 1.4" thick or tapered N/A N/A

Multi-Max FA-3, Thermaroof-3

Minimum 1.25" thick or tapered N/A N/A

Approved High Density Wood Fiberboard (base layer only)

Minimum 1" thick or tapered N/A N/A

DensDeck, DensDeck Prime

Minimum ¹/₄" thick N/A N/A

Approved Perlite (base layer only)

Minimum ³/₄" thick N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sarnafil S327 or Sikaplan 45 attached to deck as specified below.

Fastening #1: Sarnafastener or SFS Fasteners with approved discs spaced 6" o.c. within the

5.5" side lap spaced 73" o.c. and sealed with a minimum 1.5" weld.

Fastening #2: Sarnafastener with approved discs spaced 6" o.c. in rows 12' o.c. maximum, or

Sarnabars spaced 12' o.c. maximum fastened with Sarnafastener spaced 6 in. o.c. through the field of the membrane and covered with a 7" minimum width

cover strip with 1.5" welds on each side.

Maximum Design

Pressures: -52.5 psf. (See General Limitation #9)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 25 of 32

Deck Type 2I: Steel, Insulated

Deck Description: Minimum 18-22 ga. Steel with supports at maximum 6' o.c.

System Type D(7): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply.

Vapor Retarders: (Optional) a FM approved vapor barrier applied directly to the deck or over the

base insulation layer.

Barrier: (Optional) Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade

County approved insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4' and not less than four fasteners for any board with

any greater dimension than 4'.

One or more layers of any approved insulation listed in Table 2.

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Minimum 48 mil thick Sarnafil S327 or Sikaplan 45 attached to deck as specified

below with Sarnarail Polymer Batten Strips.

Fastening: Sarnafastener MAXLoad fasteners spaced 18" o.c. through batten strip spaced

maximum 73.25" o.c. within the 5.5" wide side lap. Batten strip splice joints are

made by overlapping the batten 24" and securing with two Sarnafastener

MAXLoad screws spaced 18" o.c. Laps are sealed with at 1.5" wide heat weld on

the outside edge and 1.0" wide heat weld on the inside edge.

Maximum Design

-52.5 psf. (See General Limitation #7)

Pressures:



NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 26 of 32

Deck Type 2I: Steel, Insulated

Deck Description: 18 ga. steel deck fastened to supports spaced maximum 6 ft. o.c. with Traxx 5

fasteners spaced 6 in. o.c. and with side laps fastened with two Traxx 1 fasteners

spaced maximum 24 in. o.c.

System Type D(8): Membrane attached over preliminary fastened insulation.

The following assembly is approved to a maximum design pressure listed with specific fastening patterns. No substitutions shall be made. All General and System Limitations apply.

Deck: Minimum 18 ga. steel deck shall be secured to structural supports spaced a maximum of 6

ft. o.c. with Traxx 5 fasteners spaced 6 in. o.c. and with side laps fastened with two Traxx

1 fasteners minimum 24 in. o.c.

All General and System Limitations apply.

One or more of the following.

<u>Base Insulation Layer</u> <u>Fastener Density/ft²</u> <u>Fastener Type</u>

Any Approved Insulation listed in Table 2

Minimum 0.25" thick N/A N/A

<u>Top Insulation Layer (Optional)</u> <u>Fastener Density/ft²</u> <u>Fastener Type</u>

Any Approved Cover Board listed in Table 2

Minimum 0.25" thick N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sarnafil S327, S327 Felt Backed or Sikaplan 45 attached to deck as specified

below.

Fastening: Sarnafastener-XP fasteners with Sarnadisc-XPN plates spaced 6 in. o.c. in

staggered rows spaced 9.5 ft. o.c. Side lap is sealed with minimum ³/₄" wide heat

weld.

Maximum Design

Pressures:

-52.5 psf (See General Limitations # 7)

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 27 of 32



Deck Type 2I: Steel, Insulated

Deck Description: Minimum 18-22 ga. steel

System Type D(9): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply.

Vapor Retarders: (Optional) a FM approved vapor barrier applied directly to the deck or over the

base insulation layer.

Barrier: (Optional) Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade

County approved insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4' and not less than four fasteners for any board with

any greater dimension than 4'.

One or more layers of any approved insulation listed in Table 2.

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sarnafil S327 or Sikaplan 45 attached to deck as specified below with Sarnarail

Polymer Batten Strips spaced at 114.5" o.c. within a 5.5" wide lap.

Fastening #1: Sarnafastener-XP fasteners spaced 6" o.c. through batten strip. Batten strip is

lapped 8" and sealed with a 1.25" wide heat weld on outside edge and a 0.75" wide

heat weld on inside edge.

Maximum Design Pressure -52.5 psf. (See General Limitation #7)

Fastening #2: Sarnafastener MAXLoad fasteners spaced 12" o.c. through batten strip. Batten

strip is lapped 14" and sealed with a 1.25" wide heat weld on outside edge and a

0.75" wide heat weld on inside edge.

Maximum Design Pressure -52.5 psf. (See General Limitation #7)

Fastening #3: Sarnafastener MAXLoad fasteners spaced 6" o.c. through batten strip. Batten strip

is lapped 8" and sealed with a 1.25" wide heat weld on outside edge and a 0.75"

wide heat weld on inside edge.

Maximum Design Pressure -67.5 psf. (See General Limitation #7)

Maximum Design

Pressures:

See Fastening Pattern. (See General Limitation #7)

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 28 of 32



Deck Type 2I: Steel, Insulated

Deck Description: Minimum 18-22 ga. steel

System Type D(10): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply.

Vapor Retarders: (Optional) a FM approved vapor barrier applied directly to the deck or over the

base insulation layer.

Barrier: (Optional) Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade

County approved insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4' and not less than four fasteners for any board with

any greater dimension than 4'.

One or more layers of any approved insulation listed in Table 2.

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sarnafil S327 or Sikaplan 45 attached to deck as specified below.

Fastening: Sarnafastener-XP fasteners and Sarnadisc-XPN plates spaced 6" o.c. within 5.5"

wide laps spaced 114.5" o.c. Laps are sealed with a 1.75" wide heat weld on

outside edge of lap.

Maximum Design

-60.0 psf. (See General Limitation #7)

Pressures:

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 29 of 32



Deck Type 2I: Steel, Insulated

Deck Description: Minimum 18-22 ga. Steel with supports at maximum 5.5' o.c.

System Type D(11): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply.

Vapor Retarders: (Optional) a FM approved vapor barrier applied directly to the deck or over the

base insulation layer.

Barrier: (Optional) Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade

County approved insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4' and not less than four fasteners for any board with

any greater dimension than 4'.

One or more layers of any approved insulation listed in Table 2.

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Minimum 48 mil thick Sarnafil S327 or Sikaplan 45 attached to deck as specified

below with Sarnarail Polymer Batten Strips.

Fastening: Sarnafastener-XP fasteners spaced 6" o.c. through batten strip spaced maximum

144" o.c. within the 5.5" wide side lap. Batten strip splice joints are made by overlapping the batten 12" and securing with two Sarnafastener XP screws spaced 6" o.c. Laps are sealed with at 1.5" wide heat weld on the outside edge and 1.0"

wide heat weld on the inside edge.

Maximum Design

-60.0 psf. (See General Limitation #7)

Pressures:



NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 30 of 32

Deck Type 2I: Steel, Insulated

Deck Description: Minimum 18-22 ga. Steel with supports at maximum 5.5' o.c.

System Type D(12): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply.

Vapor Retarders: (Optional) a FM approved vapor barrier applied directly to the deck or over the

base insulation layer.

Barrier: (Optional) Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade

County approved insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4' and not less than four fasteners for any board with

any greater dimension than 4'.

One or more layers of any approved insulation listed in Table 2.

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Minimum 45 mil thick Sarnafil S327 or Sikaplan 45 attached to deck as specified

below.

Fastening: Sarnafastener MAXLoad fasteners and ¾" wide Sarnarail Polymer Batten Strip

spaced 6" o.c. within 5.5" wide side laps spaced maximum 114.5" o.c. Batten Strip is lapped 8" within lap to provide a minimum 2 screw securement in lap. Laps are sealed with a minimum 1.25" wide outside edge heat weld and minimum

0.75" wide inside edge heat weld.

Maximum Design

-75.0 psf (See General Limitation #7)

Pressures:

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 31 of 32

MIAMI-DADE COUNTY
APPROVED

STEEL DECK SYSTEM LIMITATIONS:

1. If mechanical attachment to the structural deck through the lightweight insulating concrete is proposed, a field withdrawal resistance testing shall be performed to determine equivalent or enhanced fastener patterns and density. All testing and fastening design shall be in compliance with Testing Application Standard TAS 105 and Roofing Application Standard RAS 117 and/or RAS 137; calculations shall be signed and sealed by a Florida Registered Engineer, Architect, or Registered Roof Consultant.

GENERAL LIMITATIONS:

- 1. Fire classification is not part of this acceptance; refer to a current Approved Roofing Materials Directory for fire ratings of this product.
- 2. Insulation may be installed in multiple layers. The first layer shall be attached in compliance with Product Control Approval guidelines. All other layers shall be adhered in a full mopping of approved asphalt applied within the EVT range and at a rate of 20-40 lbs./sq., or mechanically attached using the fastening pattern of the top layer
- 3. All standard panel sizes are acceptable for mechanical attachment. When applied in approved asphalt, panel size shall be 4' x 4' maximum.
- 4. An overlay and/or recovery board insulation panel is required on all applications over closed cell foam insulations when the base sheet is fully mopped. If no recovery board is used the base sheet shall be applied using spot mopping with approved asphalt, 12" diameter circles, 24" o.c.; or strip mopped 8" ribbons in three rows, one at each side lap and one down the center of the sheet allowing a continuous area of ventilation. Encircling of the strips is not acceptable. A 6" break shall be placed every 12' in each ribbon to allow cross ventilation. Asphalt application of either system shall be at a minimum rate of 12 lbs./sq. Note: Spot attached systems shall be limited to a maximum design pressure of -45 psf.
- 5. Fastener spacing for insulation attachment is based on a Minimum Characteristic Force (F') value of 275 lbf., as tested in compliance with Testing Application Standard TAS 105. If the fastener value, as field-tested, are below 275 lbf. Insulation attachment shall not be acceptable.
- 6. Fastener spacing for mechanical attachment of anchor/base sheet or membrane attachment is based on a minimum fastener resistance value in conjunction with the maximum design value listed within a specific system. Should the fastener resistance be less than that required, as determined by the Building Official, a revised fastener spacing, prepared, signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant may be submitted. Said revised fastener spacing shall utilize the withdrawal resistance value taken from Testing Application Standards TAS 105 and calculations in compliance with Roofing Application Standard RAS 117.
- 7. Perimeter and corner areas shall comply with the enhanced uplift pressure requirements of these areas. Fastener densities shall be increased for both insulation and base sheet as calculated in compliance with Roofing Application Standard RAS 117 and/or RAS 137. Calculations prepared, signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant (When this limitation is specifically referred within this NOA, General Limitation #9 will not be applicable.)
- 8. All attachment and sizing of perimeter nailers, metal profile, and/or flashing termination designs shall conform to Roofing Application Standard RAS 111 and applicable wind load requirements.
- 9. The maximum designed pressure limitation listed shall be applicable to all roof pressure zones (i.e. field, perimeters, and corners). Neither rational analysis, nor extrapolation shall be permitted for enhanced fastening at enhanced pressure zones (i.e. perimeters, extended corners and corners). (When this limitation is specifically referred within this NOA, General Limitation #7 will not be applicable.)
- 10. All products listed herein shall have a quality assurance audit in accordance with the Florida Building Code and Rule 9N-3 of the Florida Administrative Code.

END OF THIS ACCEPTANCE

MIAMI-DADE COUNTY
APPROVED

NOA No.: 12-0313.16 Expiration Date: 07/08/13 Approval Date: 06/28/12 Page 32 of 32