

#### MIAMI-DADE COUNTY PRODUCT CONTROL SECTION

11805 SW 26 Street, Room 208 Miami, Florida 33175-2474 T (786)315-2590 F (786) 31525-99

www.miamidade.gov/economy

#### DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER) BOARD AND CODE ADMINISTRATION DIVISION

# **NOTICE OF ACCEPTANCE (NOA)**

**Seaman Corporation** 1000 Venture Boulevard Wooster, OH 44691

#### **SCOPE:**

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER - Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code including the High Velocity Hurricane Zone of the Florida Building Code.

**DESCRIPTION:** FiberTite Single Ply Roof Systems over Steel Decks.

**LABELING:** Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA

**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This revises NOA #11-1219.02 and consists of pages 1 through 31. The submitted documentation was reviewed by Alex Tigera. ALTHU



NOA No.: 12-1019.29 **Expiration Date: 01/05/16** Approval Date: 06/06/13

Page 1 of 31

## **ROOFING SYSTEM APPROVAL**

Category:RoofingSub-Category:Single PlyMaterial:KEEDeck Type:SteelMaximum Design Pressure-105 psf

# TRADE NAMES OF PRODUCTS MANUFACTURED OR LABELED BY APPLICANT: TABLE 1

D.,, J., ,4	D:	Test	Product
<u>Product</u>	<u>Dimensions</u>	<b>Specification</b>	<u>Description</u>
FiberTite	Various	ASTM D 6754	KEE, polyester reinforced, single ply membrane
FiberTite-XT	Various	ASTM D 6754	KEE, polyester reinforced, single ply membrane
FiberTite-SM	Various	ASTM D 6754	KEE, polyester reinforced, single ply membrane
FiberTite-XTreme	Various	ASTM D 6754	KEE, polyester reinforced, single ply membrane
Style 80, Style 80-M	Various	ASTM D 6754	KEE, polyester reinforced, single ply membrane
FiberTite FB	Various	ASTM D 6754	KEE, fleece-backed, single ply membrane
FiberTite-XT FB	Various	ASTM D 6754	KEE, fleece-backed, polyester reinforced, single ply membrane
FiberTite-SM FB	Various	ASTM D 6754	KEE, fleece-backed, polyester reinforced, single ply membrane
Style 80 FB, Style 80-M FB	Various	ASTM D 6754	KEE, fleece-backed, polyester reinforced, single ply membrane
FTR Non-Reinforced	0.060" x 48" x 24'	ASTM D 6754	KEE flashing accessory
FTR Cones	1" to 8"	ASTM D 6754	premolded "KEE" pipe flashing
FTR Corners	2' x 2'	ASTM D 6754	premolded "KEE" corner flashing (4 per unit)
FTR 190		Proprietary	Two side "contact" bonding adhesive
FTR 190e		Proprietary	Low VOC solvent based "contact" adhesive
FTR 290		Proprietary	One side "substrate only" fleece back solvent based adhesive
FTR 390		Proprietary	One side "substrate only" fleece back asphalt based adhesive
FTR 490		Proprietary	One side "substrate only" fleece backed water based adhesive
FTR 601		Proprietary	Elastomeric, One step foamable adhesive
FiberClad	48" x 120"	N/A	Polymeric coated G-90 galvanized steel, stainless steel or aluminum
Tuff Trac	0.080" x 28" or 56" x 43' 1/4" x 24" x 48"	N/A	Vinyl walk way Vinyl protection pad



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 2 of 31

# **APPROVED INSULATIONS:**

## TABLE 2

<b>Product Name</b>	<b>Product Description</b>	Manufacturer (With Current NOA)
FTR-Value, FTR-Value A, FTR-Value IV A, FTR-Value H	Isocyanurate Insulation	Seaman Corporation
ACFoam-II, ACFoam-IV	Isocyanurate Insulation	Atlas Roofing Corporation
ACFoam Composite	Isocyanurate Insulation with perlite facer	Atlas Roofing Corporation
EnergyGuard Composite	Polyisocyanurate foam insulation with high density fiberboard or perlite insulation.	GAF Materials Corporation
DensDeck, DensDeck Prime	Silicon treated gypsum	Georgia-Pacific Gypsum LLC
Type X Gypsum	Gypsum Wallboard	Generic
Multi-Max-3, Multi-Max FA-3	Polyisocyanurate foam insulation	Rmax Operating, LLC
Thermaroof Composite-3	Polyisocyanurate/perlite composite insulation.	Rmax Operating, LLC
SECUROCK Gypsum-Fiber Roof Board	Gypsum Coverboard	United States Gypsum Corporation
H-Shield	Polyisocyanurate insulation	Hunter Panels, LLC
ENRGY 3, ENRGY 3 25 PSI	Isocyanurate Insulation	Johns Manville Corporation
High Density Roof Fiberboard	Wood Fiber insulation board.	Generic
FiberTop E	Wood Fiber insulation board.	Firestone Building Products Company, LLC



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 3 of 31

# **APPROVED FASTENERS:**

## TABLE 3

<u>Fastener</u> <u>Number</u>	<u>Product</u> <u>Name</u>	Product Description	<u>Dimensions</u>	Manufacturer (With Current NOA)
1.	FTR Magnum	Membrane fastener	Various	Seaman Corporation
2.	FTR #14	Membrane fastener	Various	Seaman Corporation
3.	FTR Magnum plate	Galvalume AZ50 stress plate	1.5" x 2.5"	Seaman Corporation
4.	FTR Magnum 2 <sub>s</sub>	Barbed, galvalume AZ50 stress plate	2-3/8" Dia.	Seaman Corporation
5.	Dekfast Galvalume Steel Round 2-3/8 in 20-Ga. Barbed Plate	Barbed, galvalume AZ50 stress plate	2-3/8" Dia.	SFS Intec, Inc.
6.	Dekfast Isofast IF-2.375- AT Membrane Plate	Galvalume AZ50 stress plate, #15 belted fasteners	2-3/8" Dia.	SFS Intec, Inc.
7.	Dekfast Fasteners	Insulation and membrane fasteners	Various	SFS Intec, Inc.
8.	Dekfast Galvalume Steel Hex	Galvalume AZ50 steel plate	2 7/8" x 3 <sup>1</sup> / <sub>4</sub> "	SFS Intec, Inc.
9.	OMG Heavy Duty	Self-drilling fastener for use in steel, wood or concrete decks	Various	OMG, Inc.
10.	OMG 3-in Galvalume Steel Plate	Galvalume coated steel plate	3" round	OMG, Inc.
11.	OMG 3-in Ribbed Galvalume Plate	Galvalume coated steel plate	3" round	OMG, Inc.
12.	Dekfast #15 HS	Self-drilling, carbon fastener	Various	SFS Intec, Inc.
13.	OMG ASAP Fastener	Preassembled fastener and plate	3" round	OMG, Inc.
14.	Flat Bottom Plate	Aluminized steel plate	3" squre	OMG, Inc.
15.	OMG Standard Fastener	Steel fastener for use in steel and wood decks	Various	OMG, Inc.
16.	Dekfast 1½" x 2¾"Oval Barbed Plate	Oval stress plate	1½" x 2¾"	SFS Intec, Inc.
17.	FTR Magnum T	#15 threaded fastener	Various	Seaman Corp.
18.	FTR Magnum R275	AZ-55 Galvalume steel stress plate	2.75" round	Seaman Corp.
19.	Trufast #21 SHD Fasteners	Insulation fastener for wood, steel and concrete decks	Various	Altenloh, Brinck & Co. U.S., Inc.
20.	Trufast #15 EHD fasteners	Insulation fastener for wood, steel and concrete decks	Various	Altenloh, Brinck & Co. U.S., Inc.
21.	Trufast 2-3/4" Barbed Seam Plate	AZ-55 Galvalume steel stress plate	2.75" round	Altenloh, Brinck & Co. U.S., Inc.
22.	FTR Magnum Plus	Oval stress plate	1½" x 2¾"	Seaman Corp.



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 4 of 31

# **APPROVED FASTENERS:**

## TABLE 3

<u>Fastener</u> <u>Number</u>	<u>Product</u> <u>Name</u>	<u>Product</u> <u>Description</u>	<b>Dimensions</b>	Manufacturer (With Current NOA)
23.	Deckfast Galvalume Steel 3-in Round Plate	Galvalume AZ50 stress plate	3" round	SFS Intec, Inc.
24.	FTR 3-in Steel Plate	Galvalume AZ50 stress plate	3" round	Seaman Corp.
25.	Trufast #12 DP Fastener	Tru-Kote PC-3 coated, carbon steel fastener	Various	Altenloh, Brinck & Co. U.S., Inc.
26.	Trufast 3" Metal Insulation Plate	Galvalume AZ50 stress plate	3.23" round	Altenloh, Brinck & Co. U.S., Inc.
27.	OMG 3-in Galvalume Steel Plate	Galvalume coated steel plate	3" round	OMG, Inc.
28.	OMG 3-in Ribbed Galvalume Plate	Galvalume coated steel plate	3" round	OMG, Inc.
29.	OMG Standard Roofgrip	CR-10 coated, carbon steel fastener	Various	OMG, Inc.
30.	Trufast #14 HD Fastener	Insulation fastener for steel and wood decks	Various	Altenloh, Brinck & Co. U.S., Inc.
31.	OMG Accutrac Hextra	Carbon steel fastener	Various	OMG, Inc.
32.	OMG Accutrac Flat Bottom	Galvalume steel plate	3" square	OMG, Inc.
33.	ASAP RoofGrip Pre- Assembled System	Pre-assembled system consisting of Roofgrip fasteners and plates	Various	OMG, Inc



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 5 of 31

# **EVIDENCE SUBMITTED:**

Test Agency/Identifier	<u>Name</u>	Report	<u>Date</u>
Factory Mutual Research Corp.	FMRC 4470	J.I. #1Z2A5.AM	01/12/96
1	Class 4470	J.I. 1Z3A8.AM	08/13/97
	Class 4470	30003251	10/15/99
	Class 4470	3006872	06/13/2000
	Class 4470	3009071	01/03/02
	Class 4470	3014050	07/08/03
	FM 4470	3038211	06/30/10
	FM 4470	3036192	11/23/09
	FM 4470	3028651	04/17/08
	FM 4470	3033396	09/04/09
	FM 4470	3030785	08/12/08
	FM 4470	3037168	04/12/10
	FM 4470	3037770	10/22/09
	FM 4470	3013125	09/23/03
	FM 4470	3013068	09/23/03
	FM 4470	3023458	07/18/06
	FM 4470	3026964	07/25/07
	FM 4470	3033314	08/26/08
	FM 4470	3003689	09/22/99
Underwriters Laboratories	UL 790	98NK12810	8/11/98
		98NK17212	8/21/98
Exterior Research & Design, LLC	TAS 114	4015.10.96-1-R1	07/20/10
	TAS 114	4006.07.97-1-R1	07/15/10
	TAS 114	4006.08.00-1-R1	10/18/05
	TAS 114	02843.02.05-08	02/04/05
	TAS 114/117	C12410.08.09	08/14/09
	TAS 117 & ASTM D6862	C850SC.11.07-R1	08/07/09
	FM 4470 / TAS 114	S32410.09.10	09/21/10
	ASTM D6754	S34070.06.11-R3	05/30/13
Trinity   ERD	ASTM D 6754	S34070.06.11-R1	06/18/12
PRI Construction Materials Technologies LLC	ASTM D 3747	HGC-142-02-03	02/09/12



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 6 of 31

## **APPROVED ASSEMBLIES**

**Membrane Type:** Single Ply, KEE

Deck Type 2I: Steel Decks, Insulated

Deck Description: Min. 18-22 ga. steel

System Type B(1): Base layer of insulation mechanically attached, top layer adhered; membrane adhered

### All General and System Limitations apply.

One or more layers of the following insulations:

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
FTR-Value, FTR-Value A, FTR-Value H, ACFoam-II, Minimum 1.5" thick	H-Shield, ENRGY 3, Multi-Max FA-3 7 (#12) with 8	1:2 ft <sup>2</sup>
DensDeck, DensDeck Prime Minimum ¼" thick	7 (#12) with 8	1:2 ft <sup>2</sup>

Note: Base layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

**Membrane:** FiberTite-SM, FiberTite-XTreme or Style 80-M roof cover adhered to the insulation with

with FTR-490 water based adhesive at 0.66 to 0.71 gal/sq or with FTR-190e Bonding

Adhesive applied to substrate and cover at 0.5 gal/sq.

Or

FiberTite-FB, FiberTite-XT FB, FiberTite-SM FB, Style 80 FB or Style 80-M FB roof cover

adhered to the insulation with FTR-490 water based adhesive at 0.83 to 1 gal/sq.

**Maximum Design** 

**Pressure:** 

-45 psf (See General Limitation #9.)



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13

Page 7 of 31

Deck Type 21: Steel Decks, Insulated

Deck Description: Min. 18-22 ga. steel

System Type B(2): Base layer of insulation mechanically attached, top layer adhered; membrane adhered

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following insulations:

Base Insulation Layer	<b>Insulation Fasteners</b>	<u>Fastener</u>
	<u>(Table 3)</u>	Density/ft <sup>2</sup>
FTR-Value, FTR-Value A, FTR-Value H, ACFo	oam–II, H-Shield, ENRGY 3	
Minimum 2" thick	2, 9 or 7 (#14)	$1:2.67 \text{ ft}^2$
Minimum 2" thick	2, 7 (#14) or 9	$1:1.33 \text{ ft}^2$

Note: Base layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Top Insulation Layer</u>	<b>Insulation Fasteners</b>	<b>Fastener</b>
	<u>(Table 3)</u>	<b>Density/ft<sup>2</sup></b>
SECUROCK Gypsum-Fiber Roof Board		
Minimum 0.25" thick	N/A	N/A

Note: Apply top layer of insulation in a full mopping of any approved mopping hot asphalt within the EVT range and at a rate of 25 lbs/100 ft<sup>2</sup> or Olybond applied in a full coating application of 1gal/100 ft<sup>2</sup> or ¾" to 1" wide beads 12" o.c. of FTR 601, Olybond 500, Millennium One Step Foamable Insulation Adhesive or Insta-Stik Adhesive. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate.

**Membrane:** FiberTite, FiberTite-XT, FiberTite-SM, FiberTite-XTreme, Style 80 or Style 80-M roof cover

adhered to the insulation with FTR-190 Bonding Adhesive or FTR-190e Bonding Adhesive

applied at an application rate of 50 ft<sup>2</sup>/gal. Laps are sealed with 1.5-inch heat weld.

Or

FiberTite–FB, FiberTite-XT FB, FiberTite-SM FB, Style 80 FB or Style 80-M FB roof cover adhered to the insulation with approved asphalt at 20-25 lbs./sq., FTR-290 solvent adhesive at 90 ft²/gal or FTR-490 water based adhesive at 100 ft²/gal. Laps are sealed with 1.5-inch heat

weld.

Maximum Design -45 psf (See General Limitation #9.)

**Pressure:** -60 psf (attached at 1 fastener per 1.33 ft<sup>2</sup>) (See General Limitation #7.)



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 8 of 31

**Deck Type 2I**: Steel Decks, Insulated

**Deck Description:** 18-22 ga. steel

System Type B(3): Base layer of insulation mechanically attached, top layer adhered; membrane adhered

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Base Insulation Layer	<b>Insulation Fasteners</b>	<b>Fastener</b>
	<u>(Table 3)</u>	Density/ft <sup>2</sup>
FTR-Value A, ACFoam-II, Multi-Max FA-3, FTR-Value H, H-Shield	d	
Minimum 1.5" thick	2 or 7 (#14)	$1:2 \text{ ft}^2$
Minimum 2" thick	2 or 7 (#14)	$1:4 \text{ ft}^2$
DensDeck, DensDeck Prime		
Minimum 0.25" thick	2 or 7 (#14)	$1:2 \text{ ft}^2$

Note: Base layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Top Insulation Layer (Optional)	<b>Insulation Fasteners</b>	<b>Fastener</b>
	<u>(Table 3)</u>	<b>Density/ft<sup>2</sup></b>
FTR-Value A, ACFoam-II, Multi-Max FA-3, FTR-Value H, H-Shield		
Minimum 1.5" thick	N/A	N/A

Note: Apply optional top layer of insulation in a full mopping of any approved mopping hot asphalt within the EVT range and at a rate of 20-40 lbs/100 ft<sup>2</sup> or in <sup>3</sup>/<sub>4</sub>" to 1" wide beads 12" o.c. of FTR 601 or Insta-Stik Adhesive or OlyBond Adhesive Fastener at application rate of 1gal/100 ft<sup>2</sup>. Refer to Roofing Application Standard RAS 117 and insulation adhesive manufacturer's Roofing Component Product Control Approval for insulation attachment requirements. Insulations listed as base layer shall be used only as base layers with an optional top layer insulation installed as the final membrane substrate.

**Vapor Retarders:** (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck or over a base

layer of insulation.

Fire Barrier: (Optional) 1/4" DensDeck or DensDeck Prime applied to the base or top insulation layer in a

full mopping of approved hot asphalt within the EVT range and at a rate of 20-40 lbs./100 ft<sup>2</sup> or in <sup>3</sup>/<sub>4</sub>" to 1" wide beads 12" o.c. of FTR 601 or Insta-Stik Adhesive or OlyBond Adhesive Fastener at application rate of 1gal/100 ft<sup>2</sup> or Type X Gypsum applied in <sup>3</sup>/<sub>4</sub>" to 1" wide beads

of Insta-Stik Adhesive, 12" o.c.



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 9 of 31

#### **Membrane:**

FiberTite, FiberTite-XT, FiberTite-SM, FiberTite-XTreme, Style 80 or Style 80-M roof cover adhered to the insulation with FTR-190 Bonding Adhesive or FTR-190e Bonding Adhesive applied at an application rate of 1 gal./sq. to the backside of the membrane and to the substrate. Laps are sealed with 1.5-inch heat weld.

Or

FiberTite-FB, FiberTite-XT FB, FiberTite-SM FB, Style 80 FB or Style 80-M FB roof cover adhered to the insulation with approved asphalt at 20-25 lbs./sq., FTR-290 solvent adhesive at 1 gal. per 100 ft<sup>2</sup> or FTR-390 asphalt based adhesive at 1 gal. per 60 ft<sup>2</sup> or FTR-490 water based adhesive at 100 ft<sup>2</sup>/gal. Laps are sealed with 1.5-inch heat weld.

## **Maximum Design Pressure:**

-45 psf (for applications utilizing FleeceBacked membranes) (See General Limitation #9.) -60 psf (for 2" thick insulation attached at 1 fastener per 4 ft<sup>2</sup> with FiberTite, FiberTite-XT or Style 80) (See General Limitation #9.)

-67.5 psf (for 1.5" thick insulation attached at 1 fastener per 2 ft<sup>2</sup> with FiberTite, FiberTite-XT or Style 80) (See General Limitation #9.)



NOA No.: 12-1019.29 **Expiration Date: 01/05/16** Approval Date: 06/06/13

Page 10 of 31

Single Ply, KEE **Membrane Type:** 

Deck Type 2I: Steel Decks, Insulated **Deck Description:** Min. 18-22 ga. steel

**System Type C(1):** All layers of insulation simultaneously attached; membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following.

Base Insulation Layer (Optional)	<u>Insulation Fasteners</u> (Table 3)	<u>Fastener</u> <u>Density/ft²</u>
FTR-Value, FTR-Value A, FTR-Value H, ACFoam-II, H-Shio	eld, ENRGY 3	
Minimum 1.5" thick	N/A	N/A
Top Insulation Layer	<u>Insulation Fasteners</u> (Table 3)	<u>Fastener</u> <u>Density/ft²</u>
SECUROCK Gypsum-Fiber Roof Board		
Minimum 0.25" thick	2 with 24, 7 (#12 or #14) with 8 or 23, 9 or 15(#12) with 27, 25 or 30 with 26	1:2 ft <sup>2</sup>

Note: All layers shall be simultaneously fastened; see top or base layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: FiberTite, FiberTite-XT, FiberTite-SM, FiberTite-XTreme, Style 80 or Style80-M roof cover

adhered to the insulation with FTR-190 Bonding Adhesive or FTR-190e Bonding Adhesive

applied at an application rate of 50 ft<sup>2</sup>/gal. Laps are sealed with 1.5-inch heat weld.

Or

FiberTite-FB, FiberTite-XT FB, FiberTite-SM FB, Style 80 FB or Style 80-M FB roof cover adhered to the insulation with approved asphalt at 20-25 lbs./sq., FTR-290 solvent adhesive at 90 ft<sup>2</sup>/gal or FTR-490 water based adhesive at 100 ft<sup>2</sup>/gal. Laps are sealed with 1.5-inch heat

weld.

**Maximum Design** 

-45 psf (See General Limitation #9)

**Pressures:** 



NOA No.: 12-1019.29 **Expiration Date: 01/05/16** Approval Date: 06/06/13 Page 11 of 31

**Deck Type 2I:** Steel Decks, Insulated

**Deck Description:** Min. 22 ga., Grade 80 steel attached to structural steel supports spaced max. 6 ft o.c. attached

with ITW Buildex Traxx/5 fasteners spaced max. 6 in. o.c. at each rib. Deck side laps

secured with ITW Buildex Traxx/1 fasteners spaced max. 12" o.c.

**System Type C(2):** All layers of insulation simultaneously attached; membrane adhered.

All General and System Limitations apply.

One or more layers of the following.

Base Insulation Layer	<b>Insulation Fasteners</b>	<b>Fastener</b>
	<u>(Table 3)</u>	Density/ft <sup>2</sup>
FTR-Value IV A or ACFoam-IV (Flat or Tapered)		
Minimum 2.0" thick	15 (#12), 29 (#12) with 14, 27, 28	$1:1.3 \text{ ft}^2$
	or 31 with 32 or 33	

Note: All layers shall be simultaneously fastened; see top or base layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** FiberTite, FiberTite-XT, FiberTite-SM, FiberTite-XTreme, Style 80 or Style 80-M roof cover

adhered to the insulation with FTR-190 Bonding Adhesive or FTR-190e Bonding Adhesive

applied at an application rate of 50 ft<sup>2</sup>/gal.

**Maximum Design** 

**Pressures:** 

-60.0 psf (See General Limitation #7)



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13

Page 12 of 31

**Deck Type 2I:** Steel Decks, Insulated

**Deck Description:** Min. 22 ga., Grade 80 steel attached to structural steel supports spaced max. 6 ft o.c. attached

with ITW Buildex Traxx/5 fasteners and steel washers spaced max. 6 in. o.c. at each rib.

Deck side laps secured with ITW Buildex Traxx/1 fasteners spaced max. 12" o.c.

**System Type C(3):** All layers of insulation simultaneously attached; membrane adhered.

All General and System Limitations apply.

One or more layers of the following.

<b>Base Insulation Lay</b>	<u>ver</u>	<b>Insulation Fasteners</b>	<b>Fastener</b>
		<u>(Table 3)</u>	Density/ft <sup>2</sup>
FTR-Value IV A or	· ACFoam-IV (Flat or Tapered)		
Fastening #1:	Minimum 2.0" thick	15 (#12), 29 (#12) with 14, 27, 28	$1:2.67 \text{ ft}^2$
		or 31 with 32 or 33	
Fastening #2:	Minimum 2.0" thick	15 (#12), 29 (#12) with 14, 27, 28	$1:2 \text{ ft}^2$
_		or 31 with 32 or 33	
Fastening #3:	Minimum 2.0" thick	15 (#12), 29 (#12) with 14, 27, 28	$1:1.3 \text{ ft}^2$
_		or 31 with 32 or 33	
Fastening #4:	Minimum 2.0" thick	15 (#12), 29 (#12) with 14, 27, 28	$1:1 \text{ ft}^2$
		or 31 with 32 or 33	

Note: All layers shall be simultaneously fastened; see top or base layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** FiberTite, FiberTite-XT, FiberTite-SM, FiberTite-XTreme, Style 80 or Style 80-M roof cover

adhered to the insulation with FTR-190 Bonding Adhesive or FTR-190e Bonding Adhesive

applied at an application rate of 50 ft<sup>2</sup>/gal.

**Maximum Design** -60.0 psf for Fastening #1 (See General Limitation #7)

**Pressures:** -75.0 psf for Fastening #2 (See General Limitation #7)

-120.0 psf for Fastening #3 (See General Limitation #7)

-172.5 psf for Fastening #4 (See General Limitation #7)



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 13 of 31

Single Ply, Thermoplastic **Membrane Type:** 

Deck Type 2I: Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33 steel deck attached to structural steel supports spaced max. 6 ft

o.c. attached with ITW Buildex Traxx/5 fasteners spaced max, 6 in, o.c. at each rib. Deck

side laps secured with ITW Buildex Traxx/1 fasteners spaced max. 24" o.c.

Membrane mechanically attached over perliminary fastened insulation. **System Type D(1):** 

All General and System Limitations apply.

**Insulation Fasteners Base Insulation Layer** Fastener (Table 3) Density/ft<sup>2</sup>

H-Shield, FTR-Value H Minimum 1.5" thick

N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

FiberTite, FiberTite-FB, FiberTite-SM, FiberTite-SM FB, FiberTite-XT, FiberTite-XT FB, **Membrane:** 

> Style 80, Style 80-M, Style 80 FB, Style 80-M FB or FiberTite-XTreme secured through the preliminarily attached insulation with FTR Magnum fasteners and FTR Magnum<sup>2</sup> plates. spaced 6" o.c. within the 6" laps in rows spaced 95" o.c. The side laps are sealed with a

minimum 1.5" heat weld.

**Maximum Design** 

**Pressures:** 

-45.0 psf (See General Limitation #7)



NOA No.: 12-1019.29 **Expiration Date: 01/05/16** Approval Date: 06/06/13

Page 14 of 31

**Deck Type 2I:** Steel Decks, Insulated

**Deck Description:** 18-22 ga. Steel

System Type D(2): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Insulation Layer	<u>Insulation Fasteners</u> (Table 3)	<u>Fastener</u> <u>Density/ft<sup>2</sup></u>
FTR-Value A, ACFoam-II, H-Shield, FTR-Value H Minimum 1" thick	N/A	N/A
ENRGY 3, H-Shield, FTR-Value, FTR-Value H Minimum 1.4" thick	N/A	N/A

**Multi-Max-3, ACFoam Composite, EnergyGuard Composite, Thermaroof Composite-3, ENRGY-3 Composite**Minimum 1.5" thick

N/A

N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

**Vapor Retarders:** (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck or over a base

layer of insulation.

Fire Barrier: (Optional) 1/4" DensDeck or DensDeck Prime attached with 4 fasteners per 4' x 8' sheet.

**Membrane:** FiberTite, FiberTite-XT, FiberTite-SM, FiberTite-XTreme, Style 80 or Style 80-M roof cover

attached through the preliminary fastened insulation to the deck as specified below:

**Fastening #1:** Fasten with OMG ASAP fasteners spaced 18" o.c. through the 3.5" head laps or fastening

tabs spaced 48" o.c. Laps are sealed with 1.5-inch heat weld.

Maximum Design Pressure: -45 psf (See General Limitation #9.)

**Fastening #2:** Fasten with OMG ASAP fasteners spaced 6" o.c. through the 3.5" head laps or fastening tabs

spaced 98" o.c. Laps are sealed with 1.5-inch heat weld.

Maximum Design Pressure: -45 psf (See General Limitation #7.)

**Fastening #3:** Fasten with OMG ASAP fasteners spaced 6" o.c. through the top of the roof cover spaced at

maximum intervals of 9 feet. Fastener rows are sealed by either welding a 6" cover strip or prefabricated 4.5" surface tab (closed lap configuration) over the fasteners. The edge of the stripping and/or surface tabs shall be welded a minimum of 1". Laps are sealed with 1.5-inch

heat weld.

Maximum Design Pressure: -52.5 psf (See General Limitation #7.)



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 15 of 31 **Fastening #4:** Fasten with FTR Magnum fasteners and stress plates spaced 12" o.c. through the 3.5" head

laps or fastening tabs spaced 53" o.c. Laps are sealed with 1.5-inch heat weld.

Maximum Design Pressure: -52.5 psf (See General Limitation #7.)

**Maximum Design** 

**Pressures:** See Fastenings Options Above



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13

Page 16 of 31

**Membrane Type:** Single Ply, Thermoplastic

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 80 steel deck attached to structural steel supports spaced max. 6 ft

o.c. attached with 12-24 x 11/4 HWH Impax 45 fasteners spaced max. 6" o.c. at supports.

Deck side laps secured 24" o.c. with 14x7/8 HWH Lap-S/D fasteners.

System Type D(3): Membrane mechanically attached over perliminary fastened insulation.

All General and System Limitations apply.

Base Insulation LayerInsulation Fasteners<br/>(Table 3)Fastener<br/>Density/ft²ACFoam-II, FTR-Value AN/AN/AMinimum 1.0" thickN/AN/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

**Membrane:** FiberTite, FiberTite-FB, FiberTite-XT, FiberTite-XT FB, FiberTite-SM, FiberTite-SM FB,

FiberTite-XTreme, Style 80, Style 80-M, Style 80 FB or Style 80-M FB secured through the

preliminarily attached insulation as specified below.

**Fastening #1:** Deckfast #15 HS fasteners with Dekfast 1½" x 2¾" Oval Barbed Plates or FTR Magnum

fasteners with FTR Magnum Plus plates, spaced 12" o.c. within the 5" laps in rows spaced

95" o.c. The side laps are sealed with a minimum 1.5" heat weld. Maximum Design Pressure -45.0 psf. (See General Limitation #7)

**Fastening #2:** Deckfast #15 HS fasteners with Dekfast 1½" x 2¾" Oval Barbed Plates or FTR Magnum

fasteners with FTR Magnum Plus plates, spaced 6" o.c. within the 5" laps in rows spaced

95" o.c. The side laps are sealed with a minimum 1.5" heat weld. *Maximum Design Pressure -52.5 psf. (See General Limitation #7)* 

**Maximum Design** 

**Pressures:** 

See Fastening Options Above



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 17 of 31 **Membrane Type:** Single Ply, Thermoplastic

Deck Type 2I: Steel, Insulated

**Deck Description:** Minimum 22 ga., steel deck attached to structural supports spaced max. 6 ft o.c. attached

with ITW Buildex Traxx/5 fasteners spaced max. 6 in. o.c. at each rib. Deck side laps

secured with ITW Buildex Traxx/1 fasteners spaced max. 24" o.c.

System Type D(4): Membrane mechanically attached over perliminary fastened insulation.

All General and System Limitations apply.

**Insulation Fasteners Base Insulation Layer** Fastener (Table 3) Density/ft<sup>2</sup>

**ENRGY 3, FTR-Value** 

Minimum 1.5" thick N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: FiberTite, FiberTite-FB, FiberTite-SM, FiberTite-SM FB, FiberTite-XT, FiberTite-XT FB,

> FiberTite-XTreme, Style 80, Style 80-M, Style 80 FB or Style 80-M FB secured through the preliminarily attached insulation with FTR Magnum fastener with FTR Magnum plates or FTR Magnum Plus plates, spaced 12" o.c. within the 5" laps in rows spaced 69" o.c. The

side laps are sealed with a minimum 1.5" heat weld.

**Maximum Design** 

-45.0 psf (See General Limitation #7). **Pressures:** 



NOA No.: 12-1019.29 **Expiration Date: 01/05/16** Approval Date: 06/06/13

Page 18 of 31

**Membrane Type:** Single Ply, Thermoplastic

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 80 steel deck attached to structural supports spaced max. 6 ft o.c.

attached with ITW Buildex Traxx/5 fasteners spaced max. 6 in. o.c. at supports (one fastener was installed at each bearing attachment). Deck side laps secured with ITW

Buildex Traxx/1 fasteners spaced max. 24" o.c.

**System Type D(5):** Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply.

Base Insulation Layer	Insulation Fasteners	<u>Fastener</u>
	<u>(Table 3)</u>	Density/ft <sup>2</sup>

ENRGY 3, FTR-Value, Multi-Max FA-3, H-Shield, FTR-Value H, ACFoam II, FTR-Value A

Minimum 1.5" thick N/A N/A

(Optional) Top Insulation Layer	<u>Insulation Fasteners</u> ( <u>Table 3</u> )	<u>Fastener</u> <u>Density/ft</u> <sup>2</sup>
DensDeck, DensDeck Prime Minimum 1/4" thick	N/A	N/A
FiberTop E, High Density Roof Fiberboard		

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

**Membrane:** FiberTite, FiberTite-FB, FiberTite-SM, FiberTite-SM FB, FiberTite-XT, FiberTite-XT FB,

Style 80, Style 80-M, Style 80 FB, Style 80-M FB or FiberTite-XTreme secured through the

N/A

preliminarily attached insulation as specified below.

**Fastening:** FTR Magnum T fasteners and FTR Magnum R275 stress plates or with Trufast #15 EHD

fasteners and Trufast 2-3/4" Barbed Seam Plate (EHD) or Trufast #21 SHD Fasteners and Trufast 2-3/4" Barbed Seam Plates (SHD) spaced 12" o.c. within the 6" wide side laps in rows spaced 94" o.c. The roof cover side laps are sealed with a minimum 1.5" heat weld.

**Maximum Design** 

Minimum ½" thick

**Pressures:** 

-45 psf. (See General Limitation #7)



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 19 of 31

N/A

**Membrane Type:** Single Ply, Thermoplastic

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33, Type B steel deck attached to structural supports spaced max. 6

ft o.c. attached with ITW Buildex Traxx/5 fasteners spaced max. 6 in. o.c. at supports (one fastener was installed at each bearing attachment). Deck side laps secured with ITW

Buildex Traxx/1 fasteners spaced max. 24" o.c.

System Type D(6): Membrane mechanically attached over perliminary fastened insulation.

All General and System Limitations apply.

Base Insulation Layer	<b>Insulation Fasteners</b>	<b>Fastener</b>
	<u>(Table 3)</u>	Density/ft <sup>2</sup>

ENRGY 3, FTR-Value, Multi-Max FA-3, H-Shield, FTR-Value H, ACFoam-II, FTR-Value A

Minimum 1.5" thick N/A N/A

(Optional) Top Insulation Layer	<u>Insulation Fasteners</u> ( <u>Table 3)</u>	<u>Fastener</u> <u>Density/ft<sup>2</sup></u>
DensDeck, DensDeck Prime Minimum 1/4" thick	N/A	N/A
FiberTop E, High Density Roof Fiberboard Minimum ½" thick	N/A	N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

**Membrane:** FiberTite, FiberTite-FB, FiberTite-SM, FiberTite-SM FB, FiberTite-XT, FiberTite-XT FB,

Style 80, Style 80-M, Style 80 FB, Style 80-M FB or FiberTite-XTreme secured through the

preliminarily attached insulation as specified below.

**Fastening #1:** FTR Magnum T fasteners and FTR Magnum R275 stress plates or with Trufast #15 EHD

fasteners and Trufast 2-3/4" Barbed Seam Plate (EHD) or Trufast #21 SHD Fasteners and Trufast 2-3/4" Barbed Seam Plates (SHD) spaced 12" o.c. within the 6" wide side laps in rows spaced 94" o.c. The roof cover side laps are sealed with a minimum 1.5" heat weld.

Maximum Design Pressure: -45 psf. (See General Limitation #7)

**Fastening #2:** FTR Magnum T fasteners and FTR Magnum R275 stress plates or with Trufast #15 EHD

fasteners and Trufast 2-3/4" Barbed Seam Plate (EHD) or Trufast #21 SHD Fasteners and Trufast 2-3/4" Barbed Seam Plates (SHD) spaced 6" o.c. within the 6" wide side laps in rows spaced 94" o.c. The roof cover side laps are sealed with a minimum 1.5" heat weld.

Maximum Design Pressure: -67.5 psf. (See General Limitation #7)

**Maximum Design** 

**Pressures:** 

See Fastening Options Above



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 20 of 31

Deck Type 2I: Steel Decks, Insulated

**Deck Description:** Minimum 18 - 22 gage steel

System Type D(7): Membrane mechanically attached over perliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Insulation Layer	<b>Insulation Fasteners</b>	<b>Fastener</b>
	<u>(Table 3)</u>	<b>Density/ft<sup>2</sup></b>
Any approved polyisocyanurate Listed in Table 2		
Minimum 1.5" thick	N/A	N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

**Membrane:** FiberTite, FiberTite-XT, FiberTite-XM, FiberTite-XTreme, Style 80 or Style 80-M secured

through the preliminarily attached insulation as specified below.

Fastening #1: FTR Magnum fasteners with FTR Magnum 2<sub>s</sub> plates, or Dekfast fasteners with Dekfast

Galvalume Steel Round 2-3/8" 20-Ga. Barbed Plates or Dekfast #15 HS fasteners and Dekfast Isofast IF-2.375-AT Membrane Plate, spaced 6" o.c. within the 5" open laps in rows spaced 144.0" o.c., or installed through integral 3-1/2" fastening tab. The outside 1.5" of the

lap is heat welded.

Maximum Design Pressure: -45 psf. (See General Limitation #7)

FTR Magnum fasteners with FTR Magnum 2<sub>s</sub> plates, or Dekfast fasteners with Dekfast

Galvalume Steel Round 2-3/8" 20-Ga. Barbed Plates or Dekfast #15 HS fasteners and Dekfast Isofast IF-2.375-AT Membrane Plate, spaced 6" o.c. through the top of the roof cover in rows spaced 144.0" o.c.. Rows are sealed by either welding a 6" cover strip or prefabricated 4.5" surface tab (closed lap configuration) over the fasteners. The edge of tab or both edges of cover strip are heat welded min. 1.5". The outside 1.5" of the lap is heat

welded.

Maximum Design Pressure: -52.5 psf. (See General Limitation #7)

FTR Magnum fasteners with FTR Magnum 2<sub>s</sub> plates, or Dekfast fasteners with Dekfast

Galvalume Steel Round 2-3/8" 20-Ga. Barbed Plates or Dekfast #15 HS fasteners and Dekfast Isofast IF-2.375-AT Membrane Plate, spaced 6" o.c. within the 5" open laps in rows spaced 72.0" o.c., or installed through integral 3-1/2" fastening tab. The outside 1.5" of the

lap is heat welded.

Maximum Design Pressure: -67.5 psf. (See General Limitation #7)

**Maximum Design** 

**Pressures:** 

See Fastening Options Above



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 21 of 31

**Deck Type 2I**: Steel Decks, Insulated

**Deck Description:** Minimum 22 gage ASTM A 611 Grade E Type B Steel deck fastened to steel support at a

maximum span of 6' o.c. Steel deck shall be fastened with ITW Buildex Traxx/5 at a maximum spacing of 6" o.c. Side laps shall be fastened with Traxx/1 screws at a maximum

spacing of 30 inches o.c.

**System Type D(8):** Membrane mechanically attached over perliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Insulation Layer	<b>Insulation Fasteners</b>	<u>Fastener</u>
	<u>(Table 3)</u>	Density/ft <sup>2</sup>
Any approved polyisocyanurate Listed in Table 2		
Minimum 1.5" thick	N/A	N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

**Vapor Retarders:** (Optional) Any UL or FM approved vapor retarder applied to the roof deck or over a base

layer of insulation.

Fire Barrier: (Optional) <sup>1</sup>/<sub>4</sub>" DensDeck or DensDeck Prime attached with 4 fasteners per 4' x 8' sheet.

**Membrane:** FiberTite, FiberTite XT, FiberTite SM, FiberTite XTreme, Style 80 or Style 80-M secured

through the preliminarily attached insulation as specified below.

FTR Magnum fasteners with plates spaced 18" o.c. within the 5" open laps in rows spaced

51" o.c. The outside 1.5" of the lap is heat welded.

Maximum Design Pressure: -45 psf. (See General Limitation #7)

**Fastening #2:** FTR Magnum fasteners with plates spaced 12" o.c. in the 5" open laps in rows spaced 51"

o.c. The outside 1.5" of the lap is heat welded.

Maximum Design Pressure: -60 psf. (See General Limitation #7)

**Fastening #3:** Fasten with FTR Magnum fasteners and plates spaced 6" o.c. through the top of the roof

cover spaced at maximum intervals of 104.5" Fastener rows are sealed by either welding a 6" cover strip or prefabricated 4.5" surface tab.(closed lap configuration) over the fasteners. The edge of the stripping and/or surface tabs shall be welded a minimum of 1". Laps are

sealed with 1.5-inch heat weld.

Maximum Design Pressure: -75 psf. (See General Limitation #7)



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 22 of 31 FTR Magnum fasteners with plates spaced 6" o.c. within the 5" closed laps in rows spaced

104.5" o.c. The outside 1.5" of the laps is heat welded.

Maximum Design Pressure: -82.5 psf. (See General Limitation #7)

**Maximum Design** 

**Pressures:** 

See Fastening Options Above



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13

Page 23 of 31

**Deck Type 2I**: Steel Decks, Insulated

**Deck Description:** 18-22 ga. Steel (See Specific Deck type below)

System Type D(9): Membrane mechanically attached over perliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>
Any approved polyisocyanurate Listed in Table 2		
Minimum 1.5" thick	N/A	N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

**Vapor Retarders:** (Optional) Any UL or FM approved vapor retarder applied to the roof deck or over a base

layer of insulation.

**Fire Barrier:** (Optional) <sup>1</sup>/<sub>4</sub>" DensDeck or DensDeck Prime attached with 4 fasteners per 4' x 8' sheet.

**Membrane:** FiberTite, FiberTite XT, FiberTite SM, FiberTite XTreme, Style 80 or Style 80-M secured

through the preliminarily attached insulation as specified below.

**Deck:** Minimum 22 gage ASTM A653 SS Grade 33 Type B Steel deck fastened to steel support at

a maximum span of 6' o.c. Steel deck shall be fastened with SFS Intec Impax 5 or ITW Buildex Traxx/5 at a maximum spacing of 6" o.c. Side laps shall be fastened with SFS Intec

<sup>1</sup>/<sub>4</sub>-14 Lap Tek or Traxx/1 screws at a maximum spacing of 30 inches o.c.

**Fastening #1:** FTR Magnum fasteners with plates spaced 12" o.c. in the 5" lap of membrane in rows

spaced 51" o.c. The outside 1.5" of the lap is heat welded.

Maximum Design Pressure: -52.5 psf. (See General Limitation #7)

**Fastening #2:** FTR Magnum fasteners with plates spaced 6" o.c. in the 5" lap of membrane in rows spaced

51" o.c. The outside 1.5" of the lap is heat welded.

Maximum Design Pressure: -60 psf. (See General Limitation #7)

**Deck:** Minimum 22 gage ASTM A1008 SS Grade 80 Type B Steel deck fastened to steel support at

a maximum span of 6' o.c. Steel deck shall be fastened with SFS Intec Impax 5 or ITW Buildex Traxx/5 at a maximum spacing of 6" o.c. Side laps shall be fastened with SFS Intec

1/4-14 Lap Tek or Traxx/1 screws at a maximum spacing of 30 inches o.c.

**Fastening #1:** FTR Magnum fasteners with plates spaced 12" o.c. in the 5" lap of membrane in rows

spaced 72" o.c. The outside 1.5" of the lap is heat welded.

Maximum Design Pressure: -45 psf. (See General Limitation #7)



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 24 of 31 **Fastening #2:** FTR Magnum fasteners with plates spaced 6" o.c. in the 5" lap of membrane in rows spaced

96" o.c. The outside 1.5" of the lap is heat welded.

Maximum Design Pressure: -52.5 psf. (See General Limitation #7)

**Fastening #3:** FTR Magnum fasteners with plates spaced 6" o.c. in the 5" lap of membrane in rows spaced

51" o.c. The outside 1.5" of the lap is heat welded.

Maximum Design Pressure: -60 psf. (See General Limitation #7)

**Deck:** Minimum 20 gage ASTM A653 SS Grade 33 Type B Steel deck fastened to steel support at

a maximum span of 6' o.c. Steel deck shall be fastened with SFS Intec Impax 5 or ITW Buildex Traxx/5 at a maximum spacing of 6" o.c. Side laps shall be fastened with SFS Intec

<sup>1</sup>/<sub>4</sub>-14 Lap Tek or Traxx/1 screws at a maximum spacing of 30 inches o.c.

**Fastening #1:** FTR Magnum fasteners with plates spaced 12" o.c. in the 5" lap of membrane in rows

spaced 51" o.c. The outside 1.5" of the lap is heat welded.

Maximum Design Pressure: -52.5 psf. (See General Limitation #7)

**Fastening #2:** FTR Magnum fasteners with plates spaced 6" o.c. in the 5" lap of membrane in rows spaced

51" o.c. The outside 1.5" of the lap is heat welded.

Maximum Design Pressure: -67.5 psf. (See General Limitation #7)

**Maximum Design** 

**Pressures:** 

See Fastening Options Above



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 25 of 31 **Membrane Type:** Single Ply, Thermoplastic

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33 steel deck attached to structural steel supports spaced max. 6 ft

o.c. attached with ITW Buildex Traxx/5 fasteners spaced max. 6 in. o.c. at each rib. Deck

side laps secured with ITW Buildex Traxx/1 fasteners spaced max. 24" o.c.

System Type D(10): Membrane mechanically attached over perliminary fastened insulation.

All General and System Limitations apply.

Base Insulation LayerInsulation FastenersFastener(Table 3)Density/ft²

H-Shield, FTR-Value H Minimum 1.5" thick

N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

**Membrane:** FiberTite, FiberTite-FB, FiberTite-SM, FiberTite-SM FB, FiberTite-XT, FiberTite-XT FB,

Style 80, Style 80-M, Style 80 FB, Style 80-M FB or FiberTite-XTreme secured through the preliminarily attached insulation using FTR Magnum fastener with FTR Magnum plates or FTR Magnum Plus plates, spaced 6" o.c. within the 6" laps in rows spaced 104.5" o.c. The

side laps are sealed with a minimum 1.5" heat weld.

**Maximum Design** 

**Pressures:** -60.0 psf (See General Limitation #7).



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 26 of 31 **Membrane Type:** Single Ply, Thermoplastic

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33 steel deck attached to structural supports spaced max. 6 ft o.c.

attached with ITW Buildex Traxx/5 fasteners spaced max. 6 in. o.c. at each rib. Deck side

laps secured with ITW Buildex Traxx/1 fasteners spaced max. 24" o.c.

System Type D(11): Membrane mechanically attached over perliminary fastened insulation.

All General and System Limitations apply.

Base Insulation LayerInsulation Fasteners<br/>(Table 3)Fastener<br/>Density/ft²ENRGY 3, FTR-ValueN/AN/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

**Membrane:** FiberTite, FiberTite-FB, FiberTite-SM, FiberTite-SM FB, FiberTite-XT, FiberTite-XT FB,

FiberTite-XTreme, Style 80, Style 80-M, Style 80 FB or Style 80-M FB secured through the preliminarily attached insulation using FTR Magnum fastener with FTR Magnum plates or FTR Magnum Plus plates, spaced 6" o.c. within the 5" laps in rows spaced 69" o.c. The side

laps are sealed with a minimum 1.5" heat weld.

**Maximum Design** 

**Pressures:** -60.0 psf (See General Limitation #7).



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 27 of 31

**Deck Type 2I**: Steel Decks, Insulated

**Deck Description:** Minimum 22 ga., type B, steel decking placed over minimum 0.25" thick structural supports

having maximum 5 ft spans. Deck shall be anchored with ITW Buildex Traxx/4 or Traxx/5 fasteners spaced at maximum 6" o.c. at supports. Deck side laps shall be secured with ITW

Buildex Traxx/1 fasteners spaced at a maximum 18" o.c.

**System Type D(12):** Membrane mechanically attached over perliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Insulation Layer	<b>Insulation Fasteners</b>	<u>Fastener</u>
	<u>(Table 3)</u>	<b>Density/ft<sup>2</sup></b>
Any approved polyisocyanurate Listed in Table 2		
Minimum 1" thick	N/A	N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

**Vapor Retarders:** (Optional) Any UL or FM approved vapor retarder applied to the roof deck or over a base

layer of insulation.

Fire Barrier: (Optional) 1/4" DensDeck or DensDeck Prime attached with 4 fasteners per 4' x 8' sheet.

**Membrane:** FiberTite, FiberTite-XT, FiberTite-SM, FiberTite-XTreme, Style 80 or Style 80-M roof cover

attached through the presecured insulation to the deck using FTR Magnum fasteners and plates spaced 6" o.c. through the tabs spaced a maximum of 51" o.c. Laps are sealed with 1.5-

inch heat weld.

Maximum Design Pressures:-75 psf (See General Limitation #7)

Or

FiberTite TopSider system consisting of FiberTite, FiberTite-XT, FiberTite-SM, FiberTite-XTreme, Style 80 or Style 80-M attached using FTR Magnum fasteners and plates spaced 6" o.c. through the top of the membrane spaced at intervals of 104.5". Laps are sealed with 1.5-

inch heat weld.

Maximum Design Pressures:-90 psf (See General Limitation #7)

**Maximum Design** 

**Pressures:** 

See Membrane attachment above.



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 28 of 31

**Deck Type 2I**: Steel Decks, Insulated

**Deck Description:** Minimum 22 ga., 1.5" deep, ASTM A611, Grade E or ASTM A446, Grade E steel decking

placed over minimum 0.25" thick structural supports having maximum 6 ft spans. Deck shall be anchored with ITW Buildex Traxx/4 or Traxx/5 fasteners spaced at maximum 6" o.c. at supports. Deck side laps shall be secured with ITW Buildex Traxx/1 fasteners spaced at a

maximum 30" o.c.

**System Type D(13):** Membrane mechanically attached over perliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Insulation Layer	<b>Insulation Fasteners</b>	<u>Fastener</u>
	<u>(Table 3)</u>	<u>Density/ft<sup>2</sup></u>
Any approved polyisocyanurate Listed in Table 2		
Minimum 1.5" thick	N/A	N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

**Vapor Retarders:** (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck or over a base

layer of insulation.

Fire Barrier: (Optional) 1/4" DensDeck or DensDeck Prime attached with 4 fasteners per 4' x 8' sheet.

**Membrane:** FiberTite, FiberTite-XT, FiberTite-SM, FiberTite-XTreme, Style 80 or Style 80-M roof cover

attached through the presecured insulation to the deck using FTR Magnum fasteners and plates spaced 12" o.c. through the tabs spaced a maximum of 24" o.c. Laps are sealed with

1.5-inch heat weld.

**Maximum Design** 

-82.5 psf (See General Limitation #7.)

**Pressures:** 



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 29 of 31 **Membrane Type:** Single Ply, Thermoplastic

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 80 steel deck attached to structural steel supports spaced max. 6 ft

o.c. attached with ITW Buildex Traxx/5 fasteners spaced max, 6 in. o.c. at each rib. Deck

side laps secured with ITW Buildex Traxx/1 fasteners spaced max. 24" o.c.

System Type D(14): Membrane mechanically attached over perliminary fastened insulation.

All General and System Limitations apply.

Base Insulation LayerInsulation FastenersFastener(Table 3)Density/ft²

H-Shield, FTR-Value H Minimum 1.5" thick

N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

**Membrane:** FiberTite, FiberTite-FB, FiberTite-SM, FiberTite-SM FB, FiberTite-XT, FiberTite-XT FB,

Style 80, Style 80-M, Style 80 FB, Style 80-M FB or FiberTite-XTreme secured through the

preliminarily attached insulation as specified below.

**Fastening #1:** FTR Magnum fastener with FTR Magnum plates or FTR Magnum Plus plates, spaced 6"

o.c. within the 6" laps in rows spaced 94" o.c. The side laps are sealed with a minimum 1.5"

heat weld.

Maximum Design Pressure –82.5 psf. (See General Limitation #7)

FTR Magnum fastener with FTR Magnum plates or FTR Magnum Plus plates, spaced 6"

o.c. within the 6" laps in rows spaced 47" o.c. The side laps are sealed with a minimum 1.5"

heat weld.

Maximum Design Pressure -112.5 psf. (See General Limitation #7)

**Maximum Design** 

**Pressures:** 

See Fastening Options Above.



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 30 of 31

#### STEEL DECK SYSTEM LIMITATIONS:

- 1. If mechanical attachment to the structural deck through the lightweight insulating concrete is proposed, a field withdrawal resistance testing shall be performed to determine equivalent or enhanced fastener patterns and density. All testing and fastening design shall be in compliance with Testing Application Standard TAS 105 and Roofing Application Standard RAS 117 and/or RAS 137, calculations shall be signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant.
- 2. For steel deck application where specific deck construction is not referenced: The deck shall be a minimum 22 gage attached with 5/8" puddle welds with weld washers at every flute with maximum deck spans of 5 ft. o.c.

#### **GENERAL LIMITATIONS:**

- 1. Fire classification is not part of this acceptance, refer to a current Approved Roofing Materials Directory for fire ratings of this product.
- 2. Insulation may be installed in multiple layers. The first layer shall be attached in compliance with Product Control Approval guidelines. All other layers shall be adhered in a full mopping of approved asphalt applied within the EVT range and at a rate of 20-40 lbs./sq., or mechanically attached using the fastening pattern of the top layer
- 3. All standard panel sizes are acceptable for mechanical attachment. When applied in approved asphalt, panel size shall be 4' x 4' maximum.
- 4. An overlay and/or recovery board insulation panel is required on all applications over closed cell foam insulations when the base sheet is fully mopped. If no recovery board is used the base sheet shall be applied using spot mopping with approved asphalt, 12" diameter circles, 24" o.c.; or strip mopped 8" ribbons in three rows, one at each sidelap and one down the center of the sheet allowing a continuous area of ventilation. Encircling of the strips is not acceptable. A 6" break shall be placed every 12' in each ribbon to allow cross ventilation. Asphalt application of either system shall be at a minimum rate of 12 lbs./sq. Note: Spot attached systems shall be limited to a maximum design pressure of -45 psf.
- 5. Fastener spacing for insulation attachment is based on a Minimum Characteristic Force (F') value of 275 lbf., as tested in compliance with Testing Application Standard TAS 105. If the fastener value, as field-tested, are below 275 lbf. insulation attachment shall not be acceptable.
- 6. Fastener spacing for mechanical attachment of anchor/base sheet or membrane attachment is based on a minimum fastener resistance value in conjunction with the maximum design value listed within a specific system. Should the fastener resistance be less than that required, as determined by the Building Official, a revised fastener spacing, prepared, signed and sealed by a Florida Registered Engineer, Architect, or Registered Roof Consultant may be submitted. Said revised fastener spacing shall utilize the withdrawal resistance value taken from Testing Application Standards TAS 105 and calculations in compliance with Roofing Application Standard RAS 117.
- 7. Perimeter and corner areas shall comply with the enhanced uplift pressure requirements of these areas. Fastener densities shall be increased for both insulation and base sheet as calculated in compliance with Roofing Application Standard RAS 117 and/or RAS 137. Calculations prepared, signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant (When this limitation is specifically referred within this NOA, General Limitation #9 will not be applicable.)
- 8. All attachment and sizing of perimeter nailers, metal profile, and/or flashing termination designs shall conform with Roofing Application Standard RAS 111 and applicable wind load requirements.
- 9. The maximum designed pressure limitation listed shall be applicable to all roof pressure zones (i.e. field, perimeters, and corners). Neither rational analysis, nor extrapolation shall be permitted for enhanced fastening at enhanced pressure zones (i.e. perimeters, extended corners and corners). (When this limitation is specifically referred within this NOA, General Limitation #7 will not be applicable.)
- 10. All products listed herein shall have a quality assurance audit in accordance with the Florida Building Code and Rule 9N-3 of the Florida Administrative Code.

## END OF THIS ACCEPTANCE



NOA No.: 12-1019.29 Expiration Date: 01/05/16 Approval Date: 06/06/13 Page 31 of 31