MIAMI-DADE COUNTY
DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)
BOARD AND CODE ADMINISTRATION DIVISION

MIAMI–DADE COUNTY, FLORIDA
PRODUCT CONTROL SECTION
11805 SW 26 Street, Room 208
T (786) 315–2590 F (786) 315–2599
www.miamidade.gov/economy

NOTICE OF ACCEPTANCE (NOA)

ES Windows, LLC
10653 N.E. Quaybridge Court
Miami, FL 33138

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami–Dade County RER–Product Control Section to be used in Miami–Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami–Dade County Product Control Section (In Miami–Dade County) and/ or the AHJ (in areas other than Miami–Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami–Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Series "ES 7100S" Aluminum Window Wall System – S.M.I.

APPROVAL DOCUMENT: Drawing No. **W12–51**, titled "Series 7100 Alum. Window Wall System (S.M.I.)", sheets 1, 2, 3, 3.1, 4, 4.1, 5 and 6 through 13 and 13.1 of 16, dated 09/12/12 with revision "**A**" dated 10/29/13, prepared by Al–Farooq Corporation, signed and sealed by Javad Ahmad, P. E., bearing the Miami–Dade County Product Control Section stamp with the Notice of Acceptance number and expiration date by the Miami–Dade County Product Control Section.

MISSILE IMPACT RATING: Small Missile Impact Resistant

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state, series, and following statement: "Miami–Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/ or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami–Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA consists of this page 1 and evidence pages E–1 and E–2, as well as approval document mentioned above.

The submitted documentation was reviewed by **Jaime D. Gascon, P. E.**

MIAMI-DADE COUNTY APPROVED

J. Gascon 11/7/13

ES Windows, LLC

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

A. DRAWINGS

1. Manufacturer's die drawings and sections.
2. Drawing No. **W12–51**, titled "Series 7100 Alum. Window Wall System (S.M.I.)", sheets 1, 2, 3, 3.1, 4, 4.1, 5 and 6 through 13 and 13.1 of 16, dated 09/12/12 with revision "**A**" dated 10/29/13, prepared by Al–Farooq Corporation, signed and sealed by Javad Ahmad, P. E.

B. TESTS

1. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202–94
   2) Uniform Static Air Pressure Test, Loading per FBC, TAS 202–94
   3) Water Resistance Test, per FBC, TAS 202–94
   4) Small Missile Impact Test per FBC, TAS 201–94
   5) Cyclic Wind Pressure Loading per FBC, TAS 203–94
   6) Forced Entry Test, per FBC 2411.3.2.1, and TAS 202–94

   along with marked–up drawings and installation diagram of a window wall system, prepared by Fenestration Testing Laboratory, Inc., Test Report No. **FTL–7155**, dated 07/15/13, signed and sealed by Jorge A. Naya, P. E.

C. CALCULATIONS

1. Anchor verification calculations and structural analysis, complying with **FBC–2010**, prepared by Al–Farooq Corporation, dated 07/01/13, signed, sealed and 10/29/13 by Javad Ahmad, P. E.
2. **Glazing complies with ASTM E1300–04/ 09**

D. QUALITY ASSURANCE

1. Miami–Dade Department of Regulatory and Economic Resources (RER).

E. MATERIAL CERTIFICATIONS

1. Notice of Acceptance No. **13–0129.27** issued to **E.I. DuPont DeNemours & Co., Inc.** for their **"DuPont Butacite® PVB Interlayer"** dated 04/11/13, expiring on 12/11/16.
2. Soluciones En Caucho, S.A.S., Columbia, Parts No.'s **80–356 & 80–378 EPDM exterior glazing gaskets & P/N. 27-157 Interior Spacer ES–7100–G01** complying with ISO 9001 and with ASTM C864 Specification for Dense Elastomeric Compression Seal Gaskets, Setting Blocks, and Spacers; ASTM D412 Standard Test Methods for Vulcanized Rubber and Thermoplastic Elastomers—Tension of 1145 psi; ASTM D395B Test Methods for Rubber Property—Compression Set for 22 HRS 158°F; ASTM D 624 Test Method for Tear Strength of Conventional Vulcanized Rubber and Thermoplastic Elastomers.

Jaime D. Gascon, P. E.
Product Control Section Supervisor
NOA No. 13–0617.25
Expiration Date: November 07, 2018
Approval Date: November 07, 2013

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

F. STATEMENTS

1. Statement letter of no financial interest, conformance and complying with **FBC–2010**, issued by Al–Farooq Corporation, dated 07/27/13, signed and sealed by Javad Ahmad, P. E.
2. Laboratory compliance letter for Test Report no. **FTL–7155**, issued by Fenestration Testing Laboratory, Inc., dated 07/15/13, signed and sealed by Jorge A. Naya, P. E.
3. Proposal issued by Product Control, dated 09/14/12, signed by Jaime D. Gascon, P. E.

G. OTHERS

1. None.

Jaime D. Gascon, P. E.
Product Control Section Supervisor
NOA No. 13–0617.25
Expiration Date: November 07, 2018
Approval Date: November 07, 2013



TYPICAL ELEVATIONS

THIS SYSTEM IS RATED FOR SMALL MISSILE IMPACT.
MIAMI-DADE COUNTY APPROVED IMPACT RESISTANT SHUTTERS
REQUIRED FOR INSTALLATIONS UP TO 30 FT. OF GRADE.
SHUTTERS NOT REQD. FOR INSTALLATIONS ABOVE 30 FT. OF GRADE.

SERIES 7100 ALUMINUM WINDOW WALL SYSTEM

THIS SYSTEM MAY BE USED IN CONJUNCTION WITH MIAMI-DADE COUNTY APPR'D SMALL MISSILE IMPACT RESISTANT DOORS. LOWER DESIGN PRESSURE FROM STOREFRONT OR DOOR APPROVAL WILL APPLY TO ENTIRE SYSTEM.

CODE REQUIREMENTS FOR SAFEGUARDS MUST BE OBSERVED.

THIS PRODUCT HAS BEEN DESIGNED AND TESTED TO COMPLY WITH THE REQUIREMENTS OF THE FLORIDA BUILDING CODE INCLUDING HIGH VELOCITY HURRICANE ZONE (HVHZ).

ANCHORS SHALL BE AS LISTED, SPACED AS SHOWN ON DETAILS, ANCHORS EMBEDMENT TO BASE MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO.

ANCHORING OR LOADING CONDITIONS NOT SHOWN IN THESE DETAILS ARE NOT PART OF THIS APPROVAL.

MATERIALS INCLUDING BUT NOT LIMITED TO STEEL/METAL SCREWS, THAT COME INTO CONTACT WITH OTHER DISSIMILAR MATERIALS SHALL MEET THE REQUIREMENTS OF THE FLORIDA BLDG. CODE SECTION 2003.8.4.

INSTRUCTIONS:

USE CHARTS AS FOLLOWS.

STEP 1 DETERMINE DESIGN WIND PRESSURE REQUIREMENTS BASED ON WIND VELOCITY, BLDG. HEIGHT, WIND ZONE USING APPLICABLE ASCE 7 STANDARD.

STEP 2 SEE CHARTS ON SHEET 2 FOR GLASS DESIGN LOAD CAPACITY.

STEP 3 CHECK MULLION DESIGN LOAD CAPACITY FOR A GIVEN SPACING AND HEIGHT USING CHARTS ON SHEETS 3, 4 & 6 THE CAPACITY SHOULD EXCEED THE DESIGN LOAD.

STEP 4 USING CHARTS ON SHEET 5 SELECT ANCHOR OPTION WITH DESIGN LOAD CAPACITY MORE THAN DESIGN LOAD SPECIFIED IN STEP 1 ABOVE.

STEP 5 THE LOWEST VALUE RESULTING FROM STEPS 2, 3 AND 4 THAT EXCEED THE DESIGN WIND PRESSURES DETERMINED THRU STEP 1 SHALL APPLY TO ENTIRE SYSTEM.

STEP 6 FOR SYSTEMS WITH UNANCHORED JAMBS, USING SHEET 11, DETERMINE THE MIN. & MAX. GAP DIMENSIONS.

STEP 7 WHEN USING THIS SYSTEM WITH DOORS, THE LOWER VALUE OF THE DESIGN PRESSURE RATING FOR THE SYSTEM AND THE DOOR SHALL APPLY.

Approved as complying with the
Florida Building Code
Date 11/8/2013
NOA# 13-0626.07 & 7.25
Miami-Dade Product Control
By

LAMINATED GLASS
INSUL. LAM. GLASS
SMALL MISSILE IMPACT

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538
OCT 2[illegible] 2013

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
STORE\W12-51ES

SERIES 7100 ALUM WINDOW WALL SYSTEM (S.M.I.)

E.S. WINDOWS, LLC
5220 N.W. 72 AVE. BAY #4
MIAMI, FL. 33166
TEL. (305) 624-7775 FAX. (305) 624-7777

revisions:

no	date	by	description
A	10.29.13	RER	REV. PER COMMENTS

date: 09-12-12
scale: 1/2"=1'-0"
dr. by: HAMID
chk. by:

drawing no.
W12-51

sheet 1 of 13

GLASS DESIGN LOAD CAPACITY – PSF			
NOMINAL DIMS.		GLASS TYPE 'A'	GLASS TYPE 'B'
D.L.O. WIDTH	D.L.O. HEIGHT	EXT. (+) INT. (–)	EXT. (+) INT. (–)
36"	88	150.0	150.0
39"		150.0	150.0
42"		150.0	150.0
45 1/2"		150.0	150.0
48"		145.7	150.0
51"		140.0	150.0
54"		134.6	147.0
57 1/2"		110.0	110.0
36"	92	150.0	150.0
39"		150.0	150.0
42"		150.0	150.0
45 1/2"		146.4	150.0
48"		141.8	150.0
51"		134.8	147.0
54"		129.4	140.0
57 1/2"		110.0	110.0
36"	96	150.0	150.0
39"		150.0	150.0
42"		150.0	150.0
45 1/2"		143.3	150.0
48"		136.7	150.0
51"		129.7	141.0
54"		110.0	110.0
57 1/2"		110.0	110.0
36"	100	150.0	150.0
39"		150.0	150.0
42"		149.1	150.0
45 1/2"		138.1	150.0
48"		131.8	150.0
51"		110.0	110.0
54"		110.0	110.0
57 1/2"		110.0	110.0
36"	104	150.0	150.0
39"		150.0	150.0
42"		144.3	150.0
45 1/2"		133.7	147.0
48"		127.3	145.0
51"		110.0	110.0
54"		110.0	110.0
57 1/2"		110.0	110.0
36"	108	150.0	150.0
39"		150.0	150.0
42"		140.2	150.0
45 1/2"		129.7	142.0
48"		110.0	110.0
51"		110.0	110.0
54"		110.0	110.0
57 1/2"		105.7	110.0

GLASS DESIGN LOAD CAPACITY – PSF			
NOMINAL DIMS.		GLASS TYPE 'A'	GLASS TYPE 'B'
D.L.O. WIDTH	D.L.O. HEIGHT	EXT. (+) INT. (–)	EXT. (+) INT. (–)
36"	112	150.0	150.0
39"		146.3	150.0
42"		136.5	150.0
45 1/2"		110.0	110.0
48"		110.0	110.0
51"		110.0	110.0
54"		107.6	110.0
36"	116	150.0	150.0
39"		142.7	150.0
42"		133.3	147.0
45 1/2"		110.0	110.0
48"		110.0	110.0
51"		110.0	110.0
36"	120	150.0	150.0
39"		142.2	150.0
42"		110.0	110.0
45 1/2"		110.0	110.0
48"		110.0	110.0
51"		106.6	110.0
36"	124	150.0	150.0
39"		142.6	150.0
42"		110.0	110.0
45 1/2"		110.0	110.0
48"		110.0	110.0
36"	128	150.0	150.0
39"		142.9	150.0
42"		110.0	110.0
45 1/2"		110.0	110.0
48"		108.5	110.0
36"	132"	150.0	150.0
39"		110.0	110.0
42"		110.0	110.0
45 1/2"		110.0	110.0
36"	136"	150.0	150.0
39"		110.0	110.0
42"		110.0	110.0
45 1/2"		110.0	110.0
36"	139"	150.0	150.0
39"		110.0	110.0
42"		110.0	110.0





GLASS TYPE 'A'
9/16" OVERALL NOMINAL THK.



GLASS TYPE 'B'
1-1/4" OVERALL NOMINAL THK.

GLAZING OPTIONS

Approved as complying with the Florida Building Code
Date 11/6/2013
NOA# 13-0617.25
Miami Dade Product Control
By

NOTE:
GLASS CAPACITIES ON THIS SHEET ARE BASED ON ASTM E1300–09 (3 SEC. GUSTS).

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538

OCT 2 9 2013

afc

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
STORE\W12-51ES

SERIES 7100 ALUM WINDOW WALL SYSTEM (S.M.I.)

E.S. WINDOWS, LLC
5220 N.W. 72 AVE. BAY #4
MIAMI, FL. 33166
TEL. (305) 624-7775 FAX. (305) 624-7777

revisions:

no	date	by	description
A	10.29.13	RER	REV. PER COMMENTS

date: 09-12-12
scale: 3/8" = 1"
dr. by: HAMID
chk. by:

drawing no.
W12-51

sheet 2 of 13

MULLION DESIGN LOAD CAPACITY - PSF
CHART FOR LAMINATED GLASS MULLIONS
WITHOUT INTERMEDIATE HORIZONTALS

NOMINAL DIMS.		JAMB 'J1' MULL 'M1'	
WIDTH (W)	FRAME HEIGHT	EXT. (+)	INT. (−)
30"	114"	100.0	110.0
36"		100.0	110.0
42"		100.0	110.0
48"		100.0	110.0
54"		100.0	110.0
60"		100.0	110.0
30"	120"	100.0	110.0
36"		100.0	110.0
42"		100.0	110.0
48"		100.0	110.0
54"		100.0	109.8
57"		100.0	105.1
30"	126"	100.0	110.0
36"		100.0	110.0
42"		100.0	110.0
48"		100.0	104.2
54"		94.1	94.1
30"	132"	100.0	110.0
36"		100.0	110.0
42"		100.0	101.7
48"		90.1	90.1
52"		84.0	84.0
30"	138"	100.0	110.0
36"		100.0	102.4
42"		88.7	88.7
48"		78.5	78.5
50"		75.7	75.7
30"	144"	100.0	107.2
36"		90.0	90.0
42"		77.8	77.8
48"		68.8	68.8

MULLION DESIGN LOAD CAPACITY - PSF
CHART FOR LAMINATED GLASS MULLIONS
WITHOUT INTERMEDIATE HORIZONTALS

NOMINAL DIMS.		JAMB 'J2' MULL 'M2'		JAMB 'J3' MULL 'M3'	
WIDTH (W)	FRAME HEIGHT	EXT. (+)	INT. (−)	EXT. (+)	INT. (−)
30"	96"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
48"		100.0	150.0	100.0	150.0
54"		100.0	150.0	100.0	150.0
56"		100.0	150.0	100.0	150.0
60"		100.0	140.0	100.0	140.0
30"	102"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
48"		100.0	150.0	100.0	150.0
54"		100.0	150.0	100.0	150.0
55"		100.0	150.0	100.0	150.0
60"		100.0	140.0	100.0	140.0
30"	108"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
48"		100.0	150.0	100.0	150.0
52"		100.0	150.0	100.0	150.0
54"		100.0	140.0	100.0	140.0
60"		100.0	140.0	100.0	140.0
30"	114"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
48"		100.0	150.0	100.0	150.0
49"		100.0	150.0	100.0	150.0
54"		100.0	140.0	100.0	140.0
60"		100.0	140.0	100.0	140.0
30"	120"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
47"		100.0	150.0	100.0	150.0
48"		100.0	140.0	100.0	140.0
54"		100.0	138.6	100.0	140.0
57"		100.0	132.3	100.0	140.0
30"	126"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
44"		100.0	150.0	100.0	150.0
48"		100.0	138.6	100.0	140.0
54"		100.0	124.8	100.0	140.0
30"	132"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	142.2	100.0	150.0
48"		100.0	125.8	100.0	140.0
52"		100.0	117.0	100.0	140.0
30"	138"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
40"		100.0	135.9	100.0	150.0
42"		100.0	129.8	100.0	140.0
48"		100.0	114.6	100.0	140.0
50"		100.0	110.4	100.0	140.0
30"	144"	100.0	150.0	100.0	150.0
36"		100.0	137.7	100.0	150.0
39"		100.0	127.6	100.0	150.0
42"		100.0	118.9	100.0	140.0
48"		100.0	104.9	100.0	140.0



WIDTH (W) = W1
AT JAMB

WIDTH (W) = $\frac{W2 + W3}{2}$
AT MULLION



WIDTH (W) = $\frac{W1 + W2}{2}$
AT MULLION



WIDTH (W) = $\frac{W1}{2} + \frac{W2}{4}$
AT MULLION

MAX. DOOR HEIGHTS FOR WINDOW WALL WITH DOORS
TO BE LIMITED TO THE MAX. APPROVED DOOR HEIGHTS.



JAMB 'J1' & 'J2'

Ix IN^4	Sx IN^3
14.6111	4.6414



JAMB 'J3'

	Ix IN^4	Sx IN^3
ALUMINUM	14.6111	4.6414
STEEL	3.797	1.687
TOTAL Ix ALUM + Ix STL X 2.9	25.622	



MULLION 'M1'

Ix IN^4	Sx IN^3
15.385	4.546



MULLION 'M2'

	Ix IN^4	Sx IN^3
ALUMINUM	15.385	4.546
STEEL	3.797	1.6875
TOTAL Ix ALUM + Ix STL X 2.9	26.396	



MULLION 'M3'

	Ix IN^4	Sx IN^3
ALUMINUM	15.385	4.546
STEEL	7.594	3.375
TOTAL Ix ALUM + Ix STL X 2.9	37.407	

Approved as complying with the
Florida Building Code
Date 11-5-2013
NOA# 13-0617.25
Miami Dade Product Control
By

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538
OCT 29 2013

NOTE:
INTERPOLATION BETWEEN WIDTHS ALLOWED.

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978

STORE\W12-51ES

SERIES 7100 ALUM WINDOW WALL SYSTEM (S.M.I.)

E.S. WINDOWS, LLC
5220 N.W. 72 AVE. BAY #4
MIAMI, FL. 33166
TEL. (305) 624-7775 FAX. (305) 624-7777

revisions:

no	date	by	description
A	10.29.13		REV. PER RER COMMENTS

date: 09-12-12
scale: 3/8" = 1"
dr. by: HAMID
chk. by:

drawing no.
W12-51

sheet 3 of 13

MULLION DESIGN LOAD CAPACITY - PSF CHART FOR LAMINATED GLASS MULLIONS WITH INTERMEDIATE HORIZONTALS			
NOMINAL DIMS.		JAMB 'J1' MULL 'M1'	
WIDTH (W)	FRAME HEIGHT	EXT. (+)	INT. (−)
30"	108"	100.0	110.0
36"		100.0	110.0
42"		100.0	110.0
48"		100.0	110.0
54"		100.0	110.0
60"		100.0	110.0
30"	114"	100.0	110.0
36"		100.0	110.0
42"		100.0	110.0
48"		100.0	110.0
54"		100.0	110.0
60"		100.0	106.3
30"	120"	100.0	110.0
36"		100.0	110.0
42"		100.0	110.0
48"		100.0	110.0
54"		100.0	101.3
57"		96.0	96.0
30"	126"	100.0	110.0
36"		100.0	110.0
42"		100.0	110.0
48"		98.4	98.4
54"		87.5	87.5
30"	132"	100.0	110.0
36"		100.0	110.0
42"		97.9	97.9
48"		85.6	85.6
52"		79.0	79.0
30"	138"	100.0	110.0
36"		99.9	99.9
42"		85.6	85.6
48"		74.9	74.9
50"		71.9	71.9
30"	144"	100.0	105.5
36"		87.9	87.9
42"		75.4	75.4
48"		66.0	66.0

MULLION DESIGN LOAD CAPACITY - PSF CHART FOR LAMINATED GLASS MULLIONS WITH INTERMEDIATE HORIZONTALS					
NOMINAL DIMS.		JAMB 'J2' MULL '2'		JAMB 'J3' MULL 'M3'	
WIDTH (W)	FRAME HEIGHT	EXT. (+)	INT. (−)	EXT. (+)	INT. (−)
30"	96"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
48"		100.0	150.0	100.0	150.0
54"		100.0	150.0	100.0	150.0
58"		100.0	150.0	100.0	150.0
60"		100.0	140.0	100.0	140.0
30"	102"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
48"		100.0	150.0	100.0	150.0
54"		100.0	150.0	100.0	150.0
55"		100.0	150.0	100.0	150.0
60"		100.0	140.0	100.0	140.0
30"	108"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
48"		100.0	150.0	100.0	150.0
52"		100.0	150.0	100.0	150.0
54"		100.0	140.0	100.0	140.0
60"		100.0	140.0	100.0	140.0
30"	114"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
48"		100.0	150.0	100.0	150.0
49"		100.0	150.0	100.0	150.0
54"		100.0	140.0	100.0	140.0
60"		100.0	129.1	100.0	140.0
30"	120"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
47"		100.0	148.7	100.0	150.0
48"		100.0	140.0	100.0	140.0
54"		100.0	129.5	100.0	140.0
57"		100.0	122.6	100.0	140.0
30"	126"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
44"		100.0	144.1	100.0	150.0
48"		100.0	132.1	100.0	140.0
54"		100.0	117.4	100.0	140.0
30"	132"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	137.6	100.0	150.0
48"		100.0	120.4	100.0	140.0
52"		100.0	111.1	100.0	140.0
30"	138"	100.0	150.0	100.0	150.0
36"		100.0	146.8	100.0	150.0
40"		100.0	132.1	100.0	150.0
42"		100.0	125.8	100.0	140.0
48"		100.0	110.1	100.0	140.0
50"		100.0	105.7	100.0	140.0
30"	144"	100.0	150.0	100.0	150.0
36"		100.0	134.8	100.0	150.0
39"		100.0	124.5	100.0	150.0
42"		100.0	115.6	100.0	140.0
48"		100.0	101.1	100.0	140.0



WIDTH (W) = W1
AT JAMB

WIDTH (W) = $\frac{W2 + W3}{2}$
AT MULLION



WIDTH (W) = $\frac{W1 + W2}{2}$
AT MULLION

MAX. DOOR HEIGHTS FOR WINDOW WALL WITH DOORS TO BE LIMITED TO THE MAX. APPROVED DOOR HEIGHTS.

Approved as complying with the Florida Building Code
Date 11/8/2013
NOA# 13-0611.25
Miami Dade Product Control
By

NOTE:
INTERPOLATION BETWEEN WIDTHS ALLOWED.

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538
OCT 29 2013

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978

STORE\W12-51ES

SERIES 7100 ALUM WINDOW WALL SYSTEM (S.M.I.)

E.S. WINDOWS, LLC
5220 N.W. 72 AVE. BAY #4
MIAMI, FL. 33166
TEL. (305) 624-7775 FAX. (305) 624-7777

revisions:

no	date	by	description
A	10.29.13		REV. PER RER COMMENTS

date: 09-12-12
scale: 3/8" = 1"
dr. by: HAMID
chk. by:

drawing no.
W12-51

sheet 3.1 of 13

MULLION DESIGN LOAD CAPACITY - PSF CHART FOR INSUL. LAM. GLASS MULLIONS WITHOUT INTERMEDIATE HORIZONTALS			
NOMINAL DIMS.		JAMB 'J1' MULL 'M1'	
WIDTH (W)	FRAME HEIGHT	EXT. (+)	INT. (–)
30"	114"	100.0	110.0
36"		100.0	110.0
42"		100.0	110.0
48"		100.0	110.0
54"		100.0	110.0
60"		100.0	110.0
30"	120"	100.0	110.0
36"		100.0	110.0
42"		100.0	110.0
48"		100.0	110.0
54"		100.0	102.9
57"		98.4	98.4
30"	126"	100.0	110.0
36"		100.0	110.0
42"		100.0	110.0
48"		97.6	97.6
54"		88.1	88.1
30"	132"	100.0	110.0
36"		100.0	109.9
42"		95.2	95.2
48"		84.4	84.4
52"		78.7	78.7
30"	138"	100.0	110.0
36"		96.0	96.0
42"		83.1	83.1
48"		73.5	73.5
50"		70.9	70.9
30"	144"	100.0	100.4
36"		84.3	84.3
42"		72.9	72.9
48"		64.5	64.5

MULLION DESIGN LOAD CAPACITY - PSF CHART FOR INSUL. LAM. GLASS MULLIONS WITHOUT INTERMEDIATE HORIZONTALS					
NOMINAL DIMS.		JAMB 'J2' MULL 'M2'		JAMB 'J3' MULL 'M3'	
WIDTH (W)	FRAME HEIGHT	EXT. (+)	INT. (–)	EXT. (+)	INT. (–)
30"	96"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
48"		100.0	150.0	100.0	150.0
54"		100.0	150.0	100.0	150.0
58"		100.0	140.0	100.0	140.0
60"		100.0	140.0	100.0	140.0
30"	102"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
48"		100.0	150.0	100.0	150.0
54"		100.0	140.0	100.0	140.0
55"		100.0	140.0	100.0	140.0
60"		100.0	140.0	100.0	140.0
30"	108"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
48"		100.0	150.0	100.0	150.0
52"		100.0	140.0	100.0	140.0
54"		100.0	140.0	100.0	140.0
60"		100.0	140.0	100.0	140.0
30"	114"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
48"		100.0	140.0	100.0	140.0
49"		100.0	140.0	100.0	140.0
54"		100.0	140.0	100.0	140.0
58"		100.0	137.0	100.0	140.0
60"		100.0	134.1	100.0	140.0
30"	120"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
47"		100.0	140.0	100.0	140.0
48"		100.0	140.0	100.0	140.0
54"		100.0	130.9	100.0	140.0
55"		100.0	128.9	100.0	140.0
57"		100.0	125.0	100.0	140.0
30"	126"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	148.0	100.0	150.0
44"		100.0	140.0	100.0	140.0
48"		100.0	131.0	100.0	140.0
52"		100.0	122.3	100.0	140.0
54"		100.0	118.0	100.0	140.0
30"	132"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	134.4	100.0	140.0
48"		100.0	118.8	100.0	140.0
50"		100.0	114.4	100.0	140.0
52"		100.0	110.5	100.0	140.0
30"	138"	100.0	150.0	100.0	150.0
36"		100.0	138.4	100.0	150.0
40"		100.0	125.4	100.0	140.0
42"		100.0	119.8	100.0	140.0
48"		100.0	106.0	100.0	138.6
50"		100.0	102.2	100.0	133.6
30"	144"	100.0	140.0	100.0	140.0
36"		100.0	121.5	100.0	140.0
39"		100.0	113.3	100.0	138.6
42"		100.0	105.1	100.0	137.3
48"		93.0	93.0	100.0	121.5



WIDTH (W) = W1 AT JAMB

WIDTH (W) = $\frac{W2 + W3}{2}$ AT MULLION



WIDTH (W) = $\frac{W1 + W2}{2}$ AT MULLION



WIDTH (W) = $\frac{W1}{2} + \frac{W2}{4}$ AT MULLION

MAX. DOOR HEIGHTS FOR WINDOW WALL WITH DOORS TO BE LIMITED TO THE MAX. APPROVED DOOR HEIGHTS.



JAMB 'J1' & 'J2'

Ix IN^4	Sx IN^3
14.1989	4.5744



JAMB 'J3'

	Ix IN^4	Sx IN^3
ALUMINUM	14.1989	4.5744
STEEL	2.197	1.172
TOTAL Ix ALUM + Ix STL X 2.9	20.571	



MULLION 'M1'

Ix IN^4	Sx IN^3
14.414	4.488



MULLION 'M2'

	Ix IN^4	Sx IN^3
ALUMINUM	14.414	4.488
STEEL	2.197	1.172
TOTAL Ix ALUM + Ix STL X 2.9	20.786	



MULLION 'M3'

	Ix IN^4	Sx IN^3
ALUMINUM	14.414	4.488
STEEL	4.394	2.344
TOTAL Ix ALUM + Ix STL X 2.9	27.158	

Approved as complying with the Florida Building Code
Date 11/07/2013
NOA# 13-0617.26
Miami-Dade Product Control
By

NOTE:
INTERPOLATION BETWEEN WIDTHS ALLOWED.

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978

STORE\W12-51ES

SERIES 7100 ALUM WINDOW WALL SYSTEM (S.M.I.)

E.S. WINDOWS, LLC
5220 N.W. 72 AVE. BAY #4
MIAMI, FL. 33166
TEL. (305) 624-7775 FAX. (305) 624-7777

revisions:

no	date	by	description
A	10.29.13	RER	REV. PER COMMENTS

date: 09-12-12
scale: 3/8" = 1"
dr. by: HAMID
chk. by:

drawing no.
W12-51

sheet 4 of 13

MULLION DESIGN LOAD CAPACITY – PSF CHART FOR INSUL. LAM. GLASS MULLIONS WITH INTERMEDIATE HORIZONTALS			
NOMINAL DIMS.		JAMB 'J1' MULL 'M1'	
WIDTH (W)	FRAME HEIGHT	EXT. (+)	INT. (–)
30"	108"	100.0	110.0
36"		100.0	110.0
42"		100.0	110.0
48"		100.0	110.0
54"		100.0	110.0
60"		100.0	110.0
30"	114"	100.0	110.0
36"		100.0	110.0
42"		100.0	110.0
48"		100.0	110.0
54"		100.0	110.0
60"		99.6	99.6
30"	120"	100.0	110.0
36"		100.0	110.0
42"		100.0	110.0
48"		100.0	106.8
54"		94.9	94.9
57"		89.9	89.9
30"	126"	100.0	110.0
36"		100.0	110.0
42"		100.0	105.4
48"		92.2	92.2
54"		82.0	82.0
30"	132"	100.0	110.0
36"		100.0	106.9
42"		91.7	91.7
48"		80.2	80.2
52"		74.0	74.0
30"	138"	100.0	110.0
36"		93.6	93.6
42"		80.2	80.2
48"		70.2	70.2
50"		67.4	67.4
30"	144"	98.8	98.8
36"		82.4	82.4
42"		70.6	70.6
48"		61.8	61.8

MULLION DESIGN LOAD CAPACITY – PSF CHART FOR INSUL. LAM. GLASS MULLIONS WITH INTERMEDIATE HORIZONTALS					
NOMINAL DIMS.		JAMB 'J2' MULL 'M2'		JAMB 'J3' MULL 'M3'	
WIDTH (W)	FRAME HEIGHT	EXT. (+)	INT. (–)	EXT. (+)	INT. (–)
30"	96"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
48"		100.0	150.0	100.0	150.0
54"		100.0	150.0	100.0	150.0
58"		100.0	140.0	100.0	140.0
60"		100.0	140.0	100.0	140.0
30"	102"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
48"		100.0	150.0	100.0	150.0
54"		100.0	140.0	100.0	140.0
55"		100.0	140.0	100.0	140.0
60"		100.0	140.0	100.0	140.0
30"	108"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
48"		100.0	150.0	100.0	150.0
52"		100.0	140.0	100.0	140.0
54"		100.0	140.0	100.0	140.0
60"		100.0	135.9	100.0	140.0
30"	114"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
48"		100.0	140.0	100.0	140.0
49"		100.0	139.2	100.0	140.0
54"		100.0	135.5	100.0	140.0
58"		100.0	128.7	100.0	140.0
60"		100.0	122.0	100.0	140.0
30"	120"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	150.0	100.0	150.0
47"		100.0	140.0	100.0	140.0
48"		100.0	137.6	100.0	140.0
54"		100.0	122.3	100.0	140.0
55"		100.0	120.1	100.0	140.0
57"		100.0	115.9	100.0	140.0
30"	126"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	142.6	100.0	150.0
44"		100.0	136.2	100.0	140.0
48"		100.0	124.8	100.0	140.0
52"		100.0	115.5	100.0	140.0
54"		100.0	110.9	100.0	140.0
30"	132"	100.0	150.0	100.0	150.0
36"		100.0	150.0	100.0	150.0
42"		100.0	130.0	100.0	140.0
48"		100.0	113.7	100.0	140.0
50"		100.0	109.3	100.0	140.0
52"		100.0	105.0	100.0	137.2
30"	138"	100.0	150.0	100.0	150.0
36"		100.0	135.0	100.0	150.0
40"		100.0	122.1	100.0	147.5
42"		100.0	115.7	100.0	140.0
48"		100.0	101.2	100.0	132.3
50"		97.2	97.2	100.0	127.0
30"	144"	100.0	140.0	100.0	140.0
36"		100.0	118.8	100.0	140.0
39"		100.0	110.3	100.0	136.5
42"		100.0	101.8	100.0	133.0
48"		89.1	89.1	100.0	116.4



WIDTH (W) = W1
AT JAMB

WIDTH (W) = $\frac{W2 + W3}{2}$
AT MULLION



WIDTH (W) = $\frac{W1 + W2}{2}$
AT MULLION

MAX. DOOR HEIGHTS FOR WINDOW WALL WITH DOORS TO BE LIMITED TO THE MAX. APPROVED DOOR HEIGHTS.

Approved as complying with the Florida Building Code
Date 11/27/2013
NOA# 13-0617.28
Miami Dade Product Control
By

NOTE:
INTERPOLATION BETWEEN WIDTHS ALLOWED.

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538

OCT 29 2013

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8400 FAX. (305) 262-6978

STORE\W12-51ES

SERIES 7100 ALUM WINDOW WALL SYSTEM (S.M.I.)

E.S. WINDOWS, LLC
5220 N.W. 72 AVE.
MIAMI, FL. 33166
TEL. (305) 624-7775 FAX. (305) 624-7777

revisions:

no	date	by	description
A	10.29.13		REV. PER RER COMMENTS

date: 09-12-12
scale: 3/8" = 1"
dr. by: HAMID
chk. by:

drawing no.
W12-51

ANCHOR DESIGN LOAD CAPACITY – PSF
EXT.(+) & INT.(–)

NOMINAL DIMS.		TYPE 'A'		TYPE 'B'		TYPE 'C'	
WIDTH (W)	FRAME HEIGHT	A3	A4	B3	B4	C3	C4
30"	90"	150.0	150.0	150.0	150.0	150.0	150.0
36"		150.0	150.0	150.0	150.0	150.0	150.0
42"		132.6	150.0	150.0	150.0	150.0	150.0
48"		116.0	150.0	150.0	150.0	140.0	150.0
54"		103.1	137.5	149.3	150.0	124.4	150.0
60"		92.8	123.7	134.0	150.0	112.0	149.3
30"	96"	150.0	150.0	150.0	150.0	150.0	150.0
36"		145.0	150.0	150.0	150.0	150.0	150.0
42"		124.3	150.0	150.0	150.0	150.0	150.0
48"		108.8	145.0	150.0	150.0	131.3	150.0
54"		96.7	128.9	140.0	150.0	116.7	150.0
60"		87.0	116.0	126.0	150.0	105.0	140.0
30"	102"	150.0	150.0	150.0	150.0	150.0	150.0
36"		136.5	150.0	150.0	150.0	150.0	150.0
42"		117.0	150.0	150.0	150.0	141.2	150.0
48"		102.4	136.5	148.2	150.0	123.5	150.0
54"		91.0	121.3	131.8	150.0	109.8	146.4
60"		81.9	109.2	118.6	150.0	98.8	131.8
30"	108"	150.0	150.0	150.0	150.0	150.0	150.0
36"		128.9	150.0	150.0	150.0	150.0	150.0
42"		110.5	147.3	150.0	150.0	133.3	150.0
48"		96.7	128.9	140.0	150.0	116.7	150.0
54"		85.9	114.6	124.4	150.0	103.7	138.3
60"		77.3	103.1	112.0	149.3	93.3	124.4
30"	114"	146.5	150.0	150.0	150.0	150.0	150.0
36"		122.1	150.0	150.0	150.0	147.4	150.0
42"		104.7	139.5	150.0	150.0	126.3	150.0
48"		91.6	122.1	132.6	150.0	110.5	147.4
54"		81.4	108.5	117.9	150.0	98.2	131.0
60"		73.3	97.7	106.1	141.5	88.4	117.9
30"	120"	139.2	150.0	150.0	150.0	150.0	150.0
36"		116.0	150.0	150.0	150.0	140.0	150.0
42"		99.4	132.6	144.0	150.0	120.0	150.0
48"		87.0	116.0	126.0	150.0	105.0	140.0
54"		77.3	103.1	112.0	149.3	93.3	124.4
30"	126"	132.6	150.0	150.0	150.0	150.0	150.0
36"		110.5	147.3	150.0	150.0	133.3	150.0
42"		94.7	126.3	137.1	150.0	114.3	150.0
48"		82.9	110.5	120.0	150.0	100.0	133.3
54"		73.7	98.2	106.7	142.2	88.9	118.5
30"	132"	126.5	150.0	150.0	150.0	150.0	150.0
36"		105.5	140.6	150.0	150.0	127.3	150.0
42"		90.4	120.5	130.9	150.0	109.1	145.5
48"		79.1	105.5	114.5	150.0	95.5	127.3
52"		73.0	97.3	105.7	141.0	88.1	117.4
30"	138"	121.0	150.0	150.0	150.0	146.1	150.0
36"		100.9	134.5	146.1	150.0	121.7	150.0
42"		86.5	115.3	125.2	150.0	104.3	139.1
48"		75.7	100.9	109.6	146.1	91.3	121.7
30"	144"	116.0	150.0	150.0	150.0	140.0	150.0
36"		96.7	128.9	140.0	150.0	116.7	150.0
42"		82.9	110.5	120.0	150.0	100.0	133.3
48"		72.5	96.7	105.0	140.0	87.5	116.7



WIDTH (W) = W1
AT FRAME JAMB

WIDTH (W) = $\frac{W2 + W3}{2}$
AT FRAME MULLION

ANCHORS TYPES: SEE SHEET 7 FOR DESCRIPTION

A3 = (3) ANCHORS TYPE 'A' AT EACH SIDE OF JAMB AND MULLION
B3 = (3) ANCHORS TYPE 'B' AT EACH SIDE OF JAMB AND MULLION
C3 = (3) ANCHORS TYPE 'C' AT EACH SIDE OF JAMB AND MULLION

A4 = (4) ANCHORS TYPE 'A' AT EACH SIDE OF JAMB AND MULLION
B4 = (4) ANCHORS TYPE 'B' AT EACH SIDE OF JAMB AND MULLION
C4 = (4) ANCHORS TYPE 'C' AT EACH SIDE OF JAMB AND MULLION

ALL OTHER ANCHORS TO BE SPACED AS PER ELEVATION.

Approved as complying with the
Florida Building Code
Date 11/07/2013
NOA# 13-0617.25
Miami Dade Product Control
By

NOTE:
INTERPOLATION BETWEEN WIDTHS OR HEIGHTS ALLOWED.

Engr: JAVAD AHMAD
CML
FLA. PE # 70592
C.A.N. 3538
OCT 29 2013

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
STORE\W12-51ES

SERIES 7100 ALUM WINDOW WALL SYSTEM (S.M.I.)

E.S. WINDOWS, LLC
5220 N.W. 72 AVE. BAY #4
MIAMI, FL. 33166
TEL. (305) 624-7775 FAX. (305) 624-7777

revisions:

no	date	by	description
A	10.29.13		NO CHANGE THIS SHEET

date: 04-24-13
scale: 3/8" = 1"
dr. by: HAMID
chk. by:

drawing no.
W12-51

DOOR MULLION DESIGN LOAD CAPACITY-PSF				
SIDELITE WIDTH INCHES	FRAME HEIGHT INCHES	MULL 'MD1' EXT. (+) INT. (−)	MULL 'MD2' EXT. (+) INT. (−)	MULL 'MD3' EXT. (+) INT. (−)
30	120	90.0	90.0	90.0
36		90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		90.0	90.0	90.0
57		89.7	90.0	90.0
30	126	90.0	90.0	90.0
36		90.0	90.0	90.0
42		85.7	90.0	90.0
48		81.3	90.0	90.0
54		77.3	90.0	90.0
30	132	81.4	90.0	90.0
36		76.8	90.0	90.0
42		72.8	90.0	90.0
48		69.1	90.0	90.0
52		66.9	90.0	90.0
30	138	69.7	90.0	90.0
36		65.8	90.0	90.0
42		62.4	90.0	90.0
48		59.3	86.8	90.0
50		58.4	85.4	90.0
30	144	60.2	90.0	90.0
36		57.0	85.8	90.0
42		54.1	81.6	90.0
48		51.5	77.8	90.0



DOOR MULLION DESIGN LOAD CAPACITY-PSF				
SIDELITE WIDTH INCHES	FRAME HEIGHT INCHES	MULL 'MD1' EXT. (+) INT. (−)	MULL 'MD2' EXT. (+) INT. (−)	MULL 'MD3' EXT. (+) INT. (−)
30	120	90.0	90.0	90.0
36		90.0	90.0	90.0
42		90.0	90.0	90.0
48		90.0	90.0	90.0
54		86.2	90.0	90.0
57		84.0	90.0	90.0
30	126	90.0	90.0	90.0
36		84.9	90.0	90.0
42		80.3	90.0	90.0
48		76.2	90.0	90.0
54		72.4	90.0	90.0
30	132	76.2	90.0	90.0
36		72.0	90.0	90.0
42		68.2	90.0	90.0
48		64.7	90.0	90.0
52		62.6	89.1	90.0
30	138	65.3	90.0	90.0
36		61.7	89.0	90.0
42		58.5	84.3	90.0
48		55.6	80.2	90.0
50		54.7	78.9	90.0
30	144	56.4	81.4	90.0
36		53.4	77.0	90.0
42		50.7	73.1	90.0
48		48.2	69.5	90.0

LAMINATED GLASS MULLIONS



MULLION 'MD1'

Ix IN^4	Sx IN^3
15.385	4.546



MULLION 'MD2'

	Ix IN^4	Sx IN^3
ALUMINUM	15.385	4.546
STEEL	3.797	1.6875
TOTAL Ix ALUM + Ix STL X 2.9	26.396	



MULLION 'MD3'

	Ix IN^4	Sx IN^3
ALUMINUM	15.385	4.546
STEEL	7.594	3.375
TOTAL Ix ALUM + Ix STL X 2.9	37.407	

INSUL. LAM. GLASS MULLIONS



MULLION 'MD1'

Ix IN^4	Sx IN^3
14.414	4.488



MULLION 'MD2'

	Ix IN^4	Sx IN^3
ALUMINUM	14.414	4.488
STEEL	2.197	1.172
TOTAL Ix ALUM + Ix STL X 2.9	20.786	



MULLION 'MD3'

	Ix IN^4	Sx IN^3
ALUMINUM	14.414	4.488
STEEL	4.394	2.344
TOTAL Ix ALUM + Ix STL X 2.9	27.158	

Approved as complying with the
Florida Building Code
Date 11/07/2013
NOA# 13-0617.25
Miami-Dade Product Control
By

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538
OCT 29 2013

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978

STORE\W12-51ES

SERIES 7100 ALUM WINDOW WALL SYSTEM (S.M.I.)

E.S. WINDOWS, LLC
5220 N.W. 72 AVE. BAY #4
MIAMI, FL. 33166
TEL. (305) 624-7775 FAX. (305) 624-7777

revisions:

no	date	by	description
A	10.29.13		NO CHANGE THIS SHEET

date: 09-12-12
scale: 3/8" = 1"
dr. by: HAMID
chk. by:

drawing no.
W12-51



LAMINATED GLASS



INSUL. LAM. GLASS

METAL STRUCTURES NOT BY E.S. WDW.
MUST SUPPORT LOADS IMPOSED BY GLAZING SYSTEM AND TRANSFER THEM TO THE BUILDING STRUCTURE.

TYPICAL ANCHORS: SEE ELEV. FOR SPACING

TYPE 'A'

1/4" DIA ULTRACON BY 'ELCO' (Fu=177 KSI, Fy=155 KSI)

DIRECTLY INTO CONCRETE
WITH 1-3/4" MIN. EMBED INTO CONC.

ANCHOR EDGE DISTANCES

INTO CONCRETE = 2-1/2" MIN.

TYPE 'B'

5/16" DIA ULTRACON BY 'ELCO' (Fu=177 KSI, Fy=155 KSI)

DIRECTLY INTO CONCRETE
WITH 1-3/4" MIN. EMBED INTO CONC.

ANCHOR EDGE DISTANCES

INTO CONCRETE = 3-1/8" MIN.

TYPE 'C'

#14 SMS OR SELF DRILLING SCREWS ST/ST (Fu=100 KSI, Fy=65 KSI)

INTO METAL STRUCTURES

STEEL : 1/8" THK. MIN. (Fy = 36 KSI MIN.)
ALUMINUM : 1/8" THK. MIN. (6063-T6 MIN.)
(STEEL IN CONTACT WITH ALUMINUM TO BE PLATED OR PAINTED)

ANCHOR EDGE DISTANCES

INTO METAL STRUCTURE = 1" MIN.

SEALANTS:

ALL FRAME CORNERS, JOINTS, MULLION SEAMS AND PERIMETER OF GLAZING BEAD TO FRAME SEALED WITH SILICONE SEALANT.

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538

OCT 29 2013

Approved as complying with the
Florida Building Code
Date 11/07/2013
NOA# 13-0626.23
Miami-Dade Product Control
By

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978

STORE\W12-51ES

SERIES 7100 ALUM ALUM WINDOW WALL SYSTEM (S.M.I.)

E.S. WINDOWS, LLC
5220 N.W. 72 AVE. BAY #4
MIAMI, FL. 33166
TEL. (305) 624-7775 FAX. (305) 624-7777

revisions:

no	date	by	description
A	10.29.13		REV. PER RER COMMENTS

date: 04-14-13
scale: 3/8" = 1"
dr. by: HAMID
chk. by:

drawing no.
W12-51

sheet 7 of 13







Approved as complying with the
Florida Building Code
Date 11/07/2013
NOA# 13-0619.25
Miami Dade Product Control
By

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538
OCT 29 2013

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978

STORE\W12-51ES

SERIES 7100 ALUM WINDOW WALL SYSTEM (S.M.I.)

E.S. WINDOWS, LLC
5220 N.W. 72 AVE. BAY #4
MIAMI, FL. 33166
TEL. (305) 624-7775 FAX. (305) 624-7777

revisions:

no	date	by	description
A	10.29.13		REV. PER RER COMMENTS

date: 09-12-12
scale: 3/8" = 1"
dr. by: HAMID
chk. by:

drawing no.
W12-51



LAMINATED GLASS



INSUL. LAM. GLASS

SEE SEPARATE NOA FOR DESIGN LOAD CAPACITY OF DOORS AND DOOR ANCHORS.

LOWER VALUES FROM DOORS NOA OR WINDOWALL SYSTEM CAPACITY CHARTS WILL APPLY TO ENTIRE SYSTEM.

Approved as complying with the Florida Building Code
Date 11/8/2013
NOA# 13-0814.25
Miami-Dade Product Control
By

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538
OCT 29 2013

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL (305) 264-8100 FAX. (305) 262-6978

STORE\W12-51ES

SERIES 7100 ALUM WINDOW WALL SYSTEM (S.M.I.)

E.S. WINDOWS, LLC
5220 N.W. 72 AVE. BAY #4
MIAMI, FL. 33166
TEL (305) 624-7775 FAX. (305) 624-7777

revisions:

no	date	by	description
A	10.29.13		REV. PER RER COMMENTS

date: 09-12-12
scale: 3/8" = 1"
dr. by: HAMID
chk. by:

drawing no. W12-51

sheet 9 of 13









LAMINATED GLASS

INSUL. LAM. GLASS

SEE SEPARATE NOA FOR DESIGN LOAD CAPACITY OF DOORS AND DOOR ANCHORS.

LOWER VALUES FROM DOORS NOA OR WINDOWALL SYSTEM CAPACITY CHARTS WILL APPLY TO ENTIRE SYSTEM.

Approved as complying with the Florida Building Code
Date 11/04/2013
NOA# 13-0614.25
Miami-Dade Product Control
By

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538
OCT 29 2013

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
STORE\W12-51ES

SERIES 7100 ALUM. WINDOW WALL SYSTEM (S.M.I.)

E.S. WINDOWS, LLC
5220 N.W. 72 AVE. BAY #4
MIAMI, FL. 33166
TEL. (305) 624-7775 FAX. (305) 624-7777

revisions:

no	date	by	description
A	10.29.13		REV. PER RER COMMENTS

date: 09-12-12
scale: 3/8" = 1"
dr. by: HAMID
chk. by:

drawing no.
W12-51

UNANCHORED JAMB DEFLECTION AT 100 PSF DESIGN WIND PRESSURE DEFLECTION – IN. (CHART D100)					
NOMINAL DIMS.		LAM. GLASS		INSUL. LAM. GLASS	
WIDTH (W)	FRAME HEIGHT	UNREINF.	REINF.	UNREINF.	REINF.
30"	96"	.079	.045	.081	.056
36"		.095	.054	.097	.067
42"		.110	.063	.114	.078
48"		.126	.072	.130	.090
54"		.142	.081	.146	.101
60"		.158	.090	.162	.112
30"	102"	.100	.057	.103	.071
36"		.121	.069	.124	.086
42"		.141	.080	.145	.100
48"		.161	.092	.165	.114
54"		.181	.103	.186	.128
60"		.201	.115	.207	.143
30"	108"	.126	.072	.130	.090
36"		.152	.086	.156	.108
42"		.177	.101	.182	.126
48"		.202	.115	.208	.144
54"		.227	.130	.234	.161
60"		.253	.144	.260	.179
30"	114"	.157	.089	.161	.111
36"		.188	.107	.194	.134
42"		.220	.125	.226	.156
48"		.251	.143	.258	.178
54"		.282	.161	.290	.200
60"		.314	.179	.323	.223
30"	120"	.192	.110	.198	.137
36"		.231	.132	.238	.164
42"		.269	.154	.277	.191
48"		.308	.176	.317	.219
57"		.365	.198	.376	.260
30"	126"	.234	.133	.241	.166
36"		.281	.160	.289	.199
42"		.328	.187	.337	.233
48"		.374	.213	.385	.266
54"		.421	.240	.433	.299
30"	132"	.282	.161	.290	.200
36"		.338	.193	.348	.240
42"		.395	.225	.406	.280
48"		.451	.257	.464	.320
52"		.488	.278	.503	.347
30"	138"	.337	.192	.346	.239
36"		.404	.230	.416	.287
42"		.471	.269	.485	.335
48"		.539	.307	.554	.383
30"	144"	.399	.228	.411	.284
36"		.479	.273	.493	.340
42"		.559	.319	.575	.397
48"		.639	.364	.657	.454



UNANCHORED JAMBS MOVEMENT AND JOINT SEALANT DETERMINATION CHART D100 AT LEFT TO BE USED TO DETERMINE JAMB DEFLECTION AT 100 PSF DESIGN WIND PRESSURE FOR ANY OF THE POSSIBLE UNANCHORED CONDITIONS.
THIS VALUE CAN BE USED TO DETERMINE THE ACTUAL PROJECT DEFLECTION USING INSTRUCTIONS SHOWN BELOW.
USING GAP/DEFLECTION CHART DETERMINE THE MAX. DEFLECTION ALLOWED FOR THE GAPS SHOWN FOR TWO SEALANT TYPES.

INSTRUCTIONS: TO OBTAIN DEFLECTION AT PROJECT (Pd)

1. DETERMINE APPLICABLE JAMB (UNREINFORCED OR REINFORCED)
2. OBTAIN REQUIRED DESIGN WIND PRESSURE.
3. READ DEFLECTION AT 100 PSF (D100) FROM CHART AT LEFT.
4. OPTAIN PROJECT DEFLECTION (PD)

$$PD = \frac{P}{100} \times D100$$

(PD MUST NOT EXCEED L/180)

5. FROM CHART BELOW DETERMINE MAX. DEFLECTION ALLOWABLE FOR A GIVEN PROJECT GAP AND SEALANT TYPE.

GAP/DEFL. CHART		
	MAX. DEFL. IN.	
GAP. IN.	50%	100%
.250"	.28"	.433"
.375"	.420"	.649"
.500"	.560"	.800"
.625"	.700"	.800"
.750"	.800"	.800"
1.000"	.800"	.800"

MAXIMUM GAP = 1"
MINIMUM GAP = 1/4"

EXAMPLE:
FOR A GAP OF 1/2"
MAX. DEFLECTION ALLOWED = .560" FOR 50% STRETCH SEALANT
= .800" FOR 100% STRETCH SEALANT

ALTERNATE SEALANTS AT JAMB GAPS CAN BE DESIGNED BY ENGINEER OF RECORD BASED ON MANUFACTURER GUIDE LINES.

GAPS LESS THAN 1/4" MAY BE DESIGNED BY ENGINEER OF RECORD BY THE USE OF BOND BREAKER TAPE OR 15% OF GAP ALLOWED MOVEMENT.

Approved as complying with the Florida Building Code
Date 11/07/2013
NOA# 13-0617.25
Miami Dade Product Control
By

LAMINATED GLASS



Ix IN^4	Sx IN^3
14.6111	4.6414



	Ix IN^4	Sx IN^3
ALUMINUM	14.6111	4.6414
STEEL	3.797	1.687
TOTAL Ix ALUM + Ix STL X 2.9	25.622	

INSUL. LAM. GLASS



Ix IN^4	Sx IN^3
14.1989	4.5744



	Ix IN^4	Sx IN^3
ALUMINUM	14.1989	4.5744
STEEL	2.197	1.172
TOTAL Ix ALUM + Ix STL X 2.9	20.571	

NOTE:
DATA IN THIS SHEET MAY BE USED TO QUALIFY SEALANT TO BE USED AT UNANCHORED JAMBS.
MAX. MOVEMENT CONSIDERED=50% OR 100% STRETCH.
PLEASE REFER TO SEALANT MANUFACTURER'S DATA AND APPLICATION MANUAL FOR COMPATABILITY OF SEALANT TO SUBSTRATE & WINDOW WALL MATERIAL/FINISH AND COMPLIANCE FOR WARRANTY.
REFER TO ACI-117-10 FOR CONSTRUCTION TOLERANCES.

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538
OCT 2 2013

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
STORE\W12-51ES

SERIES 7100 ALUM WINDOW WALL SYSTEM (S.M.I.)

E.S. WINDOWS, LLC
5220 N.W. 72 AVE. BAY #4
MIAMI, FL. 33166
TEL. (305) 624-7775 FAX. (305) 624-7777

revisions:			
no	date	by	description
A	10.29.13		REV. PER RER COMMENTS

date: 09-12-12
scale: NONE
dr. by: HAMID
chk. by:

drawing no.
W12-51



(1) FRAME HEAD/SILL (LAM. GLASS)



(5) INTERMEDIATE HORIZONTAL (LAM. GLASS)



(16) TRANSOM MULLION (LAM. GLASS)



(4) ANCHOR BASE



(1A) FRAME HEAD/SILL (LAM. INSUL. GLASS)



(5A) INTERMEDIATE HORIZONTAL (LAM. INSUL. GLASS)



(16A) TRANSOM MULLION (LAM. INSUL. GLASS)



(2) GLAZING STOP



(9) SECURED JAMB (LAM. GLASS)



(10) UNSECURED JAMB (LAM. GLASS)



(7) MALE MULLION (LAM. GLASS)



(8) FEMALE MULLION (LAM. GLASS)



(6) REINF. BAR (LAM. GLASS)



(3) SNAP COVER



(9A) SECURED JAMB (LAM. INSUL. GL.)



(10A) UNSECURED JAMB (LAM. INSUL. GL.)



(7A) MALE MULLION (LAM. INSUL. GL.)



(8A) FEMALE MULLION (LAM. INSUL. GL.)



(6A) REINF. BAR (LAM. INSULATED GLASS)

Approved as complying with the Florida Building Code
Date 11/07/2013
NOA# 13-0917.26
Miami Dade Product Control
By

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538

OCT 29 2013

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978

STORE\W12-51ES

SERIES 7100 ALUM WINDOW WALL SYSTEM (S.M.I.)

E.S. WINDOWS, LLC
5220 N.W. 72 AVE. BAY #4
MIAMI, FL. 33166
TEL. (305) 624-7775 FAX. (305) 624-7777

revisions:

no	date	by	description
A	10.29.13		NO CHANGE THIS SHEET

date: 09-12-12
scale: 3/8" = 1"
dr. by: HAMID
chk. by:

drawing no.
W12-51

sheet 12 of 13

ITEM NO.	PART NUMBER	QUANTITY	DESCRIPTION	MATERIAL	MANF./SUPPLIER/REMARKS
1	ES7001A	AS REQD.	FRAME HEAD/SILL (LAM. GLASS)	6005-T5	-
1A	ES7021	AS REQD.	FRAME HEAD/SILL (INSUL. LAM. GLASS)	6005-T5	-
2	ES7006	AS REQD.	GLAZING STOP	6063-T6	-
3	ES7003	AS REQD.	SNAP COVER	6063-T5	-
4	ES7004	AS REQD.	ANCHOR BASE, 9" LONG	6005-T5	-
5	ES7005	AS REQD.	INTERMEDIATE HORIZONTAL (LAM. GLASS)	6005-T5	-
5A	ES7022	AS REQD.	INTERMEDIATE HORIZONTAL (INSUL. LAM. GLASS)	6005-T5	-
6	-	AS REQD.	REINFORCING BAR (LAM. GLASS)	STEEL	A36, Fu MIN. = 58 KSI
6A	-	AS REQD.	REINFORCING BAR (INSUL. LAM. GLASS)	STEEL	A36, Fu MIN. = 58 KSI
7	ES7007	AS REQD.	MALE MULLION (LAM. GLASS)	6005-T5	-
7A	ES7023	AS REQD.	MALE MULLION (INSUL. LAM. GLASS)	6005-T5	-
8	ES7008	AS REQD.	FEMALE MULLION (LAM. GLASS)	6005-T5	-
8A	ES7024	AS REQD.	FEMALE MULLION (INSUL. LAM. GLASS)	6005-T5	-
9	ES7009	AS REQD.	SECURED JAMB (LAM. GLASS)	6063-T6	-
9A	ES7025	AS REQD.	SECURED JAMB (INSUL. LAM. GLASS)	6063-T6	-
10	ES7010	AS REQD.	UNSECURED JAMB (LAM. GLASS)	6005-T5	-
10A	ES7026	AS REQD.	UNSECURED JAMB (INSUL. LAM. GLASS)	6005-T5	-
11	-	AS REQD.	INTERIOR GASKET	EPDM	DUROMETER 60±5 SHORE A
12	ES7012	AS REQD.	EXTERIOR GLASS SEAL	EPDM	SILICONE DUROMETER 60±5 SHORE A
13	#12 X 1"	AS REQD.	FRAME ASSEMBLY SCREWS	-	PH SMS
13A	#14 X 1"	AS REQD.	FRAME ASSEMBLY SCREWS	-	PH SMS
14	-	AS REQD.	1/4" X 1" BAR WITH 3/8" THREADED HOLE	ALUMINUM	6063-T5 MIN.
15	3/8" BOLT	AS REQD.	LEVELING SCREW	ST/ST	-
16	-	AS REQD.	TRANSOM MULLION (LAM. GLASS)	6005-T5	-
16A	-	AS REQD.	TRANSOM MULLION (INSUL. LAM. GLASS)	6005-T5	-
17	-	2/ LITE	SETTING BLOCK	EPDM	DUROMETER 80±5 SHORE A

Approved as complying with the
Florida Building Code
Date 11/6/2013
NOA# 13-0617.25
Miami Dade Product Control
By

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538

OCT 2 7 2013

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978

STORE\W12-51ES

SERIES 7100 ALUM WINDOW WALL SYSTEM (S.M.I.)

E.S. WINDOWS, LLC
5220 N.W. 72 AVE. BAY #4
MIAMI, FL. 33166
TEL. (305) 624-7775 FAX. (305) 624-7777

revisions:

no	date	by	description
A	10.29.13		REV. PER RER COMMENTS

date: 09-12-12
scale: 3/8" = 1"
dr. by: HAMID
chk. by:

drawing no.
W12-51

sheet 13 of 13



TOP & BOTTOM CORNERS



TOP & BOTTOM CORNERS



HORIZONTAL CORNER



HORIZONTAL CORNER

Approved as complying with the Florida Building Code
Date 10/29/2013
NOA# 13-0617.25
Miami-Dade Product Control
By

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538

OCT 29 2013

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978

STORE\W12-51ES

SERIES 7100 ALUM WINDOW WALL SYSTEM (S.M.I.)

E.S. WINDOWS, LLC
5220 N.W. 72 AVE. BAY #4
MIAMI, FL. 33166
TEL. (305) 624-7775 FAX. (305) 624-7777

revisions:			
no	date	by	description
A	10.29.13		NO CHANGE THIS SHEET

date: 09-12-12
scale: 3/8" = 1"
dr. by: HAMID
chk. by:

drawing no.
W12-51

sheet 13.1 of 13