



DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)
BOARD AND CODE ADMINISTRATION DIVISION

MIAMI-DADE COUNTY, FLORIDA
PRODUCT CONTROL SECTION
11805 SW 26 Street, Room 208
T (786) 315-2590 F (786) 315-2599

www.miamidade.gov/economy

NOTICE OF ACCEPTANCE (NOA)

Historical Arts & Casting, Inc.
5580 West Bagley Park Road
West Jordan, UT 84081-5697

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER-Product Control Section to be used in Miami-Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami-Dade County) and/ or the AHJ (in areas other than Miami-Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Series "Palmetto" Bronze Fixed Window - L.M.I.

APPROVAL DOCUMENT: Drawing No. H222.1008.10, titled "Palmetto Series Outswing Fixed Windows", sheets 01 through 08 of 08, dated 02/21/11 with the latest revision dated 04/01/14, prepared by Wolters Engineering, Inc., signed and sealed by Scott Wolters, P. E., bearing the Miami-Dade County Product Control Section Revision stamp with the Notice of Acceptance number and Expiration date by the Miami-Dade County Product Control Section.

MISSILE IMPACT RATING: Large and Small Missile Impact Resistant

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state, series, and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/ or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA revises NOA No. 11-0602.05 and consists of this page 1 and evidence pages E-1 and E-2, as well as approval document mentioned above.

The submitted documentation was reviewed by **Jaime D. Gascon, P. E.**



J. Gascon
7/28/14

NOA No. 13-1217.25
Expiration Date: March 29, 2017
Approval Date: May 08, 2014
Page 1

Historical Arts and Casting, Inc.

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

A. DRAWINGS

1. Manufacturer's die drawings and sections.
2. Drawing No. **H222.1008.10**, titled "Palmetto Series Outswing Fixed Windows", sheets 01 through 08 of 08, dated 02/21/11 with the latest revision, dated 04/01/14, prepared by Wolters Engineering, Inc., signed and sealed by Scott Wolters, P. E.

B. TESTS

1. Test reports on:
 - 1) Air Infiltration Test, per FBC, TAS 202-94
 - 2) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94
 - 3) Water Resistance Test, per FBC, TAS 202-94
 - 4) Large Missile Impact Test per FBC, TAS 201-94
 - 5) Cyclic Wind Pressure Loading per FBC, TAS 203-94
 - 6) Forced Entry Test, per FBC 2411.3.2.1, TAS 202-94 and AAMA 1304-02

along with marked-up drawings and installation diagram of fixed window, prepared by Architectural Testing, Inc., Test Report No. **ATI-B3805.01-450-18**, dated 04/26/12, signed and sealed by Vinu J. Abraham, P. E.

2. Test reports on:
 - 1) Air Infiltration Test, per FBC, TAS 202-94
 - 2) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94
 - 3) Water Resistance Test, per FBC, TAS 202-94
 - 4) Large Missile Impact Test per FBC, TAS 201-94
 - 5) Cyclic Wind Pressure Loading per FBC, TAS 203-94
 - 6) Forced Entry Test, per FBC 2411.3.2.1, and TAS 202-94

along with marked-up drawings and installation diagram of fixed window, prepared by Hurricane Test Laboratory, LLC, Test Report No. **HTL-0222-0701-09**, dated 04/13/10, signed and sealed by Vinu J. Abraham, P. E.

(Submitted under previous NOA No. 11-0602.05)

C. CALCULATIONS

1. Anchor verification calculations and structural analysis, complying with FBC, prepared by Wolters Engineering, Inc., dated 12/13/13, signed and sealed by Scott Wolters, P. E.
2. **Glazing complies with ASTM E1300-04**

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER).



Jaime D. Gascon, P. E.
Product Control Section Supervisor
NOA No. 13-1217.25
Expiration Date: March 29, 2017
Approval Date: May 08, 2014

Historical Arts and Casting, Inc.

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

E. MATERIAL CERTIFICATIONS

1. Notice of Acceptance No. **12-1231.08** issued to **Eastman Chemical Company (MA)** for their "**Saflex CP – Saflex and Saflex HP Composite Glass Interlayers with PET Core**" dated 03/28/13, expiring on 12/11/18.
2. Notice of Acceptance No. **12-1213.04** issued to **SAF-GLAS, LLC** for their "**SAF-GLAS Polycarbonate Glass Interlayer**", dated 01/17/13, expiring on 12/16/13.

F. STATEMENTS

1. Statement letter of conformance, complying with **FBC-2010**, issued by **Wolters Engineering, Inc.**, dated 12/13/13, signed and sealed by **Scott Wolters, P. E.**
2. Statement letter of no financial interest, issued by **Wolters Engineering, Inc.**, dated 12/13/13, signed and sealed by **Scott Wolters, P.E.**
3. Laboratory compliance letter for Test Report No. **ATI-B3805.01-450-18**, issued by **Architectural Testing, Inc.**, dated 04/26/12, signed and sealed by **Vinu J. Abraham, P. E.**
4. Laboratory compliance letter for Test Report No. **HTL-0222-0701-09**, issued by **Hurricane Test Laboratory, LLC**, dated 04/13/10 and 10/21/11, both signed and sealed by **Vinu J. Abraham, P. E.**
(Submitted under previous NOA No. 11-0602.05)
5. Division of Corporations and Commercial Code of **HISTORICAL ARTS & CASTING, INC.** as a for profit corporation, active and organized under the laws of the State of Utah, dated 06/27/11 and signed by Secretary of State.
(Submitted under previous NOA No. 11-0602.05)


G. OTHERS

1. Notice of Acceptance No. **11-0602.05**, issued to **Historical Arts and Casting, Inc.** for their Series "**HACI 2000**" **Bronze Fixed Window – L.M.I.**", approved on 03/29/12 and expiring on 03/29/17.




Jaime D. Gascon, P. E.
Product Control Section Supervisor
NOA No. 13-1217.25
Expiration Date: March 29, 2017
Approval Date: May 08, 2014


FIXED WINDOWS WITH MUNTINS
GLASS TYPE A OR B FOR UNITS 1-4
GLASS TYPE B ONLY FOR UNITS 5 AND 6



① **FIXED WINDOW WITH CASEMENT
EXTERIOR ELEVATION**



② **MULLIED FIXED WINDOW
EXTERIOR ELEVATION**




① **MULLION AND MTG STILE ENDS, HEAD AND SILL
ANCHOR CLUSTER DETAIL**


PRODUCT REVISED
 as complying with the Florida
 Building Code
 Acceptance No. **13-1217.25**
 Expiration Date **03/29/2017**
 By *[Signature]*
 Miami Dade Product Control

[Signature]
SCOTT WOLTERS
 FLPE# 62354
WOLTERS ENGINEERING, INC.
 (COA# 27194)
 1725 SW 25TH AVENUE
 FT. LAUDERDALE, FL 33312


APR 01 2014




③ **SINGLE FIXED WINDOW, 2 LITES WIDE
EXTERIOR ELEVATION**



④ **SINGLE FIXED WINDOW, 1 LITE WIDE
EXTERIOR ELEVATION**



⑤ **DUAL ARCH TRANSOM
EXTERIOR ELEVATION**



⑥ **DIVIDED LITE TRANSOM WITH ARCH
EXTERIOR ELEVATION**

PALMETTO SERIES OUTSWING FIXED WINDOW


HISTORICAL ARTS & CASTING, INC.
 5580 West Bayley Park Rd., West Jordan, UT, 84081
 PHONE 801-280-2400 FAX 801-280-2493




NOTES	REVISIONS
	12/6/13
	RKH

FIXED WINDOWS WITHOUT MUNTINS GLASS TYPE B ONLY


BILL OF MATERIALS				
INDEX	PART DESCRIPTION	MATERIAL	MANUFACTURE	DET/SHEET
PALMETTO SERIES OUTSWING FIXED WINDOWS				
BRONZE EXTRUSIONS				
15	1.A. SASH	BRONZE 385	HACI	15/7 OF 8
11	1.B. JAMB	BRONZE 385	HACI	11/7 OF 8
14	1.C. DRIP MOLDING	BRONZE 385	HACI	14/7 OF 8
3	1.D. FIXED JAMB	BRONZE 385	HACI	3/7 OF 8
1	1.E. MUNTIN	BRONZE 385	HACI	1/7 OF 8
2	1.F. GLASS STOP	BRONZE 385	HACI	2/7 OF 8
	1.G. 1/8" KICK PLATE HORIZONTAL DIVIDER	BRONZE 385	HACI	
5	1.H. EXTERIOR MULLION	BRONZE 385	HACI	5/7 OF 8
6	1.I. INTERIOR MULLION	BRONZE 385	HACI	6/7 OF 8
7	1.K. INTERIOR MEETING STILE	BRONZE 385	HACI	7/7 OF 8
8	1.L. FIXED JAMB/SILL	BRONZE 385	HACI	8/7 OF 8
9	1.M. APPLIED BRICKMOLD	BRONZE 385	HACI	9/7 OF 8
	1.N. 1/8" BRONZE EXTERIOR FILLER PLATE	BRONZE 385	HACI	
17	1.O. KICK PLATE MOLDING	BRONZE 385	HACI	17/7 OF 8
18	1.P. KICK PLATE MOLDING W/ NOTCH	BRONZE 385	HACI	18/7 OF 8
19	1.Q. LARGE MUNTIN	BRONZE 385	HACI	19/7 OF 8
4	1.R. TRANSOM DRIP EX. B	BRONZE 385	HACI	4/7 OF 8
10	1.S. SILL	BRONZE 385	HACI	10/7 OF 8
12	1.T. HEAD	BRONZE 385	HACI	12/7 OF 8
13	1.U. TRANS WIN & DR HEAD	BRONZE 385	HACI	13/7 OF 8
16	1.V. SASH MEETING STILE	BRONZE 385	HACI	16/7 OF 8
GASKETS				
20	2.A. SILICONE GASKET	SILICONE	WEST COAST	20/7 OF 8
21	2.B. SILICONE GASKET	SILICONE	WEST COAST	21/7 OF 8
22	2.C. SILICONE GASKET	SILICONE	WEST COAST	22/7 OF 8
HARDWARE				
	3.A. #14 X 2" BRASS WOOD SCREW	BRONZE 385	HACI	4 OF 8
	3.B. #14 X 2-1/2" BRASS WOOD SCREW	BRONZE 385	HACI	4 OF 8
	3.C. #14 X 3-1/2" BRASS WOOD SCREW	BRONZE 385	HACI	4 OF 8
	3.D. #10-24 FHMS	BRONZE 385	HACI	5 OF 8
	3.E. 1/4"-20 X 1/2" FHMS	BRONZE 385	HACI	5 OF 8
	3.F. 1/4"-20 X 3/4" FHMS	BRONZE 385	HACI	4 OF 8
	3.G. 1/4"-20 X 1" FHMS	BRONZE 385	HACI	4 OF 8
	3.H. 1/4"-20 X 2" FHMS	BRONZE 385	HACI	5 OF 8
	3.I. #8-32 FHMS	BRONZE 385	HACI	5 OF 8
	3.J. #10-20 FHMS	BRONZE 385	HACI	5 OF 8
23	3.K. CONTINUOUS BLOCKING	TREX PLASTIC	HACI	23/7 OF 8
GLASS & GLAZING				
	4.A. GLASS 9/16" LAMINATED			1 OF 8
	4.B. 1/8" FOAM GLAZING TAPE EXTERIOR	NORSEAL	NORTON	4 OF 8
	4.C. 1/8" FOAM GLAZING TAPE INTERIOR	NORSEAL	NORTON	4 OF 8
	4.D. SEALANT DOW 795	SILICONE	DOW	4 OF 8




7 TRANSOM OVER OPERABLE EXTERIOR ELEVATION



8 FIXED HALF-CIRCLE / TRANSOM EXTERIOR ELEVATION



9 FIXED EYEBROW / TRANSOM EXTERIOR ELEVATION



10 FIXED EXTERIOR ELEVATION

PRODUCT REVISED
 s complying with the Florida
 Building Code
 Acceptance No. **13-1217.25**
 Expiration Date **03/29/2017**
 By *[Signature]*
 Miami Dade Product Control


[Signature]
SCOTT WOLTERS
 FLPE# 62354
 WOLTERS ENGINEERING, INC.
 (COA# 27194)
 1725 SW 25TH AVENUE
 FT. LAUDERDALE, FL 33312

APR 11 2014


PALMETTO SERIES OUTSWING FIXED WINDOW	HISTORICAL ARTS & CASTING, INC. 5580 WEST BAYVIEW PARK RD., WEST JORDAN, UT. 84081 PHONE 801-280-2400 FAX 801-280-2498	NOTES	REVISIONS
		12/6/13	RKH
3 OF 8			

MOUNTING OPTIONS


FOR UNITS 1-4, AND 7-10 ONLY




1 MOUNT TO WOOD



2 MOUNT TO CONCRETE/CMU



3 MOUNT TO METAL STUD




4 MOUNT TO STEEL TUBE

LISTED IN NO PARTICULAR ORDER. SEALANT APPLIED BY OTHERS
ANCHOR SPACING PER ELEVATIONS ON SHEETS 2 AND 3 OF 8


PRODUCT REVISED
to comply with the Florida
Building Code
Acceptance No. 13-1217-25
Expiration Date 23/29/2017
By: [Signature]
Miami Dade Product Control

MOUNTING OPTIONS


FOR UNITS 5 & 6 ONLY




1 MOUNT TO STUD/STEEL FRAME



2 MOUNT TO BLOCK/CONCRETE/CMU



3 MOUNT TO WOOD



4 MOUNT TO BLOCK/CONCRETE/CMU THROUGH WOOD BUCK

LISTED IN NO PARTICULAR ORDER. SEALANT APPLIED BY OTHERS
ANCHOR SPACING PER ELEVATIONS ON SHEET 2 OF 8


[Signature]
SCOTT WOLTERS
FLPE# 62354
WOLTERS ENGINEERING, INC.
(COA# 27194)
1725 SW 25TH AVENUE
FT. LAUDERDALE, FL 33312
APR 01 2016

PALMETTO SERIES OUTSWING FIXED WINDOW


HISTORICAL ARTS & CASTING, INC.
5580 WEST BAGLEY PARK RD., WEST JORDAN, UT. 84081
PHONE 801-280-2400 FAX 801-280-2493

NOTES REVISIONS


12/6/13	RKH
---------	-----




SECTION DETAILS




(A) SILL SECTION




(B) HEAD SECTION




(J) MUNTIN SECTION




(I) FIX JAMB SECTION



(G) MULLION SECTION



(D) MEETING STILE SECTION




(K) TRANSOM SECTION

PRODUCT REVISED
 Building Code
 Acceptance No. 13-1217.25
 Expiration Date 03/29/2017
 By: *Scott Walters*
 Miami Dade Product Control


Scott Walters
 SCOTT WALTERS
 FLPE# 62354
 WALTERS ENGINEERING, INC.
 (COA# 27194)
 1725 SW 25TH AVENUE
 FT. LAUDERDALE, FL 33312
 APR 5 2014

MOLDING OPTIONS


LISTED IN NO PARTICULAR ORDER. SEALANT APPLIED BY OTHERS




(1) FLAT MOLDING



(2) FLUSH MOLDING




(3) STANDARD BRICK MOLDING




(4) APPLIED BRICK MOLDING

PALMETTO SERIES OUTSWING FIXED WINDOW	HISTORICAL ARTS & CASTING, INC. 5580 WEST BAYVIEW PARK RD., WEST JORDAN, UT. 84081 PHONE 801-280-2400 FAX 801-280-2498	12/6/13	RKH
		NOTES	REVISIONS
5 OF 8			


SECTION DETAILS




(A) TYPICAL FIXED UNIT AT FRAME




(B) MULTI UNIT ATTACHMENT




(C) SECTION AT BOTTOM PANEL CONDITION



(E) TYPICAL SECTION AT MUNTIN



(F) SECTION AT LARGE MUNTIN




(G) TYPICAL SECTION AT FIXED UNIT SILL

PRODUCT REVISED as complying with the Florida Building Code
Acceptance No. 13-1217.25
Expiration Date 03/29/2017
By: [Signature]
Miami Dade Product Control


SCOTT WOLTERS
FLPE# 62354
WOLTERS ENGINEERING, INC.
(COA# 27194)
1725 SW 25TH AVENUE
FT. LAUDERDALE, FL 33312
APR 5 2016

PALMETTO SERIES OUTSWING FIXED WINDOW	HISTORICAL ARTS & CASTING, INC. 5580 WEST Bayley PARK Rd., WEST JORDAN, UT. 84081 PHONE 801-280-2400 FAX 801-280-2498	12/6/13	RKH
		NOTES	REVISIONS
6 OF 8			


EXTRUSION PROFILES




DF2000.05/CS9922.8
① MUNTIN (1.E.)




DF2000.06/CS9923
② GLASS STOP (1.F)




DF2000.45
③ FIXED JAMB (1.D.)




DF2000.11
④ TRANSOM DRIP EXTRUSION B (1.R)




DF2000.41
⑤ EXTERIOR MULLION (1.H)




DF2000.40
⑥ INTERIOR MULLION (1.I)




DF2000.04
⑦ INTERIOR MEETING STILE (1.K)




DF2000.34
⑧ FIXED SILL/JAMB (1.L)




DF2000.15
⑨ APPLIED BRICKMOLD (1.M)




P.M.CS991.1
⑩ SILL (1.S)




P.M.CS991.2
⑪ JAMB (1.B)




P.M.CS991.3
⑫ HEAD (1.T)




P.M.CS991.7
⑬ TRANS WIN & DR HEAD (1.U)




P.M.CS991.4
⑭ DRIP MOLDING (1.C)




P.M.CS991.1
⑮ SASH (1.A)




P.M.CS991.3
⑯ SASH MEETING STILE (1.V)



P.M.CS992.4
⑰ KICK PLATE MOLDING (1.O)



P.M.CS992.4A
⑱ KICK PLATE MOLDING W/ NOTCH (1.P)



P.M.CS992.5
⑲ LARGE MUNTIN (1.Q)



DF2000.01
⑳ SILICONE GASKET (2.A)


WEST COAST GASKET COMPANY
RED SILICONE 40/SHORE
.425" WD X .425" TALL
D-SHAPED EXTRUSION PER
PRINT



P.M.CS995
㉑ SILICONE GASKET (2.B)
WEST COAST GASKET COMPANY
RED SILICONE 40/SHORE
.425" WD X .425" TALL
D-SHAPED EXTRUSION PER
PRINT



P.M.CS996.1
㉒ MEETING STILE SILICONE GASKET (2.C)
WEST COAST GASKET COMPANY
RED SILICONE 40/SHORE
.425" WD X .425" TALL
D-SHAPED EXTRUSION PER
PRINT



㉓ TREX BLOCKING (3.K)

ALL METAL EXTRUSIONS
BRONZE ALLOY 385 OR 380

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 13-1217.25
Expiration Date 03/29/2017
by *Scott Wolters*
Miami Dade Product Control

Scott Wolters
SCOTT WOLTERS
FLPE# 62354
WOLTERS ENGINEERING, INC.
(COA# 27194)
1725 SW 25TH AVENUE
FT. LAUDERDALE, FL 33312
APR 01 2014



PALMETTO SERIES OUTSWING FIXED WINDOW

HISTORICAL ARTS & CASTING, INC.

5580 WEST Bagley PARK Rd., WEST JORDAN, UT. 84081
PHONE 801-280-2400 FAX 801-280-2493

NOTES	REVISIONS
	12/6/13
	RKH

1 ISOMETRIC VIEW TYPICAL CORNER




4 DOOR TRANSOM SIDE (EXTERIOR VIEW) EXTRUSIONS JOINTS


ISOMETRIC VIEWS

PRODUCT REVISED
 as complying with the Florida
 Building Code
 Acceptance No. 13-1217-25
 Expiration Date 03/29/2017
 by *[Signature]*
 Miami Dade Product Control


[Signature]
 SCOTT WOLTERS
 FLPE# 62354
 WOLTERS ENGINEERING, INC.
 (COA# 27194)
 1725 SW 25TH AVENUE
 FT. LAUDERDALE, FL 33312
 APR 01 2014




2 ISOMETRIC VIEW TYPICAL MUNTINS




5 ISOMETRIC VIEW TYPICAL FIXED TO CASEMENT MEETING RAIL




3 ISOMETRIC VIEW TYPICAL CORNERS/MULLION



6 FIXED WINDOW SILL (EXTERIOR VIEW) EXTRUSIONS JOINTS



7 FIXED WINDOW CORNER (EXTERIOR VIEW) EXTRUSIONS JOINTS



8 ARCH TRANSOM JAMB TYPICAL CURVED HEAD TO JAMB

PALMETTO SERIES OUTSWING FIXED WINDOW	HISTORICAL ARTS & CASTING, INC. 5580 WEST BAGLEY PARK RD., WEST JORDAN, UT. 84081 PHONE 801-280-2400 FAX 801-280-2493	12/6/13	RKH
		NOTES	REVISIONS
8 OF 8			