

# MIAMI-DADE COUNTY PRODUCT CONTROL SECTION

11805 SW 26 Street, Room 208 Miami, Florida 33175-2474 T (786)315-2590 F (786) 31525-99

www.miamidade.gov/economy

# DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER) BOARD AND CODE ADMINISTRATION DIVISION

### **NOTICE OF ACCEPTANCE (NOA)**

Firestone Building Products Company, LLC 250 West 96<sup>th</sup> Street Indianapolis, IN 46260

#### SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER - Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code including the High Velocity Hurricane Zone of the Florida Building Code.

**DESCRIPTION:** Firestone UltraPly TPO & TPO XR Single Ply Roof Systems over Recover Decks.

**LABELING:** Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA revises NOA No. 13-1212.04 and consists of pages 1 through 116. The submitted documentation was reviewed by Jorge L. Acebo.



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 1 of 116

## **ROOFING SYSTEM APPROVAL**

<u>Category:</u> Roofing

**Sub-Category:** Single Ply Roofing

Material: TPO Recover

**Maximum Design Pressure:** See Specific Deck Type

# TRADE NAMES OF PRODUCTS MANUFACTURED OR LABELED BY APPLICANT: TABLE 1

		<u>Test</u>	
<b>Product</b>	<b>Dimensions</b>	<b>Specifications</b>	<b>Product Description</b>
UltraPly TPO	Various	TAS 131 ASTM D6878	Reinforced TPO 0.045" to 0.080" thick membrane.
UltraPly TPO XR 100	Various	TAS 131 ASTM D6878	Reinforced TPO 0.045" membrane with 8 oz. fleece backing.
UltraPly TPO XR 115	Various	TAS 131 ASTM D6878	Reinforced TPO 0.060" membrane with8 oz. fleece backing.
UltraPly TPO XR 135	Various	TAS 131 ASTM D6878	Reinforced TPO .080" membrane with 8 oz. fleece backing.
SBS Poly Base	39.4" x 50'	ASTM D6164	Polyester reinforced SBS modified bitumen membrane with sanded surfaces.
UltraPly TPO Reinforced Curb Corner	Various	TAS 131 ASTM D6878	TPO curb flashing
UltraPly 18" Curb Flashing	Various	TAS 131 ASTM D6878	TPO curb flashing
UltraPly TPO Inside/Outside Corner	Various	TAS 131 ASTM D6878	Molded TPO for corner flashing
UltraPly TPO Large Pipe Flashing	Various	TAS 131 ASTM D6878	TPO flashing for large round penetrations
UltraPly TPO T-Joint Cover	Various	TAS 131 ASTM D6878	TPO flashing for T-joints
UltraPly TPO Penetration Kit	Various	TAS 131 ASTM D6878	Penetration sealing kit for UltraPly TPO
UltraPly TPO Walkway Pad	Various	TAS 131 ASTM D6878	TPO walkway pad
UltraPly TPO Coated Metal	Various	TAS 131 ASTM D6878	TPO laminated to hot-dipped galvanized steel for flashing
UltraPly TPO Premium Walkway Pad	Various	TAS 131 ASTM D6878	TPO walkway pad



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 2 of 116

		<u>Test</u>	
<b>Product</b>	<b>Dimensions</b>	<b>Specifications</b>	<b>Product Description</b>
UltraPly TPO Reinforced Split Pipe Boot	Various	TAS 131 ASTM D6878	TPO flashing for round penetrations 1" to 9" in diameter
UltraPly TPO 8" Reinforced Cover Strip	Various	TAS 131 ASTM D6878	8" wide 60 mil TPO cover strip
UltraPly TPO Universal Pipe Boot	Various	TAS 131 ASTM D6878	TPO flashing for round penetrations 1" to 6" in diameter
UltraPly TPO Unsupported Flashing	Various	TAS 131 ASTM D6878	Unreinforced TPO used for flashing
UltraPly QuickSeam R.M.A. Strip	10" x 100'	Proprietary	Strip of UltraPly TPO with QuickSeam Tape for anchoring membrane to substrate.
Single-Ply QuickPrime Primer	1 gallon, 3 gallon	Proprietary	Primer for TPO Flashing.
XR Bonding Adhesive	5 gal. pail	Proprietary	Solvent based adhesive.
UltraPly Bonding Adhesive	5 gal. pail	Proprietary	Solvent based adhesive.
XR Stick Membrane Adhesive	5 gal. pail	Proprietary	A low-rise polyurethane, low VOC, membrane adhesive.
I.S.O. Stick	5 gal & 1500 ml	Proprietary	A dual component polyurethane adhesive.
I.S.O. Twin Pack Insulation Adhesive	1500 ml	Proprietary	A dual component polyurethane adhesive.
I.S.O. Fix II	30 lbs.	Proprietary	A single component polyurethane adhesive.
I.S.O. Spray R	15 gal pail & 55 gal drum	Proprietary	A two part polyurethane adhesive
Single-Ply LVOC Bonding Adhesive	5 gal. pail	Proprietary	Solvent based bonding adhesive.
Single-Ply LVOC Bonding Adhesive 1168	5 gal. pail	Proprietary	Solvent based bonding adhesive.
Water Based Bonding Adhesive P	5 gal. pail	Proprietary	Water based bonding adhesive.



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 3 of 116

## **APPROVED INSULATIONS:**

SECUROCK Glass-Mat

Roof Board

TABLE 2			
Product Name	<b>Product Description</b>	Manufacturer (With Current NOA)	
ISO 95+ GL and tapered	Polyisocyanurate foam insulation	Firestone Building Products Company, LLC	
ISOGARD HD	Polyisocyanurate with a coated fiberglass facer	Firestone Building Products Company, LLC	
ISOGARD HD Composite	Polyisocyanurate with a coated fiberglass facer composite insulation.	Firestone Building Products Company, LLC	
RESISTA and tapered	Polyisocyanurate foam core laminated to a coated fiberglass facer.	Firestone Building Products Company, LLC	
DensDeck, DensDeck Prime	Silicon treated gypsum	Georgia Pacific Gypsum LLC	
SECUROCK Gypsum-Fiber Roof Board	Rigid, gypsum-based board stock	United States Gypsum Corp.	

Rigid, gypsum-based board stock



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 4 of 116

United States Gypsum Corp.

## **APPROVED FASTENERS:**

#### TABLE 3

Fastener Number	Product Name	Product Description	Dimensions	Manufacturer (With Current NOA)
1.	Firestone Heavy-Duty	#15 Fastener for steel, Wood, concrete decks.	N/A	Firestone Building Products Company, LLC
2.	Firestone All-Purpose	#14 Fastener for steel, Wood, concrete decks.	N/A	Firestone Building Products Company, LLC
3.	Firestone Heavy Duty Plus	Insulation and membrane fastener.	Various	Firestone Building Products Company, LLC
4.	Concrete Drive	Structural concrete fastener.	Various	Firestone Building Products Company, LLC
5.	Purlin Fasteners	#12 purlin fastener.	Various	Firestone Building Products Company, LLC
6.	Insulation Fastening Plate	Galvalume insulation plate.	3" diameter	Firestone Building Products Company, LLC
7.	Firestone HD Plus Seam Plate	Galvalume insulation plate.	2 <sup>3</sup> / <sub>4</sub> " diameter	Firestone Building Products Company, LLC
8.	Firestone HD Seam Plates	AZ55 or AZ50 galvalume insulation plate.	2-3/8" diameter	Firestone Building Products Company, LLC
9.	UltraPly TPO InvisiWeld Plates	High-performance TPO membrane fastening system.	3" diameter	Firestone Building Products Company, LLC
10.	Metal Batten Bar	Galvalume AZ55 batten bar.	10' long, 1" wide	Firestone Building Products Company, LLC
11.	Firestone Polymer Batten Strip	Polymer batten	250' long, 3/4" wide	Firestone Building Products Company, LLC
12.	Coiled Metal Batten Bar	Galvalume AZ55 batten strip	220' long, I'' wide	Firestone Building Products Company, LLC
13.	Two Piece Impact Nail	Base ply fastening systems for lightweight concrete decks	Various	Firestone Building Products Company, LLC



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 5 of 116

# **EVIDENCE SUBMITTED:**

<b>Test Agency</b>	<b>Test Identifier</b>	<b>Description</b>	<u>Date</u>
Underwriters Laboratories Inc.	R9516	UL 790	04/26/16
Factory Mutual Research	3032272	FM 4470	05/22/09
Corporation	3036642	FM 4470	10/09/09
1	3030650	FM 4470	07/10/09
	3035560	FM 4470	01/11/10
	3019991	FM 4470	09/20/05
	3017120	FM 4470	04/30/04
	3038546	FM 4470	12/17/10
	3039133	FM 4470	04/07/11
	3036747	FM 4470	02/12/10
	3040535	FM 4470	10/05/10
	3035017	FM 4470	04/15/09
	3038191	FM 4470	08/04/11
	3036256	FM 4470	04/27/09
	3038546	FM 4470	12/17/10
	3038770	FM 4470	08/04/11
	3041939	FM 4470	08/14/12
	3044047	FM 4470	05/17/12
	3047398	FM 4470	08/15/13
	3047700	FM 4470	08/16/13
	3050274 797-05830-267	FM 4470 FM 4470	10/01/13 08/30/10
	797-10191-267	FM 4470 FM 4470	08/30/10
Trinity ERD	F8300.07.08	TAS 131/ ASTM D6878	07/30/08
	F8300.11.08-R3	TAS 131/ASTM D6878	02/25/11
	F45600.09.13-R1	TAS 131/ASTM D6878	12/30/13
PRI Construction Materials	FBP-054-02-05, R1	FM 4474/TAS 114 D	02/07/13
Technologies, LLC	FBP-069-02-01, R1	FM 4474/TAS 114 J	02/07/13
	FBP-070-02-01, R1	FM 4474/TAS 114 J	02/07/13
	FBP-085-02-01	TAS 114 J	10/04/12
	FBP-086-02-01	TAS 114 J	10/04/12
	FBP-044-02-01, R7	TAS 114 H, J	02/04/14
	FBP-145-02-01 FBP-094-02-01	TAS 131/ASTM D6878 TAS 131/ASTM D6878	06/26/14 11/20/13
	FBP-120-02-01	TAS 131/AS1M D08/8	07/23/13
	FBP-122-02-01, R1	TAS 114 J	02/04/14
	FBP-125-02-01	TAS 114 C	07/23/13
	FBP-148-02-01	TAS 114 J	12/18/13
	FBP-149-02-01	TAS 114 J	12/18/13
	FBP-153-02-01	TAS 114 J	12/18/13
	FBP-154-02-02	TAS 114 J	12/18/13
	FBP-165-02-01	TAS 114 J	04/28/14
	FBP-165-02-01A	TAS 114 J	04/28/14
	FBP-175-02-01	TAS 114 J	04/28/14
	-	-	



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 6 of 116

# **EVIDENCE SUBMITTED: (CONTINUED)**

<b>Test Agency</b>	<b>Test Identifier</b>	<b>Description</b>	<u>Date</u>
PRI Construction Materials	FBP-190-02-01	TAS 114 D	07/31/14
Technologies, LLC	FBP-193-02-02	TAS 114 J	10/16/14
	FBP-196-02-04.1	TAS 114 J	10/21/14
	FBP-206-02-01	TAS 114 J	02/02/15
	FBP-213-02-01	TAS 114 J	11/20/14
	FBP-220-02-01.1	TAS 114 J	01/29/15
	FBP-225-02-01	TAS 114 J	03/19/15
	FBP-230-02-01	TAS 114 J	04/02/15
	FBP-233-02-01	TAS 114 J	06/01/15
	FBP-233-02-02	TAS 114 C	04/03/15
	FBP-233-02-03	TAS 114 J	06/01/15
	FBP-235-02-01	TAS 114 J	06/01/15
	FBP-238-02-01	TAS 114 J	07/01/15
	FBP-238-02-03	TAS 114 J	07/15/15
	FBP-239-02-01	TAS 114 J	07/15/15
	FBP-241-02-01	TAS 114 J	07/22/15



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 7 of 116

#### **APPROVED ASSEMBLIES**

Membrane Type: Single Ply, TPO

Deck Type 7I: Recover, Insulated

**Deck Description:** Concrete

**System Type A(1):** One or more layers of insulation adhered with approved adhesive over existing

asphaltic BUR; membrane adhered with approved adhesive.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL	,	•
Minimum: 1.0" thick	N/A	N/A
Tapered ISO 95+ GL		
Minimum: 1/2" thick with a 1/4" per ft. taper	N/A	N/A
ISOGARD HD		
Minimum: ½" thick	N/A	N/A
DensDeck, DensDeck Prime, SECUROCK Gypsum-	-Fiber Roof Board	
Minimum: 1/4" thick	N/A	N/A

Note: All layers of insulation shall be adhered using I.S.O. Twin Pack Insulation Adhesive in continuous  $\frac{1}{2}$ " –  $\frac{3}{4}$ " wide beads spaced 12" o.c. or I.S.O. Fix II or I.S.O. Stick applied in continuous  $\frac{3}{4}$ " – 1" wide ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO XR adhered with XR Stick Membrane Adhesive applied in

continuous 1" minimum beads spaced a maximum of 4" o.c. and allowed to expand to full coverage application prior to placement of the roof cover. The 2" wide roof cover side laps are sealed with a minimum 1.5 in. heat weld

placed on the outside edge of the lap.

Or

UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a

minimum 1.5 in. heat weld.

Or



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 8 of 116 **Membrane:** (Continued)

UltraPly TPO XR (over SECUROCK and DensDeck only) roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a rate of 70-90

ft<sup>2</sup>/gal to the substrate only.

Or

UltraPly TPO XR is adhered with I.S.O. Spray R applied in 3/4" to 1" wide

ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -172.5 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16

Page 9 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Steel/Wood/Gypsum/Cementitious Wood Fiber

**System Type A(2):** One or more layers of insulation adhered with approved adhesive over existing

asphaltic BUR; membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISOGARD HD		
Minimum: ½" thick	N/A	N/A
DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board	d	
Minimum: ¼" thick	N/A	N/A

Note: Insulation shall be adhered using I.S.O. Twin Pack Insulation Adhesive in continuous ½" – ¾" wide beads spaced 12" o.c. or, I.S.O. Fix II or I.S.O. Stick applied in continuous ¾" – 1" wide ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO XR adhered with XR Stick Membrane Adhesive applied in

continuous 1" minimum beads spaced a maximum of 4" o.c. and allowed to expand to full coverage application prior to placement of the roof cover. The 2" wide roof cover side laps are sealed with a minimum 1.5 in. heat weld placed on the outside edge of the lap.

 $\Omega$ r

UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive, Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a

minimum 1.5 in. heat weld.

Or

UltraPly TPO XR (over SECUROCK and DensDeck only) roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a rate of 70-90 ft²/gal to the substrate only.

Or

UltraPly TPO XR is adhered with I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 10 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Steel/Concrete

**System Type A(3):** One or more layers of insulation adhered with approved adhesive; membrane

fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Insulation Layer Insulation Fasteners Fastener (Table 3) Fastener

DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board

Minimum ¼" thick N/A N/A

Note: All insulation shall be adhered to the deck in full mopping of approved asphalt within the EVT range and at a rate of 20-25 lbs./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

Or

UltraPly TPO XR roof cover is fully adhered to with Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a

rate of 70-90 ft<sup>2</sup>/gal to the substrate only.

**Maximum Design** 

**Pressure:** -300 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16

Page 11 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Steel/Concrete

**System Type A(4):** One or more layers of insulation adhered with approved adhesive; membrane

fully adhered with hot asphalt.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Insulation Layer Insulation Fasteners Fastener (Table 3) Fastener

DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board

Minimum ¼" thick N/A N/A

Note: All insulation shall be adhered to the deck in full mopping of aproved asphalt within the EVT range and at a rate of 20-25 lbs./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO XR fully adhered to insulation layer with hot asphalt applied at a

rate of 20-25 lbs./sq. The minimum 3" roof cover laps are sealed with a minimum

1.5 in. heat weld along the outside edge.

**Maximum Design** 

**Pressure:** -457.5 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 12 of 116

**Deck Description:** Concrete

**System Type B(1):** Base layer of insulation mechanically fastened, top layer adhered: membrane

adhered with approved adhesive. .

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL		
Minimum 1.5" thick	1 or 4 with 6	1:2 ft <sup>2</sup>
Middle Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL	, ,	•
Minimum 1" thick	N/A	N/A
(Optional) Additional Middle Insulation Layer	<b>Insulation Fasteners</b>	Fastener
` •                       •	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL		•
Minimum 1" thick	N/A	N/A
Tapered ISO 95+ GL		
Minimum 1/2" thick with a 1/4" per ft. taper	N/A	N/A
Top Insulation Layer (cover board)	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum-Fiber Roof	f Board	
Minimum 1/4" thick	N/A	N/A

Note: Base layer shall be mechanically attached with fasteners and density described. All other layers of insulation shall be adhered to base insulations with I.S.O. Twin Pack Insulation Adhesive in continuous  $\frac{1}{2}$ " –  $\frac{3}{4}$ " wide beads spaced 12" o.c. or I.S.O. Fix II, I.S.O. Stick applied in continuous  $\frac{3}{4}$ " – 1" wide ribbons spaced 12" o.c. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive, Single-

Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum 1.5 in.

heat weld.

Or



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 13 of 116 **Membrane:** (Continued)

UltraPly TPO XR (over SECUROCK and DensDeck only) roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a rate of 70-90 ft²/gal

to the substrate only.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1"

wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 14 of 116

**Deck Description:** Concrete

**System Type B(2):** Base layer of insulation mechanically fastened, top layer adhered: membrane

adhered with approved adhesive. .

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL	,	·
Minimum 1.5" thick	1 or 4 with 6	1:2 ft <sup>2</sup>
Middle Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL	,	·
Minimum 1" thick	N/A	N/A
(Optional) Additional Middle Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft2
ISO 95+ GL	,	v
Minimum 1" thick	N/A	N/A
Tapered ISO 95+ GL		
Minimum 1/2" thick with a 1/4" per ft. taper	N/A	N/A
Top Insulation Layer (cover board)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISOGARD HD	` ,	v
Minimum ½" thick	N/A	N/A

Note: Base layer shall be mechanically attached with fasteners and density described. All other layers of insulation shall be adhered to base insulations with I.S.O. Twin Pack Insulation Adhesive in continuous  $\frac{1}{2}$ " –  $\frac{3}{4}$ " wide beads spaced 12" o.c. or I.S.O. Fix II, I.S.O. Stick applied in continuous  $\frac{3}{4}$ " – 1" wide ribbons spaced 12" o.c. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: UltraPly TPO XR 100 or UltraPly TPO XR 115 or UltraPly TPO 135 adhered with

XR Stick Membrane Adhesive applied in continuous 1" minimum beads spaced a maximum of 4" o.c. and allowed to expand to full coverage application prior to placement of the roof cover. The 2" wide roof cover side laps are sealed with a

minimum 1.5 in. heat weld placed on the outside edge of the lap.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 15 of 116

**Deck Description:** Concrete

System Type B(3): Base layer of insulation mechanically fastened, top layer adhered; membrane

adhered with approved adhesive.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL	,	v
Minimum 1.5" thick	1 or 4 with 6	1:1.6 ft <sup>2</sup>
Top Insulation Layer (cover board)	<b>Insulation Fasteners</b>	Fastener
• • • • • • • • • • • • • • • • • • • •	(Table 3)	Density/ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum-Fiber Roof H	Board	•
Minimum 1/2" thick	N/A	N/A

Note: Base layer shall be mechanically attached with fasteners and density described. Top layer of insulation shall be adhered to base insulations with I.S.O. Twin Pack Insulation Adhesive in continuous  $\frac{1}{2}$ " –  $\frac{3}{4}$ " wide beads spaced 6" o.c. or I.S.O. Fix II or I.S.O. Stick applied in continuous  $\frac{3}{4}$ " – 1" wide ribbons spaced 6" o.c. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: UltraPly TPO XR 100 or UltraPly TPO XR 115 or UltraPly TPO 135 membrane

adhered to the top insulation layer with XR Stick Membrane Adhesive applied in continuous  $\frac{3}{4}$ " – 1" wide ribbons spaced 6" o.c. The 2 in. wide roof cover side and end laps are sealed with a minimum 1.5 in. heat weld placed on outside edge of lap.

Or

UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive, Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum 1.5 in, heat weld.

Or

UltraPly TPO XR roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a rate of 70-90 ft²/gal to the substrate only.

Or

UltraPly TPO XR is adhered with I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 16 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Concrete

System Type B(4): Base layer of insulation mechanically fastened, top layer adhered; membrane

adhered with approved adhesive.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL	(=======)	_ = ===================================
Minimum 2" thick	1 or 4 with 6	1:1.6 ft <sup>2</sup>
Top Insulation Layer (cover board)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL	,	•
Minimum 1" thick	N/A	N/A

Note: Base layer shall be mechanically attached with fasteners and density described. Top layer of insulation shall be adhered to base insulations with I.S.O. Twin Pack Insulation Adhesive in continuous  $\frac{1}{2}$ " –  $\frac{3}{4}$ " wide beads spaced 6" o.c. I.S.O. Fix II or I.S.O. Stick applied in continuous  $\frac{3}{4}$ " – 1" wide ribbons spaced 6" o.c. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane:

UltraPly TPO XR 100 or UltraPly TPO XR 115 or UltraPly TPO 135 membrane adhered to the top insulation layer with XR Stick Membrane Adhesive applied in continuous <sup>3</sup>/<sub>4</sub>" – 1" wide ribbons spaced 6" o.c. The 2 in. wide roof cover side and end laps are sealed with a minimum 1.5 in. heat weld placed on outside edge of lap

Or

UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive, Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum 1.5 in, heat weld.

Or

UltraPly TPO XR is adhered with I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -75 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 17 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Concrete

**System Type B(5):** Base layer of insulation mechanically fastened, top layer adhered; membrane

fully adhered with approved adhesive..

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Base Insulation Layer	Insulation Fasteners	Fastener
·	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL		
Minimum 2" thick	4 with 6	1:1 ft <sup>2</sup>
Top Insulation Layer (cover board)	<b>Insulation Fasteners</b>	Fastener
• • • • • • • • • • • • • • • • • • • •	(Table 3)	Density/ft <sup>2</sup>
ISOGARD HD		•
Minimum ½" thick	N/A	N/A

Note: Base layer shall be mechanically attached with fasteners and density described. Top layer of insulation shall be adhered to base insulations with I.S.O. Twin Pack Insulation Adhesive in continuous  $\frac{1}{2}$ " –  $\frac{3}{4}$ " wide beads spaced 12" o.c. or I.S.O. Fix II or I.S.O. Stick applied in continuous  $\frac{3}{4}$ " – 1" wide ribbons spaced 12" o.c. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** UltraPly TPO membrane fully adhered to the top insulation layer with UltraPly

Bonding Adhesive, Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied to both the substrate and the underside of the roof cover for a combined rate of 120 ft<sup>2</sup>/gal or Water Based Bonding Adhesive P applied at a rate of 100-120ft<sup>2</sup>/gallon. The roof cover side and end laps are sealed

with a minimum 1.5 in. heat weld.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1"

wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -90 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 18 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Concrete

System Type B(6): Base layer of insulation mechanically fastened, top layer adhered; membrane

adhered with approved adhesive.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL	( : -)	
Minimum 2" thick	1 or 4 with 6	1:1 ft <sup>2</sup>
Top Insulation Layer (cover board)	<b>Insulation Fasteners</b>	Fastener
• • • • • • • • • • • • • • • • • • • •	(Table 3)	Density/ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum-Fiber	r Roof Board	-
Minimum ½" thick	N/A	N/A

Note: Base layer shall be mechanically attached with fasteners and density described. Top layer of insulation shall be adhered to base insulations with I.S.O. Twin Pack Insulation Adhesive in continuous  $\frac{1}{2}$ " –  $\frac{3}{4}$ " wide beads spaced 4" o.c., I.S.O. Fix II or I.S.O. Stick applied in continuous  $\frac{3}{4}$ " – 1" wide ribbons spaced 4" o.c. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

#### Membrane:

UltraPly TPO XR 100 or UltraPly TPO XR 115 or UltraPly TPO 135 membrane adhered to the top insulation layer with XR Stick Membrane Adhesive applied in continuous <sup>3</sup>/<sub>4</sub>" – 1" wide ribbons spaced 4" o.c. The 2 in. wide roof cover side and end laps are sealed with a minimum 1.5 in. heat weld placed on outside edge of lap.

Or

UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive, Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum 1.5 in. heat weld.

Or

UltraPly TPO XR roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a rate of 70-90 ft²/gal to the substrate only.

Or

UltraPly TPO XR is adhered with I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -127.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 19 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Concrete

**System Type B(7):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL Minimum 2" thick	1 & 6 or 4 & 6	1:1 ft <sup>2</sup>
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISOGARD HD Minimum ½" thick	N/A	N/A

Note: Base layer shall be mechanically attached with fasteners and density described. Top layer of insulation shall be adhered to base insulations with I.S.O. Twin Pack Insulation Adhesive in continuous  $\frac{1}{2}$ " –  $\frac{3}{4}$ " wide beads spaced 12" o.c. or I.S.O. Stick applied in continuous  $\frac{3}{4}$ " – 1" wide ribbons spaced 12" o.c. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1"

wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -90 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 20 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Concrete

**System Type B(8):** Base layer of insulation mechanically fastened, top layer insulation adhered and

membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
RESISTA Minimum 1.5" thick	1 & 6 or 4 & 6	1:1 ft <sup>2</sup>
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
RESISTA Minimum 1 5" thick	N/A	N/A

Note: Base layer shall be mechanically attached with fasteners and density described. Top layer of insulation shall be adhered to base insulations with I.S.O. Twin Pack Insulation Adhesive in continuous  $\frac{1}{2}$ " –  $\frac{3}{4}$ " wide beads spaced 12" o.c. or I.S.O. Stick applied in continuous  $\frac{3}{4}$ " – 1" wide ribbons spaced 12" o.c. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive.

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of  $60 \mathrm{ft^2/gallon}$  (120  $\mathrm{ft^2/gallon}$  to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of  $100\text{-}120 \mathrm{ft^2/gallon}$ . The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1"

wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -120 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 21 of 116

**Deck Description:** Concrete

**System Type B(9):** Base layer of insulation mechanically fastened, top layer adhered: membrane

adhered with approved adhesive. .

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL		
Minimum 2" thick	1 or 4 with 6	1:1 ft <sup>2</sup>
Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL	, ,	•
Minimum 1" thick	N/A	N/A

Note: Base layer shall be mechanically attached with fasteners and density described. Top insulation layer shall be adhered to base insulations with I.S.O. Twin Pack Insulation Adhesive in continuous  $\frac{1}{2}$ " –  $\frac{3}{4}$ " wide beads spaced 4" o.c. or I.S.O. Fix II, I.S.O. Stick applied in continuous  $\frac{3}{4}$ " – 1" wide ribbons spaced 4" o.c. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

Or

UltraPly TPO XR is adhered maximum 6" o.c. with XR Stick or a maximum 12"

o.c. with I.S.O. Spray R applied in 3/4" to 1" wide ribbons.

**Maximum Design** 

**Pressure:** -127.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 22 of 116

**Deck Description:** Minimum 22 ga. steel decking attached to steel supports spaced maximum 6 ft.

o.c. or structural concrete. \*The deck should record a Minimum Characteristic Resistance Force (MCRF) of 240 lbf. When tested with Firestone All Purpose (steel only), Heavy Duty fasteners, or Concrete Drive (concrete only) in

accordance with TAS 105.

**System Type B(10):** Base layer of insulation mechanically fastened, top layer adhered: membrane

adhered with approved adhesive. .

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

one of more layers of any of the following modifications.		
Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA	,	•
Minimum 2" thick	1 or 2 with 6 (steel) 1 or 4 with 6 (concrete)	1:1.78 ft <sup>2</sup>
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISOGARD HD	,	•
Minimum 1/2" thick	N/A	N/A
ISOGARD HD Composite		
Minimum 1.5" thick	N/A	N/A
DensDeck Prime, SECUROCK Gypsum-Fiber Roof I	Board	
Minimum 1/4" thick	N/A	N/A

Note: Base layer shall be mechanically attached with fasteners and density described. Top insulation layer shall be adhered to base insulations with I.S.O. Twin Pack Insulation Adhesive (ISOGARD HD only) in continuous  $\frac{1}{2}$ " –  $\frac{3}{4}$ " wide beads spaced 6" o.c. or I.S.O. Fix II (except DensDeck Prime) or I.S.O. Stick applied in continuous  $\frac{3}{4}$ " – 1" wide ribbons spaced 6" o.c. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive, Single-

Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum 1.5 in.

heat weld.

Or

UltraPly TPO XR roof cover is adhered with XR Stick or I.S.O. Spray R applied

in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -67.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 23 of 116

**Deck Description:** Minimum 22 ga. steel decking attached to steel supports spaced maximum 6 ft.

o.c. or structural concrete. \*The deck should record a Minimum Characteristic Resistance Force (MCRF) of 214 lbf. When tested with Firestone All Purpose (steel only), Heavy Duty fasteners, or Concrete Drive (concrete only) in

accordance with TAS 105.

**System Type B(11):** Base layer of insulation mechanically fastened, top layer adhered: membrane

adhered with approved adhesive. .

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners	Fastener
ISO 95+ GL, RESISTA	(Table 3)	Density/ft <sup>2</sup>
Minimum 2" thick	1 or 2 with 6 (steel) 1 or 4 with 6 (concrete)	1:1.78 ft <sup>2</sup>
Middle Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA	()	
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISOGARD HD	,	•
Minimum 1/2" thick	N/A	N/A
ISOGARD HD Composite		
Minimum 1.5" thick	N/A	N/A
DensDeck Prime, SECUROCK Gypsum-Fiber Roof B	oard	
Minimum 1/4" thick	N/A	N/A

Note: Base layer shall be mechanically attached with fasteners and density described. Middle and Top insulation layers shall be adhered to base insulations with I.S.O. Twin Pack Insulation Adhesive (ISOGARD HD only) in continuous  $\frac{1}{2}$ " –  $\frac{3}{4}$ " wide beads spaced 6" o.c. or I.S.O. Fix II (except DensDeck Prime) or I.S.O. Stick applied in continuous  $\frac{3}{4}$ " – 1" wide ribbons spaced 6" o.c. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive, Single-Ply

LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft2/gallon (120 ft2/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft2/gallon. The roof cover side and end laps are sealed with a minimum 1.5 in. heat weld.

Or

UltraPly TPO XR roof cover is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 24 of 116

Single Ply, TPO **Membrane Type:** 

Deck Type 7I: Recover, Insulated

**Deck Description:** Concrete

Membrane adhered over mechanically fastened insulation. **System Type C(1):** 

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners	Fastener
·	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL		
Minimum 1.5" thick	1 or 4 with 6	1:2 ft <sup>2</sup>

Note: Insulation layer shall be mechanically attached with fasteners and density described. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft<sup>2</sup>/gallon (120 ft<sup>2</sup>/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft<sup>2</sup>/gallon. The roof cover side and end laps are sealed with

a minimum 1.5 in. heat weld.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to

1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

Pressure: -45 psf. (See General Limitation #9)



NOA No.: 14-0606.04 **Expiration Date: 02/03/20** Approval Date: 05/26/16 Page 25 of 116

**Deck Description:** Concrete

**System Type C(2):** Membrane adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

<b>Base Insulation Layer (Optional)</b>	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL Minimum 1" thick	N/A	N/A
Tapered ISO 95+ GL Minimum ½" thick with a ¼" per ft. taper	N/A	N/A

Note: Base layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
ISO 95+ GL	,	v
Minimum 2 1/4" thick	1 or 4 with 6	1:4 ft <sup>2</sup>
Additional Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft²
ISO 95+ GL	, ,	·
Minimum 1.5" thick	N/A	N/A

Note: Top layer shall be mechanically attached with fasteners and density described. Additional layers of insulation shall be adhered to top insulation with I.S.O. Twin Pack Insulation Adhesive in continuous  $\frac{1}{2}$ " –  $\frac{3}{4}$ " wide beads spaced 12" o.c., I.S.O. Fix II or I.S.O. Stick applied in continuous  $\frac{3}{4}$ " – 1" wide ribbons spaced 12" o.c. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1"

wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #9)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 26 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Concrete

System Type C(3): Membrane adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL	,	·
Minimum 1.5" thick	N/A	N/A
(Optional) Middle Insulation Layer	<b>Insulation Fasteners</b>	Fastener
•	(Table 3)	Density/ft2
Tapered ISO 95+ GL		
Minimum 1/2" thick with a 1/4" per ft. taper	N/A	N/A

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Top Insulation Layer (cover board)	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum-Fiber Roc	of Board	•
Minimum ¼" thick	1 or 4 with 6	1:2 ft <sup>2</sup>
Plywood		
Minimum 19/32" thick	1 or 4 with 6	1:2 ft <sup>2</sup>

**Membrane:** UltraPly TPO XR 100 or UltraPly TPO XR 115 or UltraPly TPO 135 membrane

adhered to the top insulation layer with XR Stick Membrane Adhesive applied in continuous  $\sqrt[3]{4}$ " – 1" wide ribbons spaced 12" o.c. The 2 in. wide roof cover side and end laps are sealed with a minimum 1.5 in. heat weld placed on outside edge

of lap.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 27 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Steel

System Type C(4): Membrane adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum-Fibe	r Roof Board	
Minimum <sup>1</sup> / <sub>4</sub> " thick	1 or 2 with 6	1:2 ft <sup>2</sup>

Note: Insulation layer shall be mechanically attached with fasteners and density described. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

Or

UltraPly TPO XR roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR

Bonding Adhesive at a rate of 70-90 ft<sup>2</sup>/gal to the substrate only.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1"

wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 28 of 116

Single Ply, TPO **Membrane Type:** 

Deck Type 7I: Recover, Insulated

**Deck Description:** Steel

Membrane adhered over mechanically fastened insulation. System Type C(5):

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners	Fastener
•	(Table 3)	Density/ft <sup>2</sup>
Plywood		
Minimum 19/32" thick	1 or 2 with 6	1:2 ft <sup>2</sup>

Note: Insulation layer shall be mechanically attached with fasteners and density described. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** UltraPly TPO XR 100 or UltraPly TPO XR 115 or UltraPly TPO 135 membrane

> adhered to the top insulation layer with XR Stick Membrane Adhesive applied in continuous  $\frac{3}{4}$ " – 1" wide ribbons spaced 12" o.c. The 2 in. wide roof cover side and end laps are sealed with a minimum 1.5 in. heat weld placed on outside edge

of lap.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #9)



NOA No.: 14-0606.04 **Expiration Date: 02/03/20** Approval Date: 05/26/16 Page 29 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Steel (Existing Structural Non-Insulated Metal Roof Panel Assembly)

System Type C(6): Membrane bonded over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer: To be placed between the ribs or over panels of existing structural metal roof system.	Insulation Fasteners (Table 3)	Fastener Density/ft²
ISO 95+ GL Minimum 1.5" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
ISOGARD HD		
Minimum ½" thick	N/A	N/A
DensDeck; DensDeck Prime, SECUROCK Gypsum-Fibe Fiber Roof Board	r Roof Board, SECURO	CK Glass-Mat
Minimum ¼" thick	N/A	N/A
Plywood		
Minimum 19/32" thick	N/A	N/A

Note: All insulation shall have preliminary attachment prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Please refer to Roofing Application Standard RAS 117 for insulation attachment. A minimum insulation thickness of 1 inch must be used with UltraPly InvisiWeld Plates.

**Membrane:** UltraPly TPO is mechanically fastened to the deck through the insulation to 16 ga.

purlins spaced 5 ft. o.c. maximum using Purlin fasteners and UltraPly TPO InvisiWeld Plates, fastened 12" o.c. maximum along the purlins. (Areas where the metal panels do not lay flush on purlin shall have a ¼" pilot pre-drilled into the panel prior to fastening) and then bonded to the UltraPly TPO InvisiWeld Plates using a RhinoBond Portable Bonding Tool and weighted RhinoBond Cooling Clamps. The minimum 3 in. wide roof cover side laps are sealed with a minimum

1.5 in. wide heat weld on the outside edge of the lap.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 30 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Steel

Minimum 1/2" thick

**System Type C(7):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL		

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISOGARD HD	(146.0)	Delisity/It
Minimum ½" thick	2 or 1 and 6	1:2.7ft <sup>2</sup>

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of  $60 \mathrm{ft^2/gallon}$  (120  $\mathrm{ft^2/gallon}$  to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of  $100\text{-}120 \mathrm{ft^2/gallon}$ . The roof cover side and end laps are sealed with a minimum

N/A

N/A

1.5 in. heat weld.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1"

wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** –45 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 31 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Steel (Existing Structural Non-Insulated Metal Roof Panel Assembly)

**System Type C(8):** Membrane bonded over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer: To be placed between the ribs or over panels of existing structural metal roof system. ISO 95+ GL	Insulation Fasteners (Table 3)	Fastener Density/ft²
Minimum 1" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL	(== = )	_ 5
Minimum 1.5" thick	N/A	N/A
ISOGARD HD		
Minimum ½" thick	N/A	N/A
DensDeck; DensDeck Prime, SECUROCK Gypsum-Fibe Fiber Roof Board	er Roof Board, SECURO	CK Glass-Mat
Minimum 1/4" thick	N/A	N/A
Plywood		
Minimum 19/32" thick	N/A	N/A

Note: All insulation shall have preliminary attachment prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Please refer to Roofing Application Standard RAS 117 for insulation attachment. A minimum insulation thickness of 1 inch must be used with UltraPly InvisiWeld Plates.

**Membrane:** UltraPly TPO is mechanically fastened to the deck through the insulation to 16 ga.

purlins spaced 10-ft. o.c. maximum using Purlin fasteners and UltraPly TPO InvisiWeld Plates, fastened 6" o.c. maximum along the purlins. (Areas where the metal panels do not lay flush on purlin shall have a ¼" pilot pre-drilled into the panel prior to fastening) and then bonded to the UltraPly TPO InvisiWeld Plates using a RhinoBond Portable Bonding Tool and weighted RhinoBond Cooling Clamps. The minimum 6 in. wide roof cover side laps are sealed with a minimum

1.5 in. wide heat weld on the outside edge of the lap.

**Maximum Design** 

**Pressure:** -52.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 32 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** ASTM A1008 Grade 33, minimum 22 gauge, Type B steel deck secured to ½

in. thick steek strutural supports spaced a maximum 6 ft. o.c. with Traxx/5 fasteners spaced at a maximum 6 in. on center at the supports The deck side

laps were secured approximately 24 in o.c. with TRAXX/1 fasteners;

Or

Concrete.

**System Type C(9):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Base Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft<sup>2</sup>

**ISO 95+ GL** 

Minimum 1.5" thick N/A N/A

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Top Insulation Layer (cover board)

Insulation Fasteners
(Table 3)

ISOGARD HD

1 or 2 (steel only) with 6

Minimum ½" thick

1 or 4 (concrete only) with 6

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1"

wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 33 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Concrete

**System Type C(10):** Membrane adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL		
Minimum 2" thick	1 or 4 with 6	1:1.6 ft <sup>2</sup>

Note: Insulation layer shall be mechanically attached with fasteners and density described. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

**Membrane:** UltraPly TPO XR 100 or UltraPly TPO XR 115 or UltraPly TPO 135 membrane adhered

to the top insulation layer with XR Stick Membrane Adhesive applied in continuous <sup>3</sup>/<sub>4</sub>" – 1" wide ribbons spaced 6" o.c. The 2 in. wide roof cover side and end laps are sealed

with a minimum 1.5 in. heat weld placed on the outside edge of lap.

Or

UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive, Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum 1.5 in, heat weld.

Or

UltraPly TPO XR is adhered with I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -82.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 34 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Steel (Existing Structural Non-Insulated Metal Roof Panel Assembly)

System Type C(11): Membrane bonded over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer: To be placed between the ribs or over panels of existing structural metal roof system.	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL Minimum 1" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL Minimum 1.5" thick	N/A	N/A
ISOGARD HD Minimum ½" thick	N/A	N/A
DensDeck; DensDeck Prime, SECUROCK Gypsum-Fibe	er Roof Board, SECURO	CK Glass-Mat
Fiber Roof Board Minimum <sup>1</sup> / <sub>4</sub> " thick	N/A	N/A
Plywood Minimum 19/32" thick	N/A	N/A

Note: All insulation shall have preliminary attachment prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Please refer to Roofing Application Standard RAS 117 for insulation attachment. A minimum insulation thickness of 1 inch must be used with UltraPly InvisiWeld Plates.

**Membrane:** UltraPly TPO is mechanically fastened to the deck through the insulation to 16 ga.

purlins spaced 5 ft. o.c. maximum using Purlin fasteners and UltraPly TPO InvisiWeld Plates, fastened 6" o.c. maximum along the purlins. (Areas where the metal panels do not lay flush on purlin shall have a ¼" pilot pre-drilled into the panel prior to fastening) and then bonded to the UltraPly TPO InvisiWeld Plates using a RhinoBond Portable Bonding Tool and weighted RhinoBond Cooling Clamps. The minimum 3 in. wide roof cover side laps are sealed with a minimum 1.5 in. wide heat weld on the outside edge of the lap.

**Maximum Design** 

**Pressure:** -82.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 35 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Concrete

System Type C(12): Membrane adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL		
Minimum 2" thick	1 or 4 with 6	1:1 ft <sup>2</sup>

Note: Insulation layer shall be mechanically attached with fasteners and density described. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** 

UltraPly TPO XR 100 or UltraPly TPO XR 115 or UltraPly TPO 135 membrane adhered to the top insulation layer with XR Stick Membrane Adhesive applied in continuous <sup>3</sup>/<sub>4</sub>" – 1" wide ribbons spaced 4" o.c. The 2 in. wide roof cover side and end laps are sealed with a minimum 1.5 in. heat weld placed on the outside edge of lap.

Or

UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive, Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum 1.5 in. heat weld.

Or

UltraPly TPO XR is adhered with I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

#### **Maximum Design**

**Pressure:** -142.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 36 of 116

Single Ply, TPO **Membrane Type:** 

Recover, Insulated Deck Type 7I:

**Deck Description:** Minimum 22 ga. Grade 33, Type B steel deck secured to supports space at

maximum 6 ft. o.c. with ITW Buildex Traxx/5 spaced at 6" o.c. Side lap

fastened with ITW Buildex Traxx/1 spaced at 24" o.c.

Or

Concrete

All layers of insulation simultaneously attached; membrane fully adhered. System Type C(13):

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations (not to exceed 1" for steel deck):

Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISOGARD HD Composite		
Minimum 1.0" thick	1 & 6 or 2 & 6 (for steel) 1 & 6 or 4 & 6 (for concrete)	1:1.33 ft <sup>2</sup>

Note: All layers shall be simultaneously fastened. See above for fasteners and density. Insulation panels listed are minimum sizes and dimensions. If larger panels are used, the number of fasteners shall be increased using the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

> Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft<sup>2</sup>/gallon (120 ft<sup>2</sup>/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft<sup>2</sup>/gallon. The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1"

wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)



NOA No.: 14-0606.04 **Expiration Date: 02/03/20** Approval Date: 05/26/16

Page 37 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Concrete

**System Type C(14):** All layers of insulation simultaneously attached; membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
ISOGARD HD Composite		
Minimum 1.5" thick	1 & 6 or 4 & 6	1:1.33 ft <sup>2</sup>

Note: All layers shall be simultaneously fastened. See above for fasteners and density. Insulation panels listed are minimum sizes and dimensions. If larger panels are used, the number of fasteners shall be increased using the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1"

wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -112.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16

Page 38 of 116

Deck Type 7I: Recover, Insulated

**Deck Description:** Concrete

System Type C(15): All layers of insulation simultaneously attached; membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
ISOGARD HD Composite		
Minimum 2.0" thick	1 & 6 or 4 & 6	1:1.33 ft <sup>2</sup>

Note: All layers shall be simultaneously fastened. See above for fasteners and density. Insulation panels listed are minimum sizes and dimensions. If larger panels are used, the number of fasteners shall be increased using the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft<sup>2</sup>/gallon (120 ft<sup>2</sup>/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft<sup>2</sup>/gallon. The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1"

wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

Pressure: -120 psf. (See General Limitation #7)



NOA No.: 14-0606.04 **Expiration Date: 02/03/20** Approval Date: 05/26/16

Page 39 of 116

Single Ply, TPO **Membrane Type:** 

Deck Type 7I: Recover, Insulated

**Deck Description:** Concrete

System Type C(16): All layers of insulation simultaneously attached; membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
RESISTA Minimum 2" thick	1 & 6 or 4 & 6	See Design Pressures

Note: All layers shall be simultaneously fastened. See above for fasteners and density. Insulation panels listed are minimum sizes and dimensions. If larger panels are used, the number of fasteners shall be increased using the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive, Single-**Membrane:** 

> Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft<sup>2</sup>/gallon. The roof cover side and end laps are sealed with a minimum 1.5 in.

heat weld.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1"

wide ribbons spaced a maximum 12" o.c.

-82.5 psf. at 1:1.6 ft<sup>2</sup> (See General Limitation #7) **Maximum Design Pressure:** -105 psf. at 1:1.33 ft<sup>2</sup> (See General Limitation #7)

-150 psf. at 1:1 ft<sup>2</sup> (See General Limitation #7)



NOA No.: 14-0606.04 **Expiration Date: 02/03/20** Approval Date: 05/26/16

Page 40 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Concrete

**System Type C(17):** All layers of insulation simultaneously attached; membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

 $\begin{array}{cccc} Insulation \ Layer & Insulation \ Fasteners & Fastener \\ (Table 3) & Density/ft^2 \\ RESISTA & & & & \\ Minimum \ 1.5" \ thick & 1 \ \& \ 6 \ or \ 4 \ \& \ 6 & 1:1.6 \ ft^2 \\ \end{array}$ 

Note: All layers shall be simultaneously fastened. See above for fasteners and density. Insulation panels listed are minimum sizes and dimensions. If larger panels are used, the number of fasteners shall be increased using the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1"

wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -75 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16

Page 41 of 116

Single Ply, TPO **Membrane Type:** 

Deck Type 7I: Recover, Insulated

Concrete or Min. 22 ga. Steel **Deck Description:** 

Membrane bonded over mechanically fastened insulation. System Type C(18):

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA, ISOGARD HD		
Minimum 1/2" thick	1 with 9	1:5.3 ft <sup>2</sup>
	4 (concrete only) with 9	

DensDeck; DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Fiber Roof Board

Minimum 1/4" thick 1 with 9 1:5.3 ft<sup>2</sup> 4 (concrete only) with 9

Note: All layers shall be simultaneously fastened. See above for fasteners and density. Insulation panels listed are minimum sizes and dimensions. If larger panels are used, the number of fasteners shall be increased using the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment. A minimum insulation thickness of 1 inch must be used with UltraPly InvisiWeld Plates.

UltraPly TPO is bonded to the UltraPly TPO InvisiWeld Plates using a RhinoBond **Membrane:** 

> Portable Bonding Tool and weighted RhinoBond Cooling Clamps. The minimum 6" wide roof cover side laps are sealed with a minimum 1.5" wide heat weld on

the outside edge of the lap.

**Maximum Design** 

**Pressures:** -45 psf. (See General Limitation #9)



NOA No.: 14-0606.04 **Expiration Date: 02/03/20** Approval Date: 05/26/16

Page 42 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 33, Type B steel deck secured to supports space at

maximum 6 ft. o.c. with ITW Buildex Traxx/5 spaced at 6" o.c. Side lap

fastened with ITW Buildex Traxx/1 spaced at 24" o.c.

Or

Concrete

System Type C(19): Membrane bonded over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA, ISOGARD HD		

Minimum ½" thick 1 with 9 See Design 4 (concrete only) with 9 Pressures

DensDeck; DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat

Fiber Roof Board

Minimum ¼" thick 1 with 9 See Design 4 (concrete only) with 9 Pressures

ISOGARD HD Composite

Minimum 1.5" thick

1 with 9

4 (concrete only) with 9

Pressures

Note: All layers shall be simultaneously fastened. See above for fasteners and density. Insulation panels listed are minimum sizes and dimensions. If larger panels are used, the number of fasteners shall be increased using the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment. A minimum insulation thickness of 1 inch must be used with UltraPly InvisiWeld Plates.

**Membrane:** UltraPly TPO is bonded to the UltraPly TPO InvisiWeld Plates using a RhinoBond

Portable Bonding Tool and weighted RhinoBond Cooling Clamps. The minimum 6" wide roof cover side laps are sealed with a minimum 1.5" wide heat weld on

the outside edge of the lap.

**Maximum Design** -60 psf. at 1:4 ft<sup>2</sup> (See General Limitation #7) **Pressures:** -75 psf. at 1:2.7 ft<sup>2</sup> (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 43 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 3, Type B steel deck secured to supports space at

maximum 6 ft. o.c. with two (2) ITW Buildex Traxx/5 spaced at 6" o.c. Side lap

fastened with ITW Buildex Traxx/1 spaced at 24" o.c.;

Or

Concrete

System Type C(20): Membrane bonded over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA, ISOGARD HD		
Minimum ½" thick	1 with 9 4 (concrete only) with 9	1:2 ft <sup>2</sup>

DensDeck; DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat

Fiber Roof Board

Minimum ¼" thick 1 with 9

4 (concrete only) with 9 1:2 ft<sup>2</sup>

**ISOGARD HD Composite** 

Minimum 1.5" thick

4 (concrete only) with 9 1:2 ft<sup>2</sup>

Note: All layers shall be simultaneously fastened. See above for fasteners and density. Insulation panels listed are minimum sizes and dimensions. If larger panels are used, the number of fasteners shall be increased using the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment. A minimum insulation thickness of 1 inch must be used with UltraPly InvisiWeld Plates.

**Membrane:** UltraPly TPO is bonded to the UltraPly TPO InvisiWeld Plates using a RhinoBond

Portable Bonding Tool and weighted RhinoBond Cooling Clamps. The minimum 6" wide roof cover side laps are sealed with a minimum 1.5" wide heat weld on

the outside edge of the lap.

**Maximum Design** 

**Pressures:** -105 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 44 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 3, Type B steel deck secured to supports space at

maximum 6 ft. o.c. with two (2) ITW Buildex Traxx/5 spaced at 6" o.c. Side lap

fastened with ITW Buildex Traxx/1 spaced at 24" o.c.;

Or

Concrete

System Type C(21): Membrane bonded over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer Insulation Fasteners Fastener (Table 3) Pensity/ft²

ISO 95+ GL, RESISTA, ISOGARD HD

Minimum ½" thick 1 with 9

4 (concrete only) with 9

See Below

DensDeck, DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat

Fiber Roof Board

Minimum <sup>1</sup>/<sub>4</sub>" thick 1 with 9

4 (concrete only) with 9 See Below

**ISOGARD HD Composite** 

Minimum 1.5" thick

4 (concrete only) with 9 See Below

Note: All insulation shall have preliminary attachment prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Please refer to Roofing Application Standard RAS 117 for insulation attachment. A minimum insulation thickness of 1 inch must be used with UltraPly InvisiWeld Plates.

**Membrane:** UltraPly TPO is bonded to the UltraPly TPO InvisiWeld Plates are secured

through the insulation layer to the deck at a maximum 6" o.c. in rows in rows spaced a maximum 60" o.c. UltraPly TPO is bonded to the UltraPly TPO InvisiWeld Plates using a RhinoBond Portable Bonding Tool and weighted RhinoBond Cooling Clamps. The minimum 6" wide roof cover side laps are sealed with a minimum 1.5" wide heat weld on the outside edge of the lap.

**Maximum Design** 

**Pressures:** -82.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 45 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Concrete

**System Type C(22):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

**ISO 95+ GL** 

Minimum 1-1/4" thick 1 or 4 with 6 1:2.7 ft<sup>2</sup>

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon.

The roof cover side and end laps are sealed with

a minimum 1.5 in. heat weld.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to

1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 46 of 116

Deck Type 7I: Recover, Insulated

**Deck Description:** Min. 22 ga. steel deck with supports spaced maximum 6 ft. o.c. or structural

concrete. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 213 lbf. when tested with Firestone All Purpose (steel only), Heavy Duty fasteners, or Concrete Drive (concrete only) installed through to the deck

in accordance with TAS 105.

System Type C(23): Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

**Insulation Layer Insulation Fasteners** Fastener Density/ft<sup>2</sup> (Table 3) ISO 95+ GL Minimum 1.5" thick 1:1.78 ft<sup>2</sup> 1 or 2 with 6 (steel)

1 or 4 with 6 (concrete)

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

UltraPly TPO roof cover is fully adhered with UltraPly Bonding Membrane:

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft<sup>2</sup>/gallon (120 ft<sup>2</sup>/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft<sup>2</sup>/gallon. The roof cover side and end laps are sealed with a

minimum 1.5 in heat weld

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1"

wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

Pressure: -60 psf. (See General Limitation #7)



NOA No.: 14-0606.04 **Expiration Date: 02/03/20** Approval Date: 05/26/16

Page 47 of 116

Single Ply, TPO **Membrane Type:** 

Recover, Insulated Deck Type 7I:

Minimum 15/32" plywood attached to structural supports spaced a maximum **Deck Description:** 

24" o.c. with 0.113" ring shank nails spaced 6" o.c. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 280 lbf. when tested with Firestone Heavy-Duty fasteners installed through to the deck in accordance with

TAS 105.

Membrane bonded over mechanically fastened insulation. System Type C(24):

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

<b>Bottom Insulation Layer (Optional)</b>	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA		
Minimum 0.5" thick	N/A	N/A
<b>Top Insulation Layer</b>	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
DensDeck,, SECUROCK Gypsum-Fiber Roof Boar	rd, SECUROCK Glass-Mat F	iber Roof Board
Minimum ¼" thick	1 with 9	1:2.67 ft <sup>2</sup>
ISOGARD HD Composite		

Minimum 1.5" thick

1 with 9 1:267 ft<sup>2</sup>

Note: All insulation shall have preliminary attachment prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Please refer to Roofing Application Standard RAS 117 for insulation attachment. A minimum insulation thickness of 1 inch must be used with UltraPly InvisiWeld Plates.

UltraPly TPO (min. 0.060") is bonded to the UltraPly TPO InvisiWeld Plates **Membrane:** 

> using a RhinoBond Portable Bonding Tool and weighted RhinoBond Cooling Clamps. The minimum 6" wide roof cover side laps are sealed with a minimum

1.5" wide heat weld on the outside edge of the lap.

**Maximum Design** 

**Pressures:** -52.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 **Expiration Date: 02/03/20** Approval Date: 05/26/16 Page 48 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 15/32" plywood attached to structural supports spaced a maximum

24" o.c. with 0.113" ring shank nails spaced 6" o.c. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 420 lbf. when tested with Firestone Heavy-Duty fasteners installed through to the deck in accordance with

TAS 105.

System Type C(25): Membrane bonded over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

<b>Bottom Insulation Layer (Optional)</b>	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA		

Minimum 1/2" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Pensity/ft²

DensDeck, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Fiber Roof Board Minimum 1/4" thick 1 with 9 1:4 ft<sup>2</sup>

ISOGARD HD Composite

Minimum 1.5" thick 1 with 9 1:2 ft<sup>2</sup>

Note: All insulation shall have preliminary attachment prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Please refer to Roofing Application Standard RAS 117 for insulation attachment. A minimum insulation thickness of 1 inch must be used with UltraPly InvisiWeld Plates.

Membrane: UltraPly TPO is bonded to the UltraPly TPO InvisiWeld Plates using a RhinoBond

Portable Bonding Tool and weighted RhinoBond Cooling Clamps. The minimum 6" wide roof cover side laps are sealed with a minimum 1.5" wide heat weld on

the outside edge of the lap.

**Maximum Design** 

**Pressures:** -52.5 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 49 of 116

Single Ply, TPO **Membrane Type:** 

Deck Type 7I: Recover, Insulated

**Deck Description:** Min. 22 ga. steel deck with supports spaced maximum 6 ft. o.c. or structural

> concrete. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 360 lbf. when tested with Firestone Heavy-Duty fasteners installed

through to the deck in accordance with TAS 105.

System Type C(26): Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA	,	·
Minimum ½" thick	1 with 9	1:4 ft <sup>2</sup>
DensDeck, SECUROCK Gypsum-Fiber Roof Board		
Minimum 1/4" thick	1 with 9	1:4 ft <sup>2</sup>
ISOGARD HD Composite		
Minimum 1½" thick	1 with 9	1:4 ft <sup>2</sup>

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment. A minimum insulation thickness of 1 inch must be used with UltraPly InvisiWeld Plates.

Membrane: UltraPly TPO is bonded to the UltraPly TPO InvisiWeld Plates using a RhinoBond

> Portable Bonding Tool and weighted RhinoBond Cooling Clamps. The minimum 6" wide roof cover side laps are sealed with a minimum 1.5" wide heat weld on

the outside edge of the lap.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #7)



NOA No.: 14-0606.04 **Expiration Date: 02/03/20** Approval Date: 05/26/16

Page 50 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Min. 22 ga. steel deck with supports spaced maximum 6 ft. o.c. or structural

concrete. The existing shall be minimum 1" in total thickness. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 160 lbf. when tested with Firestone All Purpose (steel only), Heavy Duty fasteners, or Concrete Drive (concrete only) installed through to the deck in accordance

with TAS 105.

**System Type C(27):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA		•
Minimum 1" thick	N/A	N/A
Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
SECUROCK Gypsum-Fiber Roof Board		
Minimum <sup>1</sup> / <sub>4</sub> " thick	1 or 2 with 6 (steel)	1:1.78 ft <sup>2</sup>
	1 or 4 with 6 (concrete)	

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

Or

UltraPly TPO XR (over SECUROCK and DensDeck only) roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a rate of 70-90 ft²/gal

to the substrate only.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1"

wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 51 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Min. 22 ga. steel deck with supports spaced maximum 6 ft. o.c. or structural

concrete. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 240 lbf. when tested with Firestone All Purpose (steel only), Heavy Duty fasteners, or Concrete Drive (concrete only) installed through to the deck

in accordance with TAS 105.

**System Type C(28):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+GL		
Minimum 2" thick	1 or 2 with 6 (steel)	1:2.67 ft <sup>2</sup>
	1 or 4 with 6 (concrete)	

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1"

wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 52 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Min. 22 ga. steel deck with supports spaced maximum 6 ft. o.c. or structural

concrete. Existing roof shall be a minimum of 1" in total thickness. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 214 lbf. when tested with Firestone All Purpose (steel only), Heavy Duty fasteners, or Concrete Drive (concrete only) installed through to the deck in accordance with

TAS 105.

**System Type C(29):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA		•
Minimum ½" thick	N/A	N/A
Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
SECUROCK Gypsum-Fiber Roof Board		
Minimum ½" thick	1 or 2 with 6 (steel)	1:1.78 ft <sup>2</sup>
	1 or 4 with 6 (concrete)	

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of  $60 \mathrm{ft^2/gallon}$  (120  $\mathrm{ft^2/gallon}$  to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of  $100\text{-}120 \mathrm{ft^2/gallon}$ . The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

Or

UltraPly TPO XR (over SECUROCK and DensDeck only) roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a rate of 70-90 ft²/gal

to the substrate only.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 53 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Min. 22 ga. steel deck with supports spaced maximum 6 ft. o.c. or concrete

\*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 168 lbf. when tested with Firestone All Purpose (steel only), Heavy Duty fasteners, or Concrete Drive (concrete only) installed through to the deck in

accordance with TAS 105.

**System Type C(30):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA	,	·
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
RESISTA		
Minimum 1" thick	1 or 2 with 6 (steel)	1:1.6 ft <sup>2</sup>
	1 or 4 with 6 (concrete)	

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1"

wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -52.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 54 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Min. 22 ga. steel deck with supports spaced maximum 6 ft. o.c. or concrete

\*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 256 lbf. when tested with Firestone All Purpose (steel only), Heavy Duty fasteners, or Concrete Drive (concrete only) in accordance with TAS 105. The

existing roof shall be a minimum 1/2" thick.

**System Type C(31):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA		•
Minimum ½" thick	N/A	N/A
Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
SECUROCK Gypsum-Fiber roof Board		
Minimum ½" thick	1 or 2 with 6 (steel)	1:2.13 ft <sup>2</sup>
	1 or 4 with 6 (concrete)	

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive, Single-

Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum 1.5 in.

heat weld.

Or

UltraPly TPO XR roof cover is adhered with XR Stick or I.S.O. Spray R applied

in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 55 of 116

**Deck Description:** Min. 22 ga. steel deck with supports spaced maximum 6 ft. o.c. or concrete

\*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 216 lbf. when tested with Firestone All Purpose (steel only), Heavy Duty fasteners, or Concrete Drive (concrete only) in accordance with TAS 105. The

existing roof shall be a minimum 1/2" thick.

**System Type C(32):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA	` ,	•
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
SECUROCK Gypsum-Fiber roof Board	, ,	•
Minimum 1/4" thick	1 or 2 with 6 (steel)	1:1.6 ft <sup>2</sup>
	1 or 4 with 6 (concrete)	
RESISTA		
Minimum 1" thick	1 or 2 with 6 (steel)	1:1.6 ft <sup>2</sup>
	1 or 4 with 6 (concrete)	

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of  $60 \mathrm{ft^2/gallon}$  (120  $\mathrm{ft^2/gallon}$  to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of  $100\text{-}120 \mathrm{ft^2/gallon}$ . The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

Or

UltraPly TPO XR (over SECUROCK and DensDeck only) roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a rate of 70-90 ft²/gal

to the substrate only.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -67.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 56 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 33 Steel

Or

Concrete

**System Type C(33):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
SECUROCK Gypsum-Fiber Roof Board	,	v
Minimum ½" thick	1 or 2 with 6 (for steel) 3 (for steel) 4 with 6 (for concrete)	1:4.0 ft <sup>2</sup>
ISOGARD HD Composite		
Minimum 1.5" thick	1 or 2 with 6 (for steel) 4 with 6 (for concrete)	1:4.0 ft <sup>2</sup>

Note: All layers shall be simultaneously fastened. See above for fasteners and density. Insulation panels listed are minimum sizes and dimensions. If larger panels are used, the number of fasteners shall be increased using the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO membrane fully adhered to the top insulation layer with UltraPly

surface of roof cover is then broomed to ensure contact.

Bonding Adhesive, Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 roller applied at a rate of 60 ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate), or Water Based Bonding Adhesive P applied at a rate of 120 ft²/gallon (240 ft²/gallon to both the underside of membrane and the substrate). The 3 in. wide roof cover side and end laps are sealed with a minimum 1.5 in. heat weld on the outside edge of the lap. Top

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 57 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 33, Type B steel deck, concrete, or wood

**System Type C(34):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum-Fiber	Roof Board	
Minimum 1/4" thick	1 or 2 with 6 (for steel)	$1:2.7 \text{ ft}^2$
	4 with 6 (for concrete)	
RESISTA		
Minimum 1" thick	1 or 2 with 6 (for steel)	$1:2.7 \text{ ft}^2$
	4 with 6 (for concrete)	
ISO 95 +GL, ISOGARD HD Composite		
Minimum 1.5" thick	1 or 2 with 6 (for steel)	$1:2.7 \text{ ft}^2$
	4 with 6 (for concrete)	

Note: All layers shall be simultaneously fastened. See above for fasteners and density. Insulation panels listed are minimum sizes and dimensions. If larger panels are used, the number of fasteners shall be increased using the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO membrane fully adhered to the top insulation layer with UltraPly

Bonding Adhesive or Single-Ply LVOC Bonding Adhesive applied at a rate of 60 ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate).

Maximum Design

**Pressure:** -45 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 58 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Min. 22 ga. steel deck with supports spaced maximum 6 ft. o.c. or concrete

\*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 401 lbf, when tested with Firestone Heavy-Duty fasteners installed through to

the deck in accordance with TAS 105.

System Type C(35): Membrane bonded over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

<b>Bottom Insulation Layer (Optional)</b>	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA		•
Minimum 1/2" thick	N/A	N/A
<b>Top Insulation Layer</b>	<b>Insulation Fasteners</b>	Fastener
•	(Table 3)	Density/ft <sup>2</sup>
ISOGARD HD	` ,	•
Minimum 1/2" thick	1 with 9	1:2.67 ft <sup>2</sup>
DensDeck,, SECUROCK Gypsum-Fiber Roof	Board, SECUROCK Glass-Mat F	iber Roof Board
Minimum 1/4" thick	1 with 9	1:2.67 ft <sup>2</sup>
ISO 95 +GL, RESISTA		
Minimum 1" thick	1 with 9	1:2.67 ft <sup>2</sup>
ISOGARD HD Composite		
Minimum 1.5" thick	1 with 9	$1:2.67 \text{ ft}^2$

Note: All insulation shall have preliminary attachment prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Please refer to Roofing Application Standard RAS 117 for insulation attachment. A minimum insulation thickness of 1 inch must be used with UltraPly InvisiWeld Plates.

Membrane: UltraPly TPO is bonded to the UltraPly TPO InvisiWeld Plates using a RhinoBond

Portable Bonding Tool and weighted RhinoBond Cooling Clamps. The minimum 2" wide roof cover side laps are sealed with a minimum 1.5" wide heat weld on

the outside edge of the lap.

**Maximum Design** 

**Pressures:** -75 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 59 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Min. 22 ga. steel deck with supports spaced maximum 6 ft. o.c. or concrete.

\*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 294 lbf. when tested with Firestone All-Purpose fasteners (steel only), Heavy Duty fasteners, or Concrete Drive (concrete only) installed through to the deck

in accordance with TAS 105.

**System Type C(36):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA	,	·
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
SECUROCK Gypsum-Fiber roof Board		
Minimum ½" thick	1 or 2 with 6 (steel)	1:1.78 ft <sup>2</sup>
	1 or 4 with 6 (concrete)	
ISOGARD HD Composite		
Minimum 1.5" thick	1 or 2 with 6 (steel)	1:1.78 ft <sup>2</sup>
	1 or 4 with 6 (concrete)	

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive, Single-

Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum 1.5 in.

heat weld.

Or

UltraPly TPO XR roof cover is adhered with XR Stick or I.S.O. Spray R applied

in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -82.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 60 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 15/32" plywood attached to structural supports spaced a maximum

24" o.c. with 0.113" ring shank nails spaced 6" o.c. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 240 lbf. when tested with Firestone All Purpose Fasteners or Heavy Duty Fasteners installed through to

the deck in accordance with TAS 105.

System Type C(37): Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

<b>Bottom Insulation Layer (Optional)</b>	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA		
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
SECUROCK Gypsum-Fiber Roof Board	,	·
Minimum ½" thick	1or 2 with 6	1:1.78 ft <sup>2</sup>
ISOGARD HD Composite		
Minimum 1.5" thick	1or 2 with 6	$1:1.78 \text{ ft}^2$

Note: All insulation shall have preliminary attachment prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive, Single-

Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum 1.5 in.

heat weld.

Or

UltraPly TPO XR roof cover is adhered with XR Stick or I.S.O. Spray R applied

in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressures:** -67.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 61 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 15/32" plywood attached to structural supports spaced a maximum

24" o.c. with 0.113" ring shank nails spaced 6" o.c. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 144 lbf. when tested with Firestone All Purpose Fasteners or Heavy Duty Fasteners installed through to

the deck in accordance with TAS 105.

System Type C(38): Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

<b>Bottom Insulation Layer (Optional)</b>	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA		
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
RESISTA	•	·
Minimum 1" thick	1or 2 with 6	1:1.60 ft <sup>2</sup>
ISO 95 + GL, ISOGARD HD Composite		
Minimum 1.5" thick	1or 2 with 6	$1:1.60 \text{ ft}^2$

Note: All insulation shall have preliminary attachment prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive, Single-

Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum 1.5 in.

heat weld.

Or

UltraPly TPO XR roof cover is adhered with XR Stick or I.S.O. Spray R applied

in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressures:** -45 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 62 of 116

**Deck Description:** Minimum 15/32" plywood attached to structural supports spaced a maximum

24" o.c. with 0.113" ring shank nails spaced 6" o.c. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 160 lbf. when tested with Firestone All Purpose or Heavy Duty fasteners installed through to the deck in

accordance with TAS 105.

**System Type C(39):** Membrane adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA Minimum 1/2" thick	NA	N/A
Top Insulation Layer	Insulation Fasteners	Fastener
Top Insulation Layer	(Table 3)	Density/ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum-Fib	er Roof Board	
Minimum 1/4" thick	1 or 2 with 6	1:1.78 ft <sup>2</sup>
RESISTA Minimum 1" thick	1 or 2 with 6	1:1.78 ft <sup>2</sup>
ISO 95+ GL, ISOGARD HD Composite Minimum 1.5" thick	1 or 2 with 6	1:1.78 ft <sup>2</sup>

Note: Insulation layer shall be mechanically attached with fasteners and density described. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a

minimum 1.5 in. heat weld.

Or

UltraPly TPO XR (over SECUROCK and DensDeck only) roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a rate of 70-90 ft²/gal to the substrate only.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 63 of 116

**Deck Description:** Minimum 15/32" plywood attached to structural supports spaced a maximum

24" o.c. with 0.113" ring shank nails spaced 6" o.c. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 214 lbf. when tested with Firestone All Purpose or Heavy Duty fasteners installed through to the deck in

accordance with TAS 105.

**System Type C(40):** Membrane adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA	,	v
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
RESISTA, ISOGARD HD Composite		
Minimum 1-1/2" thick	1 or 2 with 6	1:1.78 ft <sup>2</sup>
ISO 95+ GL Minimum 2" thick	1 or 2 with 6	1:1.78 ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum Fiber Roof Boa Minimum ½" thick	ord 1 or 2 with 6	1:1.78 ft <sup>2</sup>

Note: Insulation layer shall be mechanically attached with fasteners and density described. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive.

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with

a minimum 1.5 in. heat weld.

Or

UltraPly TPO XR (over SECUROCK and DensDeck only) roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a rate of 70-90 ft²/gal to the substrate only.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 64 of 116

**Deck Description:** Minimum 15/32" plywood attached to structural supports spaced a maximum

24" o.c. with 0.113" ring shank nails spaced 6" o.c at the perimeter and 12" o.c. in the field of each board. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 144 lbf. when tested with Firestone All Purpose or Heavy Duty fasteners installed through to the deck in accordance with TAS 105.

**System Type C(41):** Membrane adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft2
ISO 95+ GL, RESISTA		
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft2
SECUROCK Gypsum-Fiber Roof Board	, ,	·
Minimum ¼" thick	1 or 2 with 6	1:1.60 ft2
DensDeck Prime Minimum ½" thick	1 or 2 with 6	1:1.60 ft2
RESISTA		
Minimum 1" thick	1 or 2 with 6	1:1.60 ft2
ISO 95+ GL, ISOGARD HD Composite		
Minimum 1½" thick	1 or 2 with 6	1:1.60 ft2

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft2/gallon (120 ft2/gallon to both the underside of membrane and

the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-

120ft2/gallon. The roof cover side and end laps are sealed with a minimum 1.5 in. heat

weld. Or

UltraPly TPO XR (over SECUROCK and DensDeck only) roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a rate of 70-90 ft2/gal to the substrate only.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 65 of 116

Single Ply, TPO **Membrane Type:** 

Deck Type 7I: Recover, Insulated

Minimum 15/32" plywood attached to structural supports spaced a maximum **Deck Description:** 

> 24" o.c. with 0.113" ring shank nails spaced 6" o.c. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 240 lbf. when tested with Firestone All Purpose or Heavy Duty fasteners installed through to the deck in

accordance with TAS 105.

Membrane adhered over mechanically fastened insulation. System Type C(42):

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

**Insulation Laver Insulation Fasteners Fastener** Density/ft<sup>2</sup> (Table 3) **ISOGARD HD Composite** Minimum 1.5" thick 1:2.67 ft<sup>2</sup> 1 or 2 with 6

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft<sup>2</sup>/gallon (120 ft<sup>2</sup>/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft<sup>2</sup>/gallon. The roof cover side and end laps are sealed with a

minimum 1.5 in. heat weld.

UltraPly TPO XR roof cover is adhered with XR Stick or I.S.O. Spray R applied

in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

-45 psf. (See General Limitation #7) Pressure:



NOA No.: 14-0606.04 **Expiration Date: 02/03/20** Approval Date: 05/26/16

Page 66 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 15/32" plywood attached to structural supports spaced a maximum

24" o.c. with 0.113" ring shank nails spaced 6" o.c. at the perimeter and 12" o.c. in the field of each board. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 224 lbf. when tested with Firestone All Purpose or Heavy Duty fasteners installed through to the deck in accordance with TAS 105.

System Type C(43): Membrane adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
RESISTA, ISO 95+ GL	( ,	
Minimum 1/2" thick	NA	NA
Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
SECUROCK Gypsum-Fiber Roof Board		
Minimum 1/2" thick	1 or 2 with 6	1:2.13 ft <sup>2</sup>

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with

a minimum 1.5 in. heat weld.

Or

UltraPly TPO XR (over SECUROCK and DensDeck only) roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a rate of 70-90 ft²/gal

to the substrate only.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to

1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -52.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 67 of 116

**Deck Description:** Minimum 15/32" plywood attached to structural supports spaced a maximum

24" o.c. with 0.113" ring shank nails spaced 6" o.c. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 187 lbf. when tested with Firestone All Purpose and Heavy Duty fasteners installed through to the deck in

accordance with TAS 105.

System Type C(44): Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA	,	•
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
•	(Table 3)	Density/ft <sup>2</sup>
ISOGARD HD COMPOSITE		
Minimum 1-1/2" thick	1 or 2 with 6	$1:1.78 \text{ ft}^2$
DensDeck; DensDeck Prime, SECUROCK Gypsum-Fibe	er Roof Board	
Minimum ½" thick	1 or 2 with 6	1:1.78 ft <sup>2</sup>
RESISTA		
Minimum 2" thick	1 or 2 with 6	1:1.78 ft <sup>2</sup>

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a

minimum 1.5 in. heat weld.

Or

UltraPly TPO XR (over SECUROCK and DensDeck only) roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a rate of 70-90

ft<sup>2</sup>/gal to the substrate only.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -52.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 68 of 116

**Deck Description:** Minimum 19/32" plywood attached to structural supports spaced a maximum

24" o.c. with 0.113" ring shank nails spaced 6" o.c. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 234 lbf. when tested with Firestone All Purpose or Heavy Duty fasteners installed through to the deck in

accordance with TAS 105.

**System Type C(45):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA		
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISOGARD HD		
Minimum 1/2" thick	1 or 2 with 6	1:2.13 ft <sup>2</sup>
ISO 95+ GL, RESISTA		
Minimum 1" thick	1 or 2 with 6	1:2.13 ft <sup>2</sup>
DensDeck; DensDeck Prime, SECUROCK Gypsum-Fil	oer Roof Board	
Minimum 1/4" thick	1 or 2 with 6	1:2.13 ft <sup>2</sup>
ISOGARD HD Composite		
Minimum 1.5" thick	1 or 2 with 6	1:2.13 ft <sup>2</sup>

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft2/gallon (120 ft2/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft2/gallon. The roof cover side and end laps are sealed with

a minimum 1.5 in. heat weld.

Or

UltraPly TPO XR (over SECUROCK and DensDeck only) roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a rate of 70-90

ft2/gal to the substrate only.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -55 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 69 of 116

**Deck Description:** Minimum 19/32" plywood Minimum 19/32" plywood attached to structural

supports spaced a maximum 24" o.c. with 0.113" ring shank nails spaced 6" o.c. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of

280 lbf. when tested with Firestone All Purpose or Heavy Duty fasteners

installed through to the deck in accordance with TAS 105.

**System Type C(46):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA	,	v
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISOGARD HD COMPOSITE	,	·
Minimum 1.5" thick	1 or 2 with 6	$1:2.67 \text{ ft}^2$
DensDeck Prime, SECUROCK Gypsum-Fiber Roof Boar Minimum ½" thick	rd 1 or 2 with 6	1:2.67 ft <sup>2</sup>
RESISTA Minimum 2" thick	1 or 2 with 6	1:2.67 ft <sup>2</sup>

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft2/gallon (120 ft2/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft2/gallon. The roof cover side and end laps are sealed with

a minimum 1.5 in. heat weld.

Or

UltraPly TPO XR (over SECUROCK and DensDeck only) roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a rate of 70-90

ft2/gal to the substrate only.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -52.5 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 70 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 15/32" plywood attached to structural supports spaced a maximum

24" o.c. with 0.113" ring shank nails spaced 6" o.c. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 240 lbf. when tested with Firestone All Purpose or Heavy Duty fasteners installed through to the deck in

accordance with TAS 105.

System Type C(47): Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

<b>Bottom Insulation Layer (Optional)</b>	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA		
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
SECUROCK Gypsum-Fiber Roof Board	,	·
Minimum ½" thick	1 or 2 with 6	1:1.78 ft <sup>2</sup>
ISOGARD HD Composite		
Minimum 1.5" thick	1 or 2 with 6	$1:1.78 \text{ ft}^2$

Note: All insulation shall have preliminary attachment prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

Or

UltraPly TPO XR (over SECUROCK only) roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a rate of 70-90 ft<sup>2</sup>/gal to the substrate only.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressures:** -67.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 71 of 116

**Deck Description:** Minimum 22 ga. steel decking attached to steel supports spaced maximum 6 ft.

o.c. or concrete \*The deck should record a Minimum Characteristic Resistance Force (MCRF) of 288 lbf. When tested with Firestone All Purpose (steel only), Firestone Heavy-Duty fasteners, or Firestone Concrete Drive (concrete only) in

accordance with TAS 105.

System Type C(48): All layers of insulation simultaneously attached; membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA	,	·
Minimum 1" thick	N/A	N/A
<b>Top Insulation Layer</b>	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISOGARD HD Composite		
Minimum 1.5" thick	1 or 2 with 6 (steel)	See Below
	1 or 4 with 6 (concrete)	

Note: All layers shall be simultaneously fastened. See top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions. If larger panels are used, the number of fasteners shall be increased using the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive, Single-

Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of 60ft²/gallon (120 ft²/gallon to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of 100-120ft²/gallon. The roof cover side and end laps are sealed with a minimum 1.5 in.

heat weld.

Or

UltraPly TPO XR roof cover is adhered with XR Stick or I.S.O. Spray R applied

in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** -67.5 psf attached at a rate of 1:2.13 ft<sup>2</sup> (See General Limitation #7) **Pressure:** -75 psf attached at a rate of 1:1.78 ft<sup>2</sup> (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 72 of 116

Single Ply, TPO **Membrane Type:** 

Deck Type 7I: Recover, Insulated

**Deck Description:** Minimum 15/32" plywood attached to structural supports spaced a maximum

> 24" o.c. with 0.113" ring shank nails spaced 6" o.c. at the perimeter and 12" o.c. in the field of the board. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 600 lbf. when tested with Firestone Heavy Duty Plus fasteners installed through to the deck into the wood supports in accordance

with TAS 105.

System Type C(49): All layers of insulation simultaneously attached; membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA	,	·
Minimum 1" thick	N/A	N/A
Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
DensDeck, Dens Deck Prime, SECUROCK G	ypsum-Fiber Roof Board,	•
Minimum 1/4" thick	1 with 9	See below
RESISTA		
Minimum 1" thick	1 with 9	See below
ISO 95 + GL, ISOGARD HD Composite		
Minimum 1½" thick	1 with 9	See below

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. A minimum insulation thickness of 1 inch must be used with UltraPly InvisiWeld Plates.

Membrane: UltraPly TPO (min. 0.045") is placed over the insulation and mechanically

> secured to the through deck into the structural supports with Firestone Heavy Duty fasteners and UltraPly TPO InvisiWeld Plates spaced max. 6" o.c., in rows max. 96" o.c. Roof cover 2" wide side laps are sealed with a 1.5" min. wide heat weld

placed along the outer edge of the lap.

**Maximum Design** 

Pressure: -75 psf. (See General Limitation #7)



NOA No.: 14-0606.04 **Expiration Date: 02/03/20** Approval Date: 05/26/16 Page 73 of 116

Membrane Type: Single Ply, TPO

Deck Type 7I: Recover, Insulated

**Deck Description:** Minimum 22 ga. steel deck attached to structural supports spaced a maximum 6-

ft o.c. or concrete. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 187 lbf. when tested with Firestone All Purpose Fasteners (steel only), Heavy Duty, or Concrete Drive (concrete only) installed through to the deck in accordance with TAS 105. Existing roof shall be a minimum 1/2"

thick.

System Type C(50): Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA	, ,	·
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum-Fiber Roo	of Board	
Minimum ½" thick	1 or 2 with 6 (steel) 1 or 4 with 6 (concrete)	1:1.78 ft <sup>2</sup>
RESISTA		
Minimum 2" thick	1 or 2 with 6 (steel) 1 or 4 with 6 (concrete)	1:1.78 ft <sup>2</sup>

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO roof cover is fully adhered with UltraPly Bonding Adhesive,

Single-Ply LVOC Bonding Adhesive, or Single-Ply LVOC Bonding Adhesive 1168 applied at a rate of  $60 \mathrm{ft^2/gallon}$  (120  $\mathrm{ft^2/gallon}$  to both the underside of membrane and the substrate) or Water Based Bonding Adhesive P applied at a rate of  $100\text{-}120 \mathrm{ft^2/gallon}$ . The roof cover side and end laps are sealed with a minimum

1.5 in. heat weld.

Or

UltraPly TPO XR (over SECUROCK and DensDeck only) roof cover is fully adhered to with hot asphalt or Owens Corning PermaMop applied in the EVT range at a rate of 25-30 lbs./sq. or XR Bonding Adhesive at a rate of 70-90 ft²/gal

to the substrate only.

Or

UltraPly TPO XR is adhered with XR Stick or I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced a maximum 12" o.c.

**Maximum Design** 

**Pressure:** -52.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 74 of 116

Single Ply, TPO **Membrane Type:** 

Deck Type 7I: Recover, Insulated

**Deck Description:** Steel (Existing Structural Non-Insulated Metal Roof Panel Assembly)

Membrane mechanically attached over preliminary fastened insulation. **System Type D(1):** 

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer: To be placed between the ribs or over panels of existing structural metal roof system. ISO 95+ GL	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
Minimum 1" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL	,	v
Minimum 1.5" thick	N/A	N/A
ISOGARD HD		
Minimum ½" thick	N/A	N/A
DensDeck, DensDeck Prime, SECUROCK Gypsum-Fibe Roof Board	er Roof Board, SECURO	CK Glass-Mat
Minimum ¼" thick	N/A	N/A
Plywood		
Minimum 19/32" thick	N/A	N/A

Note: All insulation shall have preliminary attachment prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: UltraPly TPO shall be mechanically fastened to the deck through the insulation to

> 16 ga. purlins spaced 7.5 ft. maximum with Firestone HD Seam Plates and Purlin Fasteners. Fastener rows are spaced at a maximum 7.5 ft. o.c. and fasteners are spaced 12" o.c. within the 6" wide roof cover side laps. (Areas where the metal panels do not lay flush on purlin shall have a 1/4" pilot pre-drilled into the panel prior to fastening) The minimum 6 in. wide roof cover side laps are sealed with a

minimum 1.5 in. wide heat weld on the outside edge of the lap.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #7)



NOA No.: 14-0606.04 **Expiration Date: 02/03/20** Approval Date: 05/26/16 Page 75 of 116

Membrane Type: Single Ply, TPO

Deck Type 7I: Recover, Insulated

**Deck Description:** Steel (Existing Structural Non-Insulated Metal Roof Panel Assembly)

System Type D(2): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer: To be placed between the ribs or over panels of existing structural metal roof system.

Fastener (Table 3) Density/ft²

**ISO 95+ GL** 

Minimum 1.0" thick N/A N/A

Top Insulation Layer Insulation Fasteners (Table 3) Density/ $ft^2$ 

ISO 95+ GL

Minimum 1.5" thick N/A N/A

ISOGARD HD

Minimum ½" thick N/A N/A

DensDeck, DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat

Fiber Roof Board

Minimum ¼" thick N/A N/A

**Plywood** 

Minimum 19/32" thick N/A N/A

Note: All insulation shall have preliminary attachment prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly QuickSeam R.M.A. Strips shall be mechanically attached over the top

insulation to the purlins with Coiled Metal Batten Bar and Purlin Fasteners spaced 6" o.c. along the batten strips. UltraPly QuickSeam R.M.A. Strips are spaced 10 ft. o.c. (centered directly over purlins). (Areas where the metal panels do not lay flush on purlin shall have a ¼" pilot pre-drilled into the panel prior to fastening) UltraPly TPO is adhered to each UltraPly QuickSeam R.M.A. Strip by priming the underside of the roof cover, at the strip locations, with Single-Ply QuickPrime Primer and placing the primed portion of the roof cover onto the strips. Minimum 2" wide side laps are sealed with a minimum 1.5" wide heat weld placed along the

outside edge of lap.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 76 of 116 Membrane Type: Single Ply, TPO

Deck Type 7I: Recover, Insulated

**Deck Description:** Steel (Existing Structural Non-Insulated Metal Roof Panel Assembly) **System Type D(3):** Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer: To be placed between the ribs or over panels of existing structural metal roof	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
system. ISO 95+ GL Minimum 1" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL Minimum 1.5" thick	N/A	N/A

ISOGARD HD

Minimum ½" thick N/A N/A

 $Dens Deck; Dens Deck\ Prime, SECUROCK\ Gypsum-Fiber\ Roof\ Board, SECUROCK\ Glass-Mat$ 

Fiber Roof Board

Minimum 1/4" thick N/A N/A

Plywood

Minimum 19/32" thick N/A N/A

Note: All insulation shall have preliminary attachment prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly TPO shall be mechanically attached over the top insulation to the purlins

spaced 142" maximum with Firestone HD Seam Plates and Purlin Fasteners. Fastener rows are placed at a maximum 142" o.c. and fasteners are spaced 6" o.c. and centered within the 6" wide roof cover side laps. (Areas where the metal panels do not lay flush on purlin shall have a ¼" pilot pre-drilled into the panel prior to fastening) Minimum 6" wide side laps are sealed with a minimum 1.5"

wide heat weld on the outside edge of the lap.

**Maximum Design** 

**Pressure:** -52.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 77 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 33 steel deck secured to supports space at maximum 6 ft.

o.c. with ITW Buildex Traxx/5 spaced at 6" o.c. Side lap fastened with ITW

Buildex Traxx/1 spaced at 24" o.c.

**System Type D(4):** Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations (not to exceed 1" thick)

Insulation Layer Insulation Fasteners Fastener (Table 3) Fastener

DensDeck, SECUROCK Gypsum-Fiber Roof Board SECUROCK Glass-Mat Fiber Roof Board Minimum 1/4" thick N/A N/A

ISO 95+ GL, RESISTA, ISOGARD HD

Minimum ½" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO is placed over the insulation and mechanically secured within the 6"

wide laps with Firestone Heavy Duty Plus and Firestone HD Plus Seam Plates spaced 12" o.c. Side laps are spaced a maximum of 90" o.c. and sealed with a

minimum 1.5" wide heat weld on the outside edge of the lap.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16

Page 78 of 116

Single Ply, TPO **Membrane Type:** 

Deck Type 7I: Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 80 steel deck secured to supports space at maximum 6 ft.

o.c. with ITW Buildex Traxx/5 spaced at 6" o.c. Side lap fastened with ITW

Buildex Traxx/1 spaced at 24" o.c.

Or

Concrete.

System Type D(5): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations (not to exceed 1" thick for steel deck or 8" thick for ISO 95+ GL on concrete).

**Insulation Layer Insulation Fasteners** Fastener (Table 3) Density/ft<sup>2</sup> DensDeck, SECUROCK Gypsum-Fiber Roof Board SECUROCK Glass-Mat Fiber Roof Board Minimum 1/4" thick N/A N/A

ISO 95+ GL, RESISTA, ISOGARD HD

Minimum ½" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

Membrane: UltraPly TPO is placed over the insulation and mechanically secured within the 6"

> wide laps with Firestone Heavy-Duty and Firestone HD Seam Plates spaced 12" o.c. Side laps are spaced a maximum 90" o.c. and sealed with a minimum 1.5"

wide heat weld on the outside edge of the lap.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #7)



NOA No.: 14-0606.04 **Expiration Date: 02/03/20** Approval Date: 05/26/16

Page 79 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade E steel deck secured to supports space at maximum 6 ft.

o.c. with ITW Buildex Traxx/5 spaced at 6" o.c. Side lap fastened with ITW

Buildex Traxx/1 spaced at 24" o.c.

Or

Concrete.

System Type D(6): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations (not to exceed 1" thick for steel deck or 8" thick for ISO 95+ GL on concrete).

Insulation Layer Insulation Fasteners Fastener (Table 3) Pensity/ft²

DensDeck, SECUROCK Gypsum-Fiber Roof Board SECUROCK Glass-Mat Fiber Roof Board Minimum ¼" thick N/A N/A

ISO 95+ GL, RESISTA, ISOGARD HD

Minimum ½" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO is placed over the insulation and mechanically secured within the 6"

wide laps.

Rows at 114" o.c.: Membrane secured to the deck with Firestone Heavy-Duty and Firestone HD

Seam Plates spaced 6" o.c. Side laps are sealed with a minimum 1.5" wide heat

weld on the outside edge of the lap.

Rows at 142" o.c.: Membrane secured to the deck with Firestone Heavy-Duty and Firestone HD

Seam Plates spaced 6" o.c. Side laps are sealed with a minimum 1.5" wide heat

weld on the outside edge of the lap.

**Maximum Design** 

**Pressure:** -52.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 80 of 116

Single Ply, TPO **Membrane Type:** 

Deck Type 7I: Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 33 steel deck secured to supports space at maximum 6 ft.

o.c. with Traxx/5 spaced at 6" o.c. Side lap fastened with Traxx/1 spaced at 24"

o.c. Or

Concrete

System Type D(7): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations (not to exceed 1" thick for steel deck or 8" thick for ISO 95+ GL on concrete).

**Insulation Fasteners Insulation Layer Fastener** (Table 3) Density/ft<sup>2</sup> DensDeck, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Fiber Roof Board Minimum 1/4" thick N/A N/A ISO 95+ GL, RESISTA, ISOGARD HD Minimum 1/2" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

Membrane: UltraPly TPO is placed over the insulation and mechanically secured within the 6"

> wide laps. Membrane secured to the deck with Firestone Heavy-Duty spaced 6" o.c. through the Firestone Polymer Batten Strip spaced a maximum of 114" o.c. Side laps are sealed with a minimum 5" wide heat weld the batten and fasteners.

**Maximum Design** 

**Pressure:** -52.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 **Expiration Date: 02/03/20** Approval Date: 05/26/16

Page 81 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 80 steel deck secured to supports space at maximum 6 ft.

o.c. with Traxx/5 spaced at 6" o.c. Side lap fastened with Traxx/1 spaced at 24"

o.c. Or

Concrete

System Type D(8): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations (not to exceed 1" thick for steel deck or 8" thick for ISO 95+ GL on concrete).

Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft<sup>2</sup>

DensDeck, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Fiber Roof Board Minimum 1/4" thick N/A N/A

ISO 95+ GL, RESISTA, ISOGARD HD

Minimum ½" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO is placed over the insulation and mechanically secured to the deck

Firestone within the 6" wide side laps.

Rows at 114" o.c.: Firestone Heavy-Duty fastened 6" o.c. through the Firestone Polymer Batten Strip.

Side laps are sealed with a 5" wide heat weld which encapsulates the batten and

fasteners.

Rows at 142" o.c.: Firestone Heavy-Duty fasetened 6" o.c. through the Metal Batten Bar. Side laps

are sealed with a 5" wide heat weld which encapsulates the batten and fasteners.

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 82 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 33, Type B steel deck secured to supports space at

maximum 6 ft. o.c. with Traxx/5 spaced at 6" o.c. Side lap fastened with

Traxx/1 spaced at 24" o.c.

**System Type D(9):** Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations (not to exceed 1" thick).

Insulation Layer (Table 3) Fastener (Table 3) Density/ft²

DensDeck, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Fiber Roof Board Minimum ¼" thick N/A N/A

ISO 95+ GL, RESISTA, ISOGARD HD

Minimum ½" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO is placed over the insulation and mechanically secured to the deck

within the 6" wide side laps with Firestone Heavy Duty Plus and Firestone HD Seam Plates at 6" o.c. Side laps are spaced at maximum 142" o.c. and sealed with

a 1.5" min. wide heat weld placed along the outer edge of the lap.

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16

Page 83 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 33 steel deck secured to supports space at maximum 6 ft.

o.c. with Traxx/5 spaced at 6" o.c. Side lap fastened with Traxx/1 spaced at 24"

o.c.

System Type D(10): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations (not to exceed 1").

Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft<sup>2</sup>

DensDeck, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Fiber Roof Board Minimum 1/4" thick N/A N/A

ISO 95+ GL, RESISTA, ISOGARD HD

Minimum ½" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO is placed over the insulation and mechanically secured to the deck

within the 6" wide side laps.

Rows at 90" o.c.: Firestone Heavy-Duty fastened 6" o.c. through the Firestone Polymer Batten Strip.

Side laps are sealed with a 5" wide heat weld which encapsulates the batten and

fasteners.

Rows at 114" o.c.: Firestone Heavy Duty Plus and Firestone HD Plus Seam Plates fastened 6" o.c.

Side laps are sealed with a 1.5" wide heat placed along the outside edge of the lap.

**Maximum Design** 

**Pressure:** -67.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16

Page 84 of 116

Single Ply, TPO **Membrane Type:** 

Deck Type 7I: Recover, Insulated

**Deck Description:** Concrete

Membrane mechanically attached over preliminary fastened insulation. System Type D(11):

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations (ISO 95+ GL maximum thickness is 8"; all others shall not exceed 1").

**Insulation Laver Insulation Fasteners** Fastener (Table 3) Density/ft<sup>2</sup> DensDeck, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Fiber Roof Board Minimum 1/4" thick N/A N/A ISO 95+ GL, RESISTA, ISOGARD HD

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

UltraPly TPO is placed over the insulation and mechanically secured to the deck **Membrane:** 

> Firestone within the 6" wide side laps with Firestone Heavy-Duty fastened 6" o.c. through the Firestone Polymer Batten Strip. Side laps are spaced a maximum of 90" o.c. and are sealed with a 5" wide heat weld which encapsulates the batten and

N/A

fasteners.

**Maximum Design** 

Minimum ½" thick

**Pressure:** -67.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 **Expiration Date: 02/03/20** Approval Date: 05/26/16

N/A

Page 85 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 80 steel deck secured to supports space at maximum 6 ft.

o.c. with Traxx/5 spaced at 6" o.c. Side lap fastened with Traxx/1 spaced at 24"

o.c. Or

Concrete

**System Type D(12):** Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations (not to exceed 1" thick for steel deck or 8" thick for ISO 95+ GL on concrete).

Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²
DensDeck, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Fiber Roof Board

Minimum <sup>1</sup>/<sub>4</sub>" thick N/A N/A

ISO 95+ GL, ISOGARD HD

Minimum ½" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO is placed over the insulation and mechanically secured to the deck

with Firestone Heavy-Duty or Concrete Drive (concrete deck only) and Metal Batten Bar or Firestone Heavy Duty Plus and Firestone Polymer Batten Strip (steel deck only) centered within the 6" wide side laps. Fasteners are spaced 6" o.c. along the batten bar. Batten rows are spaced at a maximum 114" o.c. Roof cover side laps are sealed with a 5" wide heat weld which encapsulates the batten and

fasteners.

**Maximum Design** 

**Pressure:** -75 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 86 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 33 steel deck secured to supports space at maximum 6 ft.

o.c. with Traxx/5 spaced at 6" o.c. Side lap fastened with Traxx/1 spaced at 24"

o.c.

System Type D(13): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations (not to exceed 1").

Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²
DensDeck, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Fiber Roof Board

Minimum <sup>1</sup>/<sub>4</sub>" thick N/A N/A

ISO 95+ GL, RESISTA, ISOGARD HD

Minimum ½" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO is placed over the insulation and mechanically secured to the deck

within the 6" wide side laps. Firestone Heavy Duty Plus fastened 6" o.c. through the Metal Batten Bar. Side laps are spaced a maximum of 90" o.c. and sealed with

a 5" wide heat weld which encapsulates the batten and fasteners.

**Maximum Design** 

**Pressure:** -82.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 87 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 80 steel deck secured to supports space at maximum 6 ft.

o.c. with two (2) Traxx/5 at each bearing point spaced at 6" o.c. Side lap

fastened with Traxx/1 spaced at 24" o.c.

Or

Concrete

**System Type D(14):** Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations (not to exceed 1" thick for steel deck or 8" thick for ISO 95+ GL on concrete).

Insulation Layer Insulation Fasteners (Table 3) Density/ft²

DensDeck, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Fiber Roof Board Minimum ¼" thick N/A N/A

ISO 95+ GL, RESISTA, ISOGARD HD

Minimum ½" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO is placed over the insulation and mechanically secured to the deck

within the 6" wide side laps. Firestone Heavy-Duty fastened 6" o.c. through the Firestone Polymer Batten Strip. Side laps are spaced a maximum 68" o.c. are sealed with a 5" wide heat weld which encapsulates the batten and fasteners.

**Maximum Design** 

**Pressure:** -82.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 88 of 116

Single Ply, TPO **Membrane Type:** 

Deck Type 7I: Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 80 steel deck secured to supports space at maximum 6 ft.

o.c. with Traxx/5 at each bearing point spaced at 6" o.c. Side lap fastened with

Traxx/1 spaced at 24" o.c.;

System Type D(15): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations (not to exceed 1" thick).

**Insulation Layer Insulation Fasteners Fastener** (Table 3) Density/ft<sup>2</sup> DensDeck, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Fiber Roof Board Minimum 1/4" thick N/A N/A ISO 95+ GL, RESISTA, ISOGARD HD Minimum 1/2" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

Membrane: UltraPly TPO is placed over the insulation and mechanically secured to the deck

> with Firestone Heavy Duty Plus and Firestone HD Plus Seam Plates spaced maximum 6" o.c. within the 6" wide side laps, in rows sapced a maximum 90" o.c. Roof cover side laps are sealed with a 5" wide heat weld which encapsulates the

row of plates and fasteners.

**Maximum Design** 

Pressure: -90 psf. (See General Limitation #7)

MIAMI-DADE COUNTY APPROVED

NOA No.: 14-0606.04 **Expiration Date: 02/03/20** Approval Date: 05/26/16 Page 89 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 80 steel deck secured to supports space at maximum 6 ft.

o.c. with Traxx/5 at each bearing point spaced at 6" o.c. Side lap fastened with

Traxx/1 spaced at 24" o.c.

Or

Concrete

**System Type D(16):** Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations (not to exceed 1" thick for steel deck or 8" thick for ISO 95+ GL on concrete).

Insulation LayerInsulation FastenersFastener(Table 3)Density/ft²DensDeck, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Fiber Roof BoardRoof Board

ISO 95+ GL, ISOGARD HD

Minimum 1/4" thick

Minimum ½" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO is placed over the insulation and mechanically secured to the deck

with Firestone Heavy-Duty or Concrete Drive (concrete only) and Firestone Coiled Metal Batten Bar centered within the 6" wide side laps. Fasteners are spaced 6" o.c. along the batten bar. Batten rows are spaced at a maximum 90" o.c. Roof cover side laps are sealed with a 5" wide heat weld which encapsulates the

N/A

batten and fasteners.

**Maximum Design** 

**Pressure:** -90 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 90 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 80 steel deck secured to supports space at maximum 6 ft.

o.c. with Traxx/5 at each bearing point spaced at 6" o.c. Side lap fastened with

Traxx/1 spaced at 24" o.c.

System Type D(17): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations (not to exceed 1" thick)

Insulation Layer Insulation Fasteners (Table 3) Density/ft²

DensDeck, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Fiber Roof Board Minimum ¼" thick N/A N/A

ISO 95+ GL, ISOGARD HD

Minimum ½" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO is placed over the insulation and mechanically secured to the deck

with Firestone Heavy Duty Plus and Metal Batten Bar centered within the 6" wide side laps. Fasteners are spaced 6" o.c. along the batten bar. Batten rows are spaced at a maximum 90" o.c. Roof cover side laps are sealed with a 5" wide heat weld

which encapsulates the batten and fasteners.

**Maximum Design** 

**Pressure:** -97.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16

Page 91 of 116

Single Ply, TPO **Membrane Type:** 

Deck Type 7I: Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 80 steel deck secured to supports space at maximum 6 ft.

o.c. with two (2) Traxx/5 at each bearing point spaced at 6" o.c. Side lap

fastened with Traxx/1 spaced at 24" o.c.

System Type D(18): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations (not to exceed 1" thick).

**Insulation Layer Insulation Fasteners** Fastener (Table 3) Density/ft<sup>2</sup> DensDeck, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Fiber Roof Board Minimum 1/4" thick N/A N/A ISO 95+ GL, ISOGARD HD Minimum ½" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

Membrane: UltraPly TPO is placed over the insulation and mechanically secured to the deck

with Firestone Heavy Duty Plus and 3/4" wide Polymer Batten Strips 6" o.c. along the batten bar in rows spaced at a 142 in. o.c. and along one intermediate field row centered in the field of the sheet. Roof cover side laps are sealed with a 5" wide heat weld which encapsulates the batten and fasteners. The intermediate field row batten bar is sealed with a min. 5" wide strip of UltraPly TPO sealed with a min.

1.5" wide heat weld on each side of the batten.

**Maximum Design** 

**Pressure:** -135 psf. (See General Limitation #7)



NOA No.: 14-0606.04 **Expiration Date: 02/03/20** Approval Date: 05/26/16

Page 92 of 116

Membrane Type: Single Ply, TPO

Deck Type 7I: Recover, Insulated

Deck Description: Steel (Existing Structural Non-Insulated Metal Roof Panel Assembly)

System Type D(19): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer: To be placed between the ribs or over panels of existing structural metal roof system.

Insulation Fasteners (Table 3) Density/ft²

ISO 95+ GL

Minimum 1" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener

ISO 95+ GL

Minimum 1.5" thick N/A N/A

ISOGARD HD

Minimum ½" thick N/A N/A

DensDeck, DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Fiber Roof Board

Minimum 1/2" thick N/A N/A

**Plywood** 

Minimum 19/32" thick N/A N/A

Note: All insulation shall have preliminary attachment prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** UltraPly QuickSeam R.M.A. Strips shall be mechanically attached over the top

insulation to the purlins with Coiled Metal Batten Bar and Purlin Fasteners spaced 6" o.c. along the batten strips. UltraPly QuickSeam R.M.A. Strips are spaced a maximum 10 ft. o.c. (centered directly over purlins). (Areas where the metal panels do not lay flush on purlin shall have a ¼" pilot pre-drilled into the panel prior to fastening) UltraPly TPO is adhered to each UltraPly QuickSeam R.M.A. Strip by priming the underside of the roof cover, at the strip locations, with Single-Ply QuickPrime Primer and placing the primed portion of the roof cover onto the strips. Minimum 2" wide side laps are sealed with a minimum 1.5" wide heat

(Table 3)

weld placed along the outside edge of lap.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 93 of 116

Density/ft<sup>2</sup>

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. steel deck with supports spaced maximum 6 ft. o.c. or concrete

\*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 570 lbf. when tested with Firestone Heavy-Duty fasteners installed through to

the deck in accordance with TAS 105.

System Type D(20): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL	,	·
Minimum ½" thick	N/A	N/A
RESISTA		
Minimum 1" thick	N/A	N/A
ISOGARD HD Composite		
Minimum 2" thick	N/A	N/A
ISOGARD HD		
Minimum 1/2" thick	N/A	N/A
DensDeck, Dens Deck Prime, SECUROCK Gypsum-	Fiber Roof Board, SECURC	OCK Glass-Mat
Fiber Roof Board		
Minimum <sup>1</sup> / <sub>4</sub> " thick	N/A	N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO (min. 0.060") is placed over the insulation and mechanically

secured to the deck with Firestone Heavy-Duty and Firestone HD Seam Plates spaced max. 6" o.c. within the 6" wide side laps, in rows max, 114". o.c. Roof cover side laps are sealed with a 1.5" wide heat weld placed along the outside

edge of the lap..

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 94 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. steel deck with supports spaced maximum 6 ft. o.c. \*The deck

shall record a Minimum Characteristic Resistance Force (MCRF) of 641 lbf. when tested with Firestone Heavy Duty Plus fasteners installed through to the

deck in accordance with TAS 105.

System Type D(21): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>
DensDeck, Dens Deck Prime, SECUROCK Gypsum-l	Fiber Roof Board, SECURC	OCK Glass-Mat
Fiber Roof Board		
Minimum 1/4" thick	N/A	N/A
RESISTA, ISO 95+ GL		
Minimum 1" thick	N/A	N/A
ISOGARD HD Composite		
Minimum 1½" thick	N/A	N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO is placed over the insulation and mechanically secured to the deck

with Firestone Heavy Duty Plus and Firestone HD Plus Seam Plates spaced max. 6" o.c. within the 6" wide side laps, in rows max, 114" o.c. Roof cover side laps are sealed with a 1.5" min. wide heat weld placed along the outer edge of the lap.

**Maximum Design** 

**Pressure:** -67.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 95 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. steel deck with supports spaced maximum 6 ft. o.c. or concrete.

Existing roof shall be a minimum 1" in total thickness. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 499 lbf. when tested with Firestone Heavy Duty fasteners installed through to the deck in accordance with

TAS 105.

System Type D(22): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA	,	v
Minimum 1" thick	N/A	N/A
<b>Top Insulation Layer</b>	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
DensDeck, Dens Deck Prime, SECUROCK (	<b>Gypsum-Fiber Roof Board, SECURO</b>	OCK Glass-Mat
Fiber Roof Board		
Minimum 1/4" thick	N/A	N/A
ISOGARD HD		
Minimum ½" thick	N/A	N/A
RESISTA		
Minimum 1" thick	N/A	N/A
ISOGARD HD Composite		
Minimum 2" thick	N/A	N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO (min. 0.060") is placed over the insulation and mechanically

secured to the deck with Firestone Heavy-Duty and Firestone HD Seam Plates spaced max. 6" o.c. within the 6" wide side laps, in rows max, 114" o.c. Roof cover side laps are sealed with a 1.5" wide heat weld which encapsulates the row

of plates and fasteners.

**Maximum Design** 

**Pressure:** -52.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 96 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 15/32 plywood deck secured with 0.113" ring shank nails spaced 6"

o.c. at the supports spaced maximum 2 ft. o.c. \*The deck shall record a

Minimum Characteristic Resistance Force (MCRF) of 356 lbf. when tested with Firestone Heavy-Duty fasteners installed through to the deck in accordance with

TAS 105.

System Type D(23): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
ISO 95+ GL, RESISTA	,	v
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
DensDeck, Dens Deck Prime, SECUROCK G	Sypsum-Fiber Roof Board, SECURO	OCK Glass-Mat
Fiber Roof Board		
Minimum ¼" thick	N/A	N/A
ISOGARD HD		
Minimum ½" thick	N/A	N/A
RESISTA		
Minimum 1" thick	N/A	N/A
ISOGARD HD Composite		
Minimum 1½" thick	N/A	N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO (min. 0.060") is placed over the insulation and mechanically

secured to the deck with Firestone Heavy-Duty and Firestone HD Seam Plates spaced max. 5" o.c. within the 6" wide side laps, in rows max, 114" o.c. Roof cover side laps are sealed with a 1.5" min. wide heat weld placed along the outer

edge of the lap.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 97 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. Grade 33, Type B steel deck secured to supports space at

maximum 6 ft. o.c. with Traxx/5 spaced at 6" o.c. Side lap fastened with

Traxx/1 spaced at 24" o.c.

**System Type D(24):** Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations

Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>
DensDeck, SECUROCK Gypsum-Fiber Roof Boar	d, SECUROCK Glass-Mat	Fiber Roof Board
Minimum ¼" thick	N/A	N/A
ISO 95+ GL, RESISTA		
Minimum 1" thick	N/A	N/A
ISOGARD HD		
Minimum ½" thick	N/A	N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO is placed over the insulation and mechanically secured within the 6"

wide laps. Membrane secured to the deck with Firestone Heavy-Duty and Firestone HD Seam Plates 6" o.c. in rows spaced a maximum of 114" o.c. Side laps are sealed with a minimum 1.5" wide heat weld placed along the outside edge

of the lap.

**Maximum Design** 

**Pressure:** -52.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 98 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. steel deck with supports spaced maximum 6 ft. o.c. or

structural concrete. Existing roof shall be a minimum 1" in total thickness. \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 445 lbf. when tested with Firestone Heavy-Duty fasteners installed through to the

deck in accordance with TAS 105.

System Type D(25): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>

ISO 95+ GL, RESISTA

Minimum ½" thick N/A N/A

DensDeck, Dens Deck Prime, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat

Fiber Roof Board

Minimum ¼ " thick N/A N/A

**ISOGARD HD Composite** 

Minimum 2" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO is placed over the insulation and mechanically secured to the deck

with Firestone Heavy Duty and Firestone HD Seam Plates spaced max. 6" o.c. within the 7" wide side laps, in rows max, 89" o.c. Roof cover side laps are sealed with a 1.5" minimum wide heat weld placed along the outer edge of the lap.

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 99 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Minimum 22 ga. steel deck with supports spaced maximum 6 ft. o.c. \*The deck

shall record a Minimum Characteristic Resistance Force (MCRF) of 675 lbf. when tested with Firestone Heavy-Duty Plus fasteners installed through to the

deck in accordance with TAS 105.

System Type D(26): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer Insulation Fasteners Fastener (Table 3) Fastener

ISO 95+ GL, RESISTA

Minimum 1" thick N/A N/A

DensDeck, Dens Deck Prime, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat

Fiber Roof Board

Minimum ¼ " thick N/A N/A

**ISOGARD HD Composite** 

Minimum 1.5" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO is placed over the insulation and mechanically secured to the deck

with Firestone Heavy Duty Plus fasteners and Firestone HD Plus Seam Plates spaced max. 12" o.c. within the 6" wide side laps, in rows max. 90" o.c. Roof cover side laps are sealed with a 1.5" minimum wide heat weld placed along the

outer edge of the lap.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 100 of 116

**Deck Type 7I:** Recover, Insulated

**Deck Description:** Min. 300 psi Celcore Lightweight Concrete cast over minimum 22 ga. steel deck

with supports spaced maximum 6 ft. o.c. or concrete \*The deck shall record a Minimum Characteristic Resistance Force (MCRF) of 499 lbf. when tested with Firestone Heavy-Duty fasteners installed through to the deck in accordance with

TAS 105.

System Type D(27): Membrane mechanically attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer Insulation Fasteners Fastener (Table 3) Fastener

ISO 95+ GL, RESISTA

Minimum 1/2" thick N/A N/A

DensDeck, Dens Deck Prime, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat

Fiber Roof Board

Minimum ¼ " thick N/A N/A

**ISOGARD HD Composite** 

Minimum 1.5" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

**Membrane:** UltraPly TPO is placed over the insulation and mechanically secured to the deck

with Firestone Heavy Duty fasteners and Firestone HD Seam Plates spaced max. 6" o.c. within the 6" wide side laps, in rows max. 114" o.c. Roof cover side laps are sealed with a 1.5" minimum wide heat weld placed along the outer edge of the

lap.

**Maximum Design** 

**Pressure:** -52.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 101 of 116

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Minimum 22 gauge steel deck meeting ASTM Designation A1008 SS Grade 80

or A653 SS Grade 80 is secured to structural supports spaced maximum 6 ft. o.c. with TRAXX/5 fasteners spaced 6" o.c. Deck side laps are secured a maximum

24 in. o.c. with TRAXX/1 fasteners.

Or

Structural Concrete.

**System Type E(1):** Membrane mechanically fastened over existing roof system.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

**Barrier:** None.

Membrane: UltraPly TPO XR 100 or UltraPly TPO XR 115 attached to deck as described

below.

**Fastening #1:** Membrane is mechanically attached using Firestone Heavy Duty Plus and

Firestone HD Plus Seam Plates spaced 12" o.c. within minimum 6" wide laps in rows spaced 114" o.c. and sealed with minimum 1.5" heat weld along the outside

edge.

**Fastening #2:** Membrane is mechanically attached using Firestone Heavy-Duty and Firestone

HD Seam Plates spaced 6" o.c. within minimum 6" wide laps in rows spaced 114" o.c. and sealed with minimum 1.5" heat weld along the outside edge.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 102 of 116

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Minimum 22 gauge, Grade 33, Type B steel deck is secured to structural

supports spaced maximum 6 ft. o.c. with TRAXX/5 fasteners spaced 6" o.c. Deck side laps are secured a maximum 24 in. o.c. with TRAXX/1 fasteners.

Or

Structural Concrete.

**System Type E(2):** Membrane mechanically fastened over existing roof system.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

**Barrier:** None.

Membrane: UltraPly TPO XR 100 or UltraPly TPO XR 115 attached to deck as described

below.

**Fastening:** Membrane is mechanically attached using Firestone Heavy Duty Plus and

Firestone HD Plus Seam Plates spaced 6" o.c. within minimum 6" wide laps in rows spaced 114" o.c. and sealed with minimum 1.5" heat weld along the outside

edge.

**Maximum Design** 

**Pressure:** -67.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 103 of 116

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Min. 300 psi Generic Cellular Lightweight Concrete cast over steel deck<sub>o</sub>or

concrete.\*The deck should record a Minimum Characteristic Resistance Force (MCRF) of 390 lbf. when tested with Firestone Heavy-Duty installed through the

LWC to the steel deck in accordance with TAS 105.

**System Type E(3):** Membrane attached over existing roof system.

**Deck:** Minimum 22 gauge, Grade 33, Type-B steel deck is secured to supports spaced a

maximum of 6 ft. o.c. with  $\#12-24 \times 1-1/4$ " HWH SD screws with  $\frac{1}{2}$ " washers spaced at 6" o.c. Side lap fasteners secured with  $\#1/4-14 \times 7/8$ " HWH SD screws

with ½" washers spaced 12" o.c.

Or

Structural Concrete.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Membrane: UltraPly TPO attached through the lightweight concrete and engaged to the steel

deck as described below:

**Fastening:** Membrane is mechanically attached using Polymer Batten Strip spaced 4 ft. o.c.

and fastened to deck with Heavy Duty fasteners spaced 6" o.c. along the batten strip. A 6" wide UltraPly TPO Cover Strip is heat welded over battens with 1.5 in. wide heat welds. The roof cover side and end laps are sealed with a minimum

1.5" heat weld on the outside edge of the lap

**Maximum Design** 

**Pressure:** -97.5 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 104 of 116

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Min. 300 psi Generic Cellular Lightweight Concrete cast over steel deck or

concrete deck.\*The deck should record a Minimum Characteristic Resistance Force (MCRF) of 450 lbf. when tested with Firestone Heavy-Duty installed

through the LWC to the steel deck in accordance with TAS 105.

**System Type E(4):** Membrane attached over existing roof system.

**Deck:** Minimum 22 ga. steel deck is secured to supports spaced a maximum of 6 ft. o.c.

Or

Structural Concrete.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

**Membrane:** UltraPly TPO XR is attached through the lightweight concrete and engaged to the

steel deck as described below:

**Fastening:** Membrane is mechanically attached using Polymer Batten Strip spaced 4 ft. o.c.

and fastened to deck with Firestone Heavy-Duty spaced 6" o.c. along the batten strip. A 6" wide UltraPly TPO Cover Strip is heat welded over battens with 1.5" wide heat welds. The roof cover side and end laps are sealed with a minimum

1.5" heat weld on the outside edge of the lap

**Maximum Design** 

**Pressure:** -112.5 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 105 of 116

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Min. 348 psi Celcore Lightweight Concrete cast over steel deck or concrete deck.

\*The deck should record a Minimum Characteristic Resistance Force (MCRF) of

90 lbf. when tested with Two Piece Impact Nail installed into the LWC in

accordance with TAS 105.

**System Type E(5):** Membrane attached over existing roof system.

**Deck:** Minimum 22 ga. steel deck attached to supports spaced a maximum 5-ft o.c.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

**Base Sheet:** SBS Poly Base attached to the lightweight concrete with the Two Piece Impact

Nail (min. 1.8" embedment) spaced 9" o.c. in the 3.4" wide side laps and 9" o.c.

in two equally spaced and staggered rows in the field of the sheet.

**Membrane:** UltraPly TPO XR adhered in 1" to 1.5" wide ribbons of I.S.O. Spray R spaced

12" o.c.

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 106 of 116

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Minimum 3" thick Cementitious Wood Fiber panels attached structural supports

spaced a maximum 4-ft o.c. with three (3) Dekfast 14 fasteners and 2" diameter Metal Plates installed along each support and panel edge. \*The deck should record a Minimum Characteristic Resistance Force (MCRF) of 105 lbf. when tested with Two Piece Impact Nail installed into the deck in accordance with

TAS 105.

**System Type E(6):** Membrane attached over existing roof system.

**Deck:** Cementitious Wood Fiber

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

**Base Sheet:** SBS Poly Base attached to the lightweight concrete with the Two Piece Impact

Nail (min. 1.8" embedment) spaced 12" o.c. in the 3.4" wide side laps and 12"

o.c. in two equally spaced and staggered rows in the field of the sheet.

**Membrane:** UltraPly TPO XR adhered in 3/4" to 1" wide ribbons of I.S.O. Spray R spaced

12" o.c.

**Maximum Design** 

**Pressure:** -52.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 107 of 116

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Minimum 3" thick Cementitious Wood Fiber panels attached structural supports

spaced a maximum 4-ft o.c. with three (3) Dekfast 14 fasteners and 2" diameter Metal Plates installed along each support and panel edge. \*The deck should record a Minimum Characteristic Resistance Force (MCRF) of 104 lbf. when tested with Two Piece Impact Nail installed into the deck in accordance with

TAS 105.

**System Type E(7):** Membrane attached over existing roof system.

**Deck:** Cementitious Wood Fiber

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

**Base Sheet:** SBS Poly Base attached to the lightweight concrete with the Two Piece Impact

Nail (min. 1.8" embedment) spaced 7" o.c. in the 3.4" wide side laps and 7" o.c.

in two equally spaced and staggered rows in the field of the sheet.

**Membrane:** UltraPly TPO XR adhered in 3/4" to 1" wide ribbons of I.S.O. Spray R spaced

12" o.c.

**Maximum Design** 

**Pressure:** -90 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 108 of 116

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Minimum 3" thick Cementitious Wood Fiber panels attached structural supports

spaced a maximum 4-ft o.c. with three (3) Dekfast 14 fasteners and 2" diameter Metal Plates installed along each support and panel edge. \*The deck should record a Minimum Characteristic Resistance Force (MCRF) of 101 lbf. when tested with Two Piece Impact Nail installed into the deck in accordance with

TAS 105.

**System Type E(8):** Membrane attached over existing roof system.

**Deck:** Cementitious Wood Fiber

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

**Base Sheet:** SBS Poly Base attached to the lightweight concrete with the Two Piece Impact

Nail (min. 1.8" embedment) spaced 9" o.c. in the 3.4" wide side laps and 9" o.c.

in two equally spaced and staggered rows in the field of the sheet.

**Membrane:** UltraPly TPO XR adhered in 3/4" to 1" wide ribbons of I.S.O. Spray R spaced

12" o.c.

**Maximum Design** 

**Pressure:** -67.5 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 109 of 116

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Min. 347 psi Celcore Lightweight Concrete cast over steel deck or concrete

deck.\*The deck should record a Minimum Characteristic Resistance Force (MCRF) of 540 lbf. when tested with Heavy Duty fasteners installed through the

LWC into the deck in accordance with TAS 105.

**System Type E(9):** Membrane attached over existing roof system.

**Deck:** Minimum 22 ga. steel deck attached to supports spaced a maximum 5-ft o.c.

or

Structural Concrete.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

**Membrane:** UltraPly TPO XR adhered in a continuous 3/4" to 1" wide ribbon of I.S.O. Spray

R to each 5" wide, inverted "base strip" of TPO XR spaced 6-ft o.c. Each "base strip" is attached through the LWC to the deck with Heavy Duty fasteners and

HD Seam Plates spaced 6" o.c.

**Maximum Design** 

**Pressure:** -90 psf. (See General Limitation #7)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 110 of 116

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Steel/Concrete/Wood/Gypsum/Cementitious Wood Fiber

**System Type F(1):** Membrane adhered to existing asphaltic BUR

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Membrane: UltraPly TPO XR adhered with XR Stick Membrane Adhesive applied in

continuous  $\frac{3}{4}$ " – 1" wide ribbons spaced 12" o.c. The 2" roof cover side laps are

sealed with a minimum 1.5" heat weld on the outside edge of the lap.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #9)

**Membrane Type:** Single Ply, TPO

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Steel/Concrete/Wood/Gypsum/Cementitious Wood Fiber

**System Type F(2):** Membrane adhered to existing granule surfaced asphaltic modified bitumen roof

systems.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

**Membrane:** UltraPly TPO XR adhered with XR Stick Membrane Adhesive applied in

continuous  $\frac{3}{4}$ " – 1" wide ribbons spaced 6" o.c. The 2" roof cover side laps are

sealed with a minimum 1.5" heat weld on the outside edge of the lap.

Maximum Design -142.5 psf. (See General Limitation #9) for Steel and Concrete decks.

**Pressure:** -45 psf. (See General Limitation #9) for all other deck types.



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 111 of 116

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Concrete

**System Type F(3):** Membrane adhered to existing asphaltic BUR

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

**Membrane:** UltraPly TPO XR 115 adhered with XR Stick Membrane Adhesive applied in

continuous 1" minimum beads spaced a maximum of 4" o.c. and allowed to expand to full coverage application prior to placement of the roof cover. The 2" wide roof cover side laps are sealed with a minimum 1.5 in. heat weld placed on

the outside edge of the lap

**Maximum Design** 

**Pressure:** -315 psf. (See General Limitation #9)

**Membrane Type:** Single Ply, TPO

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Concrete

**System Type F(4):** Membrane adhered to existing asphaltic roof system.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

**Membrane:** One ply of UltraPly TPO XR adhered with hot asphalt at a rate of 20-25 lb./sq.

Minimum 3" roof cover laps are sealed with a minimum 1.5" heat weld along the

outside edge.

**Maximum Design** 

**Pressure:** -495 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 112 of 116

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Concrete

System Type F(5): Membrane adhered to existing torch adhered granule surfaced SBS Modified

Roofing.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Membrane: UltraPly TPO XR 100 or UltraPly TPO XR 115 Reinforced Membrane adhered

to existing roof system with XR Stick Membrane Adhesive applied in <sup>3</sup>/<sub>4</sub> - 1 in. wide ribbons spaced 12" o.c. The 2" roof cover side laps are sealed with a

minimum 1.5" heat weld on the outside edge of the lap.

**Maximum Design** 

**Pressure:** -122.5 psf. (See General Limitation #9)

**Membrane Type:** Single Ply, TPO

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Concrete

**System Type F(6):** Membrane adhered to existing asphaltic roof system.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Membrane: UltraPly TPO XR 100 or UltraPly TPO XR 115 adhered with XR Stick

Membrane Adhesive applied in continuous 1" minimum beads spaced a maximum of 4" o.c. and allowed to expand to full coverage application prior to placement of the roof cover. The 2" wide roof cover side laps are sealed with a

minimum 1.5 in. heat weld placed on the outside edge of the lap.

**Maximum Design** 

**Pressure:** -172.5 psf.; (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 113 of 116

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Concrete

**System Type F(7):** Membrane adhered to existing granule surfaced SBS Modified Roofing.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Membrane: UltraPly TPO XR 115 or UltraPly TPO XR 135 Reinforced Membrane adhered

to existing roof system with XR Stick Membrane Adhesive applied in  $\frac{3}{4}$  - 1 in. wide ribbons spaced 12" o.c. The 2" roof cover side laps are sealed with a

minimum 1.5" heat weld on the outside edge of the lap.

**Maximum Design** 

**Pressure:** -392.5 psf. (See General Limitation #9)

**Membrane Type:** Single Ply, TPO

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Concrete

**System Type F(8):** Membrane adhered to existing smooth surfaced BUR

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

**Membrane:** UltraPly TPO XR 115 or UltraPly TPO XR 135 adhered with XR Stick

Membrane Adhesive applied in continuous 1" minimum beads spaced a maximum of 12" o.c. The 2" wide roof cover side laps are sealed with a

minimum 1.5 in. heat weld placed on the outside edge of the lap

**Maximum Design** 

**Pressure:** -112.5 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 114 of 116

**Deck Type 7:** Recover, Non-Insulated

**Deck Description:** Concrete

**System Type F(9):** Membrane adhered to existing granule surfaced APP Modified Roofing.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Membrane: UltraPly TPO XR 115 or UltraPly TPO XR 135 Reinforced Membrane

adhered to existing roof system with XR Stick Membrane Adhesive applied in <sup>3</sup>/<sub>4</sub> - 1 in. wide ribbons spaced 12" o.c. The 2" roof cover side laps are sealed with a minimum 1.5" heat weld on the outside edge of the lap.

**Maximum Design** 

**Pressure:** -422.5 psf. (See General Limitation #9)



NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 115 of 116

## **RECOVER SYSTEM LIMITATIONS:**

- 1. All System Limitations and General Limitations shall apply. See specific deck type Notice of Acceptance for deck type System Limitations.
- 2. All assemblies listed herein shall be installed in compliance with the applicable sections of FBC 1521. Uplift performance of assemblies bonded to existing roofing system shall be verified per 1521.10. Uplift performance of assemblies mechanically attached through existing roofing system shall be verified per 1521.11.

## **GENERAL LIMITATIONS:**

- 1. Fire classification is not part of this acceptance; refer to a current Approved Roofing Materials Directory for fire ratings of this product.
- 2. Insulation may be installed in multiple layers. The first layer shall be attached in compliance with Product Control Approval guidelines. All other layers shall be adhered in a full mopping of approved asphalt applied within the EVT range and at a rate of 20-40 lbs./sq., or mechanically attached using the fastening pattern of the top layer.
- 3. All standard panel sizes are acceptable for mechanical attachment. When applied in approved asphalt, panel size shall be 4' x 4' maximum.
- 4. An overlay and/or recovery board insulation panel is required on all applications over closed cell foam insulations when the base sheet is fully mopped. If no recovery board is used the base sheet shall be applied using spot mopping with approved asphalt, 12" diameter circles, 24" o.c.; or strip mopped 8" ribbons in three rows, one at each side lap and one down the center of the sheet allowing a continuous area of ventilation. Encircling of the strips is not acceptable. A 6" break shall be placed every 12' in each ribbon to allow cross ventilation. Asphalt application of either system shall be at a minimum rate of 12 lbs./sq.

## Note: Spot attached systems shall be limited to a maximum design pressure of -45 psf.

- 5. Fastener spacing for insulation attachment is based on a Minimum Characteristic Force (F') value of 275 lbf, as tested in compliance with Testing Application Standard TAS 105. If the fastener value, as field-tested, are below 275 lbf. Insulation attachment shall not be acceptable.
- 6. Fastener spacing for mechanical attachment of anchor/base sheet or membrane attachment is based on a minimum fastener resistance value in conjunction with the maximum design value listed within a specific system. Should the fastener resistance be less than that required, as determined by the Building Official, a revised fastener spacing, prepared, signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant may be submitted. Said revised fastener spacing shall utilize the withdrawal resistance value taken from Testing Application Standards TAS 105 and calculations in compliance with Roofing Application Standard RAS 117.
- 7. Perimeter and corner areas shall comply with the enhanced uplift pressure requirements of these areas. Fastener densities shall be increased for both insulation and base sheet as calculated in compliance with Roofing Application Standard RAS 117 and/or RAS 137. Calculations prepared, signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant (When this limitation is specifically referred within this NOA, General Limitation #9 will not be applicable.)
- 8. All attachment and sizing of perimeter nailers, metal profile, and/or flashing termination designs shall conform to Roofing Application Standard RAS 111 and applicable wind load requirements.
- 9. The maximum designed pressure limitation listed shall be applicable to all roof pressure zones (i.e. field, perimeters, and corners). Neither rational analysis, nor extrapolation shall be permitted for enhanced fastening at enhanced pressure zones (i.e. perimeters, extended corners and corners). (When this limitation is specifically referred within this NOA, General Limitation #7 will not be applicable.)
- 10. All products listed herein shall have a quality assurance audit in accordance with the Florida Building Code and Rule 61G20-3 of the Florida Administrative Code.

## END OF THIS ACCEPTANCE

MIAMI-DADE COUNTY
APPROVED

NOA No.: 14-0606.04 Expiration Date: 02/03/20 Approval Date: 05/26/16 Page 116 of 116