

DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER) BOARD AND CODE ADMINISTRATION DIVISION

MIAMI-DADE COUNTY PRODUCT CONTROL SECTION

11805 SW 26 Street, Room 208 Miami, Florida 33175-2474 T (786) 315-2590 F (786) 315-2599 www.miamidade.gov/economy

NOTICE OF ACCEPTANCE (NOA)

Sika Sarnafil, A Division of Sika Corp. 100 Dan Road Canton, MA 02021

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER - Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code including the High Velocity Hurricane Zone of the Florida Building Code.

DESCRIPTION: Sika Sarnafil PVC Single Ply Roofing over Steel Deck

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

Stepha

This NOA revises NOA#13-1008.14 and consists of pages 1 through 45. The submitted documentation was reviewed by Alex Tigera.



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15

Page 1 of 45

ROOFING SYSTEM APPROVAL

Category:RoofingSub-Category:Single PlyMaterial:PVCDeck Type:SteelMaximum Design Pressure:-127.5 psf.

TRADE NAMES OF PRODUCTS MANUFACTURED OR LABELED BY APPLICANT: TABLE 1

		Test	Product
Product	Dimensions	Specification	<u>Description</u>
G410	60, 72 and 80 mils	ASTM D 4434	Fiberglass reinforced PVC roofing membrane.
G410 Felt	48, 60, 72 and 80 mils	ASTM D 4434	Fiberglass reinforced PVC roofing membrane with a non-woven felt backing.
G459	48, 60, 72 and 80 mils	ASTM D 4434	Fiberglass reinforced PVC Alloy asphalt compatible flashing membrane.
S327	48, 60, 72 and 80 mils	ASTM D 4434	Polyester reinforced PVC roofing membrane.
S327 Felt	48 mils	ASTM D 4434	Polyester reinforced PVC roofing membrane with a non-woven felt backing.
Sikaplan	45 mils	ASTM D 4434	White polyester reinforced PVC roofing membrane.
Sarnatape	Various	Proprietary	Air flow barrier tape
Sarnacol 2170	5 gallons	Proprietary	Solvent based bonding adhesive.
Sarnacol 2121	5 gallons	Proprietary	Water based bonding adhesive.
Sarnacol AD Feltback Membrane Adhesive	5 gallons	Proprietary	Two-component foamable polyurethane membrane or insulation adhesive.
Sarnacol OM Feltback Membrane Adhesive	5 gallons	Proprietary	Two-component foamable polyurethane membrane adhesive.
Sarnacol OM Board Adhesive	5 gallons	Proprietary	Two-component foamable polyurethane insulation adhesive.
OlyBond 500	5 gallons	Proprietary	Two-component foamable polyurethane insulation adhesive.
Sarnacol 2170 VC	Various	Proprietary	Solvent-based, VOC compliant adhesive.
Sarnatred	3.25' x 32.8'	Proprietary	PVC walkway protection sheet.
Sarnavap-10	20' x 100'	Proprietary	Polyethylene air/vapor barrier.
Sarnastack	Various	Proprietary	Prefabricated cone flashing.
Sarnaclad	Various	Proprietary	Heat weldable PVC/galvanized steel flashing
FR 10	48" x 250'	Proprietary	Non-asphaltic fiberglass-based fire-retardant slipsheet
FR 50	48" x 105'	Proprietary	Non-asphaltic fiberglass-based fire-retardant slipsheet



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 2 of 45

APPROVED INSULATIONS:

TABLE 2

Product Name	Product Description	Manufacturer (With Current NOA)
Sarnatherm	Isocyanurate Insulation	Sika Sarnafil, A Division of Sika Corp.
Sarnatherm-25 PSI	Polyisocyanurate insulation board.	Sika Sarnafil, A Division of Sika Corp.
Sarnatherm (a)	Isocyanurate Insulation	Sika Sarnafil, A Division of Sika Corp.
ACFoam-III, ACFoam-III	Isocyanurate Insulation	Atlas Roofing Corp.
ACFoam-IV	Isocyanurate Insulation	Atlas Roofing Corp.
ACFoam Supreme	Isocyanurate Insulation	Atlas Roofing Corp.
DensDeck, DensDeck Prime	Silicon treated gypsum	Georgia Pacific Gypsum LLC
ENRGY 3	Isocyanurate Insulation	Johns Manville Corp.
ENRGY 3 Plus	Isocyanurate Insulation with wood fiberboard facer	Johns Manville Corp.
ENRGY 3 25 PSI	Isocyanurate Insulation	Johns Manville Corp.
Perlite Insulation Board	Perlite Insulation	Generic
Type X Gypsum	Gypsum Wallboard	Generic
H-Shield	Isocyanurate Insulation	Hunter Panels, LLC
H-Shield HD	Isocyanurate Insulation	Hunter Panels, LLC
ISO 95+ GL	Isocyanurate Insulation	Firestone Building Products Company, LLC
SECUROCK Gypsum-Fiber Roof Board	A rigid gypsum based board	United States Gypsum Corp.
SECUROCK Glass-Mat Roof Board	A rigid gypsum based board	United States Gypsum Corp.
Invinsa Roof Board	High density polyisocyanurate	Johns Manville Corp.



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 3 of 45

APPROVED FASTENERS:

TABLE 3

Fastener Number	<u>Product</u> <u>Name</u>	Product Description	<u>Dimensions</u>	<u>Manufacturer</u> (With Current NOA)
1.	#12 Standard Roofgrip, #14 Roofgrip, #15 Roofgrip	Insulation and membrane fastener	Various	OMG, Inc.
2.	Dekfast 12, Dekfast 14, Dekfast 15 HS	Insulation and membrane fastener	Various	SFS Intec, Inc.
3.	Sarnafastener	Insulation and membrane fastener	Various	Sika Sarnafil, A Division of Sika Corp.
4.	RhinoBond Insulation Plate	Insulation fastener	Various	OMG, Inc.
5.	Sarnabar	Galvanized or stainless steel membrane fastening bar.	Various	Sika Sarnafil, A Division of Sika Corp.
6.	Sarnaplate	Insulation fastening plate.	3" round	Sika Sarnafil, A Division of Sika Corp.
7.	Sarnarail Polymer Batten Strip	Polymer Batten Bar	1" x 250'	Sika Sarnafil, A Division of Sika Corp.
8.	Sarnafastener-XP	Membrane and insulation fastener.	Various	Sika Sarnafil, A Division of Sika Corp.
9.	Sarnafastener MAXLoad, Sarnafil MAXLoad	Membrane fastener	Various	Sika Sarnafil, A Division of Sika Corp.
10.	Sarnadisc MAXLoad Plate	AZ50 galvalume coated steel plate	3.5" round	Sika Sarnafil, A Division of Sika Corp.
11.	Sarnadisc XPN	Membrane and insulation fastening plate.	1.5" x 3.75"	Sika Sarnafil, A Division of Sika Corp.
12.	RhinoBond Insulation Plate	Insulation fastening plate	Various	Sika Sarnafil, A Division of Sika Corp.
13.	OMG Super XHD	Membrane and insulation fastener.	Various	OMG, Inc.
14.	OMG Heavy-Duty	Membrane and insulation fastener.	Various	OMG, Inc.



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 4 of 45

EVIDENCE SUBMITTED:

Test Agency	Test Identifier	Description	Date
Celotex Technical Center	MTS Job No. 258215	TAS 114	09/09/97
Factory Mutual Research	0P6A6.AM	FM 4470	03/03/94
Corporation	0X3A3.AM	FM 4470	01/31/94
	2X2A5.AM	FM 4470	01/31/94
	0B9A0.AM	FM 4470	10/22/96
	4B3A2.AM	FM 4470	06/19/97
	2B6A9.AM	FM 4470	08/25/98
	3D8A1.AM	FM 4470	12/23/97
	3012964	FM 4470	06/11/02
	3015643	FM 4470	12/06/02
	3016201	FM 4470	01/28/03
	3006785	FM 4470	05/06/04
	3017292	FM 4470	09/03/04
	3021131	FM 4470	07/07.05
	3024229	FM 4470	11/16/05
	3030053	FM 4470	09/12/07
	3028309	FM 4470	03/30/07
	3041256	FM 4470	07/12/11
	3001396	FM 4470	05/28/99
	3053265	FM 4470	10/30/14
	3039809	FM 4470	07/06/11
	3043459	FM 4470	05/11/12
Underwriters Laboratories, Inc.	R8992	UL 790	05/15/13
Trinity ERD	4740.04.98-1	FM 4470	04/09/98
	S44790.06.13	ASTM D4434	06/05/13
	S42480.08.12	Physical Properties	08/20/12
	S44790.08.13	ASTM D4434	08/26/13
	S36600.03.14	FM 4474 & TAS 114	03/04/14
	S44790.07.14	ASTM D4434	07/31/14
	S45990.06.14	ASTM D4434	06/02/14



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 5 of 45

APPROVED ASSEMBLIES:

Membrane Type: Single Ply, PVC

Deck Type 2I: Steel, Insulated

Deck Description: 18 – 22ga. steel

System Type B(1): Base layer of insulation mechanically attached, optional top insulation layer fully adhered

with approved asphalt, membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder An FM approved vapor barrier approved for use with hot asphalt may be applied to the deck

(Optional): or perlite base layer.

Fire Barrier Minimum ⁵/₈ "Type X Gypsum or ¹/₄ "DensDeck.

(Optional):

One or more layers of any of the following insulations:

Base Insulation Layer:	Insulation Fasteners	Fastener
	<u>(Table 3)</u>	Density/ft ²
Sarnatherm (a), Sarnatherm, Sarnatherm-25 PSI, ACFoam-II, H	I-Shield	
Minimum 1.3" thick or tapered	1 or 2	1:2 ft ²
Minimum 2" thick or tapered	1 or 2	1:4 ft ²
Sarnatherm (a), Sarnatherm, Sarnatherm-25 PSI, ACFoam-II, E	NRGY 3, ENRGY 3 Plus, EN	RGY 3 25 PSI,
H-Shield		
Minimum 1.4" thick or tapered	1, 2 or 3	1:3 ft ²
Minimum 2" thick or tapered	1, 2 or 3	1:4 ft ²
DensDeck Prime		
Minimum 1/4" thick	1, 2 or 3	1:1.2 ft ²
Minimum 1/2" thick	1, 2 or 3	1:1.7 ft ²
Approved Perlite Insulation Board		
Minimum 3/4" thick	1, 2 or 3	1:1 ft ²

Note: Base layer shall be mechanically attached with fasteners and density described. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15

Page 6 of 45

Top Insulation Layer:	<u>Insulation Fasteners</u> (<u>Table 3)</u>	Fastener Density/ft ²
Sarnatherm (a), Sarnatherm-25 PSI, ACFoam-II Minimum 1.3" thick or tapered	N/A	N/A
ENRGY 3, ENRGY 3 Plus, ENRGY 3 25 PSI Minimum 1.4" thick or tapered	N/A	N/A
DensDeck Prime Minimum 1/4" thick	N/A	N/A

Note: Optional top layer of insulation shall be adhered with approved asphalt within the EVT range and at a rate of 20-40 lbs./100 ft². Please refer to Roofing Application Standard RAS 117 for insulation attachment. Composite insulation boards used as a top layer shall be installed with the polyisocyanurate face down.

Membrane:

Sarnafil G410 Felt or S327 Felt adhered with Sarnacol 2170 adhesive rolled applied as a primer at a rate of 1.0-1.25gal/sq. to the substrate allowed to dry. Following a second coat roller applied of adhesive at a rate of 1.0gal/sq. or with Sarnacol 2121 adhesive roller applied at 0.75 gal/sq. to the insulation. The roof cover is immediately placed into the adhesive and the top surface rolled with a weighted roller. Minimum 3" wide side lap is sealed with a 1.5" wide heat weld.

Or

(*With ISO*) Sarnafil G410 or S327 adhered with Sarnacol 2121 adhesive roller applied at 0.75 gal/sq. to the insulation or with Sarnacol 2170 adhesive applied at 0.75-2gal/sq. to the substrate and 0.5 gal/sq. to the back of the membrane. The roof cover is immediately placed into the adhesive and the top surface rolled with a weighted roller. Minimum 3" wide side lap is sealed with a 1.5" wide heat weld.

Or

(*With DenDeck Prime*) Sarnafil G410 or S327 adhered with Sarnacol 2121 adhesive roller applied at 0.75 gal/sq. to the insulation or with Sarnacol 2170 adhesive applied at 0.75-2gal/sq. to the substrate and 0.5 gal/sq. to the back of the membrane. The roof cover is immediately placed into the adhesive and the top surface rolled with a weighted roller. Minimum 3" wide side lap is sealed with a 1.5" wide heat weld.

Or

(With ACFoam-II, Sarnatherm (a) and Sarnatherm-25 PSI or DensDeck Prime) Sarnafil G410 or S327 adhered with Sarnacol 2170 VC adhesive applied at 0.75 gal/sq. to the substrate and 0.5 gal/sq. to the back of the membrane or Sarnafil G410 Felt or S327 Felt adhered with Sarnacol 2170 VC adhesive applied to the substrate in two coats with a total application rate of 2.0 gal/sq or with Sarnacol AD Feltback Membrane Adhesive or Sarnacol OM Feltback Membrane Adhesive in 0.5" wide ribbons spaced 12" o.c. The roof cover is immediately placed into the adhesive and the top surface rolled with a weighted roller. Minimum 3" wide side lap is sealed with a minimum 1.25" wide heat weld.

Maximum Design

Pressures: -45 psf. (See General Limitation #9)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 7 of 45 Membrane Type: Single Ply, PVC

Deck Type 2I: Steel, Insulated

Deck Description: 18 – 22ga. steel

System Type B(2): Base layer of insulation mechanically attached, optional top insulation layer fully adhered

with approved asphalt or adhesive, membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder Any UL or FM approved vapor barrier approved for use with hot asphalt may be applied to

(Optional): the deck or perlite base layer.

Fire Barrier Minimum 1/4 " Type X Gypsum or DensDeck

(Optional):

One or more layers of any of the following insulations:

Base Insulation Layer:Insulation Fasteners
(Table 3)Fastener
Density/ft²Sarnatherm, Sarnatherm (a), Sarnatherm-25 PSI, ACFoam-II, ACFoam-III, H-Shield, ISO 95+GL, ENRGY 3

Minimum 1.4" thick or tapered

1:25 PSI, ACFORM-II, ACFORM-III, H-SNIEIG, ISO 95+GL, ENRGY 3

1:2 ft²

Note: Base layer shall be mechanically attached with fasteners and density described. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Top Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft²

Sarnatherm, Sarnatherm (a), Sarnatherm-25 PSI, ACFoam-II, ACFoam-III, H-Shield, ISO 95+GL, ENRGY 3 Minimum 1.4" thick or tapered N/A N/A

DensDeck Prime

Minimum 1/4" thick or tapered N/A N/A

Note: Optional top layer of insulation shall be adhered to the deck in full coating of OlyBond Adhesive Fastener at a rate of 1 gal/sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Insulation listed as base layer only shall be used only as base layers with a second layer of approved top layer insulation installed as the final membrane substrate



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 8 of 45

Membrane:

Sarnafil G410 Felt or S327 Felt adhered with Sarnacol 2170 adhesive rolled applied as a primer at a rate of 1.0-1.25 gal/sq. to the insulation allowed to dry. Following a second coat roller applied of adhesive at 1.0 gal/sq. or with Sarnacol 2121 adhesive roller applied at 0.75 gal/sq. to the insulation. The roof cover is immediately placed into the adhesive and the top surface rolled with a weighted roller. Minimum 3" wide side lap is sealed with a 1.5" wide heat weld.

Or

(With ISO) Sarnafil G410 or S327 adhered with Sarnacol 2121 adhesive roller applied at 0.75 gal/sq. to the insulation or with Sarnacol 2170 adhesive applied at 0.75-2gal/sq. to the substrate and 0.5 gal/sq. to the back of the membrane. The roof cover is immediately placed into the adhesive and the top surface rolled with a weighted roller. Minimum 3" wide side lap is sealed with a 1.5" wide heat weld.

Or

(With DenDeck Prime) Sarnafil G410 or S327 adhered with Sarnacol 2121 adhesive roller applied at 0.75 gal/sq. to the insulation or with Sarnacol 2170 adhesive applied at 0.75-2gal/sq. to the substrate and 0.5 gal/sq. to the back of the membrane. The roof cover is immediately placed into the adhesive and the top surface rolled with a weighted roller. Minimum 3" wide side lap is sealed with a 1.5" wide heat weld.

Or

(With ACFoam-II, ACFoam-III, Sarnatherm (a), Sarnatherm-25 PSI or DensDeck Prime) Sarnafil G410 or S327 adhered with Sarnacol 2170 VC adhesive applied at 0.75 gal/sq. to the substrate and 0.5 gal/sq. to the back of the membrane or Sarnafil G410 Felt or S327 Felt adhered with Sarnacol 2170 VC adhesive applied to the substrate in two coats with a total application rate of 2.0 gal/sq or with Sarnacol AD Feltback Membrane Adhesive or Sarnacol OM Feltback Membrane Adhesive in 0.5" wide ribbons spaced 12" o.c. The roof cover is immediately placed into the adhesive and the top surface rolled with a weighted roller. Minimum 3" wide side lap is sealed with a 1.25" wide heat weld.

Maximum Design Pressures:

-45 psf. (See General Limitation #9)



NOA No.: 14-0624.13 **Expiration Date: 07/05/16** Approval Date: 03/12/15

Page 9 of 45

Deck Description: 22ga., ASTM A653 Grade 80 steel deck fastened to 0.25 in. thick structural supports spaced 6

ft. o.c. with two Traxx/5 fasteners, with ¾ in. washers, at each rib spaced 6 in. o.c. in rows above each support 6 ft. o.c. and with side laps fastened with Traxx/1 fasteners spaced 24 in.

o.c.

System Type B(3): Base layer of insulation mechanically attached, membrane adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer:

(Table 3)

Sarnatherm (a), Sarnatherm 25 PSI, ACFoam-II, ACFoam-IV

Minimum 2" thick

6 with 8

1:1 ft²

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sarnafil G410 or S327 adhered with Sarnacol 2170 VC adhesive applied to the substrate at

0.75 gal/sq and to the roof cover at 0.5 gal/sq. or with Sarnacol 2121 adhesive roller applied at 0.75 gal/sq. to the insulation. The roof cover is immediately placed into the adhesive and the top surface rolled with a weighted roller. Minimum 3" wide side lap is sealed with a 1.25"

wide heat weld.

Or

Sarnafil G410 Felt or S327 Felt adhered with Sarnacol 2170 VC adhesive applied to only the substrate in two coats with a total application rate of 2.0 gal/sq. or with Sarnacol 2121 adhesive roller applied at 0.75 gal/sq. to the insulation or with Sarnacol AD Feltback Membrane Adhesive or OM Feltback Membrane adhesive applied in 0.5" wide ribbons spaced 12" o.c. The roof cover is immediately placed into the adhesive and the top surface rolled with

a weighted roller. Minimum 3" wide side lap is sealed with a 1.25" wide heat weld.

Maximum Design

Pressure: -97.5 psf (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 10 of 45 Membrane Type: Single Ply, PVC

Deck Type 2I: Steel, Insulated

Deck Description: 18 – 22ga. steel

System Type C(1): All layers of insulation simultaneously fastened; membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarder An FM approved vapor barrier approved for use with hot asphalt may be applied to the deck

(Optional): or perlite base layer.

Fire Barrier (Optional):

Minimum 3/4" thick

Minimum ⁵/₈ " Type X Gypsum or ¹/₄ "DensDeck

One or more layers of any of the following insulations:

Base Insulation Layer:	Insulation Fasteners	<u>Fastener</u>
	<u>(Table 3)</u>	Density/ft²
Sarnatherm (a), Sarnatherm, Sarnatherm-25 PSI, ACFoam-II, A	CFoam-III, ACFoam Supreme	, H-Shield
Minimum 1.3" thick or tapered	N/A	N/A
Sarnatherm (a), Sarnatherm, Sarnatherm-25 PSI, ACFoam-II, E ISO 95+ GL, H-Shield	NRGY 3, ENRGY 3 Plus, ENR	GY 3 25 PSI,
Minimum 1.4" thick or tapered	N/A	N/A
DensDeck Prime Minimum ¼" thick	N/A	N/A
William /4 thick	IV/A	IV/A
Approved Perlite Insulation Board (base layer only)		

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

N/A

Top Insulation Layer:	Insulation Fasteners	Fastener
	<u>(Table 3)</u>	Density/ft ²
Sarnatherm (a), Sarnatherm-25 PSI, ACFoam-II		
Minimum 1.3" thick or tapered	1, 2 or 3	1:2 ft ²
Minimum 2" thick or tapered	1, 2 or 3	1:4 ft ²
Sarnatherm (a), Sarnatherm, Sarnatherm-25 PSI, ACFoam-II, El H-Shield	NRGY 3, ENRGY 3 Plus, ENI	RGY 3 25 PSI,
	1.2 2	1.2 642
Minimum 1.4" thick or tapered	1, 2 or 3	1:3 ft ²
Minimum 2" thick or tapered	1, 2 or 3	1:4 ft ²



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 11 of 45

N/A

Top Insulation Layer (Continued):	Insulation Fasteners	Fastener
	<u>(Table 3)</u>	Density/ft ²
DensDeck Prime		
Minimum 1/4" thick	1, 2 or 3	1:1.2 ft ²
Minimum 1/2" thick	1, 2 or 3	1:1.7 ft ²

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane:

Sarnafil G410 Felt or S327 Felt adhered with Sarnacol 2170 adhesive rolled applied as a primer at a rate of 1.0-1.25gal/sq. to the substrate allowed to dry. Following a second coat roller applied of adhesive at a rate of 1.0gal/sq. or with Sarnacol 2121 adhesive roller applied at a rate of 0.75 gal/sq. to the insulation. The roof cover is immediately placed into the adhesive and the top surface rolled with a weighted roller. Minimum 3" wide side lap is sealed with a 1.5" wide heat weld.

Or

Sarnafil G410 or S327 adhered with Sarnacol 2121 adhesive roller applied at 0.75 gal/sq. to the insulation or with Sarnacol 2170 adhesive applied at 0.75-2 gal/sq. to the substrate and 0.5 gal/sq. to the back of the membrane. The roof cover is immediately placed into the adhesive and the top surface rolled with a weighted roller. Minimum 3" wide side lap is sealed with a 1.5" wide heat weld.

Or

(With ACFoam-III, ACFoam-III, Sarnatherm (a), Sarnatherm-25 PSI or DensDeck Prime) Sarnafil G410 or S327 adhered with Sarnacol 2170 VC adhesive applied at 0.75 gal/sq. to the substrate and 0.5 gal/sq. to the back of the membrane or Sarnafil G410 Felt or S327 Felt adhered with Sarnacol 2170 VC adhesive applied to the substrate in two coats with a total application rate of 2.0 gal/sq or with Sarnacol AD Feltback Membrane Adhesive or Sarnacol OM Feltback Membrane Adhesive in 0.5" wide ribbons spaced 12" o.c. The roof cover is immediately placed into the adhesive and the top surface rolled with a weighted roller. Minimum 3" wide side lap is sealed with a 1.25" wide heat weld.

Maximum Design

Pressures: -45 psf. (See General Limitation #9)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 12 of 45

Single Ply, PVC **Membrane Type:** Deck Type 2I: Steel, Insulated 16 - 22ga. steel **Deck Description:**

System Type C(2): All layers of insulation simultaneously fastened; membrane adhered using RhinoBond plate

bonding tool.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Fastener Density/ft² **Base Insulation Layer: Insulation Fasteners** (Table 3)

Sarnatherm, H-Shield

Minimum 1.5" thick 4 with 8 **See Design Pressure**

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sarnafil S327 or Sikaplan bonded to RhinoBond Insulation Plates with RhinoBond Plate

bonding tool at 6 seconds per plate so the tool reaches 400°F. Minimum 3" wide side lap is

sealed with a minimum 3/4" wide heat weld.

Maximum Pressure Fastener Spacing Fastener Row Spacing Maximum Design -45 psf 2 ft. 3 ft.

Pressures: (See General Limitation #9)



NOA No.: 14-0624.13 **Expiration Date: 07/05/16** Approval Date: 03/12/15

Page 13 of 45

Deck Description: 18 – 22ga., ASTM A653 Grade 33 steel deck fastened to 0.25 in. thick structural supports

spaced 6 ft. o.c. with Traxx 5 fasteners spaced 6 in. o.c. and with side laps fastened with

Traxx 1 fasteners spaced 24 in. o.c.

System Type C(3): All layers of insulation simultaneously fastened; membrane adhered using RhinoBond plate

bonding tool.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer:	Insulation Fasteners (Table 3)	Fastener Density/ft ²
Sarnatherm, H-Shield		

Minimum 1.5" thick N/A N/A

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

<u>Top Insulation Layer</u>	Insulation Fasteners	Fastener Density/ft ²
(Optional):	<u>(Table 3)</u>	
Any approved cover board listed in Table 2		
Minimum 0.25" thick	12 with 13	See Design Pressure

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sarnafil S327 or Sikaplan bonded to RhinoBond Insulation Plates with RhinoBond Plate bonding tool at 6 seconds per plate so the tool reaches 400°F. Minimum 3" wide side lap is sealed with a minimum 34" wide heat weld.


Maximum Design
Pressures:

Maximum Pressure
-45 psf
(See General Limitation #7)

Fastener Spacing
2 ft.

3 ft.

-60 psf 2 ft. 2 ft.





NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 14 of 45

Deck Description: 18 – 22ga., Type B, Grade 40 steel deck fastened with Tek/5 fasteners and 5/8 in. diameter

washers spaced 6 in. o.c. to bar joists at 7ft. spans. Side laps are fastened with Tek/2

fasteners spaced maximum 18 in. o.c.

System Type C(4): All layers of insulation simultaneously fastened; membrane adhered using RhinoBond plate

bonding tool.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

<u>Insulation Layer:</u> <u>Insulation Fasteners</u> <u>Fastener Density/ft²</u> (Table 3)

Sarnatherm, H-Shield

Minimum 1.5" thick 8 with 12 1:4 ft²

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sarnafil S327 or Sikaplan bonded to RhinoBond Insulation Plates with RhinoBond Plate

bonding tool at 6 seconds per plate so the tool reaches 400°F. Minimum 3" wide side lap is

sealed with a minimum 3/4" wide heat weld.

Maximum Design

Pressures: -52.5 psf (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 15 of 45

Deck Description: 18 – 22ga., ASTM A653/A653M-01a, SS Grade 33 steel deck fastened to 0.25 in. thick

structural supports spaced 6 ft o.c. with Traxx/5 fasteners spaced 6 in. o.c. and with side laps

fastened with Traxx/1 fasteners spaced 24 in. o.c.

System Type C(5): All layers of insulation simultaneously fastened; membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer:	Insulation Fasteners	<u>Fastener</u>
	<u>(Table 3)</u>	Density/ft ²
Any approved polyisocyanurate listed in Table 2		
Minimum 1.5" thick	N/A	N/A

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Top Insulation Layer:	Insulation Fasteners (Table 3)	<u>Fastener</u> <u>Density/ft²</u>	
DensDeck Prime Minimum 5/8" thick	3 with 6	1:2 ft ²	

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sarnafil G410 Felt or S327 Felt adhered with Sarnacol 2121 adhesive roller applied at a rate

of 0.75 gal/sq. to the substrate or adhered with Sarnacol 2170 VC adhesive applied to the substrate in two coats with a total application rate of 2.0 gal/sq. or with Sarnacol AD or Sarnacol OM Feltback Membrane Adhesive in 0.5" wide ribbons spaced 12" o.c. Minimum

3" wide side lap is sealed with a minimum 1.25" wide heat weld.

Or

Sarnafil G410 or S327 adhered with Sarnacol 2121 adhesive roller applied at 0.75 gal/sq. to the insulation or with Sarnacol 2170 adhesive applied at 0.75-2 gal/sq. to the substrate and 0.5 gal/sq. to the back of the membrane or Sarnacol 2170 VC adhesive applied to the substrate at a rate of 0.75 gal/sq. to the substrate and 0.5 gal/sq. to the back of the membrane. The roof cover is immediately placed into the adhesive and the top surface rolled with a weighted roller. Minimum 3" wide side lap is sealed with a minimum 1.25" wide heat weld.



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 16 of 45

-52.5 psf; with Felt membranes (See General Limitation #7) -60.0 psf; with Non-Felt membranes (See General Limitation #7) **Maximum Design**

Pressures:



NOA No.: 14-0624.13 **Expiration Date: 07/05/16** Approval Date: 03/12/15 Page 17 of 45

Deck Description: 18 – 22ga., ASTM A653 Grade 80 steel deck fastened 0.25 in.thick structural supports

spaced 6 ft. o.c. with Traxx 5 fasteners spaced 6 in. o.c. and with side laps fastened with

Traxx 1 fasteners spaced 24 in. o.c.

System Type C(6): All layers of insulation simultaneously fastened; membrane adhered using RhinoBond plate

bonding tool.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer:	<u>Insulation Fasteners</u> (Table 3)	Fastener Density/ft ²
Sarnatherm, H-Shield		
Minimum 1.5" thick	N/A	N/A

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Top Insulation Layer (Optional):	<u>Insulation Fasteners</u> (<u>Table 3)</u>	Fastener Density/ft ²
Any approved cover board listed in Table 2		
Minimum 0.25" thick	4 with 8	See Design Pressure

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sarnafil S327 or Sikaplan bonded to RhinoBond Insulation Plates with RhinoBond Plate bonding tool at 6 seconds per plate so the tool reaches 400°F. Minimum 3" wide side lap is

sealed with a minimum ³/₄" wide heat weld.

	Maximum Pressure	Fastener Spacing	Fastener Row Spacing
Maximum Design Pressures:	-45 psf	2 ft.	3 ft.
	(See General Limitation #7		
	-60 psf	2 ft.	2 ft.
	(See General Limitation #7)		



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 18 of 45

Deck Description: 18 – 22ga., Type B, Grade 40 steel deck fastened with Tek/5 fasteners and 5/8 in. diameter

washers spaced 6 in. o.c. to bar joists at 7ft. spans. Side laps are fastened with Tek/2

fasteners spaced maximum 18 in. o.c.

System Type C(7): All layers of insulation simultaneously fastened; membrane adhered using RhinoBond plate

bonding tool.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

<u>Insulation Layer:</u> <u>Insulation Fasteners</u> <u>Fastener Density/ft²</u> (Table 3)

Sarnatherm, H-Shield

Minimum 1.5" thick 9 with 12 1:4 ft²

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sarnafil S327 or Sikaplan bonded to RhinoBond Insulation Plates with RhinoBond Plate

bonding tool at 6 seconds per plate so the tool reaches 400°F. Minimum 3" wide side lap is

sealed with a minimum 3/4" wide heat weld.

Maximum Design

Pressures: -60.0 psf (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 19 of 45

Deck Description: Minimum 22 ga., Grade 33 steel deck fastened to the 0.25" thick structural supports spaced

maximum 6' o.c. with one #12 ICH Traxx 5 fastener spaced maximum 6 in. o.c. and with

side laps secured with one #10 ICH Traxx 1 fastener spaced 24 in. o.c.

System Type C(8): All layers of insulation simultaneously fastened; membrane adhered using RhinoBond plate

bonding tool.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer: Insulation Fasteners Fastener Density/ft²

<u>(Table 3)</u>

Sarnatherm, H-Shield
Minimum 1.5" thick
4 with 8
See Design Pressure

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sarnafil S327 or Sikaplan bonded to RhinoBond Insulation Plates with RhinoBond Plate

bonding tool at 6 seconds per plate so the tool reaches 400°F. Minimum 3" wide side lap is

sealed with a minimum 3/4" wide heat weld.

Maximum Design

Maximum Pressure Fastener Spacing Fastener Row Spacing

Pressures: -60 psf 2 ft. 2 ft. (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15

Page 20 of 45

Deck Description: 18 ga., Grade 33 steel deck fastened to 0.25 in. thick structural supports spaced 6 ft. o.c. with

Traxx 5 fasteners spaced 6 in. o.c. and with side laps fastened with two Traxx 1 fasteners

spaced 24 in. o.c.

System Type C(9): All layers of insulation simultaneously fastened; membrane adhered using RhinoBond plate

bonding tool.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer:	Insulation Fasteners	Fastener Density/ft ²
	<u>(Table 3)</u>	
Sarnatherm, H-Shield		
Minimum 1.5" thick	N/A	N/A

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Top Insulation Layer (Optional):	Insulation Fasteners	Fastener Density/ft ²
	<u>(Table 3)</u>	
Any approved cover board listed in Table 2		
Minimum 0.25" thick	4 with 8	See Design Pressure

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sarnafil S327 or Sikaplan bonded to RhinoBond Insulation Plates with RhinoBond Plate bonding tool at 6 seconds per plate so the tool reaches 400°F. Minimum 3" wide side lap is

sealed with a minimum ³/₄" wide heat weld.

	Maximum Pressure	Fastener Spacing	Fastener Row Spacing
Maximum Design Pressures:	-45 psf (See General Limitation #7)	12 in.	6 ft.
	-52.5 psf (See General Limitation #7)	12 in.	5 ft.
	-90 psf (See General Limitation #7)	6 in.	6 ft.
	-105 psf (See General Limitation #7)	6 in.	5 ft.



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 21 of 45

Deck Description: 22 ga., Grade 33 steel deck fastened to 0.25 in. thick structural supports spaced 6 ft. o.c.

with two Traxx 5 fasteners and 3/4" thick washers spaced 6 in. o.c. and with side laps fastened with one Traxx 1 fasteners spaced 12 in. o.c. Perimeter securement spaced 12 in. o.c. along the 24 ft length and 6 in. o.c. along the 12 ft length using Traxx/5 fasteners and

3/4" thick washers.

System Type C(10): All layers of insulation simultaneously fastened; membrane bonded.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

<u>Base Insulation Layer:</u>

<u>Insulation Fasteners</u>

(Table 3)

<u>Fastener Density/ft²</u>

Sarnatherm (a), Sarnatherm, Sarnatherm-25 PSI, ACFoam-II, ACFoam-III, ACFoam-IV, H-Shield Minimum: 1.5" thick N/A N/A

Top Insulation Layer:

Insulation Fasteners
(Table 3)

Fastener Density/ft²

DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Roof Board, Invinsa Roof Board, H-Shield HD

Minimum 0.5" thick 3 with 6 1:1 ft²

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Sarnafil S327 Felt or G410 Felt adhered with Sarnacol AD Feltback Membrane Adhesive or

Sarnacol OM Feltback Membrane Adhesive applied in four rows of 0.5" wide ribbons spaced 12" o.c. or adhered with Sarnacol 2170 VC adhesive applied to the substrate in two coats with a total application rate of 2.0 gal/sq. The roof cover is immediately placed into the adhesive and the top surface rolled with a weighted roller. Minimum 3" wide side lap is

sealed with a 1.25" wide heat weld.

Or

(*Not with SECUROCK coverboards*) Sarnafil G410 or S327 adhered with Sarnacol 2170 VC adhesive applied at 0.75 gal/sq. to the substrate and 0.5 gal/sq. to the back of the membrane. The roof cover is immediately placed into the adhesive and the top surface rolled with a weighted roller. Minimum 3" wide side lap is sealed with a 1.25" wide heat

weld.

Maximum Design

Pressure: -120.0 psf. (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 22 of 45

Deck Description: 22ga., ASTM A653 Grade 80 steel deck fastened to 0.25 in. thick structural supports spaced 6

ft. o.c. with two Traxx/5 fasteners, with ¾ in. washers, at each rib spaced 6 in. o.c. in rows above each support 6 ft. o.c. and with side laps fastened with Traxx/1 fasteners spaced 24 in.

o.c.

System Type C(11): All layers of insulation simultaneously fastened; membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Fire Barrier Minimum ¼ "DensDeck, DensDeck Prime, DenDeck DuraGuard Roof Board and

(Optional): SECUROCK Gypsum-Fiber Roof Board

One or more layers of any of the following insulations:

<u>Base Insulation Layer:</u> <u>Insulation Fasteners</u> <u>Fastener Density/ft²</u>

(Table 3)

Sarnatherm, H-Shield

Minimum 1.5" thick

N/A

N/A

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Top Insulation Layer:

Insulation Fasteners
(Table 3)

Fastener Density/ft²

DensDeck Prime, SECUROCK Glass-Mat Roof Board, SECUROCK Gypsum-Fiber Roof Board, Invinsa Roof Board

Minimum 0.25" thick 6 with 8 1:1 ft²

Note: Top insulation layer shall also be adhered with Sarnacol OM Board Adhesive or OlyBond 500 applied in ³/₄-inch ribbons spaced 12-inch o.c. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: (Not with SECUROCK coverboards) Sarnafil G410 or S327 adhered with Sarnacol 2170 VC

adhesive applied to the substrate at 0.75 gal/sq and to the roof cover at 0.5 gal/sq. The roof cover is immediately placed into the adhesive and the top surface rolled with a weighted roller.

Minimum 3" wide side lap is sealed with a 1.25" wide heat weld.

Or

Sarnafil G410 Felt or S327 Felt adhered with Sarnacol 2170 VC adhesive applied to only the substrate in two coats with a total application rate of 2.0 gal/sq. The roof cover is immediately placed into the adhesive and the top surface rolled with a weighted roller. Minimum 3" wide side lap is sealed with a 1.25" wide heat weld.



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 23 of 45 **Maximum Design**

Pressure: -127.5 psf (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 24 of 45 **Membrane Type:** Single Ply, PVC

Deck Type 2I: Steel, Insulated, New Construction

Deck Description: Minimum 18-22 ga, Grade 80 ksi steel deck fastened to 0.25 in. thick structural supports

spaced 5 ft. o.c. with Traxx 5 fasteners spaced 6 in. o.c. and with side laps fastened with two

Traxx 1 fasteners spaced 24 in. o.c.

System Type D(1): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarders:

Sarnavap-10 vapor barrier applied directly to the deck or over the base insulation layer.

(Optional)

Fire Barrier: Minimum 5/8" gypsum, 1/4" DensDeck, or Atlas FR10 or FR50 secured with Dade County (**Optional**) approved insulation fasteners at not less than 2 fasteners for a board with no dimension

approved insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4' and not less than four fasteners for any board with any greater dimension than

4°.

One or more layers of the following insulations:

Insulation Layer: Insulation Fasteners Fastener Density/ft²

(Table 3)

Any approved Polyisocyanurate insulation board listed in Table 2

Minimum 1.5" thick N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sarnafil S327 or Sikaplan attached to deck as specified below.

Fastening: Sarnafastener-XP fasteners with Sarnabars spaced 6" o.c. in rows 12' o.c. maximum fastened

with Sarnafastener #14 spaced 6" o.c. through the field of the membrane and covered with a

7" minimum width cover strip with 1.5" welds on each side.

Maximum Design

Pressures: -45.0 psf. (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 25 of 45

Single Ply, PVC **Membrane Type:** Deck Type 2I: Steel, Insulated

Minimum 18-22 ga., A1008 SS Grade 80 or A653 Grade 80 steel deck is fastened to 0.25 in. **Deck Description:**

thick structural supports, spaced 6' o.c. with Traxx 5 fasteners spaced 6 in. o.c. and with side

laps fastened with Traxx 1 fasteners spaced 24 in. o.c.

Membrane attached over preliminary fastened insulation. System Type D(2):

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Sarnavap-10 or a FM approved vapor barrier applied directly to the deck or over the base **Vapor Retarders:**

insulation layer. (Optional)

Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade County approved Fire Barrier: (Optional)

insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4'

and not less than four fasteners for any board with any greater dimension than 4'.

One or more layers of any of the following insulations:

Fastener Density/ft² **Insulation Layer: Insulation Fasteners**

(Table 3)

Any Approved Insulation listed in Table 2

Minimum 1.5" thick N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Sarnafil S327 or Sikaplan attached to deck as specified below. **Membrane:**

Sarnafastener MAXLoad fasteners spaced 18" o.c. through Sarnarail Polymer Batten Strips **Fastening:**

> spaced maximum 73.25" o.c. within the 5.5" wide side lap. Batten strip splice joints are made by overlapping the batten 24" and securing with two Sarnafastener MAXLoad screws spaced 18" o.c. Laps are sealed with at 1.5" wide heat weld on the outside edge and 1.0"

wide heat weld on the inside edge.

Maximum Design

Pressures: -52.5 psf. (See General Limitation #7)



NOA No.: 14-0624.13 **Expiration Date: 07/05/16** Approval Date: 03/12/15 Page 26 of 45

Membrane Type: Single Ply, Thermoplastic, PVC

Deck Type 2I: Steel, Insulated

Deck Description: Minimum 18, 20 or 22 ga., Wheeling Corrugating Company BW series steel deck meeting

ASTM A611 Grade E or ASTM A446 Grade E is fastened to 0.25 in. thick structural

supports with Traxx 4 or Traxx 5 fasteners spaced 6 in. o.c. and with side laps fastened with

Traxx 1 fasteners spaced 30 in. o.c.

System Type D(3): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarders Sarnavap-10 or a FM approved vapor barrier applied directly to the deck or over the base

(**Optional**): insulation layer.

Fire Barrier Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade County approved insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4'

and not less than four fasteners for any board with any greater dimension than 4'.

One or more layers of the following insulations:

<u>Base Insulation Layer</u> <u>Fastener Type</u> <u>Fastener Density/ft²</u>

Sarnatherm (a), Sarnatherm 25 PSI, ACFoam-III, ACFoam-III, ACFoam Supreme

Minimum 1.3" thick or tapered N/A N/A

Sarnatherm (a), Sarnatherm, Sarnatherm-25 PSI, ACFoam-II, ENRGY 3, ENRGY 3 Plus, ENRGY 3 PSI-25,

ISO 95+ GL, H-Shield

Minimum 1.4" thick or tapered N/A N/A

DensDeck, DensDeck Prime

Minimum 0.25" thick N/A N/A

Approved Perlite Insulation Board (base layer only)

Minimum 0.75" thick N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sarnafil S327 or Sikaplan attached to deck as specified below.

Fastening #1: (Min. 18, 20 or 22 ga. Steel max. 72" support span)

Sarnafastener or SFS Fasteners with approved discs spaced 6" o.c. within the 5.5" side lap

spaced 73" o.c. and sealed with a minimum 1.5" weld.

(Maximum Design Pressure: -52.5 psf. (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15

Page 27 of 45

Fastening #2: (Min. 18, 20 or 22 ga. Steel max. 56" support span)

Sarnafastener with Sarnabars spaced 6" o.c. in rows 12' o.c. maximum fastened with Sarnafastener spaced 6" o.c. through the field of the membrane and covered with a 7"

minimum width cover strip with 1.5" welds on each side.

(Maximum Design Pressure: -52.5 psf. (See General Limitation #7)

Maximum Design

Pressures: See Fastening Pattern. (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15

Page 28 of 45

Single Ply, PVC **Membrane Type:** Deck Type 2I: Steel, Insulated

18 ga., ASTM A653, Grade 33 steel deck fastened to 0.25 in. thick structural supports **Deck Description:**

spaced 6 ft. o.c. with Traxx 5 fasteners spaced 6 in. o.c. and with side laps fastened with two

Traxx 1 fasteners spaced 24 in. o.c.

Membrane attached over preliminary fastened insulation. System Type D(4):

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer: Insulation Fasteners Fastener Density/ft²

(Table 3)

Sarnatherm, H-Shield

Minimum 1.5" thick N/A N/A

Fastener Density/ft² **Top Insulation Layer (Optional): Insulation Fasteners**

(Table 3)

Any Approved Cover Board listed in Table 2

Minimum 0.25" thick N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sikaplan attached to deck as specified below.

Sarnafastener-XP fasteners with Sarnadisc-XPN plates spaced 6 in. o.c. in staggered rows **Fastening:**

spaced 9.5 ft. o.c. Side lap is sealed with minimum ³/₄" wide heat weld.

Maximum Design

-52.5 psf (See General Limitations #7) **Pressures:**



NOA No.: 14-0624.13 **Expiration Date: 07/05/16** Approval Date: 03/12/15

Page 29 of 45

Deck Description: 18 – 22ga., Type B, Grade 40 steel deck fastened with Tek/5 fasteners and 5/8 in. diameter

washers spaced 6 in. o.c. to bar joists at 7 ft. spans. Side laps are fastened with Tek/2

fasteners spaced 18 in. o.c.

System Type D(5): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer: <u>Insulation Fasteners</u> <u>Fastener Density/ft²</u>

<u>(Table 3)</u>

Sarnatherm, H-Shield
Minimum 1.5" thick
N/A
N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sarnafil S327 or Sikaplan attached to deck as specified below:

Fastening: Sarnafasteners-XP fasteners and Sarnadisc XPN plates spaced 6" o.c. within 5" wide side

laps spaced 54.5" o.c. Laps are sealed with a 1.5" heat weld.

Maximum Design

Pressures: -60.0 psf. (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 30 of 45

Deck Description: Minimum 18-22 ga., A1008 SS Grade 80 or A653 SS Grade 80 steel deck is fastened to 0.25

in. thick structural supports, spaced 5.5' o.c. with Traxx 5 fasteners spaced 6 in. o.c. with

side laps fastened with Traxx 1 fasteners spaced 24 in. o.c.

System Type D(6): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarders

Sarnavap-10 or a FM approved vapor barrier applied directly to the deck or over the base

(Optional):

insulation layer.

Fire Barrier (Optional):

Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade County approved insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4'

and not less than four fasteners for any board with any greater dimension than 4'.

One or more layers of any of the following insulations:

<u>Base Insulation Layer:</u> <u>Insulation Fasteners</u> <u>Fastener Density/ft²</u>

(Table 3)

ENRGY 3

Minimum 1.5" thick N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sikaplan attached to deck as specified below.

Fastening: Sarnafastener-XP fasteners and Sarnadisc-XPN plates spaced 6" o.c. within 5.5" wide laps

spaced 114.5" o.c. Laps are sealed with a 1.75" wide heat weld on outside edge of lap.

Maximum Design

Pressures: -60.0 psf. (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 31 of 45

Deck Description: Minimum 18-22 ga., A1008 SS Grade 80 or A653 SS Grade 80 steel deck is fastened to 0.25

in. thick structural supports, spaced 5.5' o.c. with Traxx 5 fasteners spaced 6 in. o.c. with

side laps fastened with Traxx 1 fasteners spaced 24 in. o.c.

System Type D(7): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarders Sarnavap-10 or a FM approved vapor barrier applied directly to the deck or over the base

(**Optional**): insulation layer.

Fire Barrier Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade County approved (**Optional**): insulation fasteners at not less than 2 fasteners for a board with no dimension greater than

4' and not less than four fasteners for any board with any greater dimension than 4'.

One or more layers of any of the following insulations:

Base Insulation Layer: Insulation Fasteners (Table 3) Fastener Density/ft²

ENRGY 3

Minimum 1.5" thick N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sarnafil S327 attached to deck as specified below with Sarnarail Polymer Batten Strips.

Fastening: Sarnafastener-XP fasteners spaced 6" o.c. through batten strip spaced maximum 144" o.c.

within the 5.5" wide side lap. Batten strip splice joints are made by overlapping the batten 12" and securing with two Sarnafastener XP screws spaced 6" o.c. Laps are sealed with at 1.5" wide heat weld on the outside edge and 1.0" wide heat weld on the inside edge.

Maximum Design

Pressures: -60.0 psf. (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 32 of 45

Deck Description: Minimum 18-22 ga., A1008 SS Grade 80 or A653 SS Grade 80, Type B, steel deck fastened

to structural supports spaced 5.5' o.c. with Traxx 5 fasteners spaced 6 in. o.c. and with side

laps secured with Traxx 1 fasteners spaced 24 in. o.c.

System Type D(8): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarders Sarnavap-10 or a FM approved vapor barrier applied directly to the deck or over the base

(Optional): insulation layer.

Fire Barrier Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade County approved (Optional): insulation fasteners at not less than 2 fasteners for a board with no dimension greater than

4' and not less than four fasteners for any board with any greater dimension than 4'.

One or more layers of any of the following insulations:

<u>Insulation Layer:</u> <u>Insulation Fasteners</u> <u>Fastener Density/ft²</u>

(Table 3)

Sarnatherm (a), Sarnatherm-25 PSI, ACFoam-II

Minimum 1.5" thick or tapered N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sikaplan attached to deck as specified below.

Fastening: Sarnafastener MAXLoad fasteners and ³/₄" wide Sarnarail Polymer Batten Strip spaced 6"

o.c. within 5.5" wide side laps spaced maximum 114.5" o.c. Batten Strip is lapped 8" within lap to provide a minimum 2 screw securement in lap. Laps are sealed with a minimum 1.25" wide outside edge heat weld and minimum 0.75" wide inside edge heat

weld.

Maximum Design

Pressures: -75.0 psf (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 33 of 45

Single Ply, PVC **Membrane Type:** Deck Type 2I: Steel, Insulated

Minimum 18-22 ga., 1.5 in. deep, Type B wide rib steel deck fastened to 0.25 in. thick **Deck Description:**

structural supports spaced 6' o.c. with Traxx 5 fasteners spaced 6 in. o.c. and with side laps

secured with Traxx 1 fasteners spaced 24 in. o.c.

Membrane attached over preliminary fastened insulation. System Type D(9):

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Sarnavap-10 or a FM approved vapor barrier applied directly to the deck or over the base **Vapor Retarders**

insulation layer. (Optional):

Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade County approved Fire Barrier (Optional):

insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4'

and not less than four fasteners for any board with any greater dimension than 4'.

One or more layers of any of the following insulations:

Fastener Density/ft² **Base Insulation Layer: Insulation Fasteners**

(Table 3)

Sarnatherm (a), Sarnatherm-25 PSI, ACFoam-II

Minimum 1.5" thick or tapered N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sikaplan attached to deck as specified below.

Sarnafastener-XP fasteners and Sarnadisc XPN plates spaced 6" o.c. within 5.5" wide side **Fastening #1:**

laps spaced maximum 114.5" o.c. Laps are sealed with a minimum 0.5" wide outside edge

heat weld.

Maximum Design Pressure -45 psf. (See General Limitation #7)

Sarnafastener MAXLoad fasteners and Sarnadisc MAXLoad plates spaced 6" o.c. within 7" **Fastening #2:**

wide side laps spaced maximum 113" o.c. Laps are sealed with a minimum 0.875" wide

outside edge heat weld.

Maximum Design Pressure -60 psf (See General Limitation #7)

Maximum Design

See Fastening Pattern. (See General Limitation #7) **Pressures:**



NOA No.: 14-0624.13 **Expiration Date: 07/05/16** Approval Date: 03/12/15 Page 34 of 45

Deck Description: Minimum 18-22 ga., A1008 SS Grade 80 or A653 SS Grade 80, Type B, steel deck fastened

to structural supports spaced 6' o.c. with Traxx 5 fasteners spaced 6 in. o.c. and with side

laps secured with Traxx 1 fasteners spaced 24 in. o.c.

System Type D(10): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarders

Sarnavap-10 or a FM approved vapor barrier applied directly to the deck or over the base

(Optional):

insulation layer.

Fire Barrier (Optional):

Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade County approved insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4'

and not less than four fasteners for any board with any greater dimension than 4'.

One or more layers of any of the following insulations:

<u>Insulation Layer:</u> <u>Insulation Fasteners</u> <u>Fastener Density/ft²</u>

(Table 3)

Sarnatherm (a), Sarnatherm-25 PSI, ACFoam-II

Minimum 1.5" thick or tapered N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sikaplan attached to deck as specified below.

Fastening #1: Sarnafastener MAXLoad fasteners and ³/₄" wide Sarnarail Polymer Batten Strip spaced 12"

o.c. within 5.5" wide side laps spaced maximum 114.5" o.c. Batten Strip is lapped 14" within lap to provide a minimum 2 screw securement in lap. Laps are sealed with a minimum 1.25"

wide outside edge heat weld and minimum 0.75" wide inside edge heat weld.

Maximum Design Pressure -45.0 psf (See General Limitation #7)

Fastening #2: Sarnafastener-XP fasteners or OMG Large Head #15 Roofgrip fasteners and ³/₄" wide

Sarnarail Polymer Batten Strip spaced 6" o.c. within 5.5" wide side laps spaced maximum 114.5" o.c. Batten Strip is lapped 8" within lap to provide a minimum 2 screw securement in lap. Laps are sealed with a minimum 1.25" wide outside edge heat weld and minimum 0.75"

wide inside edge heat weld.

Maximum Design Pressure -60.0 psf. (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 35 of 45 **Fastening #3:**

Sarnafastener MAXLoad fasteners and ¾" wide Sarnarail Polymer Batten Strip spaced 6" o.c. within 5.5" wide side laps spaced maximum 114.5" o.c. Batten Strip is lapped 8" within lap to provide a minimum 2 screw securement in lap. Laps are sealed with a minimum 1.25" wide outside edge heat weld and minimum 0.75" wide inside edge heat weld.

Maximum Design Pressure -67.5 psf (See General Limitation #7)

Maximum Design

Pressures: See Fastening Pattern. (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 36 of 45

Deck Description: Minimum 18-22 ga., A1008 SS Grade 80 or A653 SS Grade 80 steel deck fastened to

structural supports spaced 6' o.c. with Traxx 5 fasteners spaced 6 in. o.c. and with side laps

fastened with Traxx 1 fasteners spaced 24 in. o.c.

System Type D(11): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarders

Sarnavap-10 or a FM approved vapor barrier applied directly to the deck or over the base

(Optional):

insulation layer.

Fire Barrier (Optional):

 $\label{eq:minimum 5/8} Minimum 5/8"\ Type\ X\ Gypsum\ ,\ 1/4"\ Dens Deck\ secured\ with\ Dade\ County\ approved\ insulation\ fasteners\ at\ not\ less\ than\ 2\ fasteners\ for\ a\ board\ with\ no\ dimension\ greater\ than$

4' and not less than four fasteners for any board with any greater dimension than 4'.

One or more layers of the following insulations:

<u>Insulation Layer:</u> <u>Insulation Fasteners</u> <u>Fastener Density/ft²</u>

(Table 3)

Sarnatherm, H-Shield

Minimum 1.3" thick or tapered N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sikaplan attached to deck as specified below with Sarnarail Polymer Batten Strips spaced at

114.5" o.c. within a 5.5" wide lap.

Fastening #1: Sarnafastener-XP fasteners spaced 6" o.c. through batten strip. Batten strip is lapped 8" and

sealed with a 1.25" wide heat weld on outside edge and a 0.75" wide heat weld on inside

edge

Maximum Design Pressure -52.5 psf. (See General Limitation #7)

Fastening #2: Sarnafastener MAXLoad fasteners spaced 12" o.c. through batten strip. Batten strip is

lapped 14" and sealed with a 1.25" wide heat weld on outside edge and a 0.75" wide heat

weld on inside edge.

Maximum Design Pressure -52.5 psf. (See General Limitation #7)

Fastening #3: Sarnafastener MAXLoad fasteners spaced 6" o.c. through batten strip. Batten strip is lapped

8" and sealed with a 1.25" wide heat weld on outside edge and a 0.75" wide heat weld on

inside edge.

Maximum Design Pressure -67.5 psf. (See General Limitation #7)

Maximum Design

Pressures: See Fastening Pattern. (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 37 of 45

Single Ply, PVC **Membrane Type:** Deck Type 2I: Steel, Insulated

Minimum 18-22 ga., A1008 SS Grade 80 or A653 Grade 80 steel deck is fastened to 0.25 in. **Deck Description:**

thick structural supports, spaced 6' o.c. with Traxx 5 fasteners spaced 6 in. o.c. and with side

laps fastened with Traxx 1 fasteners spaced 24 in. o.c.

Membrane attached over preliminary fastened insulation. System Type D(12):

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Sarnavap-10 or a FM approved vapor barrier applied directly to the deck or over the base **Vapor Retarders:**

insulation layer. (Optional)

Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade County approved Fire Barrier: (Optional)

insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4'

and not less than four fasteners for any board with any greater dimension than 4'.

One or more layers of any of the following insulations:

Fastener Density/ft² **Insulation Layer: Insulation Fasteners**

(Table 3)

ACFoam-II, Sarnatherm (a), Sarnatherm-25 PSI, ACFoam-II

Minimum 1.5" thick or tapered N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sarnafil S327 or Sikaplan attached to deck as specified below with.

Sarnafastener MAXLoad fasteners spaced 18" o.c. through Sarnarail Polymer Batten Strips **Fastening #1:**

> spaced maximum 73.25" o.c. within the 5.5" wide side lap. Batten strip splice joints are made by overlapping the batten 24" and securing with two Sarnafastener MAXLoad screws spaced 18" o.c. Laps are sealed with at 1.5" wide heat weld on the outside edge and 1.0"

wide heat weld on the inside edge.

Maximum Design Pressure -45.0 psf. (See General Limitation #7)

Fastening #2: Sarnafasteners-XP fasteners spaced 12" o.c. through Sarnarail Polymer Batten Strips spaced

> maximum 73.25" o.c. within the 5.5" wide side lap. Batten strip splice joints are made by overlapping the batten 18" and securing with two Sarnafastener XP screws spaced 12" o.c. Laps are sealed with at 1.5" wide heat weld on the outside edge and 1.0" wide heat weld on

the inside edge.

Maximum Design Pressure -45.0 psf. (See General Limitation #7)



NOA No.: 14-0624.13 **Expiration Date: 07/05/16** Approval Date: 03/12/15 Page 38 of 45

Fastening #3:

Sarnafasteners-XP fasteners spaced 6" o.c. through Sarnarail Polymer Batten Strips spaced maximum 144" o.c.* within the 5.5" wide side lap. Batten strip splice joints are made by overlapping the batten 12" and securing with two Sarnafastener XP screws spaced 6" o.c. Laps are sealed with at 1.5" wide heat weld on the outside edge and 1.0" wide heat weld on the inside edge.

* Row spacing of 144" o.c. is not applicable for Sikaplan

Maximum Design Pressure -52.5 psf. (See General Limitation #7)

Fastening #4:

Sarnafasteners-XP fasteners spaced 6" o.c. through Sarnarail Polymer Batten Strips spaced maximum 73.25" o.c. within the 5.5" wide side lap. Batten strip splice joints are made by overlapping the batten 12" and securing with two Sarnafastener XP screws spaced 6" o.c. Laps are sealed with at 1.5" wide heat weld on the outside edge and 1.0" wide heat weld on the inside edge.

Maximum Design Pressure -75.0 psf. (See General Limitation #7)

Maximum Design

Pressures: See Fastening Pattern. (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 39 of 45

Deck Description: 22ga., ASTM A653, Grade 80 steel deck fastened with 0.25 in. thick structural supports

spaced 6 ft. o.c. with Traxx 5 fasteners spaced 6 in. o.c. and with side laps fastened with

Traxx 1 fasteners spaced 24 in. o.c.

System Type D(13): Membrane attached over preliminary fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer: Insulation Fasteners (Table 3) Fastener Density/ft²

Sarnatherm (a), Sarnatherm 25 PSI, ACFoam-II

Minimum 1.5" thick N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sarnafil S327 or Sikaplan attached to deck as specified below:

Fastening: Sarnafil MAXLoad or Sarnafastener Maxload fasteners and Sarnadisc MAXLoad Plates

spaced 6" o.c. within 7" wide side laps spaced 53" o.c. Laps are sealed with a 1.25" heat

weld.

Maximum Design

Pressures: -105.0 psf. (See General Limitation #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 40 of 45

Single Ply, PVC **Membrane Type:**

Deck Type 2I: Steel, Insulated, New Construction

Minimum 18-22 ga., A1008 SS Grade 80 steel deck fastened to supports at 6' o.c. with **Deck Description:**

Traxx 5 fasteners spaced 6 in. o.c. and with side laps fastened with Traxx 1 fasteners spaced

24 in. o.c.

Membrane attached over preliminary fastened insulation. System Type D(14):

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Sarnavap-10 or a FM approved vapor barrier applied directly to the deck or over the base **Vapor Retarders:**

insulation layer. (Optional)

Minimum 5/8" Type X Gypsum, 1/4" DensDeck secured with Dade County approved Fire Barrier: (Optional)

insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4'

and not less than four fasteners for any board with any greater dimension than 4'.

One or more layers of any of the following insulations:

Insulation Layer: Insulation Fasteners Fastener Density/ft²

(Table 3)

Sarnatherm (a), Sarnatherm-25 PSI, ACFoam-II

Minimum 1.5" thick or tapered N/A N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sarnafil S327 or Sikaplan attached to deck as specified below.

Fastening #1: Sarnafastener MAXLoad fasteners and Sarnarail Polymer Batten Strip spaced 24" o.c. within

5.5" wide side laps spaced maximum 54" o.c. Laps are sealed with a minimum 1" wide

outside heat weld and a minimum 5/8" wide inside heat weld.

Maximum Design Pressure -45.0 psf. (See General Limitation #7)

Sarnafastener MAXLoad fasteners and Sarnadisc MAXLoad plates spaced 24" o.c. within **Fastening #2:**

6.5" wide side laps spaced maximum 53" o.c. Laps are sealed with a minimum 1.6" wide

outside heat weld.

Maximum Design Pressure -45.0 psf. (See General Limitation #7)

Fastening #3: Sarnafasteners-XP fasteners and Sarnarail Polymer Batten Strip spaced 12" o.c. within 5.5"

wide side laps spaced maximum 54" o.c. Laps are sealed with a minimum 1" wide outside

heat weld and a minimum 5/8" wide inside heat weld.

Maximum Design Pressure -52.5 psf. (See General Limitation #7)



NOA No.: 14-0624.13 **Expiration Date: 07/05/16** Approval Date: 03/12/15 Page 41 of 45

Fastening #4: Sarnafastener MAXLoad fasteners and Sarnarail Polymer Batten Strip spaced 18" o.c. within

5.5" wide side laps spaced maximum 54" o.c. Laps are sealed with a minimum 1" wide

outside heat weld and a minimum 5/8" wide inside heat weld.

Maximum Design Pressure -52.5 psf. (See General Limitation #7)

Fastening #5: Sarnafastener MAXLoad fasteners and Sarnadisc MAXLoad plates spaced 18" o.c. within

6.5" wide side laps spaced maximum 53" o.c. Laps are sealed with a minimum 1.6"" wide

outside heat weld.

Maximum Design Pressure -52.5 psf. (See General Limitation #7)

Fastening #6: Sarnafasteners-XP fasteners and Sarnadic XPN plates spaced 12" o.c. within 5.5" wide side

laps spaced maximum 54" o.c. Laps are sealed with a minimum 1.6" wide outside heat weld.

Maximum Design Pressure -60.0 psf. (See General Limitation #7)

Fastening #7: Sarnafastener MAXLoad fasteners and Sarnadisc MAXLoad plates spaced 12" o.c. within

6.5" wide side laps spaced maximum 53" o.c. Laps are sealed with a minimum 1.6"" wide

outside heat weld.

Maximum Design Pressure -60.0 psf. (See General Limitation #7)

Fastening #8: Sarnafastener MAXLoad fasteners and Sarnarail Polymer Batten Strip spaced 12" o.c. within

5.5" wide side laps spaced maximum 54" o.c. Laps are sealed with a minimum 1" wide

outside heat weld and a minimum 5/8" wide inside heat weld.

Maximum Design Pressure -67.5 psf. (See General Limitation #7)

Fastening #9: Sarnafasteners-XP fasteners and Sarnadic XPN plates spaced 6" o.c. within 5.5" wide side

laps spaced maximum 54" o.c. Laps are sealed with a minimum 1.6" wide outside heat weld.

Maximum Design Pressure -90.0 psf. (See General Limitation #7)

Fastening #10: Sarnafastener MAXLoad fasteners and Sarnadisc MAXLoad plates spaced 6" o.c. within

6.5" wide side laps spaced maximum 53" o.c. Laps are sealed with a minimum 1.6"" wide

outside heat weld.

Maximum Design Pressure -105.0 psf. (See General Limitation #7)

Fastening #11: Sarnafastener MAXLoad fasteners and Sarnarail Polymer Batten Strip spaced 6" o.c. within

5.5" wide side laps spaced maximum 54" o.c. Laps are sealed with a minimum 1" wide

outside heat weld and a minimum 5/8" wide inside heat weld.

Maximum Design Pressure -112.5 psf. (See General Limitation #7)

Maximum Design

Pressures: See Fastening Pattern. (See General Limitation #7)

FM 3028309, Conclusion 9.1: Allows the use of Sikaplan 45mil membrane as an alternate to S327 in mechanically attached systems.



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 42 of 45

Deck Description: Minimum 18-22 ga., Grade E steel deck shall be secured to 1/4" thick structural supports

spaced a maximum of 6 ft on centers with ITW Buildex Traxx/5 at the bottom of each rib

(6" o/c.)

System Type D(15): Membrane attached over preliminary fastened insulation.

The following assembly is approved to a maximum design pressure listed with specific fastening patterns. No substitutions shall be made. All General and System Limitations apply.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Vapor Retarders

Sarnavap-10 or a FM approved vapor barrier applied directly to the deck or over the base

(Optional):

insulation layer.

Fire Barrier (Optional):

Minimum 5/8" Type X Gypsum or 1/4" DensDeck secured with Dade County approved insulation fasteners at not less than 2 fasteners for a board with no dimension greater than 4'

and not less than four fasteners for any board with any greater dimension than 4'.

One or more of the following.

Insulation for Base Layer

Fastener Type

Fastener Density/ft²

Sarnatherm (a), Sarnatherm, Sarnatherm 25 PSI, ACFoam-III, ACFoam-III, ACFoam Supreme, H-Shield

Minimum 1.3" thick or tapered

N/A

N/A

Sarnatherm (a), Sarnatherm, Sarnatherm-25 PSI, ACFoam-II, ENRGY 3, ENRGY 3 Plus, ENRGY 3 PSI-25,

ISO 95+ GL, H-Shield

Minimum 1.4" thick or tapered

N/A

N/A

DensDeck, DensDeck Prime

Minimum 1/4" thick

N/A

N/A

Approved Perlite Insulation Board (base layer only)

Minimum 3/4" thick

N/A

N/A

Note: All insulation shall have preliminary attachment, prior to the installation of the roofing membrane at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Sarnafil S327 or Sikaplan attached to deck as specified below.

Fastening #1: Sarnafastener-XP screws and plates spaced 12" o.c. within 6" wide side laps. Laps spaced

72.5" o.c. and pre-sealed with a shop welded 0.75" wide heat weld on the inside of the lap

and a 1.5" wide heat weld on the outside of the lap.

Maximum Design Pressure -45.0 psf. (See General Limitations #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 43 of 45 **Fastening #2:** Sarnafastener-XP screws and plates spaced 12" o.c. within 5.5" wide side laps. Laps spaced

72.5" o.c. and sealed with a 1.5" wide heat weld.

Maximum Design Pressure -45.0 psf. (See General Limitations #7)

Fastening #3: Sarnafastener-XP screws with 2" Sarnadisc- plates spaced 6" o.c. within 5.5" wide side laps.

Laps spaced 73" and sealed with a 1.5" wide heat weld.

Maximum Design Pressure -45.0 psf. (See General Limitations #7)

Fastening #4: Sarnafastener-XP screws and plates spaced 6" o.c. within 6" wide side laps. Laps spaced

72.5" o.c. and sealed with a 1.5" wide heat weld.

Maximum Design Pressure -75.0 psf. (See General Limitations #7)

Fastening #5: Sarnabars spaced 3' o.c. maximum fastened with Sarnafastener-XP spaced 6" o.c. through

the field of the membrane and covered with a 7" minimum width cover strip with 1.5" welds

on each side.

Maximum Design Pressure -112.5 psf. (See General Limitations #7)

Maximum Design

Pressures: See Fastening Pattern. (See General Limitations #7)



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 44 of 45

STEEL DECK SYSTEM LIMITATIONS:

- If mechanical attachment to the structural deck through the lightweight insulating concrete is proposed, a field
 withdrawal resistance testing shall be performed to determine equivalent or enhanced fastener patterns and density.
 All testing and fastening design shall be in compliance with Testing Application Standard TAS 105 and Roofing
 Application Standard RAS 117 and/or RAS 137; calculations shall be signed and sealed by a Florida Registered
 Engineer, Architect, or Registered Roof Consultant.
- 2. For steel deck application where specific deck construction is not referenced: The deck shall be a minimum 22 gage attached with 5/8" puddle welds with weld washers at every flute with maximum deck spans of 5 ft. o.c.

GENERAL LIMITATIONS:

- 1. Fire classification is not part of this acceptance; refer to a current Approved Roofing Materials Directory for fire ratings of this product.
- 2. Insulation may be installed in multiple layers. The first layer shall be attached in compliance with Product Control Approval guidelines. All other layers shall be adhered in a full mopping of approved asphalt applied within the EVT range and at a rate of 20-40 lbs./sq., or mechanically attached using the fastening pattern of the top layer
- 3. All standard panel sizes are acceptable for mechanical attachment. When applied in approved asphalt, panel size shall be 4' x 4' maximum.
- 4. An overlay and/or recovery board insulation panel is required on all applications over closed cell foam insulations when the base sheet is fully mopped. If no recovery board is used the base sheet shall be applied using spot mopping with approved asphalt, 12" diameter circles, 24" o.c.; or strip mopped 8" ribbons in three rows, one at each side lap and one down the center of the sheet allowing a continuous area of ventilation. Encircling of the strips is not acceptable. A 6" break shall be placed every 12' in each ribbon to allow cross ventilation. Asphalt application of either system shall be at a minimum rate of 12 lbs./sq. Note: Spot attached systems shall be limited to a maximum design pressure of -45 psf.
- 5. Fastener spacing for insulation attachment is based on a Minimum Characteristic Force (F') value of 275 lbf., as tested in compliance with Testing Application Standard TAS 105. If the fastener value, as field-tested, are below 275 lbf. Insulation attachment shall not be acceptable.
- 6. Fastener spacing for mechanical attachment of anchor/base sheet or membrane attachment is based on a minimum fastener resistance value in conjunction with the maximum design value listed within a specific system. Should the fastener resistance be less than that required, as determined by the Building Official, a revised fastener spacing, prepared, signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant may be submitted. Said revised fastener spacing shall utilize the withdrawal resistance value taken from Testing Application Standards TAS 105 and calculations in compliance with Roofing Application Standard RAS 117.
- 7. Perimeter and corner areas shall comply with the enhanced uplift pressure requirements of these areas. Fastener densities shall be increased for both insulation and base sheet as calculated in compliance with Roofing Application Standard RAS 117 and/or RAS 137. Calculations prepared, signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant (When this limitation is specifically referred within this NOA, General Limitation #9 will not be applicable.)
- 8. All attachment and sizing of perimeter nailers, metal profile, and/or flashing termination designs shall conform to Roofing Application Standard RAS 111 and applicable wind load requirements.
- 9. The maximum designed pressure limitation listed shall be applicable to all roof pressure zones (i.e. field, perimeters, and corners). Neither rational analysis, nor extrapolation shall be permitted for enhanced fastening at enhanced pressure zones (i.e. perimeters, extended corners and corners). (When this limitation is specifically referred within this NOA, General Limitation #7 will not be applicable.)
- 10. All products listed herein shall have a quality assurance audit in accordance with the Florida Building Code and Rule 61G20-3 of the Florida Administrative Code.

END OF THIS ACCEPTANCE



NOA No.: 14-0624.13 Expiration Date: 07/05/16 Approval Date: 03/12/15 Page 45 of 45