

DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER) BOARD AND CODE ADMINISTRATION DIVISION

MIAMI-DADE COUNTY PRODUCT CONTROL SECTION 11805 SW 26 Street, Room 208 Miami, Florida 33175-2474 T (786) 315-2590 F (786) 315-2599

www.miamidade.gov/economy

# NOTICE OF ACCEPTANCE (NOA)

Cast-Crete USA, Inc. P.O. Box 24567 Tampa, Florida 33623

#### Scope:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER- Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the High Velocity Hurricane Zone of the Florida Building Code.

DESCRIPTION: "Cast-Crete" 8 inch High Strength Precast and Prestressed Concrete Lintels

APPROVAL DOCUMENT: Drawing No. FD8, titled "Cast-Crete 8" Lintel Fabrication Details", sheets 1 through 3 of 3, prepared by Craig Parrino, P.E., dated June 7, 1996, last revision dated June 12, 2014, signed and sealed by Craig Parrino, P.E., on August 19, 2014, bearing the Miami-Dade County Product Control Revision stamp with the Notice of Acceptance number and the expiration date by the Miami-Dade County Product Control Section.

MISSILE IMPACT RATING: Large and Small Missile Impact Resistant

**LABELING:** Each lintel shall bear a permanent label with the manufacturer's name or logo and the Miami-Dade County logo.

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA revises NOA # 12-0209.13 and consists of this page 1, evidence submitted pages E-1, E-2, E-3, & E-4 as well as approval document mentioned above.

The submitted documentation was reviewed by Helmy A. Makar, P.E., M.S.

(MIAMI-DADE COUNTY)
| APPROVED

Hely A. Nlh

NOA No. 14-0903.02 Expiration Date: 05/21/2016 Approval Date: 10/09/2014 Page 1

# NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

# 1. EVIDENCE SUBMITTED UNDER PREVIOUS APPROVAL #96-0613.01

#### A. DRAWINGS

1. Drawing No. FD8, titled "Cast-Crete 8" Lintel Fabrication Details", prepared by Craig Parrino, P.E., dated 06/07/96, revision #1 dated 11/08/96, sheet 1 of 1, and Drawing No. LT8, titled "Cast-Crete 8" Lintel Safe Load Tables", prepared by Craig Parrino, P.E., dated 06/07/97, revision #4 dated 04/28/98, sheet 1 of 1, both drawings signed and sealed by Craig Parrino, P.E.

#### B. TESTS

1. Test report on flexural testing on Precast and Prestressed Concrete Lintels Filled Models, total of (36) concrete lintel specimens, per ASTM E-529-94, prepared by Applied Research Laboratories, Report No. 29702B, dated 07/30/97, signed and sealed by Christopher A. Hamon, P.E.

# C. CALCULATIONS

1. Calculations for Cast-Crete 8-inch Lintels, dated 06/06/96, 349 pages, prepared by Craig Parrino, P.E., signed and sealed by Craig Parrino, P.E.

2. Calculations for Cast-Crete 8-inch Lintels, dated 11/11/96, 45 pages, prepared by Craig Parrino, P.E., signed and sealed by Craig Parrino, P.E.

## D. MATERIAL CERTIFICATIONS

1. Mill Certified Inspection Report Silo #4 dated April 1996 for cement by Southdown Brooksville Cement Laboratory.

2. Mill Certified Inspection Report #20-8275 dated 06/20/95 for prestressing strand by The Crispin Company.

3. Mill Certified Inspection Report #20-8345 dated 11/13/95 for prestressing strand by The Crispin Company.

4. Mill Certified Inspection Report #2111-078240 dated 04/25/96 for #3 rebar by Ameristeel.

5. Mill Certified Inspection Report #84-M19614 dated 02/29/96 for #5 rebar by Birmingham Steel Corp.

6. Mill Certified Inspection Report #58-A66332 dated 01/28/96 for #4 rebar by Birmingham Steel Corp.

7. Mill Certified Inspection Report #84-M20749 dated 04/05/96 for #5 rebar by Birmingham Steel Corp.

8. Mill Certified Inspection Report #84-M19805 dated 03/06/96 for #4 rebar by Birmingham Steel Corp.

9. Mill Certified Inspection Report #84-M21208 dated 04/21/96 for #4 rebar by Birmingham Steel Corp.

10. Mill Certified Inspection Report #84-M20652 dated 04/03/96 for #5 rebar by Birmingham Steel Corp.

Helmy A. Makar, P.E., M.S. Product Control Unit Supervisor

NOA No. 14-0903.02

Expiration Date: 05/21/2016, Approval Date: 10/09/2014

# Cast-Crete USA, Inc.

# NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

- 11. Mill Certified Inspection Report #84-M20749 dated 04/05/96 for #5 rebar by Birmingham Steel Corp.
- 12. Quality Control Manual for Cast-Crete Machine Made Precast Lintels dated 05/14/96.
- 13. Quality Control Manual for Prestressed Products dated 03/20/95.
- 2. EVIDENCE SUBMITTED UNDER PREVIOUS APPROVAL #01-0209.03
- A. DRAWINGS
  - 1. None.
- B. TESTS
  - 1. None.
- C. CALCULATIONS
  - 1. None.
- D. MATERIAL CERTIFICATIONS
  - 1. None.
- 3. EVIDENCE SUBMITTED UNDER PREVIOUS APPROVAL # 03-0605.05
- A. DRAWINGS:
  - 1. Drawing No. FD8, titled "Cast-Crete 8" Lintel Fabrication Details", sheet 1 of 1, prepared by Craig Parrino, P.E., dated June 7, 1996, revision #2 dated January 28, 2003, and Drawing No. LT8, titled "Cast-Crete 8" Lintel Safe Load Tables", sheets 1 & 2 of 2, prepared by Craig Parrino, P.E., dated June 7, 1996, revision #5 dated March 24, 2003, all drawings are signed and sealed by Craig Parrino, P.E.
- B. TESTS:
  - 1. Test report on flexural testing on Precast Concrete Lintels Filled Models, total of (12) concrete lintel specimens, per ASTM E-529-94, prepared by Applied Research Laboratories, Report No. 30404B, dated 04/23/03, signed and sealed by Christopher A. Hamon, P.E.
- C. CALCULATIONS:
  - 1. Calculations for Cast-Crete High Strength Precast and Prestressed 8-inch Lintels, dated May 29, 2003, sheets 1.1 through 1.493 and 2.1 through 2.336, prepared by Craig Parrino, P.E., signed and sealed by Craig Parrino, P.E.
- D. MATERIAL CERTIFICATION:
  - 1. Quality System Manual for Cast-Crete Machine Made Precast Lintels revised on May 01, 2002.
  - 2. Cast-Crete Quality System Manual for Prestressed Products dated 2002.

Helmy A. Makar, P.E., M.S. Product Control Unit Supervisor

roduct Control Unit Supervisor NOA No. 14-0903.02

**Expiration Date: 05/21/2016 Approval Date: 10/09/2014** 

#### Cast-Crete USA, Inc.

#### NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

#### 4. EVIDENCE SUBMITTED UNDER PREVIOUS APPROVAL #06-0222.01

#### A. DRAWINGS

1. Drawing No. FD8, titled "Cast-Crete 8" Lintel Fabrication Details", sheets 1 through 3 of 3, prepared by Craig Parrino, P.E., dated June 7, 1996, last revision dated February 17, 2006, signed and sealed by Craig Parrino, P.E.

#### B. TESTS

1. None.

#### C. CALCULATIONS

1. None.

#### D. QUALITY ASSURANCE

1. By Miami-Dade Building Code Compliance Office.

#### E. MATERIAL CERTIFICATION

1. None.

#### F. OTHER

1. Letter from Cast-Crete Corporation, dated 02/20/2006, signed by Craig Parrino, P.E.

#### 5. EVIDENCE SUBMITTED UNDER PREVIOUS APPROVAL # 11-0121.04

#### A. DRAWINGS

1. None.

#### B. TESTS

1. None.

## C. CALCULATIONS

1. None.

#### D. QUALITY ASSURANCE

1. By Miami-Dade Building and Neighborhood Compliance Department (BNC).

#### E. MATERIAL CERTIFICATION

None.

## F. OTHER

1. Letter from Cast-Crete Corporation, dated January 18, 2011, signed by Craig Parrino, P.E., certifying compliance with the Florida Building Code, 2007 Edition.

Hermy A. Makar, P.E., M.S.

Product Control Unit Supervisor NOA No. 14-0903.02

> Expiration Date: 05/21/2016 Approval Date: 10/09/2014

# Cast-Crete USA, Inc.

# NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

#### 6. EVIDENCE SUBMITTED UNDER PREVIOUS APPROVAL #12-0209.13

#### A. DRAWINGS

1. Drawing No. FD8, titled "Cast-Crete 8" Lintel Fabrication Details", sheets 1 through 3 of 3, prepared by Craig Parrino, P.E., dated June 7, 1996, last revision dated February 17, 2006, signed and sealed by Craig Parrino, P.E., March 22, 2012.

#### B. TESTS

1. None.

#### C. CALCULATIONS

l. None.

#### D. OUALITY ASSURANCE

1. By Miami-Dade County Department of Permitting, Environment, and Regulatory Affairs.

#### E. MATERIAL CERTIFICATION

1. None.

#### F. OTHER

1. Letter from Cast-Crete Corporation, dated 02/03/2012, signed and sealed by Craig Parrino, P.E., certifying compliance with the Florida Building Code, 2010 Edition.

#### 7. NEW EVIDENCE SUBMITTED

#### A. DRAWINGS

1. Drawing No. FD8, titled "Cast-Crete 8" Lintel Fabrication Details", sheets 1 through 3 of 3, prepared by Craig Parrino, P.E., dated June 7, 1996, last revision dated June 12, 2014, signed and sealed by Craig Parrino, P.E., on August 19, 2014.

#### B. TESTS

1. None.

#### C. CALCULATIONS

1. Calculations for High Strength Precast and Prestressed 8-inch Lintels, dated August 19, 2014, sheets 14.101 through 14.124, prepared, signed and sealed by Craig Parrino, P.E.

## D. QUALITY ASSURANCE

1. By Miami-Dade County Department of Regulatory and Economic Resources (RER).

#### E. MATERIAL CERTIFICATION

1. None.

#### F. OTHER

1. Letter from Cast-Crete USA, Inc., dated August 19, 2014, signed and sealed by Craig Parrino, P.E., certifying compliance with the Florida Building Code, 2014 Edition.


Helmy A. Makar, P.E., M.S.

Product Control Unit Supervisor NOA No. 14-0903.02

**Expiration Date: 05/21/2016 Approval Date: 10/09/2014** 



PRESTRESSED CONCRETE LINTELS




8" PRECAST W/ 2" RECESS DOOR U-LINTEL

8" PRECAST U-LINTEL


8" PRESTRESSED U-LINTEL


MEMBER OF


NATIONAL CONCRETE MASONRY





PRESTRESSED LINTEL REINFORCING CAGE FABRICATION MODEL











8"	PRESTRESSED	U-L	INTEL	DATA	<b>TABLE</b>

LINTEL	VOLUME	WEIGHT		TEEL	" В " ТОР			NO. OF
SIZE	CY	LBS	TYPE	LENGTH	TYPE	LENGTH '	SPACING	STIRRUPS
14'-8"	0.134	542	7/32 BAR	1'-3"	7/32 BAR	14'-6"	4 9 3'-0"	9
15'-4"	0.140	567	7/32 BAR	1'-3"	7/32 BAR	15'-2"	4 @ 3'-2"	9
17'-4"	0.158	639	7/32 BAR	1'-3"	7/32 BAR	17'-2"	4 😝 3'-8"	9
19'-4"	0.176	713	7/32 BAR	1'-3"	7/32 BAR	19'-2"	4 @ 4'-2"	9
21'-4"	0.194	787	7/32 BAR	1'-3"	7/32 BAR	21'-2"	5 @ 3'-8 3/4"	10
21 -4	0.134	/0/	4 REBAR MIDSPAN	15 -0	7702 0111		3 9 3 3 37 7	
22'-0"	0.200	811	7/32 BAR	1'-3"	7/32 DAD	211-10"	5 @ 3'-10 3/8"	10
22 -0	0.200	611	4 REBAR DIOSPAN	10 ~0	7752 DAK	21 10	0 0 0 10 0,0	, ,
24'-0"	0.010	000	7/32 BAR	1'-3"	7/32 040	23'-10"	5 @ 4'-3 1/8"	10
24 -0	0.219	885	#4 REBAR	18'-0"	1/32 BAK	23 - 10	3 9 4 -3 1/6	'

# 8" PRECAST W/ 2" RECESS DOOR U-LINTEL DATA TABLE

LINTEL SIZE	OVERALL LENGTH	RECESS LENGTH	VOLUME	WEIGHT LBS	" A " BOTT	OM STEEL LENGTH	" B " TO	STEEL LENGTH	"C" SPACING	STIRRUPS
2'-8"	41-411	3'-0"	0.036	146	#3 REBAR	3'-10" PLUS HOOK	7/32 BAR	3'-8"	N/A	4
3'-0"	4'-6"	3'-4"	0.037	150	#3 REBAR	PLUS HOOK	7/32 BAR	3'-10"	N/A	4
4'-0"	5'-8"	4'-4"	0.047	190	#3 REBAR	PLUS HOOK		5'-0"	N/A	6
4'-4"	5'-10"	4'-8"	0.047	190	#3 REBAR	PLUS HOOK	7/32 BAR	5'-2"	N/A	6
5'-0"	6'-8"	5'-4"	0.054	219	#4 REBAR	PLUS HOOK	#3 REBAR		N/A	6
6'-0"	7'-6"	6'-4"	0.060	243	#4 REBAR	PLUS ROOK	#3 REBAR	6'-10"	N/A	6
8'-0"	9'-8"	8'-4"	0.078	316	#4 REBAR	PLUS ROOK	#3 REBAR	9'-0"	2'-0"	8

# PRECAST U-LINTEL DATA TABLE

- 1	LINTEL	VOLUME	WEIGHT I		OM SIEEL		2 SIEEL	1	STRUTS/
1	SIZE	ĊŸ	LBS	TYPE	LENGTH	TYPE	LENGTH	SPACING	<u>stirrups</u>
t	3'-6"	0.032	126	#3 REBAR	3'-5"	7/32 BAR	3'-2"	N/A	4
ı	4'-0"	0.037	144	#3 REBAR	3'-11"	7/32 BAR	3'-8"	N/A	4
ŀ	4'-6"	0.041	162	#3 REBAR	4'−5"	7/32 BAR	4'-2"	N/A	4
İ	5'-4"	0.049	192	#3 REBAR	5'-3"	7/32 BAR	5'-0"	N/A	6
ŀ	5'-10"	0.054	210	#3 REBAR	5'-9"	7/32 BAR	5'-6"	N/A	6
ţ	6'-6"	0.060	234	#4 REBAR	6'-5"	7/32 BAR	6'-2"	N/A	6
İ	7'-6"	0.069	270	#4 REBAR	7'-5"	7/32 BAR	7'-2"	N/A	6
ı	9'-4"	0.086	336	#4 REBAR	9'-3"	#3 REBAR	9'-0"	2'-0"	
ł	10'-6"		378	#4 REBAR	10'-5"	#3 REBAR	10'-2"	2'-0"	
١	11'-4"		408	#5 REBAR		#3 REBAR	11'-0"	3'-0"	
ı	12'-0"		432	#5 REBAR	11'-11"	#3 REBAR	11'-8"	3'-0"	
١	13'-4"	0.122	480	#5 REBAR	13'-3"	#3 REBAR	13'-0"	3'-0"	
١	14'-0"		504	#5 REBAR	13'-11"	#3 REBAR	13'-8"	3'-0"	' 8

THIS PROPRIETARY INFORMATION IS PROVIDED FOR PRODUCT APPROVAL. IT IS PROTECTED BY COPYRIGHT LAWS AND CANNOT BE REPRODUCED OR DISTRIBUTED WITHOUT THE PRIOR WRITTEN CONSENT OF CAST-CRETE USA, INC.

# **GENERAL NOTES:**

- REINFORCING STEEL: 7/32 BAR ASTM AS10; #3, #4, 5, NOTE: THE TOTAL NUMBER OF STIRRUPS AND #5 REBAR GRADE 60 ASTM A615; 7/16 INCH DIAMETER 270KSI LOW-RELAXATION PRESTRESSING SRTAND ASTM A416.
- . CONCRETE STRENGTHS: f'c = 6000 PSI FOR 8" PRESTRESSED LINTELS; f'c = 4000 PSI FOR ALL PRECAST 8 INCH LINTELS.
- 3. INITIAL PRESTRESS FORCE = 0.70 x fpu.
- REQUIRED IS COUNTED STARTING FROM EACH END OF THE REINFORCING CAGE; FOR EXAMPLE - NO. OF STIRRUPS = 4, THEN THE REINFORCING CAGE MODEL SHOWS 2 STIRRUPS FROM EACH END.
- 6. 2.5 POUNDS OF POLYPROPYLENE FIBERS PER CU.YD. OF CONCRETE MAY BE USED IN LIEU OF PRESTRESSED LINTEL REINFORCING CAGE TO RESIST LIFTING AND HANDLING FORCES.



PRODUCT REVISED as complying with the Florida Hullding Code Acceptance No 14-0903.02 Biophysical Date 05/21/2016

CRAIG PARRINO 6324 CR 579 SEFFNER, FL 33584

Miemi Dade Product Control

FL. P.E. LIC. NO. 44756

OTLE: CAST—C	RETE 8	3"	LINTEL	FABRICATIO	N	DETAILS

NOT TO SCALE SCALE: FILE NAME: DBSUB1-14 CRAIG PARRINO, P.E. - REG. NO. 44756 CHECKED BY: CRAIG PARRINO, P.E. - REG. NO. 44756 DRAWING No. FDB SHEET 1 OF 3 06/07/96

#### SAFE GRAVITY LOADS FOR 8" PRECAST & PRESTRESSED U-LINTELS

Cast-Casts.		SAFE LOAD - POUNDS PER LINEAR FOOT								
TYPE	0110	8F8-0B	8F12-0B	8F16-08	8F20-0B	8F24-0B	8F28-0B	8F32-0B		
LENGTH	8U8	8F8-1B	8F121B	8F16-1B	8F20-1B	8F24-1B	8F28-1B	8F321B		
7' A" (40") PREGIOT	0074	3069	3719	5163	6607	8054	9502	10951		
3'-6" (42") PRECAST	2231	3069	4605	6113	7547	8974	10394	11809		
4'-0" (48") PRECAST	1000	2561	2751	3820	4890	5961	7034	8107		
4 -0 (46) FRECASI	1966	2693	4605	6113	7547	8974	10394	11809		
4'-6" (54") PRECAST	1599	1969	2110	2931	3753	4576	5400	6224		
· o (or) Theories	1099	2189	4375	6113	7547 (1)	8672	10294	11809		
5'-4" (64") PRECAST	1217	1349	1438	1999	2560	3123	3686	4249		
3 4 (04) TRECAST	1217	1663	3090	5365	7547 (36)	7342(19)	8733(19)	10127(19)		
5'-10" (70") PRECAST	1062	1105	1173	1631	2090	2549	3009	3470		
0 10 (70 ) TALONSI	1002	1451	2622	4360	7168 (45)	6036(19)	7181(19)	8328 (20)		
6'-6" (78") PRECAST	908	1238	2177	3480	3031	3707	4383	5061		
	300	1238	2177	3480	5381	8360	10394(37)	8825 (11)		
7'-6" (90") PRECAST	743	1011	1729	2632	2205	2698	3191	3685		
7 0 (30) TRECAST	740	1011	1729	2661	3898	5681	8467 (44)	6472 (15)		
9'-4" (112") PRECAST	554	699	1160	1625	2564	3486	2818	3302		
	JJ4	752	1245	1843	2564	3486	4705(31)	6390 (47)		
10'-6" (126") PRECAST	475	535	890	1247	2093	2777	2163	2536		
10 0 (120 ) 1 Hzb/101	473	643	1052	1533	2093	2781	3643(33)	4754 (45)		
11'-4" (136") PRECAST	362	582	945	1366	1846	2423	3127	4006		
11 1 (100 ) 1 KEOKS1	302	582	945	1366	1846	2423	3127	4006		
12'-0" (144") PRECAST	337	540	873	1254	1684	2193	2805	3552		
12 0 (144 ) TREONST	337	540	873	1254	1684	2193	2805	3552		
13'-4" (160") PRECAST	296	471	755	1075	1428	1838	2316	2883		
100 / 1120/131	230	471	755	1075	1428	1838	2316	2883		
14'-0" (168") PRECAST	279	424	706	1002	1326	1697	2127	2630		
77 0 (100) 1120/101	273	442	706	1002	1326	1697	2127	2630		
14'-8" (176") PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR .		
1, 3 (1,0)	11.11.	458	783	1370	1902	2245	2517	2712		
15'-4" (184") PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR		
(, ,	7 11111	412	710	1250	1733	2058	2320	2513		
17'-4" (208") PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR		
, ,		300	548	950	1326	1609	1849	2047		
19'-4" (232") PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR		
		235	420	750	1037	1282	1515	1716		
21'-4" (256") PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR		
		180	340	598	845	1114	1359	1468		
22'-0" (264") PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR		
	,	165	315	550	784	1047	1285	1399		
24'-0" (288") PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR		
· ,	''''	129	250	450	654	884	1092	1222		

<sup>(#)</sup> THE NUMBERS IN PARENTHESIS ARE PERCENT REDUCTIONS FOR GRADE 40 FIELD ADDED REBAR. SEE GENERAL NOTE NO. 4 ON SHEET 3 OF 3.

# SAFE LATERAL LOADS FOR 8" PRECAST & PRESTRESSED U-LINTELS

Cast-Casts.	SA	AFE LO PLF	AD
TYPE LENGTH	8U8	8F8	RCMU *
3'-6" (42") PRECAST	1025	1024	1598
4'-0" (48") PRECAST	765	763	1309
4'-6" (54") PRECAST	592	591	1073
5'-4" (64") PRECAST	411	411	745
5'-10" (70") PRECAST	340	339	616
6'-6" (78") PRECAST	507	721	490
7'-6" (90") PRECAST	424	534	363
9'-4" (112") PRECAST	326	512	230
10'-6" (126") PRECAST	284	401	180
11'-4" (136") PRECAST	260	452	154
12'-0" (144") PRECAST	244	402	137
13'-4" (160") PRECAST	217	324	110
14'-0" (168") PRECAST	205	293	100
14'-8" (176") PRESTRESSED	N.R.	284	91
15'-4" (184") PRESTRESSED	N.R.	259	83
17'-4" (208") PRESTRESSED	N.R.	194	64
19'-4" (232") PRESTRESSED	N.R.	148	52
21'-4" (256") PRESTRESSED	N.R.	125	42
22'-0" (264") PRESTRESSED	N.R.	116	40
24'-0" (288") PRESTRESSED	N.R.	91	33

<sup>\*</sup> SEE GENERAL NOTE NO. 18 ON SHEET 3 OF 3.

# SAFE UPLIFT LOADS FOR 8" PRECAST & PRESTRESSED U-LINTELS

<b>€</b> as	r-Cuara.	SAFE LOAD - POUNDS PER LINEAR FOOT							
	TYPE	8F8-1T	8F121T	8F16-1T	8F20-1T	8F24-1T	8F28-1T	8F32-1	
LENGTH		8F8-2T	8F12-2T	8F16-2T	8F20-2T	8F24-2T	8F28-2T	8F32-2	
21 All / All	1 2254.55	1569	2655	3524	4394	5263	6132	7001	
3'-6" (42"	) PRECAST	1569	2655	3524	4394	5263	6132	7001	
41 On (400	\	1363	2305	3060	3815	4570	5325	6079	
4'-0" (48"	) PRECAST	1363	2305	3060	3815	4570	5325	6079	
4'-6" (54"	) PRECAST	1207	2040	2707	3375	4043	4711	5379	
4-0 (34	) FREUASI	1207	2040	2707	3375	4043	4711	5379	
C1 4" /C4"	) DDECACT	1016	1715(11)	2276 (4)	2838	3399	3961	4522	
5'-4" (64"	) PRECASI	1016	1715	2276	2838	3399	3961	4522	
5'-10" (70"	\ DDFC&CT	909	1567(18)	2080(13)	2593 (9)	3107 (6)	3620 (1)	4133	
3-10 (70	) FREUASI	929	1567	2080	2593	3107	3620	4133	
6'-6" (78"	) PRECAST	835 (12)	1407(26)	1868(21)	2329 (18)	2790(16)	3251(14)	3712	
0-0 (/0	TILLUMOI	835	1407	1868	2329	2790	3251	3712	
7' C" /00"	\ nncolet	727 (23)	1065(26)	1624(31)	2025 (28)	2426(26)	2827 (25)	3228	
7 -6 (90	) PRECAST	727	1224	1624	2025	2426	2827	3228	
9'-4" (112	)"\ DDECACT	591	708 <sub>(25)</sub>	1136(34)	1474 (34)	1815(34)	2157(31)	2500	
3 -4 (112	FILLOASI	591	862	1318	1643	1969	2294	2619	
10' 6"/126	"\ DDECACT	530	575 (24)	916 (33)	1188 (33)	1461(33)	1736 (33)	2011	
10 -0 (120	o") Precast	530	695	1180 (8)	1472 (4)			2346	
41' 4" (170	·»\ DDEOACT	474	504 (23)	800 (32)	1037 (32)			† <del></del>	
11'-4" (136	) PRECASI	494	607	1042(10)	1372 (11)			2187	
40' 0"/444	יי) החרמונים	470 (9)	458 (23)			1153(32)			
12 -0 (144	+") PRECAST	470	550	940 (10)	1302 (15)	1560(13)	1818(11)	2075	
171 41/100	n) DDECACT	418 (15)	386 (22)	607 (30)			1143(31)	1	
13 -4 (100	)") PRECAST	428	460	780 (s)	1159 (21)	1418(20)	1653(19)	1887	
441 0"/400	ייי/ מחבר אכד	384 (15)	358 (21)	560 (29)				1220	
14 -0 (100	3") PRECAST	410	425	717 (9)	1063 (21)	1358(23	1582 (22)	1807	
441 011/17/	·»\ DDECTDECCED	239	334 (21)						
14 -8 (1/0	") PRESTRESSED	246	395	663 (9)	980 (20)				
4E1 /"/40/	"\ DDESTDESSEN	224	313 (20)					<del></del>	
15 -4 (184	") PRESTRESSED	230	368	616 (a)			t	1	
17' 4"/200	3") PRESTRESSED	187	263 (19)						
17 -4 (200	) PRESINESSED	192	306	506 (8)	740 (19	1005(27			
10'_4" (23'	2") PRESTRESSED	162	229 (17)	<del> </del>					
10 -4 (202	- ) TINESTRESSED	166	263	429 (6		-	1		
21'_1" (254	6") PRESTRESSED	142	204 (16	1			1	1	
21-4 (230	)   FINESTRESSED	142	232	373 tr		1			
22'_n" (26)	4") PRESTRESSED	137	197 (15)	1		T			
22 -0 (20	+ ) ENESTRESSED	137	223	358 [7				ı	
04' 0" (000	an) DDECTDECCED	124	179 (14	1				4	
24 -U (288	B") PRESTRESSED	124	202	319 (r		1			

AN PARENTHESIS ARE PERCENT REDUCTIONS FOR GRADE 40 EE GENERAL NOTE NO. 4 ON SHEET 3 OF 3.

**CRAIG PARRINO** 6324 CR 579 SEFFNER, FL 33584 FL. P.E. LIC. NO. 44756

PRODUCT REVISED as complying with the Movida Building Code Acceptance No /4

SEE GENERAL NOTES - SHEET 3 OF 3 REVISION DATE

MEMBER OF



CAST-CRETE 8" LINTEL FABRICATION DETAILS

FILE NAME:	DBSUB2-14	DRAWN BY:	CRAIG PARRINO, P.E REG. NO. 44756	SCALE: NOT TO SCALE
DATE:	06/07/98	CHECKED BY:	CRAIG PARRINO, P.E REG. NO. 44756	DRAWING No. FD8 SHEET 2 OF 3

#### SAFE GRAVITY LOADS FOR 8" PRECAST w/ 2" RECESS DOOR U-LINTELS

<b>€</b> ∞st	-Crara	SAFE LOAD - POUNDS PER LINEAR FOOT								
	TYPE		8RF6-08	8RF10-0B	8RF14-08	8RF18-0B	8RF22-0B	8RF26-0B	8RF30~0B	
LENGTH		8RU6	8RF6-18	8RF10-1B	8RF14-18	8RF18-1B	8RF22-1B	8RF26-1B	8RF30-1B	
4' 4" /50")	DDECACT	1635	1749	3355	3280	4349	5421	6493	7567	
4'-4" (52")	PRECASI	1033	1891	3699	5206	6639	8060	9479	10893	
4' 6" (E4")	PRECAST	1404	1596	3063	2992	3968	4946	5924	6904	
4'-6" (54")	PRECASI	1494	1756	3699	5206	6639	8060	9479	10893	
5'-8" (68")	PRECAST	866	920	1770	1716	2277	2839	3402	3966	
3 0 (00)	TILONST		1167	2481	4567	6389	8060(34)	7917(19)	9311(19)	
5'-10" (70")	PRECAST	810	859	1653	1600	2124	2649	3174	3700	
0 10 (70 )			1113	2342	4242	6639 (10)	8060(39)	7402(19)	8706 (19)	
6'-8" (80")	PRECAST	797	901	1825	3120	5048	7747	9448	7360	
0 -0 (00)	FILLOASI	797	901	1825	3120	5048	7915	9479	10893(32)	
7'-6" (90")	PRECAST	669	755	1490	2459	3776	5743	7239	5623	
/ -0 (90)	I NECASI	009	755	1490	2459	3776	5743	8998(19)	10893(48)	
9'-8" (116"	) PRECAST	411	466	999	1568	2253	3129	4091	3146	
0 0 (110	) I NEOADI	411	526	999	1568	2253	3129	4150	5891 (47)	

(#) THE NUMBERS IN PARENTHESIS ARE PERCENT REDUCTIONS FOR GRADE 40 FIELD ADDED REBAR, SEE GENERAL NOTE NO. 4

#### SAFE LATERAL LOADS FOR 8" PRECAST w/ 2" RECESS DOOR U-LINTELS

CAST-CASTS	SAFE LOAD PLF				
TYPE LENGTH	8RU6	8RF6	RCMU *		
4'-4" (52") PRECAST	758	757	1164		
4'-6" (54") PRECAST	694	693	1073		
5'-8" (68") PRECAST	408	407	655		
5'-10" (70") PRECAST	382	381	616		
6'-8" (80") PRECAST	595	788	464		
7'-6" (90") PRECAST	509	674	363		
9'-8" (116") PRECAST	370	490	214		

\* SEE GENERAL NOTE 18

# SAFE UPLIFT LOADS FOR 8" PRECAST w/ 2" RECESS DOOR U-LINTELS

Cast	-Çaara	SAFE LOAD - POUNDS PER LINEAR FOOT								
	TYPE		8RF10-1T	8RF14-1T	8RF18-1T	8RF22-1T	8RF26-1T	8RF30-1T		
LENGTH		8RF6-2T	8RF10-2T	8RF14-2T	8RF18-2T	8RF22-2T	8RF26-2T	8RF30-21		
41 4" (EO")	DDFCACT	905	1668	2362	3056	3751	4445	5140		
4'-4" (52")	PRECASI	905	1668	2362	3056	3751	4445	5140		
4'-6" (54")	PRFCAST	867	1604	2272	2939	3607	4275	4943		
4 -6 (34)	PRECASI	867	1604	2272	2939	3607	4275	4943		
5'-8" (68")	PRECAST	675	1269(16)	1797	2326 (5)	2854 (2)	3382	3911		
3 0 (00)		675	1269	1797	2326	2854	3382	3911		
5'-10" (70")	PRECAST	655	1207 <sub>(16)</sub>	1746(11)	2259 (7)	2773 (5)	3286 <sub>(3)</sub>	2799 (1)		
0 10 (70 /	TILLOAST	655	1233	1746	2259	2773	3286	2799		
6'-8" (80")	DDCCACT	570	929 (16)	1530(22)	1980 (19)	2429(16)	2879(15)	3329 (14)		
0 -6 (60)	FINECAST	570	1080	1530	1980	2429	2879	3329		
7'-6" (90")	DRECAST	506	742 (16)	1364(30)	1765 (27)	2166(25)	2567(24)	2968 (23)		
7 -0 (30)	PREUASI	506	898	1364	1765	2166	2567	2968		
9'-8" (116")	PRFCAST	395	468 (15)	884 (32)	1222 (33)	1540(34)	1859 (34)	2180 (34		
3 3 (110)	TALOAST	395	560	1072	1386	1701	2016	2331		

(#) THE NUMBERS IN PARENTHESIS ARE PERCENT REDUCTIONS FOR GRADE 40 FIELD ADDED REBAR. SEE GENERAL NOTE NO. 4

#### GENERAL NOTES

- 1) Materials:

  - f'c 8" precost lintel = 4000 psi
     f'c prestressed lintel = 6000 psi
     f'c prestressed lintel = 6000 psi
     f'c grout = 3000 psi with maximum 3/8 inch aggregate
     concrete masonry units (CMU) per ASTM C90 with minimum net orea compressive strength = 1900 psi
     rebor per ASTM A615 Grade 60
     prestressing strand per ASTM A416 Grade 270 low relaxation
     mortor per ASTM C270 Type M or S
- 2) All safe load tables based on minimum 4 inch nominal bearing.

  <u>Exception:</u> Safe loads for lintel type 8U8 and 8RU6 must be reduced by 20% if bearing length is less than 6 1/2 inches.
- 3) Provide full mortar bed and head joints.
- 4) The number in parenthesis indicates the percent reduction for grade 40 field added rebor.

Example: 7'-6" Lintel 8F32-18 sofe gravity load = 6472 (15)  $\frac{15\%}{15\%}$  reduction  $\frac{1}{2}$  6472 (.85) = 5501 plf


- 5) All lintels meet or exceed L/360 deflection.


  <u>Exception:</u> Prestress lintel type 8F8 17'-4" and longer meets or exceeds L/180 deflection. Use is limited to conditions meeting the Florida Building Code Sections 1604.3.1 as applicable
- 6) Shore filled lintels as required.
- 7) One #7 rebor may be substituted for two #5 rebors.
- 8) Installation/attachment of lintel must comply with the architectural and/or structural documents.
- The designer may evaluate concentrated loads from the safe load tables by calculating the maximum resisting moment and shear at d-away from the face of support.
- 11) Bottom field added rebor to be located at the bottom of the lintel cavity.

- 12) Lintels are manufactured with 5-1/2" long notches at the ends to accompdate vertical cell reinforcing and grouting.
- 13) The exterior surface of lintels installed in exterior concrete masonry walls shall have a coating of stucco applied in accordance with ASTM C-926 or other approved coating.
- 14) Lintels loaded simultaneously with vertical (gravity or uplift) and horizontal (lateral) loads should be checked for the combined loading with the following equation: +  $\frac{\text{Applied horizontal load}}{\text{Safe horizontal load}} \le 1.0$
- 15) For composite lintel heights not shown, use safe load from next lower height shown.
- 16) For lintel lengths not shown, use safe load from next longest length shown.
- 17) Safe loads are superimposed allowable loads.

Safe vertical load

- 18) Safe loads based on rational design analysi per ACI 530 and ACI 318
- 19) Additional lateral load copacity can be obtained by the designer by providing additional reinforced concrete masonry units (RCMU) above the lintel. See sketch below:





TITLE:

- F = FILLED WITH GROUT / U = UNFILLEDQUANTITY OF #5 REBAR AT BOTTOM OF LINTEL CAVITY NOMINAL WIDTH -QUANTITY OF #5 NOMINAL HEIGHT REBAR AT TOP #5 REBAR AT TOP MIN. (1) REQ'D 1-1/2" CLEAR C.M.U. GROUT #5 REBAR AT BOTTOM OF LINTEL CAVITY BOTTOM REINFORCING PROVIDED IN LINTEL
(VARIES) 7-5/8" ACTUAL 8" NOMINAL WIDTH

TYPE DESIGNATION

PRODUCT REVISED as complying with the Plorida Building Code Acceptance No 14 Expiration Date 257

Millin Dade Product Control

**CRAIG PARRINO** 6324 CR 579 SEFFNER, FL 33584 FL. P.E. LIC. NO. 44756

CAST-CRETE 8" LINTEL FABRICATION DETAILS

FILE NAME: DBSUB3-14 DRAWN BY: CRAIG PARRINO, P.E. - REG. NO. 44756 SCALE: NOT TO SCALE DATE: 06/07/96 CHECKED BY: CRAIG PARRINO, P.E. - REG. NO. 44756 DRAWING No. FD8 SHEET 3 OF 3

MEMBER OF

