



DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)
BOARD AND CODE ADMINISTRATION DIVISION

MIAMI-DADE COUNTY
PRODUCT CONTROL SECTION
11805 SW 26 Street, Room 208
T (786) 315-2590 F (786) 315-2599

NOTICE OF ACCEPTANCE (NOA)

www.miamidade.gov/economy

Aldora Aluminum & Glass Products, Inc.
11500 Miramar Parkway, Suite 300
Miramar, FL 33025

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER-Product Control Section to be used in Miami-Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami-Dade County) and/ or the AHJ (in areas other than Miami-Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Series " SMI-090" Aluminum Window Wall System – L.M.I.

APPROVAL DOCUMENT: Drawing No. W09-24, titled "Series SMI-090 Alum Window Wall (L.M.I.)", sheets 01 through 13 plus 13.1 and 13.2 of 15, dated 04/16/09, with revision "D" dated 03/05/14, prepared by Al-Farooq Corporation, signed and sealed by Javad Ahmad, P. E., bearing the Miami-Dade County Product Control Renewal stamp with the Notice of Acceptance number and Expiration date by the Miami-Dade County Product Control Section.

MISSILE IMPACT RATING: Large and Small Missile Impact Resistant

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state, series, and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

REVISION of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/ or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA renews NOA No. 13-1224.03 and consists of this page 1 and evidence pages E-1, E-2 and E-3, as well as approval document mentioned above.

The submitted documentation was reviewed by Jaime D. Gascon, P. E.



J. Gascon
3/25/15

NOA No. 15-0120.01
Expiration Date: May 12, 2020
Approval Date: April 02, 2015
Page 1

Aldora Aluminum & Glass Products, Inc.

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

A. DRAWINGS

1. Manufacturer's die drawings and sections.
(Submitted under previous NOA's No.'s 13-1224.03 and 10-0401.03)
2. Drawing No. W09-24, titled "Series SMI-090 Alum Window Wall (L.M.I.)", sheets 1 through 13 plus 13.1 and 13.2 of 15, dated 04/16/09, with revision "D" dated 03/05/14, prepared by Al-Farooq Corporation, signed and sealed by Javad Ahmad, P. E.
(Submitted under previous NOA No. 13-1224.03)

B. TESTS

1. Test reports on:
 - 1) Air Infiltration Test per FBC, TAS 202-94
 - 2) Uniform Static Air Pressure Test Loading per FBC, TAS 202-94
 - 3) Water Resistance Test per FBC, TAS 202-94along with marked-up drawings and installation diagram of window wall system, prepared by Fenestration Testing Laboratory, Inc., Test Report No. FTL-7336, dated 05/22/13, signed and sealed by Jorge A. Naya, P. E.
(Submitted under previous NOA No. 13-1224.03)
2. Test reports on:
 - 1) Air Infiltration Test per FBC, TAS 202-94
 - 2) Uniform Static Air Pressure Test Loading per FBC, TAS 202-94
 - 3) Water Resistance Test per FBC, TAS 202-94
 - 4) Large Missile Impact Test per FBC, TAS 201-94
 - 5) Cyclic Wind Pressure Loading per FBC, TAS 203-94
 - 6) Forced Entry Test, per FBC 2411 3.2.1, TAS 202-94along with marked-up drawings and installation diagram of window wall system, prepared by Fenestration Testing Laboratory, Inc., Test Report No. FTL-5746, dated 01/27/09, signed and sealed by Carlos S. Rionda, P. E.
(Submitted under previous NOA No. 10-0128.03)

C. CALCULATIONS:

1. Anchor verification calculations and structural analysis, complying with FBC, prepared by Al-Farooq Corporation, dated 08/15/13, signed and sealed by Javad Ahmad, P. E.
(Submitted under previous NOA No. 13-1224.03)
2. Glazing complies with ASTM E1300-04/ 09.

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER)



Jaime D. Gascon, P. E.
Product Control Section Supervisor
NOA No. 15-0120.01
Expiration Date: May 12, 2020
Approval Date: April 02, 2015

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

E. MATERIAL CERTIFICATIONS

1. Notice of Acceptance No. **14-0423.16** issued to **Eastman Chemical Company (MA)** for their "**Saflex HP Clear or Color Glass Interlayers**" dated 06/19/14, expiring on 04/14/18.
2. Notice of Acceptance No. **13-1126. 20** issued to **Allnex USA, Inc.** for their "**Uvekol S Laminated Glass Interlayer**", dated 02/20/14, expiring on 02/08/19.

F. STATEMENTS

1. Department of State Certification of **ALDORA ALUMINUM & GLASS PRODUCTS, INC.** as a for foreign profit corporation, active and organized under the laws of the State of Florida, dated March 10, 2015 and filed by the Secretary of State.
2. Statement letter of conformance to, of complying with **FBC 5th Edition (2014)**, and of no financial interest, dated 04/03/14, signed and sealed by Javad Ahmad, P. E.
(Submitted under NOA No. 13-1224.03)
3. Statement letter of conformance to, of complying with **FBC-2010**, and of no financial interest, dated 08/16/13, signed and sealed by Javad Ahmad, P. E.
(Submitted under NOA's No.'s 12-0201.07 and 13-1224.03)
4. Statement letter dated 08/21/13, issued by Aldora Aluminum & Glass Products, Inc. of legally purchase of asset and rights of **NOA No. 12-0731.06** from SMI Aluminum System, LLC and requesting that said NOA be issued under their name, signed by Manny Valladares, for and on behalf of Aldora Aluminum & Glass Products, Inc.
(Submitted under NOA No. 13-1224.03)
5. Letter from owners of existing NOA stating that they have sold all assets to the applicant, that they no longer manufacture the product and relinquish their rights to the current **NOA No. 12-0731.06**, dated 08/21/13, signed by Mr. Manny Valladares, for and on behalf of SMI Aluminum Systems, LLC.
(Submitted under NOA No. 13-1224.03)
6. Assignment & Assumption agreement dated July 26, 2013 between Aldora Holdings LLC, SMI Aluminum Systems, LLC, Architectural Glass Products, LLC (each an "Assignor" and collectively, the "Assignors") and Aldora Holdco, Inc. (the "Assignee") signed by Leon Silverstein, Aldora Holdings LLC manager; Leon Silverstein, SMI Aluminum Systems, LLC, manager; Leon Silverstein, Architectural Glass Products, LLC manager and Scott Hauncher, VP Aldora Holdco, Inc.
(Submitted under NOA No. 13-1224.03)
7. Bill of Sale dated July 26, 2013, delivered by Aldora Holdco, Inc. transferring assets to Aldora Aluminum & Glass Products, Inc., signed by Mr. Scott Hauncher, Vice President, Aldora Holdco, Inc.
(Submitted under NOA No. 13-1224.03)



Jaime D. Gascon, P. E.
Product Control Section Supervisor
NOA No. 15-0120.01
Expiration Date: May 12, 2020
Approval Date: April 02, 2015

Aldora Aluminum & Glass Products, Inc.

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

F. STATEMENTS (CONTINUED)


8. Department of State Certification of **ALDORA ALUMINUM & GLASS PRODUCTS, INC.** as a for foreign profit corporation, active and organized under the laws of the State of Delaware, dated July 18, 2013 and signed by Jeffrey W. Bullock, Secretary of State.
(Submitted under NOA No. 13-1224.03)
9. Department of State Certification of **ALDORA ALUMINUM & GLASS PRODUCTS, INC.** as a for foreign profit corporation, active and organized under the laws of the State of Florida, dated July 20, 2013 and signed by T. Burgh, Secretary of State.
(Submitted under NOA No. 13-1224.03)
10. Laboratory compliance letter for Test Report No. **FTL-7336**, issued by Fenestration Testing Laboratory, Inc., dated 05/22/13, signed and sealed by Jorge A. Naya, P. E.
(Submitted under NOA No. 13-1224.03)
11. Laboratory compliance letter for Test Report No. **FTL-5746**, issued by Fenestration Testing Laboratory, Inc., dated 01/27/09, signed and sealed by Carlos S. Rionda P. E.
(Submitted under previous NOA No.10-0128.03)
12. Proposal No. **08-0557** issued by the Product Control, dated 06/18/08, signed by Manuel Perez, P. E.
(Submitted under previous NOA No. 10-0128.03)

G. OTHERS

1. Notice of Acceptance No. **13-1224.03**, issued to Aldora Aluminum & Glass Products, Inc. for their Series "**SMI-090 Aluminum Window Wall System - L.M.I.**", approved on 04/17/14 and expiring on 06/02/15.



Jaime D. Gascon, P. E.
Product Control Section Supervisor
NOA No. 15-0120.01
Expiration Date: May 12, 2020
Approval Date: April 02, 2015



TYPICAL ELEVATIONS

SERIES SMI-090 ALUMINUM WINDOW WALL

THIS SYSTEM MAY BE USED IN CONJUNCTION WITH MIAMI-DADE COUNTY APPR'D LARGE MISSILE IMPACT RESISTANT DOORS. LOWER DESIGN PRESSURE FROM STOREFRONT OR DOOR APPROVAL WILL APPLY TO ENTIRE SYSTEM.

CODE REQUIREMENTS FOR SAFEGUARDS MUST BE OBSERVED.

THIS PRODUCT HAS BEEN DESIGNED AND TESTED TO COMPLY WITH THE REQUIREMENTS OF THE FLORIDA BUILDING CODE INCLUDING HIGH VELOCITY HURRICANE ZONE (HVHZ).

WOOD BUCKS BY OTHERS, MUST BE ANCHORED PROPERLY TO TRANSFER LOADS TO THE STRUCTURE.

ANCHORS SHALL BE AS LISTED, SPACED AS SHOWN ON DETAILS, ANCHORS EMBEDMENT TO BASE MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO.

ANCHORING OR LOADING CONDITIONS NOT SHOWN IN THESE DETAILS ARE NOT PART OF THIS APPROVAL.

A LOAD DURATION INCREASE IS USED IN DESIGN OF ANCHORS INTO WOOD ONLY.

MATERIALS INCLUDING BUT NOT LIMITED TO STEEL/METAL SCREWS, THAT COME INTO CONTACT WITH OTHER DISSIMILAR MATERIALS SHALL MEET THE REQUIREMENTS OF THE FLORIDA BLDG. CODE SECTION 2003.8.4.

PRODUCT RENEWED
as complying with the Florida
Building Code
Acceptance No. **15-0120.01**
Expiration Date **05/31/2020**

By *[Signature]*
Miami Dade Product Control

INSTRUCTIONS:

USE CHARTS AS FOLLOWS.

- STEP 1** DETERMINE DESIGN WIND LOAD REQUIREMENT BASED ON WIND VELOCITY, BLDG. HEIGHT, WIND ZONE USING APPLICABLE ASCE 7 STANDARD.
- STEP 2** SEE CHARTS ON SHEET 2 FOR DESIGN LOAD CAPACITY OF DESIRED GLASS SIZE.
- STEP 3** CHECK MULLION CAPACITY FOR A GIVEN SPACING AND HEIGHT USING CHARTS ON SHEET 3 & 4 FOR STOREFRONT MULLION AND SHEET 6 & 7 FOR DOOR MULLION. THE CAPACITY SHOULD EXCEED THE DESIGN LOAD.
- STEP 4** USING CHART ON SHEETS 5 SELECT ANCHOR OPTION WITH DESIGN RATING MORE THAN DESIGN LOAD SPECIFIED IN STEP 1 ABOVE.
- STEP 5** THE LOWEST VALUE RESULTING FROM STEPS 2, 3 AND 4 SHALL APPLY TO ENTIRE SYSTEM.

SINGLE 'O' PANEL:

FRAME WIDTH = D.L.O. WIDTH + 5.500"
FRAME HEIGHT = D.L.O. HEIGHT + 5.500"
FOR ANCHORED JAMBS MAX. SIZES USE GLASS CHART ON SHEET 2.
FOR UNANCHORED JAMB FRAME USE CHARTS ON SHEETS 3 & 4.

THIS SYSTEM IS RATED FOR LARGE & SMALL MISSILE IMPACT. SHUTTERS ARE NOT REQUIRED.

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A. # 3538
[Signature]
APR 13 2014

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. **13-1224.03**
Expiration Date **12/31/2015**
By *[Signature]*
Miami Dade Product Control

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP-ANL\W09-24SM

SERIES SMI-090 ALUM WINDOW WALL (L.M.I.)
Aldora Aluminum & Glass Products Inc.
11500 MIRAMAR PARKWAY SUITE 300
MIRAMAR, FL. 33025
TEL. (305) 888-6288 FAX. (305) 888-6289



NO	DATE	BY	DESCRIPTION
A	04.06.10	REV. PER BCCO COMMENTS	
B	10.21.11	UPDATED TO 2010 FBC	
C	08.12.13	MANUF. NAME REV.	
D	03.05.14	NO CHANGE THIS SHEET	

date: 04-16-09
scale: 1/2"=1'-0"
dr. by: HAMID
chk. by:


drawing no.
W09-24
sheet 1 of 13

GLASS LOAD CAPACITY - PSF		
NOMINAL DIMS.		GLASS TYPES 'A' & 'A1'
D.L.O. WIDTH	D.L.O. HEIGHT	EXT. (+) INT. (-)
30"	66-1/2"	90.0
36"		90.0
42"		90.0
48"		90.0
54"		90.0
60"		90.0
66-1/2"		90.0
30"	72-1/2"	90.0
36"		90.0
42"		90.0
48"		90.0
54"		90.0
60"		90.0
66"		90.0
30"	78-1/2"	90.0
36"		90.0
42"		90.0
48"		90.0
54"		90.0
60"		90.0
66"		90.0
30"	84-1/2"	90.0
36"		90.0
42"		90.0
48"		90.0
54"		90.0
60"		90.0
66"		90.0
30"	90-1/2"	90.0
36"		90.0
42"		90.0
48"		90.0
54"		90.0
60"		90.0
66"		90.0
30"	96-1/2"	90.0
36"		90.0
42"		90.0
48"		90.0
54"		90.0
60"		90.0
66"		90.0
30"	102-1/2"	90.0
36"		90.0
42"		90.0
48"		90.0
54"		90.0
60"		90.0
66"		90.0
30"	108"	90.0
36"		90.0
42"		90.0
48"		90.0
54"		90.0
60"		90.0
66"		90.0
44-1/4"		90.0
30"	114"	90.0
36"		90.0
42"		90.0
48"		90.0
54"		90.0
60"		90.0
66"		90.0
44-1/4"		90.0
30"	114-1/2"	90.0
36"		90.0
42"		90.0
48"		90.0
54"		90.0
60"		90.0
66"		90.0
44-1/4"		90.0

NOTE:
INTERPOLATION BETWEEN WIDTHS OR HEIGHTS ALLOWED.




GLASS TYPE 'A'
9/16" OVERALL LAM. GLASS




GLASS TYPE 'A1'
1-5/16" OVERALL LAM. INSUL. GLASS

GLAZING OPTIONS
INTERIOR GLAZED



GLASS TYPE 'A'
9/16" OVERALL LAM. GLASS





GLASS TYPE 'A1'
1-5/16" OVERALL LAM. INSUL. GLASS

GLAZING OPTIONS
EXTERIOR GLAZED

NOTE:
WINDOW WALL FRAMES AT INSULATED GLASS OPTION
MAY BE WITH OR WITHOUT THERMAL BREAK.

GLASS

PRODUCT RENEWED
as complying with the Florida
Building Code
Acceptance No. **15-0120.01**
Expiration Date **05/12/2020**
By **Miami Dade Product Control**



1/2" AIR SPACE CONSISTING OF:
SPACER:
ALUMINUM BOX SPACER AROUND
THE PERIMETER OF THE GLASS.
PERIMETER SEALANT:
SILICONE
DOW CORNING CWS
DOW CORNING 899
GE 2000
PECORA 895

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538
APR 03 2014

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. **13-1224.03**
Expiration Date **10/12/2015**
By **Miami Dade Product Control**

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP-ANL\W09-24SM

SERIES SMI-090 ALUM WINDOW WALL (L.M.I.)
Aldora Aluminum & Glass Products Inc.
11500 MIRAMAR PARKWAY SUITE 300
MIRAMAR, FL. 33025
TEL. (305) 888-6288 FAX. (305) 888-6289


NO.	DATE	BY	DESCRIPTION
A	04.06.10	REV. PER BCCO COMMENTS	
B	10.21.11	UPDATED TO 2010 FBC	
C	08.12.13	MANUF. NAME REV.	
D	03.05.14	REV. PER PER COMMENTS	

date: 04-16-09
scale: 1/2" = 1"
dr. by: HAMID
chk. by:

drawing no.
W09-24
sheet 2 of 13


DESIGN LOAD CAPACITY - PSF JAMB/MULLION WITHOUT INTERMEDIATE HORIZONTALS				
NOMINAL DIMS.		JAMB 'J1'	JAMB 'J2'	JAMB 'J3/J4'
WIDTH (W)	FRAME HEIGHT	MULLION 'M1'	MULLION 'M2'	MULL 'M3/M4'
		EXT. (+) INT. (-)	EXT. (+) INT. (-)	EXT. (+) INT. (-)
30"	78"	50.0	90.0	90.0
36"		50.0	90.0	90.0
42"		50.0	90.0	90.0
48"		50.0	90.0	90.0
54"		50.0	90.0	90.0
60"		50.0	90.0	90.0
30"	84"	50.0	90.0	90.0
36"		50.0	90.0	90.0
42"		50.0	90.0	90.0
48"		50.0	90.0	90.0
54"		50.0	90.0	90.0
60"		-	90.0	90.0
30"	90"	50.0	90.0	90.0
36"		50.0	90.0	90.0
42"		50.0	90.0	90.0
48"		50.0	90.0	90.0
54"		50.0	90.0	90.0
60"		-	90.0	90.0
30"	96"	50.0	90.0	90.0
36"		50.0	90.0	90.0
42"		50.0	90.0	90.0
48"		50.0	90.0	90.0
54"		-	90.0	90.0
60"		-	90.0	90.0
30"	102"	-	90.0	90.0
36"		-	90.0	90.0
42"		-	90.0	90.0
48"		-	90.0	90.0
54"		-	-	80.0
60"		-	-	90.0
30"	108"	-	90.0	90.0
36"		-	90.0	90.0
42"		-	90.0	90.0
48"		-	87.5	87.5
54"		-	-	80.0
60"		-	-	90.0
30"	114"	-	-	80.0
36"		-	-	80.0
42"		-	-	80.0
48"		-	-	80.0
54"		-	-	80.0
60"		-	-	80.0
30"	120"	-	-	80.0
36"		-	-	80.0
42"		-	-	80.0
48"		-	-	78.0
54"		-	-	80.0
60"		-	-	80.0

NOTE:
INTERPOLATION BETWEEN WIDTHS OR HEIGHTS ALLOWED.




WIDTH (W) = W1
AT FRAME JAMB

WIDTH (W) = $\frac{W2 + W3}{2}$
AT FRAME MULLION



	Ix IN ⁴	Sx IN ³		Ix IN ⁴	Sx IN ³
JAMB 'J1'	3.634	1.720	JAMB 'J2'	9.241	4.375
JAMB 'J3'	9.241	4.375	JAMB 'J4'	3.634	1.720
TOTAL	10.871		TOTAL	15.657	
ALUMINUM			ALUMINUM		
STEEL		.562	STEEL		4.146
TOTAL		10.871	TOTAL		15.657
Ix ALUM + Ix STL X 2.9			Ix ALUM + Ix STL X 2.9		



	Ix IN ⁴	Sx IN ³		Ix IN ⁴	Sx IN ³
MULLION 'M1'	3.854	1.614	MULLION 'M2'	9.461	3.963
MULLION 'M3'	9.461	3.963	MULLION 'M4'	3.854	1.614
TOTAL	11.092		TOTAL	15.877	
ALUMINUM			ALUMINUM		
STEEL		.562	STEEL		4.146
TOTAL		11.092	TOTAL		15.877
Ix ALUM + Ix STL X 2.9			Ix ALUM + Ix STL X 2.9		

PRODUCT RENEWED
as complying with the Florida
Building Code
Acceptance No 15-0120.01
Expiration Date 05/12/2020
By _____
Miami Dade Product Control

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3638
APR 03 2015

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 13-1225.03
Expiration Date 12/12/2015
By _____
Miami Dade Product Control

MULLIONS

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP-ANL\W09-24SM

SERIES SMI-090 ALUM WINDOW WALL (L.M.I.)
Aldora Aluminum & Glass Products Inc.
11500 MIRAMAR PARKWAY SUITE 300
MIRAMAR, FL. 33025
TEL. (305) 888-6288 FAX. (305) 888-6289

no	date	by	description
A	04.06.10		NO CHANGE THIS SHEET
B	10.21.11		NO CHANGE THIS SHEET
C	08.12.13		MANUF. NAME REV.
D	03.05.14		NO CHANGE THIS SHEET


date: 04-16-09
scale: -
dr. by: HAMID
chk. by: _____

drawing no. W09-24
sheet 3 of 13

DESIGN LOAD CAPACITY - PSF
JAMB/MULLION WITH INTERMEDIATE HORIZONTALS


NOMINAL DIMS.		JAMB 'J1'	JAMB 'J2'	JAMB 'J3/J4'
		MULLION 'M1'	MULLION 'M2'	MULL 'M3/M4'
WIDTH (W)	FRAME HEIGHT	EXT. (+) INT. (-)	EXT. (+) INT. (-)	EXT. (+) INT. (-)
30"	78"	50.0	90.0	90.0
36"		50.0	90.0	90.0
42"		50.0	90.0	90.0
48"		50.0	90.0	90.0
54"		50.0	90.0	90.0
60"		50.0	90.0	90.0
30"	84"	50.0	90.0	90.0
36"		50.0	90.0	90.0
42"		50.0	90.0	90.0
48"		50.0	90.0	90.0
54"		50.0	90.0	90.0
60"		-	90.0	90.0
30"	90"	50.0	90.0	90.0
36"		50.0	90.0	90.0
42"		50.0	90.0	90.0
48"		50.0	90.0	90.0
54"		50.0	90.0	90.0
60"		-	90.0	90.0
30"	96"	50.0	90.0	90.0
36"		50.0	90.0	90.0
42"		50.0	90.0	90.0
48"		49.2	90.0	90.0
54"		-	90.0	90.0
60"		-	-	80.0
30"	102"	-	90.0	90.0
36"		-	90.0	90.0
42"		-	90.0	90.0
48"		-	90.0	90.0
54"		-	-	80.0
30"	108"	-	90.0	90.0
36"		-	90.0	90.0
42"		-	90.0	90.0
48"		-	81.9	85.0
30"	114"	-	-	80.0
36"		-	-	80.0
42"		-	-	80.0
48"		-	-	80.0
30"	120"	-	-	80.0
36"		-	-	80.0
42"		-	-	80.0
48"		-	-	72.1

NOTE:
INTERPOLATION BETWEEN WIDTHS OR HEIGHTS ALLOWED.




WIDTH (W) = W1
AT FRAME JAMB

WIDTH (W) = $\frac{W2 + W3}{2}$
AT FRAME MULLION



	Ix IN ⁴	Sx IN ³		Ix IN ⁴	Sx IN ³		Ix IN ⁴	Sx IN ³		Ix IN ⁴	Sx IN ³
JAMB 'J1'	3.634	1.720	JAMB 'J2'	9.241	4.375	JAMB 'J3'	9.241	4.375	JAMB 'J4'	3.634	1.720
ALUMINUM			ALUMINUM			ALUMINUM			ALUMINUM		
STEEL	.562	.375	STEEL	.562	.375	STEEL	.562	.375	STEEL	4.146	1.951
TOTAL	10.871		TOTAL	10.871		TOTAL	10.871		TOTAL	15.657	
Ix ALUM + Ix STL X 2.9			Ix ALUM + Ix STL X 2.9			Ix ALUM + Ix STL X 2.9			Ix ALUM + Ix STL X 2.9		



	Ix IN ⁴	Sx IN ³		Ix IN ⁴	Sx IN ³		Ix IN ⁴	Sx IN ³		Ix IN ⁴	Sx IN ³
MULLION 'M1'	3.854	1.614	MULLION 'M2'	9.461	3.963	MULLION 'M3'	9.461	3.963	MULLION 'M4'	3.854	1.614
ALUMINUM			ALUMINUM			ALUMINUM			ALUMINUM		
STEEL	.562	.375	STEEL	.562	.375	STEEL	.562	.375	STEEL	4.146	1.951
TOTAL	11.092		TOTAL	11.092		TOTAL	11.092		TOTAL	15.877	
Ix ALUM + Ix STL X 2.9			Ix ALUM + Ix STL X 2.9			Ix ALUM + Ix STL X 2.9			Ix ALUM + Ix STL X 2.9		

PRODUCT RENEWED
as complying with the Florida
Building Code
Acceptance No. 15-0120.01
Expiration Date 05/12/2020

By: *[Signature]*
Miami Dade Product Control

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538

APR 03 2014

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 13-1224.03
Expiration Date 12/12/2015

By: *[Signature]*
Miami Dade Product Control

MULLIONS

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP-ANL\W09-24SM


SERIES SMI-090 ALUM WINDOW WALL (L.M.I.)
Aldora Aluminum & Glass Products Inc.
11500 MIRAMAR PARKWAY SUITE 300
MIRAMAR, FL. 33025
TEL. (305) 888-6288 FAX. (305) 888-6289

no	date	by	description
A	04.05.10		NO CHANGE THIS SHEET
B	10.21.11		NO CHANGE THIS SHEET
C	08.12.13		MANUF. NAME REV.
D	03.05.14		NO CHANGE THIS SHEET

date: 04-16-09
scale: -
dr. by: HAMID
chk. by:


drawing no.
W09-24
sheet 4 of 13

ANCHOR LOAD CAPACITY -- PSF EXT.(+) & INT.(-)						
NOMINAL DIMS.		ANCHORS TYPE 'A'		ANCHORS TYPE 'B'		TYPE 'C'
WIDTH (W)	FRAME HEIGHT	A2	A3	B2	B3	C2
30"	60"	90.0	90.0	90.0	90.0	90.0
36"		90.0	90.0	90.0	90.0	90.0
42"		90.0	90.0	90.0	90.0	90.0
48"		90.0	90.0	90.0	90.0	90.0
54"		90.0	90.0	90.0	90.0	90.0
60"	90.0	90.0	90.0	90.0	90.0	
30"	66"	90.0	90.0	90.0	90.0	90.0
36"		90.0	90.0	90.0	90.0	90.0
42"		90.0	90.0	90.0	90.0	90.0
48"		90.0	90.0	90.0	90.0	90.0
54"		90.0	90.0	90.0	90.0	90.0
60"	85.5	90.0	90.0	90.0	90.0	
30"	72"	90.0	90.0	90.0	90.0	90.0
36"		90.0	90.0	90.0	90.0	90.0
42"		90.0	90.0	90.0	90.0	90.0
48"		90.0	90.0	90.0	90.0	90.0
54"		87.1	90.0	90.0	90.0	90.0
60"	78.4	90.0	90.0	90.0	90.0	
30"	78"	90.0	90.0	90.0	90.0	90.0
36"		90.0	90.0	90.0	90.0	90.0
42"		90.0	90.0	90.0	90.0	90.0
48"		90.0	90.0	90.0	90.0	90.0
54"		80.4	90.0	90.0	90.0	90.0
60"	72.4	90.0	88.6	90.0	90.0	
30"	84"	90.0	90.0	90.0	90.0	90.0
36"		90.0	90.0	90.0	90.0	90.0
42"		90.0	90.0	90.0	90.0	90.0
48"		84.0	90.0	90.0	90.0	90.0
54"		74.7	90.0	90.0	90.0	90.0
60"	67.2	90.0	82.3	90.0	90.0	
30"	90"	90.0	90.0	90.0	90.0	90.0
36"		90.0	90.0	90.0	90.0	90.0
42"		89.6	90.0	90.0	90.0	90.0
48"		78.4	90.0	90.0	90.0	90.0
54"		69.7	90.0	85.3	90.0	90.0
60"	62.7	90.0	76.8	90.0	90.0	
30"	96"	90.0	90.0	90.0	90.0	90.0
36"		90.0	90.0	90.0	90.0	90.0
42"		84.0	90.0	90.0	90.0	90.0
48"		73.5	90.0	90.0	90.0	90.0
54"		65.3	90.0	80.0	90.0	90.0
60"	58.8	88.2	72.0	90.0	90.0	
30"	102"	90.0	90.0	90.0	90.0	90.0
36"		90.0	90.0	90.0	90.0	90.0
42"		79.1	90.0	90.0	90.0	90.0
48"		69.2	90.0	84.7	90.0	90.0
54"		61.5	90.0	75.3	90.0	90.0
30"	108"	90.0	90.0	90.0	90.0	90.0
36"		87.1	90.0	90.0	90.0	90.0
42"		74.7	90.0	90.0	90.0	90.0
48"		65.3	90.0	80.0	90.0	90.0
30"	114"	90.0	90.0	90.0	90.0	90.0
36"		82.5	90.0	90.0	90.0	90.0
42"		70.7	90.0	86.6	90.0	90.0
48"		61.9	90.0	75.8	90.0	90.0
30"	120"	90.0	90.0	90.0	90.0	90.0
36"		78.4	90.0	90.0	90.0	90.0
42"		67.2	90.0	82.3	90.0	90.0
48"		58.8	88.2	72.0	90.0	90.0



WIDTH (W) = W1
AT FRAME JAMB

WIDTH (W) = $\frac{W2 + W3}{2}$
AT FRAME MULLION



- ANCHORS TYPES:**
- A2 = (2) ANCHORS TYPE 'A' AT EACH SIDE OF JAMB AND MULLION
 - B2 = (2) ANCHORS TYPE 'B' AT EACH SIDE OF JAMB AND MULLION
 - C2 = (2) ANCHORS TYPE 'C' AT EACH SIDE OF JAMB AND MULLION
 - A3 = (3) ANCHORS TYPE 'A' AT EACH SIDE OF JAMB AND MULLION
 - B3 = (3) ANCHORS TYPE 'B' AT EACH SIDE OF JAMB AND MULLION

WOOD BUCKS AND METAL STRUCTURE NOT BY 'ALDORA ALUMINUM & GLASS PRODUCTS' MUST SUSTAIN LOADS IMPOSED BY GLAZING SYSTEM AND TRANSFER THEM TO THE BUILDING STRUCTURE.

TYPICAL ANCHORS: SEE ELEV. FOR SPACING

TYPE 'A'
1/4" DIA ULTRACON BY 'ELCO' (Fu=177 KSI, Fy=155 KSI)
INTO 2BY WOOD BUCKS OR WOOD STRUCTURES WITH 1-3/8" MIN. PENETRATION INTO WOOD
THRU 1BY WOOD BUCKS INTO CONCRETE WITH 1-1/4" MIN. EMBED INTO CONCRETE

ANCHOR EDGE DISTANCES
INTO CONCRETE = 2-1/2" MIN.
INTO WOOD STRUCTURE = 1" MIN.

TYPE 'B'
1/4" DIA ULTRACON BY 'ELCO' (Fu=177 KSI, Fy=155 KSI)
DIRECTLY INTO CONCRETE WITH 1-1/4" MIN. EMBED INTO CONC.

ANCHOR EDGE DISTANCES
INTO CONCRETE = 2-1/2" MIN.

TYPE 'C'
#14 SMS OR SELF DRILLING SCREWS ST/ST (GRADE 2 CRS)
INTO METAL STRUCTURES
STEEL : 12 GA. MIN. (Fy = 36 KSI MIN.)
ALUMINUM : 1/8" THK. MIN. (6063-T5 MIN.)
(STEEL IN CONTACT WITH ALUMINUM TO BE PLATED OR PAINTED)

ANCHOR EDGE DISTANCES
INTO METAL STRUCTURE = 3/4" MIN.

CONCRETE AT HEAD, SILL OR JAMBS f'c = 3000 PSI MIN.
C-90 HOLLOW/FILLED BLOCK AT JAMBS f'm = 2000 PSI MIN.

PRODUCT RENEWED as complying with the Florida Building Code
Acceptance No. 15-0120.01
Expiration Date 25/12/2020
By: *[Signature]*
Miami Dade Product Control

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538
APR 3 2014

PRODUCT REVISED as complying with the Florida Building Code
Acceptance No. 13-1004.03
Expiration Date May 12, 2015
By: *[Signature]*
Miami Dade Product Control

ANCHORS

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP-ANL W09-24SM

SERIES SMI-090 ALUM WINDOW WALL (L.M.I.)
Aldora Aluminum & Glass Products Inc.
11500 MIRAMAR PARKWAY SUITE 300
MIRAMAR, FL. 33025
TEL. (305) 888-6288 FAX. (305) 888-6289


no	description	date	by
A	NO CHANGE THIS SHEET	04.06.10	
B	NO CHANGE THIS SHEET	10.21.11	
C	MANUF. NAME REV.	08.12.13	
D	NO CHANGE THIS SHEET	03.05.14	

date: 04-16-09
scale: 1/2" = 1"
dr. by: HAMID
chk. by:

drawing no. W09-24
sheet 5 of 13


DOOR MULLION LOAD CAPACITY		
NOMINAL DIMS.		W/O REINF.
WIDTH (W)	FRAME HEIGHT	EXT.(+) & INT.(-)
30"	81-3/4"	90.0
36"		90.0
42"		90.0
48"		90.0
30"	85-3/4"	90.0
36"		90.0
42"		90.0
48"		90.0
30"	91-3/4"	90.0
36"		90.0
42"		90.0
30"	96-3/4"	90.0
36"		90.0
42"		90.0
30"	97-3/4"	90.0
36"		90.0
42"		90.0

DOOR MULLION LOAD CAPACITY		
NOMINAL DIMS.		WITH REINF.
WIDTH (W)	FRAME HEIGHT	EXT.(+) & INT.(-)
24"	80"	90.0
30"		90.0
36"		90.0
42"		90.0
48"		90.0
54"		90.0
24"	84"	90.0
30"		90.0
36"		90.0
42"		90.0
48"		90.0
54"		90.0
24"	90"	90.0
30"		90.0
36"		90.0
42"		90.0
48"		90.0
54"		90.0
24"	96"	90.0
30"		90.0
36"		90.0
42"		90.0
48"		90.0
54"		90.0
24"	102"	90.0
30"		90.0
36"		90.0
42"		90.0
48"		90.0
54"		90.0
24"	108"	90.0
30"		90.0
36"		90.0
42"		90.0
24"	114"	80.0
30"		80.0
36"		80.0
42"		80.0
24"	120"	80.0
30"		80.0
36"		80.0
42"	80.0	




DOOR MULLION WITHOUT REINFORCING

Ix IN ⁴	Sx IN ³
5.856	2.602




DOOR MULLION WITH REINFORCING

	Ix IN ⁴	Sx IN ³
ALUMINUM	5.856	2.602
STEEL	2.740	1.391
TOTAL Ix ALUM + Ix STL X 2.9	13.802	



$$\text{WIDTH (W)} = \frac{W1 + W2}{2}$$


ANCHOR TYPES	TOTAL NO. OF ANCHORS AT DOOR MULLION SILL
AA, B, C	4
CC	3



$$\text{WIDTH (W)} = \frac{W1}{2} + \frac{W2}{4}$$

ANCHOR TYPES	TOTAL NO. OF ANCHORS AT DOOR MULLION HEAD
A	5
AA, B, C	4
CC	3

ALDORA ALUM & GLASS PRODUCTS
OUTSWING DOORS
SEE SEPARATE NOA



$$\text{WIDTH (W)} = \frac{W1 + W2}{2}$$

ANCHOR TYPES	TOTAL NO. OF ANCHORS AT DOOR MULLION SILL
AA, B, C	4
CC	3

ALDORA ALUM & GLASS PRODUCTS
OUTSWING DOORS
SEE SEPARATE NOA

PRODUCT RENEWED
as complying with the Florida
Building Code
Acceptance No 15-0120.01
Expiration Date 25/12/2020

By *[Signature]*
Miami Dade Product Control

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 13-1224.03
Expiration Date 12/12/2015
By *[Signature]*
Miami Dade Product Control

DOOR MULLION

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP - ANL \W09 - 24SM

SERIES SM1-090 ALUM WINDOW WALL (L.M.I.)
Aldora Aluminum & Glass Products Inc.
11500 MIRAMAR PARKWAY SUITE 300
MIRAMAR, FL. 33025
TEL. (305) 888-6288 FAX. (305) 888-6289

NO	DATE	BY	DESCRIPTION
A	04.06.10		REV. PER BCCO COMMENTS
B	10.21.11		NO CHANGE THIS SHEET
C	08.12.13		MANUF. NAME REV.
D	03.05.14		NO CHANGE THIS SHEET

date: 04-16-09	scale: 1/2" = 1"
dr. by: HAMID	chk. by:

drawing no.
W09-24
sheet 6 of 13

DOOR MULLION LOAD CAPACITY - PSF				
NOMINAL DIMS.				WITH REINF.
FRAME HEIGHT INCHES	DOOR HEIGHT INCHES	WIDTH (W1) INCHES	WIDTH (W2) INCHES	EXT. (+) INT. (-)
108	80	60	30	90.0
			33	90.0
			39	90.0
			42	90.0
		72	30	90.0
			33	90.0
			39	90.0
			42	90.0
		84	30	90.0
			33	90.0
			39	90.0
			42	90.0
96	30	90.0		
	33	90.0		
	39	90.0		
	42	90.0		

DOOR MULLION LOAD CAPACITY - PSF				
NOMINAL DIMS.				WITH REINF.
FRAME HEIGHT INCHES	DOOR HEIGHT INCHES	WIDTH (W1) INCHES	WIDTH (W2) INCHES	EXT. (+) INT. (-)
108	84	60	30	90.0
			33	90.0
			39	90.0
			42	90.0
		72	30	90.0
			33	90.0
			39	90.0
			42	90.0
		84	30	90.0
			33	90.0
			39	90.0
			42	90.0
96	30	90.0		
	33	90.0		
	39	90.0		
	42	90.0		

DOOR MULLION LOAD CAPACITY - PSF				
NOMINAL DIMS.				WITH REINF.
FRAME HEIGHT INCHES	DOOR HEIGHT INCHES	WIDTH (W1) INCHES	WIDTH (W2) INCHES	EXT. (+) INT. (-)
114	96	60	30	80.0
			33	80.0
			39	80.0
			42	80.0
		72	30	80.0
			33	80.0
			39	80.0
			42	80.0
		84	30	80.0
			33	80.0
			39	80.0
			42	80.0
96	30	80.0		
	33	80.0		
	39	80.0		
	42	80.0		


DOOR MULLION LOAD CAPACITY - PSF				
NOMINAL DIMS.				WITH REINF.
FRAME HEIGHT INCHES	DOOR HEIGHT INCHES	WIDTH (W1) INCHES	WIDTH (W2) INCHES	EXT. (+) INT. (-)
120	108	60	30	80.0
			33	80.0
			39	80.0
			42	80.0
		72	30	80.0
			33	80.0
			39	80.0
			42	80.0
		84	30	80.0
			33	80.0
			39	80.0
			42	80.0
96	30	80.0		
	33	80.0		
	39	80.0		
	42	80.0		

DOOR MULLION LOAD CAPACITY - PSF				
NOMINAL DIMS.				WITH REINF.
FRAME HEIGHT INCHES	DOOR HEIGHT INCHES	WIDTH (W1) INCHES	WIDTH (W2) INCHES	EXT. (+) INT. (-)
114	80	60	30	80.0
			33	80.0
			39	80.0
			42	80.0
		72	30	80.0
			33	80.0
			39	80.0
			42	80.0
		84	30	80.0
			33	80.0
			39	80.0
			42	80.0
96	30	80.0		
	33	80.0		
	39	80.0		
	42	80.0		


DOOR MULLION LOAD CAPACITY - PSF				
NOMINAL DIMS.				WITH REINF.
FRAME HEIGHT INCHES	DOOR HEIGHT INCHES	WIDTH (W1) INCHES	WIDTH (W2) INCHES	EXT. (+) INT. (-)
114	84	60	30	80.0
			33	80.0
			39	80.0
			42	80.0
		72	30	80.0
			33	80.0
			39	80.0
			42	80.0
		84	30	80.0
			33	80.0
			39	80.0
			42	80.0
96	30	80.0		
	33	80.0		
	39	80.0		
	42	80.0		

DOOR MULLION LOAD CAPACITY - PSF				
NOMINAL DIMS.				WITH REINF.
FRAME HEIGHT INCHES	DOOR HEIGHT INCHES	WIDTH (W1) INCHES	WIDTH (W2) INCHES	EXT. (+) INT. (-)
120	80	60	30	80.0
			33	80.0
			39	80.0
			42	80.0
		72	30	80.0
			33	80.0
			39	80.0
			42	80.0
		84	30	80.0
			33	80.0
			39	80.0
			42	80.0
96	30	80.0		
	33	80.0		
	39	80.0		
	42	80.0		

DOOR MULLION LOAD CAPACITY - PSF				
NOMINAL DIMS.				WITH REINF.
FRAME HEIGHT INCHES	DOOR HEIGHT INCHES	WIDTH (W1) INCHES	WIDTH (W2) INCHES	EXT. (+) INT. (-)
120	84	60	30	80.0
			33	80.0
			39	80.0
			42	80.0
		72	30	80.0
			33	80.0
			39	80.0
			42	80.0
		84	30	80.0
			33	80.0
			39	80.0
			42	80.0
96	30	80.0		
	33	80.0		
	39	80.0		
	42	80.0		



	Ix IN ⁴	Sx IN ³
ALUMINUM	5.856	2.602
STEEL	2.740	1.391
TOTAL Ix ALUM + Ix STL X 2.9	13.802	



ANCHOR TYPES	TOTAL NO. OF ANCHORS AT DOOR MULLION HEAD
A	8
AA, B, C	6
CC	4

ANCHOR TYPES	TOTAL NO. OF ANCHORS AT DOOR MULLION SILL
AA, B, C	6
CC	4

ALDORA ALUM & GLASS PRODUCTS OUTSWING DOORS SEE SEPARATE NOA

PRODUCT RENEWED as complying with the Florida Building Code
 Acceptance No. 15-0120.01
 Expiration Date 05/12/2020
 By *[Signature]*
 Miami Dade Product Control

Engr: JAVAD AHMAD CIVIL
 FLA. PE # 70592
 C.A.N. 3538
 APR 03 2015

PRODUCT REVISED as complying with the Florida Building Code
 Acceptance No. 13-1224.03
 Expiration Date 12/12/2015
 By *[Signature]*
 Miami Dade Product Control

DOOR MULLION




AL-FAROOQ CORPORATION
 ENGINEERS & PRODUCT DEVELOPMENT
 1235 S.W. 87 AVE
 MIAMI, FLORIDA 33174
 TEL. (305) 264-8100 FAX. (305) 262-6978
 COMP-ANL\W09-24SM

SERIES SMI-090 ALUM WINDOW WALL (L.M.I.)
 Aldora Aluminum & Glass Products Inc.
 11500 MIRAMAR PARKWAY SUITE 300
 MIRAMAR, FL. 33025
 TEL. (305) 888-6288 FAX. (305) 888-6289

no	date	description
A	04.05.10	REV. PER BCCO COMMENTS
B	10.21.11	NO CHANGE THIS SHEET
C	08.12.13	MANUF. NAME REV.
D	03.05.14	NO CHANGE THIS SHEET

date: 04-16-09
 scale: 1/2" = 1"
 dr. by: HAMID
 chk. by:

drawing no. W09-24
 sheet 7 of 13



PRODUCT RENEWED
 as complying with the Florida
 Building Code
 Acceptance No. **15-0120.01**
 Expiration Date **05/12/2020**

By *[Signature]*
 Miami Dade Product Control

INTERIOR GLAZED

Engr. JAVAD AHMAD
 CIVIL
 FLA. PE # 70592
 C.A.N. 3538

APR 03 2015

PRODUCT REVISED
 as complying with the Florida
 Building Code
 Acceptance No. **13-1224.03**
 Expiration Date **May 12, 2015**

By *[Signature]*
 Miami Dade Product Control

afC




AL-FAROOQ CORPORATION
 ENGINEERS & PRODUCT DEVELOPMENT
 12335 S.W. 87 AVE
 MIAMI, FLORIDA 33174
 TEL. (305) 264-8100 FAX. (305) 262-6978
 COMP-ANL\W09-24SM

SERIES SMI-090 ALUM WINDOW WALL (L.M.I.)
 Aldora Aluminum & Glass Products Inc.
 11500 MIRAMAR PARKWAY SUITE 300
 MIRAMAR, FL. 33025
 TEL. (305) 888-6288 FAX. (305) 888-6289

no	date	description	BY
A	04.08.10	NO CHANGE THIS SHEET	
B	10.21.11	NO CHANGE THIS SHEET	
C	08.12.13	MANUF. NAME REV.	
D	03.05.14	NO CHANGE THIS SHEET	

date: 04-16-09
 scale: 1/2" = 1"
 dr. by: HAMID
 chk. by:

drawing no.
W09-24
 sheet 8 of 13



PRODUCT RENEWED
 as complying with the Florida
 Building Code
 Acceptance No. **15-0120.01**
 Expiration Date **25/12/2020**
 By *[Signature]*
 Miami Dade Product Control

EXTERIOR GLAZED

Engr: JAVAD AHMAD
 CIVIL
 FLA. PE # 70592
 C.A.N. # 3538

PRODUCT REVISED
 as complying with the Florida
 Building Code
 Acceptance No. **13-1224.03**
 Expiration Date **May 12, 2015**
 By *[Signature]*
 Miami Dade Product Control


afC
AL-FAROOQ CORPORATION
 ENGINEERS & PRODUCT DEVELOPMENT
 12395 S.W. 87 AVE
 MIAMI, FLORIDA 33174
 TEL. (305) 264-8100 FAX. (305) 262-6978
 COMP-ANL\W09-24SM

SERIES SMI-090 ALUM WINDOW WALL (L.M.I.)
Aldora Aluminum & Glass Products Inc.
 11500 MIRAMAR PARKWAY SUITE 300
 MIRAMAR, FL. 33025
 TEL. (305) 888-6288 FAX. (305) 888-6289

revisions:	no.	DATE	BY	DESCRIPTION
	A	04.08.10		NO CHANGE THIS SHEET
	B	10.21.11		NO CHANGE THIS SHEET
	C	08.12.13		MANUF. NAME REV.
	D	03.05.14		NO CHANGE THIS SHEET

date:	04-16-09
scale:	1/2" = 1"
dr. by:	HAMID
chk. by:	


drawing no.	W09-24
sheet	9 of 13




SILICONE
DOW CORNING CCS
DEPTH = 3/8" MIN.

MAX. FRAME HEIGHT	GAP	
	MIN.	MAX.
72"	3/8"	1/2"
96"	1/2"	3/4"
120"	5/8"	1"

MIN. & MAX.
GAP
SEE CHART



TYPICAL ANCHORS
SEE ELEV.
FOR SPACING



NOTE:
REINFORCINGS NOT REQUIRED AT SECURED JAMBS

PRODUCT RENEWED
as complying with the Florida
Building Code
Acceptance No 15-0120.01
Expiration Date 05/12/2020
By [Signature]
Miami Dade Product Control

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 76592
C.A.N. 3538
APR 03 2014

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 13-122A.03
Expiration Date May 12, 2015
By [Signature]
Miami Dade Product Control

INTERIOR OR EXTERIOR GLAZED

afC
AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL (305) 264-8100 FAX (305) 262-6978
COMP-ANL\W09-24SM

SERIES SMI-090 ALUM WINDOW WALL (L.M.I.)
Aldora Aluminum & Glass Products Inc.
11500 MIRAMAR PARKWAY SUITE 300
MIRAMAR, FL. 33025
TEL (305) 888-6288 FAX (305) 888-6289

revisions:



NO	DATE	DESCRIPTION
A	04.06.10	NO CHANGE THIS SHEET
B	10.21.11	NO CHANGE THIS SHEET
C	08.12.13	MANUF. NAME REV.
D	03.05.14	NO CHANGE THIS SHEET

date: 04-16-09
scale: 1/2" = 1"
dr. by: HAMID
chk. by:

drawing no.
W09-24

sheet 10 of 13

SEE SEPARATE NOA FOR DESIGN LOAD CAPACITY OF DOORS AND DOOR ANCHORS.
 LOWER VALUES FROM DOORS NOA OR STOREFRONT SYSTEM CAPACITY CHARTS WILL APPLY TO ENTIRE SYSTEM.



PRODUCT RENEWED
 as complying with the Florida
 Building Code
 Acceptance No 15-0120.01
 Expiration Date 05/12/2020
 By [Signature]
 Miami Dade Product Control

Engr: JAVAD AHMAD
 CIVIL
 FLA. PE # 70592
 C.A.N. 3538
[Signature]
 APR 07 2014


PRODUCT REVISED
 as complying with the Florida
 Building Code
 Acceptance No 13-1224.03
 Expiration Date May 12, 2015
 By [Signature]
 Miami Dade Product Control

af c
AL-FAROOQ CORPORATION
 ENGINEERS & PRODUCT DEVELOPMENT
 1235 S.W. 87 AVE
 MIAMI, FLORIDA 33174
 TEL. (305) 264-8100 FAX. (305) 262-6978
 COMP-ANL\W09-24SM


SERIES SM-090 ALUM WINDOW WALL (L.M.I.)
 Aldora Aluminum & Glass Products Inc.
 11500 MIRAMAR PARKWAY SUITE 300
 MIRAMAR, FL. 33025
 TEL. (305) 888-6288 FAX. (305) 888-6289

no.	date	by	description
A	04.06.10		NO CHANGE THIS SHEET
B	10.21.11		NO CHANGE THIS SHEET
C	08.12.13		MANUF. NAME REV.
D	03.05.14		NO CHANGE THIS SHEET


date: 04-16-09
 scale: 1/2" = 1"
 dr. by: HAMID
 chk. by:
 drawing no. W09-24
 sheet 11 of 13




① FRAME HEAD/SILL/JAMB/MULLION INTERIOR GLAZED




①A FRAME HEAD/SILL/JAMB/MULLION INTERIOR GLAZED (THERMAL)




② FRAME HEAD/SILL/INTERM. HORIZ. EXTERIOR GLAZED




②A FRAME HEAD/SILL/INTERM. HORIZ. EXTERIOR GLAZED (THERMAL)




③ PLAIN SNAP INT./EXT. GLAZED




③A PLAIN SNAP INT./EXT. GLAZED (THERMAL)




④ FIN SNAP INTERIOR GLAZED




④A FIN SNAP INTERIOR GLAZED (THERMAL)




⑦ INTERIOR GLASS STOP




⑧ EXTERIOR GLASS STOP




⑤ REINFORCING SPLICE




⑥ REINFORCING BAR



⑮ REINFORCING CHANNEL



⑱ DOOR MULLION



⑰ REINFORCING CHANNELS DOOR MULLION

PRODUCT RENEWED
as complying with the Florida
Building Code
Acceptance No 15-0120.01
Expiration Date 05/22/2020
By *[Signature]*
Miami Dade Product Control

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538
APR 02 2014


PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 13-1224.03
Expiration Date May 12, 2015
By *[Signature]*
Miami Dade Product Control

af c
AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL (305) 264-8100 FAX (305) 262-6978
COMP-ANL W09-24SM


SERIES SMI-090 ALUM WINDOW WALL (L.M.I.)
Aldora Aluminum & Glass Products Inc.
11500 MIRAMAR PARKWAY SUITE 300
MIRAMAR, FL. 33025
TEL (305) 888-6288 FAX (305) 888-6289

no	date	by	description
A	04.08.10		NO CHANGE THIS SHEET
B	10.21.11		NO CHANGE THIS SHEET
C	08.12.13		MANUF. NAME REV.
D	03.05.14		NO CHANGE THIS SHEET

date: 04-16-09
scale: 1/2" = 1"
dr. by: HAMID
chk. by:
drawing no. W09-24
sheet 12 of 13



ITEM #	PART #	QUANTITY	DESCRIPTION	MATERIAL	MANF./SUPPLIER/REMARKS
1	SMI-091	AS REQD.	INT. GLAZED FRAME HEAD/SILL/JAMB/MULLION	6063-T6	SMITH MOUNTAIN
1A	SMI-091T	AS REQD.	INT. GLAZED FRAME HEAD/SILL/JAMB/MULLION (POUR & DEBRIDGE)	6063-T6	SMITH MOUNTAIN
2	SMI-098	AS REQD.	EXT. GLAZED FRAME HEAD/SILL/INTERM. HORIZ.	6063-T6	SMITH MOUNTAIN
2A	SMI-098T	AS REQD.	EXT. GLAZED FRAME HEAD/SILL/INTERM. HORIZ. (POUR & DEBRIDGE)	6063-T6	SMITH MOUNTAIN
3	SMI-094	AS REQD.	INT./EXT. GLAZED PLAIN SNAP	6063-T6	SMITH MOUNTAIN
3A	SMI-094T	AS REQD.	INT./EXT. GLAZED PLAIN SNAP (POUR & DEBRIDGE)	6063-T6	SMITH MOUNTAIN
4	SMI-093	AS REQD.	INT./EXT. GLAZED FIN SNAP	6063-T6	SMITH MOUNTAIN
4A	SMI-093T	AS REQD.	INT./EXT. GLAZED FIN SNAP (POUR & DEBRIDGE)	6063-T6	SMITH MOUNTAIN
5	SMI-095	AS REQD.	REINFORCING SPLICE	6005-T5	SMITH MOUNTAIN
6	-	AS REQD.	REINFORCING BAR	STEEL	36 KSI MIN.
7	SMI-092	AS REQD.	INTERIOR GLASS STOP	6063-T6	SMITH MOUNTAIN
8	SMI-097	AS REQD.	EXTERIOR GLASS STOP	6063-T6	SMITH MOUNTAIN
9	SMI-G01	AS REQD.	INTERIOR GASKET (DUROMETER 70±5)	EPDM	GLAZING RUBBER PRODUCTS (#116)
10	SMI-G02	AS REQD.	SINGLE FACE TAPE (3/8" X 1/2")	VINYL FOAM	FRANK LOWE
11	SMI-G07	AS REQD.	EXTERIOR GASKET (DUROMETER 70±5)	EPDM	CENTRAL PLASTICS INC.
12	SMI-SB06	2/ LITE	SETTING BLOCK LAM. GLASS (3/8" X 5/8" X 4" LG.) (DUROMETER 85±5)	EPDM	CENTRAL PLASTICS INC.
12A	SMI-SB04	2/ LITE	SETTING BLOCK LAM. INSUL. GLASS (3/8" X 1-1/4" X 4" LG.) (DUROMETER 85±5)	EPDM	CENTRAL PLASTICS INC.
13	SMI-P04	AS REQD.	THERMAL BRAKE SPACER FOR ALUM SPLICE	RIGID PVC	CENTRAL PLASTICS INC.
14	#12 X 1-1/2"	4/ CORNER	FRAME ASSEMBLY SCREWS	ST. STEEL	HEX. HEAD MACHINE SCREWS
15	-	AS REQD.	REINFORCING CHANNEL (36 KSI MIN.)	STEEL	-
16	-	-	REINFORCING CHANNEL (DOOR MULLION)	STEEL	1" X 3-15/16" X 1" X 3/16" THK.
17	-	-	REINFORCING CHANNEL (DOOR MULLION)	STEEL	3/4" X 3-1/2" X 3/4" X 1/8" THK.
18	SMI-005	AS REQD.	DOOR MULLION	6063-T6	SMITH MOUNTAIN



FRAME CORNERS

SEALANTS:

ALL FRAME CORNERS, JOINTS, MULLION SEAMS AND PERIMETER OF GLAZING BEAD TO FRAME SEALED WITH SILICONE SEALANT.

PRODUCT RENEWED
 as complying with the Florida
 Building Code
 Acceptance No. 15-0120.01
 Expiration Date 05/12/2020
 By [Signature]
 Miami Dade Product Control

Engr: JAVAD AHMAD
 CFML
 FLA. PE # 70592
 C.A.N. 3538
 APR 03 2014

PRODUCT REVISED
 as complying with the Florida
 Building Code
 Acceptance No. 13-1224.03
 Expiration Date May 12, 2015
 By [Signature]
 Miami Dade Product Control

af c
AL-FAROOQ CORPORATION
 ENGINEERS & PRODUCT DEVELOPMENT
 1235 S.W. 87 AVE
 MIAMI, FLORIDA 33174
 TEL. (305) 264-8100 FAX. (305) 262-6978
 COMP-ANL\W09-24SM

SERIES SMI-090 ALUM WINDOW WALL (L.M.I.)
 Aldora Aluminum & Glass Products Inc.
 11500 MIRAMAR PARKWAY SUITE 300
 MIRAMAR, FL. 33025
 TEL. (305) 888-6288 FAX. (305) 888-6289

no	date	description
A	04.06.10	NO CHANGE THIS SHEET
B	10.21.11	DURO ADDED
C	08.12.13	MANUF. NAME REV.
D	03.05.14	NO CHANGE THIS SHEET



date: 04-16-09
 scale: 1/2" = 1"
 dr. by: HAMID
 chk. by:
 drawing no. W09-24
 sheet 13 of 13

FOR LOUVER FRAMES WITH INTERMEDIATE VERTICAL MULLIONS.
REFER TO APPLICABLE CHARTS ON SHEETS 3 & 4.

af c

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
1235 S.W. 87 AVE
MIAMI, FLORIDA 33174
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP-ANL\W09-24SM

SERIES SMI-090 ALUM WINDOW WALL (L.M.I.)
Aldora Aluminum & Glass Products Inc.
11500 MIRAMAR PARKWAY SUITE 300
MIRAMAR, FL. 33025
TEL. (305) 888-6288 FAX. (305) 888-6289




WIDTH (W) = W1
AT FRAME JAMB

WIDTH (W) = $\frac{W2 + W3}{2}$
AT FRAME MULLION

PRODUCT RENEWED
as complying with the Florida
Building Code
Acceptance No. **15-0120.01**
Expiration Date **05/12/2020**
By *[Signature]*
Miami Dade Product Control

TYPICAL INSTALLATION OF LOUVERS IN THE WINDOW WALL SYSTEM
USE ALUMINUM LOUVERS HOLDING CURRENT NOA
DETAILS FOR 'RELIABLE PRODUCTS' APPROVED LOUVERS SHOWN



PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. **13-1224.03**
Expiration Date **May 12, 2015**
By *[Signature]*
Miami Dade Product Control

Engr: JAVAD AHMAD
CIVIL
FLA. PE # 70592
C.A.N. 3538


APR 13 2014

no.	date	by	description
C	08.12.13		NEW SHEET ADDED
D	03.05.14		REV. PER RER COMMENTS


date:	04-16-09
scale:	1/2" = 1"
dr. by:	HAMID
chk. by:	

drawing no. **W09-24**


sheet 13.1 of 13



PRODUCT RENEWED
 as complying with the Florida
 Building Code **15-0120.01**
 Acceptance No. **15-0120.01**
 Expiration Date **05/12/2020**
 By *[Signature]*
 Miami Dade Product Control



WINDOW WALL SYSTEM WITH LOUVERS TO ACCOMMODATE A/C UNIT
 USE ALUMINUM LOUVERS HOLDING CURRENT NOA
 DETAILS FOR 'RELIABLE PRODUCTS' APPROVED LOUVERS SHOWN



PRODUCT REVISED
 as complying with the Florida
 Building Code **13-1224.03**
 Acceptance No. **13-1224.03**
 Expiration Date **May 12, 2015**
 By *[Signature]*
 Miami Dade Product Control

Engr: JAVAD AHMAD
 CIVIL
 FLA. PE. # 70592
 C.A.N. 3538

APR 13 2014

af c
AL-FAROOQ CORPORATION
 ENGINEERS & PRODUCT DEVELOPMENT
 1235 S.W. 87 AVE
 MIAMI, FLORIDA 33174
 TEL. (305) 264-8100 FAX (305) 262-6978
 COMP-ANL\W09-24SM

SERIES SMI-090 ALUM WINDOW WALL (L.M.I.)
Aldora Aluminum & Glass Products Inc.
 11500 MIRAMAR PARKWAY SUITE 300
 MIRAMAR, FL. 33025
 TEL. (305) 888-6288 FAX. (305) 888-6289

no	date	description
C	08.12.13	NEW SHEET ADDED
D	03.05.14	REV. PER PER COMMENTS

date: 04-16-09
 scale: 1/2" = 1"
 dr. by: HAMID
 chk. by:

drawing no.
W09-24
 sheet 13.2 of 13