



DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)
 BOARD AND CODE ADMINISTRATION DIVISION
NOTICE OF ACCEPTANCE (NOA)

MIAMI-DADE COUNTY
 PRODUCT CONTROL SECTION
 11805 SW 26 Street, Room 208
 Miami, Florida 33175-2474
 T (786) 315-2590 F (786) 315-2599
www.miamidade.gov/economy

TKO Doors, Div. of 4Front Engineered Solutions, Inc.
 N56 W24701 N. Corporate Circle
 Sussex, WI 53089

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER-Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ). This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code. This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Model VC-2 WL Dock Plastic Sectional Garage Door up to 10'-0" Wide x 12'-0" High

APPROVAL DOCUMENT: Drawing No. 15-2400, titled "Fiberglass Dock Doors VC-2 WL Overhead Garage Door", sheet 1 through 7 of 7, dated 05/06/2013, with last revision dated 05/12/2015, prepared by Engineering Express, signed and sealed by Frank L. Bennardo, P.E., bearing the Miami-Dade County Product Control revision stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Section.

MISSILE IMPACT RATING: Large and Small Missile Impact Resistant

LABELING: A permanent label with the manufacturer's name or logo, manufacturing address, model number, the positive and negative design pressure rating, indicate impact rated if applicable, installation instruction drawing reference number, approval number (NOA), the applicable test standards, and the statement reading 'Miami-Dade County Product Control Approved' is to be located on the door's side track, bottom angle, or inner surface of a panel.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA revises NOA # 13-0521.05 and consists of this page 1 and evidence page E-1, as well as approval document mentioned above.

The submitted documentation was reviewed by Carlos M. Utrera, P.E.



[Handwritten Signature]
 12/08/2015

NOA No 15-0916.10
 Expiration Date: March 13, 2019
 Approval Date: December 17, 2015
 Page 1

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

A. DRAWINGS

1. Drawing No. 15-2400, titled "Fiberglass Dock Doors VC-2 WL Overhead Garage Door", sheet 1 through 7 of 7, dated 05/06/2013, with last revision dated 05/12/2015, prepared by Engineering Express, signed and sealed by Frank L. Bennardo, P.E.

B. TESTS "Submitted under NOA # 13-0521.05"

1. Addendum letter to Test Report No. C3614.01-602-18, dated 09/09/2013, signed and sealed by Shawn G. Collins, P.E.
2. Test reports on 1) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
2) Large Missile Impact Test per FBC, TAS 201-94
3) Cyclic Wind Pressure Loading per FBC, TAS 203-94
4) Forced Entry Test, per FBC TAS 202-94

Along with marked-up drawings and installation diagram of Verticool Doors, prepared by Architectural Testing, Inc., Test Report No. C3614.01-602-18, dated 03/28/2013, signed and sealed by Shawn G. Collins, P.E.

3. Test report on Self-ignition Temperature per ASTM D1929, Smoke Density Rating per ASTM D2843 and Rate of Burn per ASTM D635 of various plastic door components, prepared by Architectural Testing, Inc., Test Report No. C2850.01-106-18, dated 11/21/2012, signed and sealed by Gary T. Hartman, P.E.

C. CALCULATIONS

1. Jamb anchor calculations prepared by Engineering Express, dated 05/05/2015, signed and sealed by Frank L. Bennardo, P.E.

"Submitted under NOA # 13-0521.05"

2. Jamb anchor calculations prepared by Engineering Express, dated 05/14/2013 and 01/27/2014, signed and sealed by Frank L. Bennardo, P.E.

D. QUALITY ASSURANCE


1. Miami-Dade Department of Regulatory and Economic Resources (RER)

E. MATERIAL CERTIFICATIONS "Submitted under NOA # 13-0521.05"

1. Test report on Flame Spread Index and Smoke Developed Index per UL-723 of XEPS foam insulation, Test Report No. BRYX.R3573 dated 07/12/2010.

F. STATEMENTS

1. Statement letter of code conformance with the 5th edition (2014) FBC issued by Engineering Express, dated 05/19/2015, signed and sealed by Frank L. Bennardo, P.E.
2. Statement letter of no financial interest issued by Engineering Express, dated 05/19/2015, signed and sealed by Frank L. Bennardo, P.E.





Carlos M. Utrera, P.E.
Product Control Examiner
NOA No 15-0916.10


Expiration Date: March 13, 2019
Approval Date: December 17, 2015

VC-2 WL DOCK DOORS


LARGE MISSILE IMPACT RESISTANT



PLAN VIEW



SECTION A-A
SECTION SIDE VIEW



DOOR OPENING WIDTH/TRACK SPACING
INTERIOR ELEVATION

SEE SHEETS 6 OF 7 AND 7 OF 7 FOR DETAIL PANEL HARDWARE

SEE SHEET 4 OF 7 FOR DETAIL LOWER TRACK ASSEMBLY

SEE SHEET 2 OF 7 FOR DETAIL PANEL ASSEMBLY


SEE SHEET 3 OF 7 FOR DETAIL PANEL COMPONENTS

GENERAL NOTES

1. THE SYSTEM DESCRIBED HEREIN HAS BEEN DESIGNED AND TESTED IN ACCORDANCE WITH THE FLORIDA BUILDING CODE FIFTH EDITION (2014), FOR USE WITHIN AND OUTSIDE THE HIGH VELOCITY HURRICANE ZONE, PER TAS 201 / 202 / 203 STANDARDS.
2. NO 33-1/3% INCREASE IN ALLOWABLE STRESS HAS BEEN USED IN THE DESIGN OF THIS SYSTEM. WIND LOAD DURATION FACTOR Cd=1.6 HAS BEEN USED FOR WOOD ANCHOR DESIGN.
3. POSITIVE AND NEGATIVE DESIGN PRESSURES CALCULATED FOR USE WITH THIS SYSTEM SHALL BE DETERMINED PER SEPARATE ENGINEERING IN ACCORDANCE WITH THE GOVERNING CODE. PRESSURE REQUIREMENTS AS DETERMINED IN ACCORDANCE WITH ASCE 7 AND CHAPTER 1620 OF THE FLORIDA BUILDING CODE SHALL BE LESS THAN OR EQUAL TO THE POSITIVE OR NEGATIVE DESIGN PRESSURE CAPACITY VALUES LISTED HEREIN FOR ANY ASSEMBLY AS SHOWN.
4. DESIGN PRESSURES NOTED HEREIN ARE BASED ON MAXIMUM TESTED PRESSURES DIVIDED BY A 1.5 SAFETY FACTOR.
5. THE SYSTEM DETAILED HEREIN IS GENERIC AND DOES NOT PROVIDE INFORMATION FOR A SPECIFIC SITE. FOR SITE CONDITIONS DIFFERENT FROM THE CONDITIONS DETAILED HEREIN, A LICENSED ENGINEER OR REGISTERED ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE IN CONJUNCTION WITH THIS DOCUMENT.
6. CONTRACTOR SHALL VERIFY THE ADEQUACY OF THE EXISTING STRUCTURE TO WITHSTAND SUPERIMPOSED LOADS. WOOD BUCKS (BY OTHERS) SHALL BE ANCHORED PROPERLY TO TRANSFER LOADS TO THE EXISTING STRUCTURE.
7. ALL BOLTS & WASHERS SHALL BE ZINC COATED STEEL, GALVANIZED STEEL, OR STAINLESS STEEL WITH A MINIMUM TENSILE YIELD STRENGTH OF 60 KSI U.O.N.
8. ALL DISSIMILAR MATERIALS IN CONTACT SHALL BE PAINTED, PLATED OR OTHERWISE INSULATED.
9. DOOR HEIGHT MAY VARY UP TO A MAXIMUM HEIGHT OF 144", PROVIDED THAT INDIVIDUAL PANEL HEIGHTS DO NOT EXCEED 48".
10. ALL HARDWARE & FASTENERS SHALL BE IN ACCORDANCE WITH THESE DRAWINGS & MAY NOT VARY UNLESS SPECIFICALLY MENTIONED ON THE DRAWINGS.

**ALLOWABLE
DESIGN PRESSURES**

**+52.0 PSF
-52.0 PSF**



ENGINEERING EXPRESS
 160 SW 12th AVENUE, #3106
 DEERFIELD BEACH, FL 33442
 PH: (954) 354-0660 FAX: (954) 354-0443
 WWW.ENGEXP.COM
 CERT. OF AUTH. #6886
 A FRANK L. BENNARDO, P.E., INC. INNOVATION

TKO DOORS, DIVISION OF 4FRONT ENGINEERED SOLUTIONS, INC.
 N56 W24701 NORTH CORPORATE CIRCLE, SUITE A
 SUSSEX, WI 53089
 PHONE: 1-800-575-3366 FAX: (262) 246-1301
 FIBERGLASS DOCK DOORS
 VC-2 WL OVERHEAD GARAGE DOOR
 MIAMI-DADE NOTICE OF ACCEPTANCE





REMARKS	DRWN	CHKD	DATE
INIT ISSUE (13-TKO-03)	KL	FLB	05/06/13
REV. PER COMMENTS	KL	FLB	01/24/13
REV (2014 FBC)	RWN	CSL	05/12/15

THIS DOCUMENT IS THE PROPERTY OF ENGINEERING EXPRESS AND SHALL NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN CONSENT OF THE ENGINEERING EXPRESS. ADDITIONAL REPRODUCING OR OTHER MARKINGS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE OUR CERTIFICATION.

15-2400
 SCALE: -
 PAGE DESCRIPTION:
 1 OF 7

PRODUCT REVISED
 as complying with the Florida
 Building Code
 Acceptance No 15-0716.10
 Expiration Date 02/13/2019
 Miami Dade Product Control

V:\Projects\15-2400 Fiberglass Dock Doors VC-2 WL - NOA - Update 13-0521.05 (13-TKO-03) for -Project\WP15-2400a Vertical 2in Sectional Door (NOA) - 1.dwg
 05/22/2015 - 4:42pm rickn



FRANK L. BENNARDO, P.E.
 LICENSE NO. 46549
 05/22/2015
 STATE OF FLORIDA
 PROFESSIONAL ENGINEER

ENGINEERING EXPRESS

160 SW 12TH AVENUE, # 106
 DEERFIELD BEACH, FL 33442
 PH: (954) 354-0660 FAX: (954) 354-0443
 WWW.ENGEXP.COM
 CERT. OF AUTH #8885
 A FRANK L. BENNARDO, P.E., INC. INNOVATION

TKO DOORS, DIVISION OF 4FRONT ENGINEERED SOLUTIONS, INC.
 N56 W24701 NORTH CORPORATE CIRCLE, SUITE A
 SUSSEX, WI 53089
 PHONE: 1-800-575-3366 FAX: (262) 246-1301

FIBERGLASS DOCK DOORS
 VC-2 WL OVERHEAD GARAGE DOOR
 MIAMI-DADE NOTICE OF ACCEPTANCE

REMARKS	DRWN	CHKD	DATE
INIT ISSUE (13-TKO-03)	KL	FLB	05/06/13
REV. PER COMMENTS	KL	FLB	01/24/13
REV (2014 FBC)	RWN	CSL	05/12/15

THIS DOCUMENT IS THE PROPERTY OF ENGINEERING EXPRESS AND SHALL NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN CONSENT OF THE COMPANY ENGINEER. ALTERNATIONS, ADDITIONS, MODIFICATIONS OR OTHER MARKS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE ANY CONTRACT.

PRODUCT REVISED
 as complying with the Florida Building Code
 Acceptance No 15-0916-10
 Expiration Date 02/13/2019


By *[Signature]*
 Miami Dade Product Control

15-2400
 SCALE: -
 PAGE DESCRIPTION:
 2 OF 7


V:\Projects\15-2400 Fiberglass Dock Doors VC-2 WL - NOA - Update 13-0521.05 (13-TKO-03) for -Project\WP15-2400a Vertical 2in Sectional Door (NOA) - 1.dwg

05/22/2015 - 4:42pm rickn


VC-2 WL PANEL COMPONENTS



BRACKET, CORNER L, WW
PART NO. 20-00045
14-GA HRPO***, CLEAR ZINC FINISH
*** HOT-ROLLED STEEL, PICKLED & OILED




D-PROFILE, TRIM-LOK
PART NO. 20-01456
(SEE SHEET 2 OF 7 FOR LOCATION)




EPDM FOAM RUBBER-
OZONE RESISTANT
(MANUFACTURED BY
ACTION INDUSTRIES/
TORSION SOURCE
ACE EXTRUSION)


BT '3M' ACRYLIC TAPE SYSTEM





D-PROFILE, TRIM-LOK
PART NO. 20-00730
(SEE SHEET 2 OF 7 FOR
LOCATION)




SEAL, 2" HORIZONTAL WHITE PART NO. 20-00023
(MANUFACTURED BY HI-TECH)




FLEX ALCRYN (BLACK)
RIGID PVC (WHITE)
SLOT FOR SIDE
SEAL BRUSH
PART NO.s 20-01966
& 20-01967




FLEX ALCRYN (BLACK)
RIGID PVC (WHITE)
SEAL 2" T-SLOT
PART NO. 20-01953
CUT TO PANEL
HEIGHT DIMENSION




SEAL, 2" T-SLOT WHITE PART NO. 20-00027
(MANUFACTURED BY HI-TECH)



*NOTE:
-SEAL, WW, SIDE LOOP, 48-3/4"
PART NO. 20-01825 (INTERMEDIATE PANEL)
-SEAL, WW, SIDE LOOP, 49-1/2"
PART NO. 20-01826 (BOTTOM PANEL ONLY)



EPDM
(ETHYLENE PROPYLENE DIENE MONOMER)
BOTTOM LOOP SEAL PART NO. 20-00318
CUT TO DOOR OPENING WIDTH




EQUALS TRACK SPACING/ DOOR OPENING WIDTH

BRUSH, NYLON FILL
BACKING, STEEL

BRUSH, STD, #2.5, BLACK**
CUT TO PANEL HEIGHT
(MANUFACTURED BY
TANIS INCORPORATED)

SLIP-COAT, BLACK
85 DUROMETER
FLEX-COAT TPR WHITE
55 DUROMETER

SEAL, WW
SIDE LOOP, BLACK*
PNO.s 20-01825 & 20-01826
CUT TO PANEL HEIGHT



FRANK L. BENNARDO, P.E.
#PF0046549
ENGINEERING EXPRESS
160 SW 12th AVENUE, #106
DEERFIELD BEACH, FL 33442
PH: (954) 354-0660 FAX: (954) 354-0443
WWW.ENGINEXP.COM
CERT OF AUTH. #0885
A FRANK L. BENNARDO, P.E., INC. INNOVATION

TKO DOORS, DIVISION OF 4FRONT ENGINEERED SOLUTIONS, INC.
N56 W24701 NORTH CORPORATE CIRCLE, SUITE A
SUSSEX, WI 53089
PHONE: 1-800-575-3366 FAX: (262) 246-1301
FIBERGLASS DOCK DOORS
VC-2 WL OVERHEAD GARAGE DOOR
MIAMI-DADE NOTICE OF ACCEPTANCE

DRWN	CHKD	DATE
KL	FLB	05/06/13
KL	FLB	01/24/13
RWN	CSL	05/12/15


REMARKS
INIT ISSUE (13-TKO-03)
REV. PER COMMENTS
REV (2014 FBC)

THIS DOCUMENT IS THE PROPERTY OF ENGINEERING EXPRESS. IT IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREIN. ANY REUSE OR MODIFICATION OF THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF THE CERTIFYING ENGINEER, A TERMINATING AGENCY, REGULATOR OR OTHER MARKING TO THIS DOCUMENT ARE NOT PERMITTED AND WILL INFRINGE OUR CERTIFICATION.

COPYRIGHT ENGINEERING EXPRESS
15-2400
SCALE:
PAGE DESCRIPTION:
By *[Signature]*
Miami Dade Product Control
3 OF 7

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 15-0716-16
Expiration Date 03/13/2015

V:\Projects\15-2400 Fiberglass Dock Doors VC-2 WL- NOA - Update 13-0521.05 (13-TKO-03) for -Project\WP15-2400a Vertical 2in Sectional Door (NOA) - 1.dwg
 05/22/2015 - 4:42pm rick



FRANK L. BERNARDO, P.E.
 # PE0046549
 LICENSE No. 46549
 STATE OF FLORIDA
 PROFESSIONAL ENGINEER
 03/22/2015

ENGINEERING EXPRESS
 CERT. OF AUTH #886
 A FRANK L. BERNARDO, P.E., INC. INNOVATION

TKO DOORS, DIVISION OF 4FRONT ENGINEERED SOLUTIONS, INC.
 N56 W24701 NORTH CORPORATE CIRCLE, SUITE A
 SUSSEX, WI 53089
 PHONE: 1-800-575-3366 FAX: (262) 246-1301

FIBERGLASS DOCK DOORS
 VC-2 WL OVERHEAD GARAGE DOOR
 MIAMI-DADE NOTICE OF ACCEPTANCE

REVISIONS	DATE	BY	CHKD	DRWN
INIT ISSUE (13-TKO-03)	05/06/13	KL	FLB	KL
REV. PER COMMENTS	01/24/13	KL	FLB	KL
REV (2014 FBC)	05/12/15	RWN	CSL	RWN


REMARKS: THIS DOCUMENT IS THE PROPERTY OF ENGINEERING EXPRESS. IT IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREIN. ANY REUSE OR MODIFICATION OF THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF THE CERTIFYING ENGINEER, A TENTATIVE, ADDITIONAL, HIGH LIGHTING, OR OTHER MARKINGS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE OUR CERTIFICATION.

PRODUCT REVISED
 as complying with the Florida Building Code
 Acceptance No 150716-10
 Expiration Date 03/13/2019
 By *[Signature]*
 Miami Dade Product Control

COPYRIGHT ENGINEERING EXPRESS
 15-2400
 SCALE: -
 PAGE DESCRIPTION:
 OF 7
4


VC-2 WL TRACK ANCHOR MOUNTING

STEEL ANGLE TRACK TO BLOCK/CONCRETE



(SEE ANCHORING NOTES)


STEEL ANGLE TRACK ANCHOR HOLE



DETAIL A


(SEE ANCHORING NOTES)

ANGLE TO STEEL WITH PLUG WELD




(SEE ANCHORING NOTES)

ANGLE TO STEEL WITH STITCH WELD




(SEE ANCHORING NOTES)




(SEE ANCHORING NOTES)

DETAIL B

TEST MOUNTING ON WOOD



DETAIL C
FLOOR TO TRACK BRACKET
(SEE SHEET 4 OF 7 FOR DETAIL)



BRACKET, FLOOR TO TRACK PART NO. 20-00007
(SEE ANCHORING NOTES)
*TYPE OF ANCHOR DETERMINED BY FLOOR MATERIAL,
USE ANY ANCHOR SHOWN HEREIN

ANCHORING NOTES

1. THIS SYSTEM SHALL BE ANCHORED WITH ANY OF THE ANCHORING METHODS SHOWN HEREIN, WITH (2) ANCHORS LOCATED 3" AND 12" FROM THE BOTTOM OF THE TRACK AND 12" O.C. MAX THEREAFTER OR EVERY OTHER MOUNTING SLOT.
2. ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.
3. WHERE ANCHORS FASTEN TO NARROW FACE OF STUD FRAMING, ANCHOR SHALL BE LOCATED IN CENTER OF NOMINAL 2x (MIN) WOOD STUD (i.e. 3/4" EDGE DISTANCE IS ACCEPTABLE FOR ANCHORS TO WOOD FRAMING).
4. WOOD HOST STRUCTURE SHALL BE "SOUTHERN PINE" G=0.55 OR GREATER DENSITY.
5. MINIMUM EMBEDMENT SHALL BE AS NOTED IN ANCHOR DETAIL. MINIMUM EMBEDMENT AND EDGE DISTANCE EXCLUDES STUCCO, FOAM, BRICK, AND OTHER WALL FINISHES.
6. WHERE EXISTING STRUCTURE IS WOOD FRAMING, EXISTING CONDITIONS MAY VARY. FIELD VERIFY THAT FASTENERS ARE INTO ADEQUATE WOOD FRAMING MEMBERS, NOT INTO PLYWOOD.
7. WOOD BUCKS (BY OTHERS) SHALL BE ANCHORED PROPERLY TO TRANSFER LOADS TO THE EXISTING STRUCTURE.
8. MACHINE SCREWS SHALL HAVE MINIMUM OF 1/2" ENGAGEMENT OF THREADS IN BASE ANCHOR AND MAY HAVE EITHER A PAN HEAD, TRUSS HEAD, OR WAFFER HEAD ("SIDEWALK BOLT") U.N.O.

FRANK L. BENNARDO, P.E.
#PE0046549

STATE OF FLORIDA
REGISTERED PROFESSIONAL ENGINEER

ENGINEERING EXPRESS, INC.
160 SW 12th Avenue, Suite 200
Deerfield Beach, FL 33442
Ph: (954) 354-0660 Fax: (954) 354-0669
WWW.ENGEXP.COM

A. FRANK L. BENNARDO, P.E., INC. INNOVATION
CERT. OF AUTH #9885

TKO DOORS, DIVISION OF 4FRONT ENGINEERED SOLUTIONS, INC.
N56 W24701 NORTH CORPORATE CIRCLE, SUITE A
SUSSEX, WI 53089
PHONE: 1-800-575-3366 FAX: (262) 246-1301

FIBERGLASS DOCK DOORS
VC-2 WL OVERHEAD GARAGE DOOR
MIAMI-DADE NOTICE OF ACCEPTANCE

REMARKS	DRWN	CHKD	DATE
INIT. ISSUE (13-TKO-03)	KL	FLB	05/06/13
REV. PER COMMENTS	KL	FLB	01/24/13
REV. (2014 FBC)	RWN	CSL	05/12/15

THIS DOCUMENT IS THE PROPERTY OF ENGINEERING EXPRESS AND SHALL NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN PERMISSION OF ENGINEERING EXPRESS. DOCUMENTS ARE NOT PERMITTED AND INVALIDATE OUR CERTIFICATION.

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 15-0716-10
Expiration Date 03/12/2019

By *[Signature]*
Miami Dade Product Control

COPYRIGHT ENGINEERING EXPRESS

15-2400

SCALE: -

PAGE DESCRIPTION:

5 OF 7

V:\Projects\15-2400 Fiberglass Dock Doors VC-2 WL - NOA - Update 13-0521.05 (13-TKO-03) for -Project\WP15-2400a Vertical 2in Sectional Door (NOA) - 1.dwg
 05/22/2015 - 4:42pm rickn

FASTENER NOTE:




FIXED PLUNGERS, HANDLES, AND TPU BRACKETS ARE MOUNTED TO THE PANEL USING: (4) 1/4-20 X 3.00" CARRIAGE BOLTS AND (4) 1/4-20 FLANGE NUTS.

HINGE SETS ARE MOUNTED TO THE PANELS USING: (4) 1/4-20 X 3.00" CARRIAGE BOLTS AND 1/4-20 FLANGE NUTS.


PANEL PLATES ARE MOUNTED TO THE PANELS USING: (10) 1/4-20 X 3.00" CARRIAGE BOLTS AND 1/4-20 FLANGE NUTS.

SLIDE LOCKS ARE MOUNTED TO THE PANELS USING: (4) #14 X 3/4" TEK SCREWS.


VC-2 WL PANEL HARDWARE




13-GA HRPO* CLEAR ZINC FINISH BRACKET, POST PART NO. 20-02018




WALL BRACKET, WINDLOAD A36 STEEL, ZINC PLATED PART NO. 35-00057




KIT, CENTER POST, HEAVY- WLD ALUMINUM ALLOY 6005- T5 TKO PART NO. 30-00907




CENTER POST ASSEMBLY, HEAVY TKO PART NO. 30-00905



3/64" GALV. LANYARD, POST TETHER, 8' PART NO. 10-00360







U-BOLT, 1018 STEEL, ZINC PLATED PART NO. 10-00359




HINGE PLATE, FEMALE PART NO. 20-00011 13-GA HRPO* CLEAR ZINC


HINGE PLATE, MALE PART NO. 20-00010 13-GA HRPO* CLEAR ZINC




10-GA HRPO* CLEAR ZINC HANDLE PART NO. 20-00613




MIN 12-GA STEEL HOUSING




FIXED PLUNGER PART NO. 30-00676




18-GA A653 G90 COVER, PLUNGER PART NO. 20-01459




TPU CABLE LEVELING BRACKET 11-GA A653 G90 PART NO. 20-01868




12-GA A653 G90 PANEL PLATE PART NO. 20-01814




1" DIA PULL RING



KNOCK OUT LOCK PART NO. 30-00590 (SEE SHEET 7 OF 7 FOR LOCATION)



*HRPO- HOT ROLLED, PICKLED & OILED STEEL



FRANK L. BENNARDO, P.E.
PEO046549
ENGINEERING EXPRESS
160 SW 12th AVENUE, #106
DEERFIELD BEACH, FL 33442
PH: (954) 354-0660 FAX: (954) 354-0443
WWW.ENGEXP.COM
CERT OF AUTH #9885
A. FRANK L. BENNARDO, P.E., INC. INNOVATION

TKO DOORS, DIVISION OF 4FRONT ENGINEERED SOLUTIONS, INC.
N56 W24701 NORTH CORPORATE CIRCLE, SUITE A
SUSSEX, WI 53089
PHONE: 1-800-575-3366 FAX: (262) 246-1301
FIBERGLASS DOCK DOORS
VC-2 WL OVERHEAD GARAGE DOOR
MIAMI-DADE NOTICE OF ACCEPTANCE

REMARKS	DRWN/CHKD	DATE
INIT ISSUE (13-TKO-03)	KL	05/06/13
REV PER COMMENTS	KL	01/24/13
REV (2014 REC)	RWN	05/12/15


THIS DOCUMENT IS THE PROPERTY OF ENGINEERING EXPRESS AND SHALL NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN CONSENT OF THE CERTIFYING ENGINEER. AT TESTERS' ADDRESS. SIGNATURE OF THE CERTIFYING ENGINEER. DOCUMENT NOT FOR CONSTRUCTION AND NOT TO BE USED FOR CONSTRUCTION.

COPYRIGHT ENGINEERING EXPRESS
15-2400
SCALE:
PAGE DESCRIPTION:
By *[Signature]*
Miami Dade Product Control
6 of 7

V:\Projects\15-2400 Fiberglass Dock Doors VC-2 WL- NDA - Update 13-0521.05 (13-TKO-03) for -Project\WP15-2400a Vertical 2 in Sectional Door (NOA) - 1.dwg

rickn

05/22/2015 - 4:42pm



FRANK L. BENNARDO, P.E.
PE0046549
05/22/2015
FRANK L. BENNARDO, P.E.
LICENSE NO. 46549
STATE OF FLORIDA
PROFESSIONAL ENGINEER

ENGINEERING EXPRESS
160 SW 12th AVENUE, #106
DEERFIELD BEACH, FL 33442
PH: (954) 354-0660 FAX: (954) 354-0443
WWW.ENGEXP.COM
CERT OF AUTH #8865
A FRANK L. BENNARDO, P.E., INC. INNOVATION

TKO DOORS, DIVISION OF 4FRONT ENGINEERED SOLUTIONS, INC.
N56 W24701 NORTH CORPORATE CIRCLE, SUITE A
SUSSEX, WI 53089
PHONE: 1-800-575-3366 FAX: (262) 246-1301
FIBERGLASS DOCK DOORS
VC-2 WL OVERHEAD GARAGE DOOR
MIAMI-DADE NOTICE OF ACCEPTANCE

DRWN	CHKD	DATE
KL	FLB	05/06/13
KL	FLB	01/24/13
RWN	CSL	05/12/15

REMARKS
INIT ISSUE (13-TKO-03)
REV. PER COMMENTS
REV (2014 FBC)

THIS DOCUMENT IS THE PROPERTY OF ENGINEERING EXPRESS. IT IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED ON THE DRAWING. ANY REUSE, REPRODUCTION, OR OTHER VIOLATION OF THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE OUR CERTIFICATION.

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 15-0716-10
Expiration Date 03/13/2019
By *[Signature]*
Miami Code Product Control

COPYRIGHT ENGINEERING EXPRESS
15-2400
SCALE:
PAGE DESCRIPTION:
7