

# MIAMI-DADE COUNTY PRODUCT CONTROL SECTION

11805 SW 26 Street, Room 208 Miami, Florida 33175-2474 T (786)315-2590 F (786) 315-2599

www.miamidade.gov/economy

# DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER) BOARD AND CODE ADMINISTRATION DIVISION

### **NOTICE OF ACCEPTANCE (NOA)**

GAF 1 Campus Drive Parsippany, NJ 07054

#### **SCOPE:**

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER - Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code including the High Velocity Hurricane Zone of the Florida Building Code.

## **DESCRIPTION: TOPCOAT® Waterproofing**

**LABELING:** Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA revises and renews NOA No. 15-0128.10 consists of pages 1 through 7.

The submitted documentation was reviewed by Freddy Semino





NOA No.: 18-0119.11 Expiration Date: 02/28/23 Approval Date: 03/01/18 Page 1 of 7

MIAMI-DADE COUNTY
APPROVED

### **ROOFING SYSTEM APPROVAL**

<u>Category:</u> Roofing

Sub-Category: Waterproofing Systems

Deck Type:ConcreteMaterial:ElastomericMaximum Design Pressure-607.5 psf.

# TRADE NAMES OF PRODUCTS MANUFACTURED OR LABELED BY APPLICANT: TABLE 1

<b>Product</b>	<u>Dimensions</u>	Test <u>Specification</u>	Product <u>Description</u>
TOPCOAT® Elastomeric Roofing Membrane	1, 5 or 55gal.	ASTM D6083	An acrylic, water based elastomeric membrane system designed to protect various types of roofing surfaces
TOPCOAT® Surface Seal SB	5 or 55gal	ASTM D6083	Solvent based sprayable thermoplastic rubber sealant designed to protect various types of roofing surfaces.
TOPCOAT® MB Plus	5 or 55gal.	Proprietary	Water based low VOC primer designed to block asphalt bleed-through.
TOPCOAT® XR-2000	5 or 55 gal.	Proprietary	Primer for pre-finished metal: (e.g. Kynar).
TOPCOAT® Flashing Grade	1, 5 gal. or 1qt tube	TAS-139	Water-based flashing compound.
		Test	Product
<b>Product</b>	<b>Dimensions</b>	<b>Specification</b>	<b>Description</b>
TOPCOAT® Liquid Fabric Flashing Grade	5 or 55 gal.	Proprietary	Water-based, high elasticity flashing compound.
TOPCOAT® Flexseal	1, 5 gal. or 1qt tube	TAS 139	Solvent based flashing compound for gutters and other detailing.
FireOut <sup>™</sup>	5 or 55gal	Proprietary	Low VOC, water-based fire barrier coating.



NOA No.: 18-0119.11 Expiration Date: 02/28/23 Approval Date: 03/01/18

Page 2 of 7

# TRADE NAMES OF PRODUCTS MANUFACTURED BY OTHERS TABLE 2

<b>Product</b>	<b>Dimensions</b>	Test Specification	Product <u>Description</u>	<u>Manufacturer</u>
Ceramic Tiles	12" x 12" x ½"	ASTM C902	Ceramic plaza deck walking tiles, 5% water absorption max.	Generic
Portland Cement	15 lb. Box, 25 & 50 Bags	ANSI A118.4	A polymer modified Portland Cement.	Custom Building Products

## **EVIDENCE SUBMITTED:**

<b>Test Agency</b>	Test Identifier	Test Name	<u>Date</u>
Exterior Research & Design, LLC	G6040.03.07	TAS 114-D	03/19/07
	18026.03.02-2-R2	TAS 114-D	12/05/07
PRI Asphalt Technologies, Inc.	GAF-276-02-01REV	Proprietary	01/04/11
	GAF-498-02-01	ASTM D 6083	09/16/16
	GAF-499-02-01	ASTM D 6083	03/12/14
	GAF-500-02-01	ASTM D 6083	03/12/14
	GAF-658-02-01	Proprietary	06/06/16
	GAF-667-02-01	TAS 139	07/01/16
	GAF-671-02-01	TAS 139	06/30/16
Factory Mutual Research Corp.	3015619	FM 4470	03/15/05
Underwriters Laboratories, Inc.	R1306	UL 790	02/08/18



NOA No.: 18-0119.11 Expiration Date: 02/28/23 Approval Date: 03/01/18 Page 3 of 7

#### **APPROVED APPLICATIONS:**

**Deck Type 3**: Concrete Decks, Non-Insulated

**Deck Description:** 2500 psi structural concrete or concrete plank

**System Type F(1):** Fully Adhered liquid applied waterproofing system.

All General Limitations apply.

All GAF TOPCOAT® products shall be installed in accordance with manufacturer's specifications. The following are minimum installation guidelines. Consult the GAF TOPCOAT® Specification Manual or Technical Service for specific/complete installation instructions.

**Substrate** The TOPCOAT® Elastomeric Roofing Membrane system is to be applied over **Preparation:** structural concrete only with a minimum slope of ½":12". Concrete roof substrate

must be completely cured and dry before application of TOPCOAT® products.

Substrate should not pond water for a period longer that 48 hours.

**Base Coat:** Apply two or more coats of TOPCOAT® Elastomeric Roofing Membrane at a

rate of 1.25 gallons per 100 square feet per coat to a wet mil thickness of 20 mils each coat. Allow 24 hours to dry and inspect base coat for defects. Correct

unsatisfactory conditions prior to proceeding.

**Finish Coat(s):** Apply one or more finish coats of TOPCOAT® Elastomeric Roofing Membrane

at a rate of 1.75 gallons per 100 square feet per coat to a wet mil thickness of 28 mils each coat. Allow 24 hours drying time prior to allowing foot traffic or

inspection of roof surface.

**Integrity Test:** Required, and shall be performed in accordance with ASTM D 5957 by an

approved lab. Water maybe maintained for a period longer than 24 hours if

required.

**Inspection:** Contractor and a representative of the membrane manufacturer shall inspect the

waterproofing assembly and notify the contractor of any defects. Inspection must take place prior to installation of any overlay insulation, protection pads, drainage

boards and traffic surfacing. All defects observed shall be corrected.

**Maximum Design** 

**Pressure:** -576 psf. (See General Limitation #9)



NOA No.: 18-0119.11 Expiration Date: 02/28/23 Approval Date: 03/01/18

Page 4 of 7

**Deck Type 3**: Concrete Decks, Non-Insulated

**Deck Description:** 2500 psi structural concrete or concrete plank

**System Type F(2):** Tile Finish over fully adhered liquid applied waterproofing system.

All General Limitations apply.

All GAF TOPCOAT® products shall be installed in accordance with manufacturer's specifications. The following are minimum installation guidelines. Consult the GAF TOPCOAT® Specification Manual or Technical Service for specific/complete installation instructions.

**Substrate** All surfaces must be dry, smooth, and free of depressions, voids protrusions;

**Preparation:** clean and free of any non-compatible curing compounds, foam release agents and

other surface contaminants.

**Coatings:** Apply two or more coats of TOPCOAT® Surface Seal SB at a rate of 1 gallon per

100 square feet per coat to a wet mil thickness of 16 mils each coat. Allow 24 hours drying time prior to allowing foot traffic or inspection of roof surface.

Inspect completed system for defects and correct as required.

**Integrity Test:** Required, and shall be performed in accordance with ASTM D 5957 by an

approved lab. Water maybe maintained for a period longer than 24 hours if

required.

**Inspection:** Contractor and a representative of the manufacturer shall inspect the

waterproofing assembly and notify the contractor of any defects. Inspection must take place prior to installation of any overlay insulation, protection pads, drainage

boards and traffic surfacing. All defects observed shall be corrected.

Surfacing: Exterior grade ceramic plaza deck walking tiles (Minimum size of 12" x 12" ½"

thick), tiles shall be embedded into Custom Building Products Polymer modified Portland cement applied with a ¼" square notched trowel. Tiles should then be carefully embedded in the mortar bed and tapped in place to insure full solid bearing. Tile shall be installed in accordance with applicable Building Code.

**Maximum Design** 

**Pressure:** –591 psf. (See General Limitation #9)



NOA No.: 18-0119.11 Expiration Date: 02/28/23 Approval Date: 03/01/18

Page 5 of 7

Concrete Decks, Non-Insulated Deck Type 3:

**Deck Description:** 2500 psi structural concrete or concrete plank

System Type F(3): Tile Finish over fully adhered liquid applied waterproofing system.

All General Limitations apply.

All GAF TOPCOAT® products shall be installed in accordance with manufacturer's specifications. The following are minimum installation guidelines. Consult the GAF TOPCOAT® Specification Manual or Technical Service for specific/complete installation instructions.

All surfaces must be dry, smooth, and free of depressions, voids protrusions; **Substrate Preparation:** 

clean and free of any non-compatible curing compounds, foam release agents and

other surface contaminants.

Apply three or more coats of TOPCOAT® Elastomeric Roofing Membrane at a **Coatings:** 

> rate of 1 gallon per 100 square feet per coat to a wet mil thickness of 16 mils each coat. Allow 24 hours drying time prior to allowing foot traffic or inspection of roof surface. Inspect completed system for defects and correct as required.

**Integrity Test:** Required, and shall be performed in accordance with ASTM D 5957 by an

approved lab. Water maybe maintained for a period longer than 24 hours if

required.

**Inspection:** Contractor and a representative of the manufacturer shall inspect the

> waterproofing assembly and notify the contractor of any defects. Inspection must take place prior to installation of any overlay insulation, protection pads, drainage

boards and traffic surfacing. All defects observed shall be corrected.

**Surfacing:** Exterior grade ceramic plaza deck walking tiles (Minimum size of 12" x 12" ½"

> thick), tiles shall be embedded into Custom Building Products Polymer modified Portland cement applied with a 1/4" square notched trowel. Tiles should then be carefully embedded in the mortar bed and tapped in place to insure full solid bearing. Tile shall be installed in accordance with applicable Building Code.

**Maximum Design** 

-607.5 psf. (See General Limitation #9) **Pressure:** 



NOA No.: 18-0119.11 Expiration Date: 02/28/23 Approval Date: 03/01/18

Page 6 of 7

### **GENERAL LIMITATIONS:**

- 1. Fire classification is not part of this acceptance; refer to a current Approved Roofing Materials Directory for fire ratings of this product.
- 2. Required integrity flood testing report in accordance with ASTM D5957 from an approved lab shall be provided to the Building Official for review at time of final inspection.
- 3. Contractor shall be approved by GAF.
- 4. Flashings shall be installed according to the manufacturer's published standard details and shall be submitted to the Building Official for review.
- 5. Contractor shall submit to the Building Official for review the system specifications and details. Submission of these documents, as well as the proper application and installation of all materials shall be the sole responsibility of the contractor.
- 6. Systems shall not be installed over lightweight insulating concrete.
- 7. Perimeter and corner areas shall comply with the enhanced uplift pressure requirements of these areas. Fastener densities shall be increased for both insulation and base sheet as calculated in compliance with Roofing Application Standard RAS 117. Calculations prepared, signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant (When this limitation is specifically referred within this NOA, General Limitation #9 will not be applicable.)
- 8. All attachment and sizing of perimeter nailers, metal profile, and/or flashing termination designs shall conform to Roofing Application Standard RAS 111 and the wind load requirements of applicable Building Code.
- 9. The maximum designed pressure limitation listed shall be applicable to all roof pressure zones (i.e. field, perimeters, and corners). Neither rational analysis, nor extrapolation shall be permitted for enhanced fastening at enhanced pressure zones (i.e. perimeters, extended corners and corners). (When this limitation is specifically referred within this NOA, General Limitation #7 will not be applicable.)
- 10. A non-skid surfacing is required for all pedestrian areas, plaza decks or balconies.
- 11. All products listed herein shall have a quality assurance audit in accordance with the Florida Building Code and Rule **61G20-3** of the Florida Administrative Code.

### END OF THIS ACCEPTANCE



NOA No.: 18-0119.11 Expiration Date: 02/28/23 Approval Date: 03/01/18

Page 7 of 7