

# DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER) BOARD AND CODE ADMINISTRATION DIVISION

#### MIAMI-DADE COUNTY PRODUCT CONTROL SECTION

11805 SW 26 Street, Room 208 Miami, Florida 33175-2474 T (786) 315-2590 F (786) 315-2599 www.miamidade.gov/economy

### **NOTICE OF ACCEPTANCE (NOA)**

Brock Associates, LLC 180 Bilmar Drive, Suite 2 Pittsburgh, PA. 15205

#### **SCOPE:**

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER - Product Control Section to be used in Miami-Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami-Dade County) and/or the AHJ (in areas other than Miami-Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein and has been designed to comply with the Florida Building Code including the High Velocity Hurricane Zone of the Florida Building Code.

### **DESCRIPTION:** Tite-Loc Plus 24 Gage x 12in thru 18in Wide Steel Panel over Wood Deck

**LABELING:** Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA renews NOA File No. 15-0327.03 and consists of pages 1 through 5.

The submitted documentation was reviewed by *Freddy Semino* 







NOA No.: 20-0303.12 Expiration Date: 05/14/2025 Approval Date: 04/16/2020 Page 1 of 5

## **ROOFING ASSEMBLY APPROVAL:**

**Category:** 

**Sub-Category:** Non-Structural Metal Roofing

**Material:** Steel **Deck Type:** Wood **Maximum Design Pressure** -204.25 psf.

# TRADE NAMES OF PRODUCTS MANUFACTURED OR LABELED BY APPLICANT:

<b>Product</b>	<u>Dimensions</u>	Test <b>Specifications</b>	Product <u>Description</u>
Tite-Loc Plus 24 gage Steel Panel	Length: varies Width: 12" thru 18" Height: 2" Thickness: 0.024" Min. Yield Strength: 55 ksi.	TAS 110	Valspar Fluropon coated roll formed 24 ga. steel interlocking panels.
Tite-Loc Plus Clips (Option 1 & 2)	Length: 4.3" Width: 2.145" Height: 2.1" Base Thickness 18ga. Tab Thickness 22ga.	TAS 110	Galvanized Steel, Galvalume Steel or Stainless steel stamped clips for use with Tite-Loc Plus 24 gage steel panel.

## **EVIDENCE SUBMITTED:**

<b>Test Agency</b>	<b>Test Identifier</b>	Test Name/Report	<b>Date</b>
Architectural Testing, Inc.	B8437.02-450-18	TAS 125	07/30/12
	74913.01-109-18-r1	TAS 100	04/15/15
Intertek   ATI	J5603.01-450-18	TAS 100	08/12/19
	C5105.02-801-44	ASTM E2140	04/24/15
Valspar	433X515	Salt Spray	
1		ASTM B 117	
	433B173	Accelerated Weathering	
		ASTM G 23	



NOA No.: 20-0303.12 Expiration Date: 05/14/2025 **Approval Date: 04/16/2020** Page 2 of 5

#### **APPROVED ASSEMBLIES:**

System A: Tite-Loc Plus 24ga.x 12" thru 18" Wide Steel Panel

See Table A below

**Deck Type:** Wood, Non-Insulated

**Deck Description:** New Construction  $^{19}/_{32}$ " or greater plywood or wood plank.

**Slope Range:** 2": 12" or greater (1":12" or greater effective w/2020 FBC 7<sup>th</sup> Edition)

**Maximum Uplift** 

**Pressure:** 

**Deck Attachment:** In accordance with applicable building code, but in no case it shall be less than #8d ring shank

nails spaced at distance listed below in **Table A**. In re-roofing, where deck is less than  $^{19}/_{32}$ " thick (minimum  $^{15}/_{32}$ ") the above attachment method must be in addition to existing

attachment.

**Underlayment:** Minimum underlayment shall be an ASTM D 226 Type II installed with a minimum 4" side-

laps and 6" end-laps. Underlayment shall be fastened with corrosion resistant tin-caps and 1½" annular ring-shank nails, spaced 6" o.c. at all laps and two staggered rows 12" o.c. in the field of the roll. Or, any Miami-Dade County Product Control Approved underlayment

having a current NOA.

**Fire Barrier:** Any approved fire barrier having a current NOA. Refer to a current fire directory listing for

fire ratings of this roofing system assembly as well as the location of the fire barrier within

the assembly. See Limitation #1.

Valleys: Valley construction shall be in compliance with Roofing Application Standard RAS 133 and

with the current published installation instructions and details in PAC Contractors

Association's Roofing Installation Manual.

Metal Panels and Accessories:

Install the "Tite-Loc Plus 24 ga. Steel Panel" panels including flashing penetrations, valleys, end laps and accessories in compliance PAC Contractors Association's current, published installation instructions and in compliance with the minimum requirements detailed in

Roofing Application Standard RAS 133.

Tite-Loc panels shall be secured with Tite-Loc Plus clips at a spacing listed below in **Table** A. Clips are to be fastened with a minimum of two  $\#10 \times 1-1/2$ " long pancake head screws

of sufficient length to penetrate through the deck at a minimum of  $\frac{3}{16}$ ".

Place the female end of the adjacent panel over the clip/panel male assembly and seam 180° degree. See Detail A herein. Factory or field applied sealant in the seam is optional.

TABLE A MAXIMUM DESIGN PRESSURES					
Roof Areas	Field	Perimeter and Corner <sup>2</sup>			
<b>Maximum Design Pressures</b>	-114.25 psf	-204.25 psf			
Maximum Clip Spacing	24" o.c.	6" o.c.			
Maximum Plywood Nail Spacing	6" o.c.	3" o.c.			
Extrapolation shall not be allowed					



NOA No.: 20-0303.12 Expiration Date: 05/14/2025 Approval Date: 04/16/2020 Page 3 of 5


#### **SYSTEM LIMITATIONS**

- 1. Fire classification is not part of this acceptance; refer to a current Approved Roofing Materials Directory for fire ratings of this product.
- 2. The maximum designed pressure listed herein shall be applicable to all roof pressure zones (i.e. field, perimeters, and corners). Neither rational analysis, nor extrapolation shall be permitted for enhanced fastening at enhanced pressure zones (i.e. perimeters, extended corners and corners).
- Panels may be rolls formed in continuous lengths from eave to ridge. Maximum lengths shall be as described in 3. Roofing Application Standard RAS 133.
- 4. All panels shall be permanently labeled with the manufacturer's name and/or logo, city, state, and the following statement: "Miami-Dade County Product Control Approved" or with the Miami-Dade County Product Control Seal as seen below. All clips shall be permanently labeled with the manufacturer's name and/or logo, and/or model.



- 5. All products listed herein shall have a quality assurance audit in accordance with the Florida Building Code and Rule **61G20-3** of the Florida Administrative Code.
- 6. Panels may be shop or jobsite roll formed with machine model #('s) 061203 from PAC Contractors Association or manufactured at Petersen Aluminum Corporation's plant in Acworth, GA.

## PROFILE DRAWING




180 DEGREE 2" HIGH X 12" THRU 18" WIDE DOUBLE LOCK PANEL OPTIONAL FACTORY OR FIELD APPLIED SEALANT IN THE SEAM CLIP RELIEFS, STIFFENING RIBS AND STRIATIONS OPTIONAL



NOA No.: 20-0303.12 **Expiration Date: 05/14/2025 Approval Date: 04/16/2020** 

Page 4 of 5

# **CLIP DETAIL DRAWINGS**



## **CLIP OPTION 1**

FRONT VIEW

## **CLIP OPTION 2**

FRONT VIEW

# **END OF THIS ACCEPTANCE**



NOA No.: 20-0303.12 Expiration Date: 05/14/2025 Approval Date: 04/16/2020

Page 5 of 5