



DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)  
BOARD AND CODE ADMINISTRATION DIVISION  
**NOTICE OF ACCEPTANCE (NOA)**

MIAMI-DADE COUNTY  
PRODUCT CONTROL SECTION  
11805 SW 26 Street, Room 208  
Miami, Florida 33175-2474  
T (786) 315-2590 F (786) 315-2599  
[www.miamidade.gov/building](http://www.miamidade.gov/building)

**USG Corporation**  
**550 West Adams Street**  
**Chicago, IL 60661**

**SCOPE:** This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER-Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

**DESCRIPTION: USG Celebration Snap-In Aluminum Exterior Ceiling System**

**APPROVAL DOCUMENT:** Drawing No. **CSI-01 to CSI-06**, titled "Celebration Snap-In Exterior Ceiling System", sheets 1 through 6 of 6, dated 04/22/16, prepared by manufacturer, signed and sealed by Carl D. Fussner, P.E., bearing the Miami-Dade County Product Control Revision stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Section.

**MISSILE IMPACT RATING: None**

**LABELING:** Each piece shall be permanently marked at not more than 4' o.c. with a number or marking and the packaging shall include the manufacturer's name or logo, city, state, model number or name, Miami-Dade County NOA number, test standards and net free area per FBC 1709.10.2 and 1709.10.3.

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.


**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official. This NOA **revises and renews NOA No. 15-1223.04** and consists of this page 1 and evidence pages E-1 and E-2, as well as approval document mentioned above.

The submitted documentation was reviewed by **Manuel Perez, P.E.**



  
12/13/21

NOA No. 21-0923.02  
Expiration Date: October 20, 2026  
Approval Date: December 23, 2021  
Page 1

**USG Corporation**

**NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED**

**1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA's**

**A. DRAWINGS**

1. Manufacturer's die drawings and sections.  
*(Submitted under NOA No. 15-1223.04)*
2. Drawing No. **CSI-01** to **CSI-06**, titled "Celebration Snap-In Exterior Ceiling System", sheets 1 through 6 of 6, dated 04/22/16, prepared by USG Corporation, signed and sealed by Carl D. Fussner, P.E. on 08/22/16.  
*(Submitted under NOA No. 15-1223.04)*

**B. TESTS**

1. Test reports on: 1) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94  
2) Cyclic Wind Pressure Loading per FBC, TAS 203-94  
3) Tensile Test per ASTM E8-08  
along with marked-up drawings of a Celebration Suspended Ceiling, prepared by Intertek-Architectural Testing, Inc., Test Report No. **E2131.01-450-18**, dated 06/01/15, with revision 1 dated 07/02/15, signed and sealed by Michael D. Stremmel, P.E.  
*(Submitted under NOA No. 15-1223.04)*

**C. CALCULATIONS**

1. Anchorage calculations prepared by PEI Engineering Services, Inc., dated 06/01/16, signed and sealed by Carl D. Fussner, P.E.  
*(Submitted under NOA No. 15-1223.04)*

**D. QUALITY ASSURANCE**

1. Miami-Dade Department of Regulatory and Economic Resources (RER)

**E. MATERIAL CERTIFICATIONS**


1. None.

**F. STATEMENTS**

1. Statement letter of conformance, complying with **FBC 5<sup>th</sup> Edition (2014)**, dated 05/27/16, issued by PEI Engineering Services, Inc., signed and sealed by Carl D. Fussner, P.E.  
*(Submitted under NOA No. 15-1223.04)*
2. Statement letter of no financial interest, dated 05/27/16, issued by PEI Engineering Services, Inc., signed and sealed by Carl D. Fussner, P.E.  
*(Submitted under NOA No. 15-1223.04)*

**G. OTHERS**

1. None.

  
Manuel Perez, P.E.  
Product Control Examiner  
NOA No. 21-0923.02  
Expiration Date: October 20, 2026  
Approval Date: December 23, 2021

**USG Corporation**

**NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED**

**2. NEW EVIDENCE SUBMITTED**

**A. DRAWINGS**

1. None.

**B. TESTS**

1. None.

**C. CALCULATIONS**

1. None.

**D. QUALITY ASSURANCE**

1. Miami-Dade Department of Regulatory and Economic Resources (RER)

**E. MATERIAL CERTIFICATIONS**


1. None.


**F. STATEMENTS**

1. Statement letter of conformance, complying with **FBC 7<sup>th</sup> Edition (2020)**, dated 10/06/21, issued by PEI Engineering Services, Inc., signed and sealed by Carl D. Fussner, P.E.

**G. OTHERS**

1. Notice of Acceptance No. **15-1223.04**, issued to USG Corporation for USG Celebration Snap-In Aluminum Exterior Ceiling System, approved on 10/20/16 and expiring on 10/20/21.

  
Manuel Pérez, P.E.  
Product Control Examiner  
NOA No. 21-0923.02  
Expiration Date: October 20, 2026  
Approval Date: December 23, 2021



Approved as complying with the  
Florida Building Code  
Date 10/20/2016  
NOA# 21-0923.02  
Miami-Dade Product Control

**PEI Engineering Services, Inc.**

58640 State Road 15  
Goshen, IN 46528  
Phone: (574) 533-0337 - Fax: (574) 533-9736  
FL C.O.A. Number 27447


PRESSURE:  
+80PSF UPWARD  
-70 PSF DOWNWARD

**CELEBRATION SNAP-IN**  
DXFEVH 2924 WITH  
CELEBRATION ALUMINUM PANELS  
MAIN TEES AT 24" O.C.  
CROSS TEES AT 24" O.C.  
COMPRESSION POSTS AT 24" O.C.  
PANELS 2' X 2' AND 2' X 4'


**PRODUCT REVISED**  
as complying with the Florida  
Building Code  
NOA-No. **21-0923.02**

Expiration Date: **10/20/2026**

By: Manuel Jerez  
Miami-Dade Product Control



Carl D. Fussner  
AUG 22 2016






**UNITED STATES  
GYPSUM CO.**  
550 West Adams Street  
Chicago, Illinois 60661  
1-800-874-4968

DWG.# CSI-01

DATE: 04/22/2016


PLAN  
CELEBRATION SNAP-IN  
EXTERIOR CEILING SYSTEM  
MIAMI DADE CO NOA

SHEET  
1 OF 6



Approved as complying with the  
Florida Building Code  
Date 10/20/2016  
NOA# 15-1223.04  
Miami Dade Product Control

By [Signature]



AUG 22 2016

1	DXFEVH2924 MAIN TEE, Fy (MIN) 40 KSI
2	DXFEV 429 CROSS TEE, Fy (MIN) 40 KSI
3	U-2-3/32 HOLD-DOWN CLIP 10-1/2" LONG @ 12" O.C.
4	12 GA HANGER WIRE
5	2 1/2" - 22 GA. STUD COMPRESSION POST, Fy (MIN) =33 KSI
6	ARROWHEAD SPACER 2" EA. SIDE OF INTERSECTION
7	CELEBRATION PANEL
8	1/4" LAG SCREW w/ 1 1/4" EMBEDMENT
9	#8 x 7/16" PAN HEAD SCREW
10	U 2-3/32 CHANNEL WALL MOLDING
11	HILTI 3/8" KWIK BOLT TZ-CS EXPANSION ANCHOR (OR EQUIVALENT)
12	L 1-1/2 x 1-1/2 x 6" 12GA. CLIP
13	PERIMETER WOOD BEND 12" WIDE (AS TESTED)
14	1/4" HILTI HHCA CEILING HANGER WITH 1-1/4" EMBEDMENT.
15	0.145" DIA. HILTI X-U 15 (OR EQUIVALENT)
16	HILTI X-CW X-U-27 FASTENER, 1-1/4" EMBEDMENT
17	3/16" CARBON STEEL OR STAINLESS STEEL TAPCON ANCHOR.
18	#8 1-1/4" SCREW SHARP POINT
19	#8 - 1 1/8" DRILL POINT SCREW

**PRODUCT REVISED**  
as complying with the Florida  
Building Code  
NOA-No. 21-0923.02  
Expiration Date: 10/20/2026  
By: Manuel Perez  
Miami Dade Product Control

**PEI Engineering Services, Inc.**

58640 State Road 15  
Goshen, IN 46528

Phone: (574) 533-0337 - Fax: (574) 533-9736  
FL C.O.A. Number 27447



UNITED STATES  
GYPSUM CO.  
550 West Adams Street  
Chicago, Illinois 60661  
1-800-874-4968

DWG.# CSI-02  
DATE: 04/22/2016

SECTIONS  
CELEBRATION SNAP-IN  
EXTERIOR CEILING  
MIAMI DADE CO NOA


SHEET  
2 OF 6

**ANCHORING NOTES:**  
WALL MOLDING TO STRUCTURE

USE DETAILS 1 THROUGH 3 FOR ATTACHMENT.

**WOOD SUBSTRATE DETAIL 1**

MOLDING CHANNEL: USE #8 SCREW OR EQUIVALENT WITH 2" MINIMUM PENETRATION AT 16" O.C.




**DETAIL 1**

Approved as complying with the  
Florida Building Code  
Date 10/20/2016  
NOA# 15-7223.04  
Miami Dade Product Control

By [Signature]


**STEEL SUBSTRATE, DETAIL 2**

MOLDING CHANNEL: USE #8 SCREW OR EQUIVALENT AT 16" O.C.




**DETAIL 2**

[Signature]  
AUG 22 2016



**CONCRETE SUBSTRATE, DETAIL 3**

MOLDING CHANNEL: USE 3/16" DIA. TAPCON ANCHOR OR EQUIVALENT WITH 1" MINIMUM EMBEDMENT AND 2" MIN. EDGE DISTANCE IN 3000 PSI CONCRETE OR MEDIUM-WEIGHT CMU BLOCKS @ 16" o.c.



**DETAIL 3**

**PEI Engineering Services, Inc.**

58640 State Road 15  
Goshen, IN 46528  
Phone: (574) 533-0337 - Fax: (574) 533-9736  
FL C.O.A. Number 27447

**PRODUCT REVISED**  
as complying with the Florida  
Building Code  
NOA-No. 21-0923.02  
Expiration Date: 10/20/2026  
By: [Signature]  
Miami-Dade Product Control




**UNITED STATES  
GYPSUM CO.**  
550 West Adams Street  
Chicago, Illinois 60661  
1-800-874-4988

DWG.# CSI-03  
DATE: 04/22/2016


WALL DETAILS  
CELEBRATION SNAP-IN  
EXTERIOR CEILING  
MIAMI DADE CO NOA

SHEET  
3 OF 6







DETAIL 1




DETAIL 2




DETAIL 3




DETAIL 4




DETAIL 5




DETAIL 6



DETAIL 7




DETAIL 8



DETAIL 9

AUG 22 2016



Approved as complying with the  
Florida Building Code  
Date 10/20/2016  
NOA# 15-1223.02  
Miami Dade Product Control

By [Signature]

**PRODUCT REVISED**  
as complying with the Florida  
Building Code  
NOA-No. 21-0923.02  
Expiration Date: 10/20/2026  
By: Manuel Perez  
Miami-Dade Product Control

PEI Engineering Services, Inc.

58640 State Road 15  
Goshen, IN 46528  
Phone: (574) 533-0337 - Fax: (574) 533-9736  
FL C.O.A. Number 27447




UNITED STATES  
GYPSUM CO.  
550 West Adams Street  
Chicago, Illinois 60661  
1-800-874-4968

DWG.# CSI-04


DATE: 04/22/2016

ANCHORAGE DETAILS  
CELEBRATION SNAP-IN  
EXTERIOR CEILING  
MIAMI DADE CO NOA


SHEET  
4 OF 6



**COMPRESSION POST**  
250S125 - 22 GA METAL  
STUD, Fy = 33 ksi (min)




**U 2-<sup>3</sup>/<sub>32</sub> CHANNEL  
WALL MOLDING**  
(3003 H14)




**U 2-<sup>3</sup>/<sub>32</sub> HOLD-  
DOWN CLIP**

Approved as complying with the  
Florida Building Code  
Date 10/20/2016  
NOA# 15-1233.04  
Miami Dade Product Control  
By [Signature]




**ARROWHEAD  
SPACER, (PVC)**





**PRODUCT REVISED**  
as complying with the Florida  
Building Code  
NOA-No. **21-0923.02**  
Expiration Date: **10/20/2026**

By: [Signature]  
Miami-Dade Product Control




**DXFEVH2924 MAIN TEE**



**DXFEV229 CROSS TEE**

AUG 22 2016




**UNITED STATES  
GYPSUM CO.**  
550 West Adams Street  
Chicago, Illinois 60661  
1-800-874-4968

DWG.# CTS-05  
DATE: 04/22/2016

**COMPONENTS DETAILS  
CELEBRATION SNAP-IN  
EXTERIOR CEILING  
MIAMI DADE CO NOA**

**SHEET  
5 OF 6**






NOTES:



1. PANEL MATERIAL IS PAINTED ALUMINUM WITH 0.032 THICKNESS
2. PANEL SIZES USED IN TESTING: 24"X 24"; 24" X 48"

Approved as complying with the  
Florida Building Code  
Date 10/26/2016  
NOA# 15-1273.04  
Miami Dade Product Control  
By [Signature]



CELEBRATION PANEL  
3003 H14

[Signature]  
AUG 22 2016



CORNER GAP  
(MAX. .030)

CORNER NOTCH & DIMPLE SPACING  
(SCALE: 10:1)

**PRODUCT REVISED**  
as complying with the Florida  
Building Code  
NOA-No. 21-0923.02  
Expiration Date: 10/20/2026  
By: [Signature]  
Miami-Dade Product Control

**PEI Engineering Services, Inc.**

58640 State Road 15  
Goshen, IN 46528  
Phone: (574) 533-0337 - Fax: (574) 533-9736  
FL C.O.A. Number 27447



UNITED STATES  
GYPSUM CO.  
550 West Adams Street  
Chicago, Illinois 60661  
1-800-874-4968

DWG.# CSI-06  
DATE: 04/22/2016

PANELS  
CELEBRATION SNAP-IN  
EXTERIOR CEILING  
MIAMI DADE CO NOA

SHEET  
6 OF 6