



DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)
BOARD AND CODE ADMINISTRATION DIVISION

NOTICE OF ACCEPTANCE (NOA)

MIAMI-DADE COUNTY
PRODUCT CONTROL SECTION
11805 SW 26 Street, Room 208
Miami, Florida 33175-2474
T (786) 315-2590 F (786) 315-2599
www.miamidade.gov/economy

Worthington Armstrong Venture (WAVE)
101 Lindenwood Drive Suite 350
Malvern, PA 19355

SCOPE: This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER-Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: EIFS & STUCCO Ceiling System – L.M.I.

APPROVAL DOCUMENT: Drawing No. **WAV004 Rev E**, titled "EIFS and STUCCO Ceiling System LMI", sheets 1 through 6 of 6, dated 04/28/2009 and last revised on 02/21/2022, prepared by PTC Product Design Group, LLC, signed and sealed by Robert J. Amoroso, P.E., bearing the Miami-Dade County Product Control Renewal stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Section.

MISSILE IMPACT RATING: Large and Small Missile Impact Resistant

LABELING: Each unit or component shall bear a permanent label (grid piece at not more than 4' o.c.) with manufacturer's name or logo, Aberdeen, MD and following statement: "Miami-Dade County Product Control Approved" or on packaging per FBC 1709.10.3. Units or components include containers and boards.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA **revises and renews** NOA # **20-1015.02** and consists of this page 1 and evidence pages E-1, E-2, E-3 and E-4, as well as approval document mentioned above.

The submitted documentation was reviewed by **Ishaq I. Chanda, P.E.**



Ishaq I. Chanda

NOA No. 22-0309.03
Expiration Date: October 7, 2026
Approval Date: April 07, 2022
Page 1

Worthington Armstrong Venture (WAVE)

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

1. Evidence submitted under previous NOA's

A. DRAWINGS “Submitted under NOA #14-1204.05”

1. Drawing No. **WAV004**, titled “EIFS and STUCCO Ceiling System LMI”, sheets 1 through 6 of 6, dated 04/28/2009, with revision C dated 11/06/2014, prepared by PTC Product Design Group, LLC, signed and sealed by Robert J. Amoruso, P.E.

B. TESTS “Submitted under NOA #09-0512.02”

1. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94
2) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
3) Water Resistance Test, per FBC, TAS 202-94
4) Large Missile Impact Test per FBC, TAS 201-94
5) Cyclic Wind Pressure Loading per FBC, TAS 203-94
along with marked-up drawings and installation diagram of Stucco Ceiling System, prepared by Architectural Testing, Inc., Test Report No. **81352.01-109-18**, dated 01/12/2009, with Revision 1 dated 08/06/2009, signed and sealed by Michael D. Stremmel, P.E.
2. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94
2) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
3) Water Resistance Test, per FBC, TAS 202-94
4) Large Missile Impact Test per FBC, TAS 201-94
5) Cyclic Wind Pressure Loading per FBC, TAS 203-94
along with marked-up drawings and installation diagram of EFIS Ceiling System, prepared by Architectural Testing, Inc., Test Report No. **81352.02-109-18**, dated Stremmel, P.E.

C. CALCULATIONS “Submitted under NOA #09-0512.02”

1. Unbraced length analysis of steel stud, prepared by PTC, LLC, dated 09/08/2009, signed and sealed by Robert J. Amoruso, P.E.
2. Anchor calculations of ceiling systems, prepared by PTC, LLC, dated 04/15/2009, signed and sealed by Paul E. Winter, P.E.

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER)

Ishag I. Chank

Carlos M. Utrera, P.E.
Product Control Unit Supervisor
NOA No. 22-0309.03
Expiration Date: October 7, 2026
Approval Date: April 07, 2022

Worthington Armstrong Venture (WAVE)

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

E. MATERIAL CERTIFICATIONS

1. None.

F. STATEMENTS “Submitted under NOA #14-1204.05”

1. Statement letter of code conformance to the FBC 5th Edition (2014) and of no financial interest, issued by PTC Product Design Group, LLC, dated 11/06/2014, signed and sealed by Robert J. Amoruso, P.E.

G. OTHERS

1. Notice of Acceptance No. **12-0314.04**, issued to Worthington Armstrong Venture (WAVE) for their EIFS & STUCCO Ceiling System – L.M.I, approved on 06/07/2012 and expiring on 10/07/2014.

2. Evidence submitted under NOA #18-1120.11

A. DRAWINGS

1. Drawing No. **WAV004**, titled “EIFS and STUCCO Ceiling System LMI”, sheets 1 through 6 of 6, dated 04/28/2009, with revision D dated 11/01/2018, prepared by PTC Product Design Group, LLC, signed and sealed by Robert J. Amoruso, P.E.

B. TESTS

1. None

C. CALCULATIONS

1. None

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER)

E. MATERIAL CERTIFICATIONS

1. None

F. STATEMENTS

1. Statement letter of code conformance to the **FBC 6th Edition (2017)**, issued by PTC Product Design Group, LLC, dated 11/01/2018, signed and sealed by Robert J. Amoruso, P.E.

Ishaq I. Chanda

Ishaq I. Chanda, P.E.
Product Control Unit Supervisor
NOA No. 22-0309.03
Expiration Date: October 7, 2026
Approval Date: April 07, 2022

Worthington Armstrong Venture (WAVE)

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

3. Evidence submitted under previous approval

A. DRAWINGS

1. None.

B. TESTS

1. None.

C. CALCULATIONS

1. None.

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER).

E. MATERIAL CERTIFICATIONS

1. None.

F. STATEMENTS

1. Statement letter of code conformance to the FBC 7th Edition (2020) and of no financial interest, issued by PTC Product Design Group, LLC, dated 03/22/2021, signed and sealed by Robert J. Amoruso, P.E.
2. Statement letter confirming verification testing contracted with ATI/Intertek, dated 08/16/2019, signed by Timothy J. McGill, Product Testing Manager.

Ishaq I. Chanda

Ishaq I. Chanda, P.E.
Product Control Unit Supervisor
NOA No. 22-0309.03
Expiration Date: October 7, 2026
Approval Date: April 07, 2022

Worthington Armstrong Venture (WAVE)

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

4. New evidence submitted

A. DRAWINGS

1. Drawing No. **WAV004 Rev E**, titled “EIFS and STUCCO Ceiling System LMI”, sheets 1 through 6 of 6, dated 04/28/2009 and last revised on 02/21/2022, prepared by PTC Product Design Group, LLC, signed and sealed by Robert J. Amoruso, P.E. (No DWG changes except, title block)

B. TESTS

1. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94
2) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
3) Water Resistance Test, per FBC, TAS 202-94
4) Large Missile Impact Test per FBC, TAS 201-94
5) Cyclic Wind Pressure Loading per FBC, TAS 203-94
along with marked-up drawings and installation diagram of Stucco Ceiling System, prepared by Intertek Testing, Inc., Test Report No. **M9873.01-109-18**, dated 01/20/2022, signed and sealed by Vinu Abraham, P.E.

C. CALCULATIONS (submitted under previous approval)

1. None.

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER).

E. MATERIAL CERTIFICATIONS

1. None.

F. STATEMENTS


1. Statement letter of code conformance to the FBC 7th Edition (2020) and request for renewal with no change, issued by PTC Product Design Group, LLC, dated 02/23/2022, signed and sealed by Robert J. Amoruso, P.E.
2. Statement letter of code conformance to the FBC 7th Edition (2020) and of no financial interest, issued by PTC Product Design Group, LLC, dated 03/22/2021, signed and sealed by Robert J. Amoruso, P.E (submitted under # **20-1015.02**)

G. OTHER

1. This NOA **revises and renews NOA # 20-1015.02**, expiring **10/07/2026**.
2. e-mail test proposal, dated 08/12/21, issued by RER.

Ishaq I. Chanda

Ishaq I. Chanda, P.E.
Product Control Unit Supervisor
NOA No. 22-0309.03
Expiration Date: October 7, 2026
Approval Date: April 07, 2022




EIFS LAYOUT

LARGE MISSILE IMPACT
RESISTANT


DESIGN PRESSURE CAPACITY
+75.0/-75.0 PSF MAXIMUM

PRODUCT RENEWED
as complying with the Florida
Building Code
NOA-No. 22-0309.03
Expiration Date 10/07/2026
By *Ishay L. Chandra*
Miami-Dade Product Control


E	Updated to 7TH EDITION FBC (2020)	2/23/22	RJA
D	Updated to 6TH EDITION FBC (2017)	11/1/18	RJA
C	Updated to 5TH EDITION FBC (2014)	11/6/14	RJA
REV	DESCRIPTION	DATE	BY



WAVE		101 LINDENWOOD DR MALVERN, PA 19355	
TITLE: ELEVATION & CROSS SECTIONS 117" X 117" EIFS CEILING SYSTEM, LMI			
PREPARED BY:	DRN:	DATE:	
PTC	SMC	04/28/09	
SCALE:	NTS	DWG. NO:	WAV004
REV:	E	SHEET:	1 OF 6
Phone 321.690.1788		Fax 321.690.1789	




PRODUCT RENEWED
 as complying with the Florida
 Building Code
 NOA-No. 22-0309.03
 Expiration Date 10/07/2026
 By Ishag I. Chande
 Miami-Dade Product Control



NOTES:

- 1) #6 X BUGLE HEAD DRYWALL SCREW AND 1-1/4" FLAT GALVANIZED WASHER IS SPACED 8" ON CENTER MAX. THROUGH THE AREA OF THE DENSGLASS AND INTO THE MAIN RUNNERS, CROSS TEES & PERIMETER CHANNEL.
- 2) HANGER WIRE MUST BE SECURED AT EACH END WITH A MIN. OF (3) TURNS IN 3" PER ASTM C636.
- 3) HANGER WIRE TO BE SPACED A MAXIMUM OF 30" O.C.
- 4) VERTICAL BRACING TO BE INSTALLED ON MAIN BEAMS AT A MAXIMUM OF 30" O.C.
- 5) 5/8" FRX, FIRE RESISTANT, EXTERIOR PLYWOOD TO BE INSTALLED FROM THE UNDERSIDE AGAINST CROSS TEES WITH ITEM #5
- 6) THIS PRODUCT IS DESIGNED TO COMPLY WITH THE HIGH VELOCITY HURRICANE ZONE (HVHZ) OF THE CURRENT EDITION OF THE FLORIDA BUILDING CODE (FBC) AT THE DESIGN PRESSURES STATED HEREIN.
- 7) CONSTRUCTION ADHESIVE APPLIED BETWEEN PLYWOOD AND DENSGLASS.
- 8) #8 SMS IS TO BE SPACED 8" O.C. THROUGH PLYWOOD ALONG MAIN RUNNER CROSS TEES AND PERIMETER CHANNEL.


SEE NOTE 8
THIS SHEET



SECTION C-C


SCALE: 8x
DETAIL D

SECURED 8" O.C. W/
TO MAIN STRUCTURE
 (23) WOOD
 (23) STEEL
 (26) CONCRETE



REV	DESCRIPTION	DATE	BY
E	Updated to 7TH EDITION FBC (02020)	2/23/22	RJA
D	Updated to 6TH EDITION FBC (2017)	11/1/18	RJA
C	Updated to 5TH EDITION FBC (2014)	11/6/14	RJA

WAVE			
101 LINDENWOOD DR MALVERN, PA 19355			
TITLE: EIFS SYSTEM, LMI DETAILS			
PREPARED BY:	DRN: SMC	DATE: 04/28/09	
PTC	SCALE: NTS	DWG. NO: WAV004	
	REV: E	SHEET: 2 OF 6	




STUCCO LAYOUT



PRODUCT RENEWED
as complying with the Florida
Building Code
NOA-No. 22-0309.03
Expiration Date 10/07/2026
By *Ishaq I. Chande*
Miami-Dade Product Control

DESIGN PRESSURE CAPACITY
+75.0/-75.0 PSF MAXIMUM

E	Updated to 7TH EDITION FBC (2020)	2/23/22	RJA
D	Updated to 6TH EDITION FBC (2017)	11/1/18	RJA
C	Updated to 5TH EDITION FBC (2014)	11/6/14	RJA
REV	DESCRIPTION	DATE	BY




WAVE 101 LINDENWOOD DR MALVERN, PA 19355			
TITLE: ELEVATION & CROSS SECTIONS 117" X 117" STUCCO CEILING SYSTEM, LMI			
PREPARED BY:	DRN: SMC	DATE: 04/28/09	
PTC	SCALE: NTS	DWG. NO: WAV004	
REV: E		SHEET: 3 OF 6	
Phone 321.690.1788	Fax 321.690.1789		



PRODUCT RENEWED
 as complying with the Florida
 Building Code
 NOA-No. 22-0309.03
 Expiration Date 10/07/2026
 By Ishaq I. Chande
 Miami-Dade Product Control

NOTES:

- 1) ITEM #8 THE #8 X 1 1/2" SHEET METAL SCREW IS SPACED 8" ON CENTER MAX. THROUGH THE RIBBED SHEET LATH AND INTO THE MAIN RUNNERS, CROSS TEES & PERIMETER CHANNEL.
- 2) HANGER WIRE MUST BE SECURED AT EACH END WITH A MIN. OF (3) TURNS IN 3" PER ASTM C636.
- 3) HANGER WIRE TO BE SPACED A MAXIMUM OF 30" O.C.
- 4) VERTICAL BRACING TO BE INSTALLED ON MAIN BEAMS AT A MAXIMUM OF 30" O.C.
- 5) 5/8" FRX, FIRE RESISTANT, EXTERIOR PLYWOOD INSTALLED FROM UNDERSIDE AGAINST CROSS TEES WITH ITEM #8. FELT PAPER SECURED TO UNDERSIDE OF PLYWOOD WITH STAPLES.
- 6) THIS PRODUCT IS DESIGNED TO COMPLY WITH THE HIGH VELOCITY HURRICANE ZONE (HVHZ) OF THE CURRENT EDITION OF THE FLORIDA BUILDING CODE (FBC) AT THE DESIGN PRESSURES STATED HEREIN.







SECURED 8" O.C. W/
 TO MAIN STRUCTURE
 23 WOOD
 23 STEEL
 26 CONCRETE

SECTION G-G

REV	DESCRIPTION	DATE	BY
E	Updated to 7TH EDITION FBC (2020)	2/23/22	RJA
D	Updated to 6TH EDITION FBC (2017)	11/1/18	RJA
C	Updated to 5TH EDITION FBC (2014)	11/6/14	RJA




PROFESSIONAL ENGINEER
 LICENSE
 No 49752
 STATE OF
 FLORIDA
 Robert J. Amoroso, P.E.
 Florida P. E. No. 49752
 PTC Product Design Group, LLC
 P.O. Box 520775
 Longwood, Florida 32752
 FBPE Certification of Authorization NO. 25935

WAVE			
101 LINDENWOOD DR MALVERN, PA 19355			
TITLE: STUCCO SYSTEM, LMI DETAILS			
PREPARED BY: PTC	DRN: SMC	DATE: 04/28/09	
	SCALE: NTS	DWG. NO: WAV004	
	REV: E	SHEET: 4 OF 6	
Phone 321.690.1788		Fax 321.690.1789	




ANCHOR NOTES:

- 1) THE VERTICAL BRACE IS SECURED TO THE MAIN BEAM AT THE BOTTOM WITH (4) ITEM #36 & TO THE STRUCTURE AT THE TOP AS FOLLOWS:
 - a.) CONCRETE SUBSTRATE WITH (3) ITEM #26, 3/16\" DIA. RAWL TAPPER, W/1 1/4\" MINIMUM EMBEDMENT. ITEM #17.
 - b.) WOOD FRAMING SUBSTRATE WITH (3) ITEM #23, #8 WOOD SCREW, W/1 1/2\" MINIMUM EMBEDMENT.
 - c.) STEEL FRAMING SUBSTRATE WITH (3) ITEM #23, #8 SHEET METAL SCREW, W/MINIMUM 3 PITCHES OF THREAD BEYOND STEEL FRAMING.
- 2) THE HANGER WIRE IS SECURED TO THE MAIN BEAM AT THE BOTTOM WITH (1) ITEM #2 & #16 TO THE STRUCTURE AT THE TOP AS FOLLOWS:
 - a.) CONCRETE SUBSTRATE WITH (1) ITEM #29, 1/4\" DIA. HILTI KWIKBOLT III, W/2\" MINIMUM EMBEDMENT.
 - b.) CONCRETE SUBSTRATE WITH (1) ITEM #30, 1/4\" DIA. HILTI HCKB EYEBOLT, W/1 7/16\" MINIMUM EMBEDMENT.
 - c.) CONCRETE SUBSTRATE WITH (1) ITEM #31, 3/8\" DIA. HILTI HDI-P DROP-IN, W/ 3/4\" MINIMUM EMBEDMENT.
 - d.) CONCRETE SUBSTRATE WITH (1) ITEM #32, 1/4\" DIA. HILTI HHDCA EYEBOLT, W/1 7/16\" MINIMUM EMBEDMENT.
 - e.) CONCRETE SUBSTRATE WITH (1) ITEM #33, 1/4\" DIA. ITW/RED HEAD TRUBOLT, W/2 1/8\" MINIMUM EMBEDMENT.
 - f.) WOOD FRAMING SUBSTRATE WITH (1) ITEM #27, #10 WOOD EYEBOLT, W/1 1/2\" MINIMUM EMBEDMENT.
 - g.) STEEL FRAMING SUBSTRATE WITH (1) ITEM #28, #10 SHEET METAL EYEBOLT, W/MINIMUM 3 PITCHES OF THREAD BEYOND STEEL FRAMING.



PRODUCT RENEWED
as complying with the Florida
Building Code
NOA-No. 22-0309.03
Expiration Date 10/07/2026
By Ishag I. Chande
Miami-Dade Product Control



E	Updated to 7TH EDITION FBC (2022)	2/23/22	RJA
D	Updated to 6TH EDITION FBC (2017)	11/1/18	RJA
C	Updated to 5TH EDITION FBC (2014)	11/6/14	RJA
REV	DESCRIPTION	DATE	BY


WAVE			
101 LINDENWOOD DR MALVERN, PA 19355			
TITLE: ELEVATION & CROSS SECTIONS STUCCO CEILING SYSTEM INSTALLATION DETAILS			
PREPARED BY:	DRN:	DATE:	
PTC	SMC	04/28/09	
SCALE:	NTS	DWG. NO:	WAV004
REV:	E	SHEET:	5 OF 6

Robert J. Amoruso, P.E.
Florida P. E. No. 49752
PTC Product Design Group, LLC
P.O. Box 520775
Longwood, Florida 32752
FBPE Certification of Authorization NO. 25935


Phone 321.690.1788 Fax 321.690.1789

ITEM	QTY	DESCRIPTION
1	A/R	TRHA 21 GA., 1-5/8"x1-1/4" DRYWALL TRACK/ 33 KSI
2	A/R	HD8906 G-90 MAIN BEAM
3	A/R	XL7936 G-90 CROSS TEE
4	A/R	DEITRICH CSJ, 2-1/2" DEPTH, 18 GA STEEL STD, 33 KSI, 9' MAX. LENGTH - SEE NOTE 3
5	A/R	#8 X 1" LG. MODIFIED TRUSS HEAD SHEET METAL SCREW
6	A/R	3/8" RIBBED SHEET LATH, 3.4 LBS/SQ.YD., AS PER ASTM C-847
7	A/R	STUCCO BASED COAT
8	A/R	#8 X 1-1/2" LG. MODIFIED TRUSS HEAD SHEET METAL SCREW
9	A/R	#9 Ga. H.D.G. HANGER WIRE
10	A/R	5/8" FRX FIRE RESISTANT EXTERIOR PLYWOOD - 4 X 8 SHEETS
11	A/R	STUCCO FINISH COAT
12	A/R	BUILDING STRUCTURE OR 2 BY WOOD BUCK BY OTHERS
13	A/R	WATER PROOF FELT VAPOR BARRIER
14	A/R	QSUTC QS UP TIGHT CLIP
15	A/R	#9 X 1-1/2" WOODFAST DOUBLE LEAD THREAD 1/4" HEX WASHER HEAD
16	A/R	SP-135 G-90 MAIN BEAM
17	A/R	EFIS FINISH COAT
18	A/R	#6 X 1-1/4" LG BUGLE HEAD DRYWALL SCREW
19	A/R	1/2" EXTERIOR SHEET DENSGLASS GOLD, GEORGIA PACIFIC
20	A/R	PRIMER ADHESIVE MESH + EIFS FINISH
21	A/R	CROSS TEE BEAM CLIP
22	A/R	#10 I-LAG 150WS WOOD SCREW /#10 I-LAG 750SD SELF TAP W/EYELET
23	A/R	#8 X 1" LG. SHEET METAL SCREW
24	A/R	1-1/4" FLAT GALVANIZED WASHER
25	A/R	CONSTRUCTION ADHESIVE
26	A/R	3/16" DIAMETER RAWL TAPPER W/1 1/4" MIN. EMBEDMENT
27	A/R	#10 I-LAG 150WS WOOD SCREW W/EYELET
28	A/R	#10 I-LAG 750SD SELF DRILLING & TAPPING SCREW W/EYELET
29	A/R	1/4" DIA. HILTI KWIK BOLT III ANCHOR
30	A/R	1/4" DIA. HILTI HCKB CEILING HANGER W/EYELET
31	A/R	3/8" DIA. HILTI HDI-P DROP-IN ANCHOR
32	A/R	1/4" - 20 THREADED EYELET.
33	A/R	3/8" - 16 THREADED EYELET.
34	A/R	1/4" DIA. HILTI HHDCA CEILING HANGER W/EYELET
35	A/R	1/4" DIA. ITW/ RED HEAD TRUBOLT ANCHOR
36	A/R	#8 X 1" TRUSS HEAD SELF DRILLING SCREW
37	A/R	#66 3/4" CASE BEAD


1 DRYWALL TRACK/
PERIMETER CHANNEL
TRHA 21 GAUGE




3 CROSS TEE BEAM
TYP. WALL THK, .018
EIFS & STUCCO




21 CROSS TEE BEAM CLIP



37 #66 3/4" CASE BEAD
TYP. WALL THK. 21 GAUGE




14 QSUTC UP TIGHT CLIP



NOTES:

- EFIS COMPOSITION:
DRYVIT GENESIS BASE COAT MIXED WITH CEMENT 1/8" THICK BY 9" WIDE PER MANUFACTURER SPECIFICATIONS IS APPLIED TO THE DENSGLASS GOLD JOINTS ONLY, FOLLOWED BY DRYVIT BRAND #20 FIBERGLASS MESH WHICH IS WORKED INTO THE BASE MIX. ANOTHER 3/16" THICK COAT OF MIX IS TROWELED OVER THE ENTIRE SURFACE. A CONTINUOUS LAYER OF MESH IS THEN WORKED INTO THE WET BASE MIX WITH A SECOND LAYER OF BASE MIX COVERING THE MESH. THE BASE MIX IS ALLOWED TO DRY OVERNIGHT AND PRIOR TO A FINISH COAT OF DRYVIT BRAND MIX QUARTZPUTZ DPR BEING APPLIED AND TROWELED TO PRODUCE A 1/8" TO 3/16" FINISH COAT.
- A STUCCO MIX WITH A FINISH THICKNESS OF 3/4" IS TROWELED INTO THE RIBBED LATH IN THREE COATS. THE FIRST COAT IS ALLOWED TO SET, THEN A SECOND LAYER OF MIX IS TROWELED ON SIDE TO SIDE TO THE STOPS ON ALL SIDES. THE FINISH COAT MIX OF IVORY FINISH LIME, WHITE CEMENT AND WHITE SILICA SAND IS WORKED INTO THE STUCCO MIX AND TROWELED ON IN AN 1/8" TO 3/16" THICK FINISH COAT.
- STUCCO MIX CONSIST OF: 22 SHOVELS OF C-144 SAND, 2 1/2 GALLONS "THORO" BRAND ACRYL 60 ACRYLIC ADDITIVE, 1 PACK CONTROL "X" CHOPPED FIBERS, 1 BAG (50 LBS.) TYPE "S" LIME, 1 BAG (94 LBS.) TYPE "1" PORTLAND CEMENT.
- EQUIVALENT STEEL STUD MEETING THE FOLLOWING ACCEPTABLE:
 - SSMA NO. 250S162-43
 - YIELD STRENGTH 33 KSI MINIMUM.
 - 2-1/2" DEPTH
 - 1-5/8" FLANGE
 - 1/2" LIP
 - 18 GA.
 - MAX. LENGTH 9'

E	Updated to 7TH EDITION FBC (2020)	2/23/22	RJA
D	Updated to 6TH EDITION FBC (2017)	11/1/18	RJA
C	Updated to 5TH EDITION FBC (2014)	11/6/14	RJA
REV	DESCRIPTION	DATE	BY



PRODUCT RENEWED as complying with the Florida Building Code NOA-No. 22-0309.03 Expiration Date 10/07/2026 By <u>Ishag I. Chande</u> Miami-Dade Product Control			
WAVE 101 LINDENWOOD DR MALVERN, PA 19355			
TITLE: DETAILS AND BILL OF MATERIALS 117" X 117" CEILING SYSTEM INSTALLATION			
PREPARED BY: PTC	DRN: SMC SCALE: NTS REV: E	DATE: 04/28/09 DWG. NO: WAV004 SHEET: 6 OF 6	Phone 321.690.1788 Fax 321.690.1789