

### DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER) BOARD AND CODE ADMINISTRATION DIVISION NOTICE OF ACCEPTANCE (NOA)

# Sto Corporation 3800 Camp Creek Parkway, Bldg. 1400 Ste. 120 Atlanta, GA 30331

## Scope:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER-Product Control Section to be used in Miami-Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami-Dade County) and/ or the AHJ (in areas other than Miami-Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

# **DESCRIPTION:**

Sto Powerwall HI Wall Panel System with Structa Wire Twin Trac 2.5 and Stucco over 5/8" eXP. Gypsum Sheathing

**APPROVAL DOCUMENT:** Drawing titled "Sto Powerwall HI with Structa Wire Twin Trac 2.5", sheets 1 through 3 of 3, prepared by the manufacturer, dated April 2023, signed and sealed by William R. Heiden III, P.E., on 05/10/2023, bearing the Miami-Dade County Product Control approval stamp with the Notice of Acceptance number and approval date by the Miami-Dade County Product Control Section.

# MISSILE IMPACT RATING: Large and Small Missile Impact Resistant.

**LABELING:** Each unit shall bear a permanent label with the manufacturer's name or logo, model (Powerwall HI), city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein. Each container (bucket or drum) needs to be labeled. Unit is further defined as each roll of reinforcing mat or mesh.

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/ or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA consists of this page 1 and evidence page E-1, as well as approval document mentioned above. The submitted documentation was reviewed by **Carlos M. Utrera, P.E.** 



Atun

NOA No. 23-0518.03 Expiration Date: August 03, 2028 Approval Date: August 03, 2023 Page 1

# **NOTICE OF ACCEPTANCE:** EVIDENCE SUBMITTED

# A. DRAWINGS

1. Drawing titled "Sto Powerwall HI with Structa Wire Twin Trac 2.5", sheets 1 through 3 of 3, prepared by the manufacturer, dated April 2023, signed and sealed by William R. Heiden III, P.E., on 05/10/2023.

# **B. TESTS**

- 1. Test reports on 1) Air Infiltration Test, per FBC, TAS 202-94
  - 2) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
  - 3) Water Resistance Test, per FBC, TAS 202-94
  - 4) Large Missile Impact Test per FBC, TAS 201-94
  - 5) Cyclic Wind Pressure Loading per FBC, TAS 203-94

along with marked-up drawings and installation diagram of Powerwall HI with Structa Wire Twin Trac 2.5 by ClarkDietrich, prepared by Intertek, Test Report No. **P5478.01-550-18 R0**, dated 03/01/2023, revised on 04/04/2023, signed and sealed by Tanya A. Dolby, P.E.

# C. CALCULATIONS

1. None.

# D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER).


# E. MATERIAL CERTIFICATIONS

1. None

# F. STATEMENTS

1. Statement letters of code conformance to the 7<sup>th</sup> edition (2020) of the FBC and of no financial interest, issued by William R. Heiden III, P.E., both dated 07/06/2023, and signed and sealed by William R. Heiden III, P.E.

Carlos M. Utrera, P.E. Product Control Examiner NOA No. 23-0518.03 Expiration Date: August 03, 2028 Approval Date: August 03, 2023



# **Description:**

### Substrates and Sto products approved with the system 1.0

- 1.1 18 ga., 6" x 1 5/8" steel studs at 16" o.c.
- 1.2 5/8" National Gypsum eXP ASTM C 1177 compliant sheathing fastened to framing with No. 8 wafer head screws at 8" o.c. along studs and perimeter
- Sto Primer/Adhesive-B polymer modified portland cement base coat used to embed reinforcing mesh on sheathing 1.3
- Sto Armor Mat XX, 20 oz./yd<sup>2</sup> glass fiber reinforcing embedded in Sto Primer/Adhesive-B on sheathing 1.4
- 1.5 StoGuard with Sto Gold Coat air and moisture barrier coating applied to dry Sto Primer/Adhesive-B
- Sto Powerwall Stucco: pre-bagged portland cement stucco mixed with sand and water in the field 1.6
- Sto finish: Ready-to-use polymeric finish 1.7


### Application 2.0

- 2.1 Sto Primer/Adhesive-B base coat is mixed in accordance with written instructions on the bag and used to fully embed Sto Armor Mat XX reinforcing mesh on the sheathing surface. Base coat is allowed to dry overnight.
- 2.2 Sto Guard with Sto Gold Coat is applied to the dry base coat in accordance with Sto written instructions.
- 2.3 One layer of Type D, No. 15 asphalt saturated kraft paper is placed over dry Sto Gold Coat as a slip-sheet.
- Fasten Structa Wire Twin Trac 2.5 at nominal 6" o.c. along studs in accordance with ASTM C 1063 and 2.4 Structa Wire published installation instructions.
- Apply Sto Powerwall stucco as scratch and brown coat. Mix stucco with approximately 200 lbs of clean sand and potable water 2.5 in accordance with instructions printed on bag. Moist cure brown coat minimum 48 hours, then allow to dry, before applying finish
- 2.6 Mix Sto finish to a uniform consistency and apply with a clean stainless steel trowel.

# **General Notes:**

- This system has been designed in accordance with the Florida Building Code, 2020 Edition. 1.
- This system has been tested in accordance with Florida Building Code TAS 201, TAS 202, and TAS 203. 2.
- 3. This system shall be applied by a licensed plastering contractor.
- 4. The Engineer or Architect of Record for each project using this system shall design the framing and sheathing as required by governing codes and this document.
- All studs used with this system shall be completely sheathed at the interior flange or bridged at a maximum every 5 ft. of stud 5. length or as specified by stud manufacturer.
- 6. All steel studs shall be structural with 1 5/8" minimum flange width and a minimum yield strength of 33000 psi.


**PRODUCT APPROVED** as complying with the Florida Building Code NOA-No. 23-0518.03 Approval Date 08/03/2023 Front Βv Miami-Dade Product Control




# Sto Powerwall HI with Structa Wire Twin Trac 2.5

Large Missile Impact Stucco System over frame construction

Corp. 00 Camp Creek Pkwy g. 1400, Ste 120 anta, GA 30331		Drawing 1 of 3	
IL 2023	Not to Scale		Drawn by: TLV



orp. Camp Creek Pkwy I400, Ste 120 a, GA 30331		Drawing 2	of 3
2023	Not to Scale		Drawn by: TLV



METAL PARAPET CAP

WOOD NAILER WITH WATERPROOFING BY ROOFER OR CAP INSTALLER

STOGUARD WATERPROOFING DETAIL COMPONENT

STO GOLD COAT

SLIP SHEET

STO POWERWALL HI WITH STRUCTA WIRE **TWIN TRAC 2.5** AS SHOWN ON PAGE 1 OF 3

<b>PRODUCT APPROVED</b> as complying with the Florida Building Code				
NOA-No.	23-0518.03			
Approval Date	08/03/2023			
By this				

TYPICAL DETAIL SHEET

# **Sto Powerwall HI** with Structa Wire Twin Trac 2.5

Large Missile Impact Stucco System over frame construction

3800 Camp Creek Pkwy Bldg. 1400, Ste 120 Atlanta, GA 30331

Drawing 3 OF 3

23		
20	Not to Scale	Drawn by: TLV