



DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)  
BOARD AND CODE ADMINISTRATION DIVISION

## NOTICE OF ACCEPTANCE (NOA)

MIAMI-DADE COUNTY  
PRODUCT CONTROL SECTION  
11805 SW 26 Street, Room 208  
Miami, Florida 33175-2474  
T (786) 315-2590 F (786) 315-2599

[www.miamidade.gov/building](http://www.miamidade.gov/building)

E.S. Windows, LLC  
3550 NW 49<sup>th</sup> Street  
Miami, FL 33142

### SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER-Product Control Section to be used in Miami-Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami-Dade County) and/ or the AHJ (in areas other than Miami-Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

### DESCRIPTION: Series "2100" Aluminum Horizontal Sliding Window – S.M.I.

**APPROVAL DOCUMENT:** Drawing No. **W04-101**, titled "Series-2100 Alum. Horiz. Sliding Wdw. (S.M.I.)", sheets 1 through 8 of 8, dated 11/26/04, with revision **I** dated 07/06/23, prepared by Al-Farooq Corporation, signed and sealed by Jalal Farooq, P.E., bearing the Miami-Dade County Product Control Revision stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Section.

### MISSILE IMPACT RATING: Small Missile Impact Resistant

**LABELING:** Each unit shall bear a permanent label with the manufacturer's name or logo, **Barranquilla, Colombia**, model/series, and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/ or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.


**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA **revises** NOA No. **20-1202.07** and consists of this page 1 and evidence pages E-1, E-2, and E-3, as well as approval document mentioned above.

The submitted documentation was reviewed by **Manuel Perez, P.E.**



  
8/21/23

NOA No. 23-0731.07  
Expiration Date: February 10, 2025  
Approval Date: August 31, 2023  
Page 1

**NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED**

**1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA's**

**A. DRAWINGS**


1. Manufacturer's die drawings and sections.  
*(Submitted under NOA No. 04-1208.02)*
2. Drawing No. **W04-101**, titled "Series-2100 Alum. Horiz. Sliding Wdw. (S.M.I)", sheets 1 through 8 of 8, dated 11/26/04, with revision **H** dated 11/05/20, prepared by Al-Farooq Corporation, signed and sealed by Jalal Farooq, P.E.  
*(Submitted under NOA No. 20-1202.07)*

**B. TESTS**

1. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94  
2) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94  
3) Water Resistance Test, per FBC, TAS 202-94  
4) Large Missile Impact Test per FBC, TAS 201-94  
5) Cyclic Wind Pressure Loading per FBC, TAS 203-94  
6) Forced Entry Test, per FBC 2411.3.2.1, and TAS 202-94  
along with marked-up drawings and installation diagram of a horizontal sliding window, prepared by Fenestration Testing Laboratory, Inc., Test Reports No. **FTL-5686**, dated 12/30/08, signed and sealed by Carlos S. Rionda, P.E. and **FTL-5811**, dated 02/16/09, signed and sealed by Michael R. Wenzel, P.E.  
*(Submitted under NOA No. 09-1008.04)*
2. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94  
2) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94  
3) Water Resistance Test, per FBC, TAS 202-94  
4) Forced Entry Test, per FBC 2411.3.2.1, and TAS 202-94  
along with marked-up drawings and installation diagram of a horizontal sliding window, prepared by Hurricane Engineering & Testing, Inc., Test Reports No. **HETI-04-1412**, **HETI-05-1937** and **HETI-05-1423**, dated 10/13/04, 01/26/05 and 01/12/05 respectively, all signed and sealed by Ivonne Ghia, P.E.  
*(Submitted under NOA's No. 04-1208.02 and 05-0303.02)*

**C. CALCULATIONS**

1. Anchor verification calculations and structural analysis, complying with **FBC 6<sup>th</sup> Edition (2017)**, dated 09/22/17, and updated on 10/26/20 to comply with **FBC 7<sup>th</sup> Edition (2020)**, prepared by Al-Farooq Corporation, signed and sealed by Jalal Farooq, P.E.  
*(Submitted under NOA No. 20-1202.07)*
2. Glazing complies with **ASTM E1300-09**

  
Manuel Perez, P.E.  
Product Control Examiner  
NOA No. 23-0731.07  
Expiration Date: February 10, 2025  
Approval Date: August 31, 2023

**NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED**

**1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA's (CONTINUED)**

**D. QUALITY ASSURANCE**

1. Miami-Dade Department of Regulatory and Economic Resources (RER).

**E. MATERIAL CERTIFICATIONS**


1. Notice of Acceptance No. **18-0725.11** issued to **Kuraray America, Inc.** for their "**Kuraray SentryGlas® Xtra™ (SGX™) Clear Glass Interlayer**" dated 05/23/19, expiring on 05/23/24.
2. Notice of Acceptance No. **19-0305.02** issued to **Kuraray America, Inc.** for their "**Trosifol® Ultraclear, Clear and Color PVB Glass Interlayers**" dated 05/09/19, expiring on 07/08/24.

**F. STATEMENTS**

1. Statement letter of conformance, complying with **FBC 6<sup>th</sup> Edition (2017)**, with **FBC 7<sup>th</sup> Edition (2020)**, and of no financial interest, dated October 26, 2020, issued by Al-Farooq Corporation, signed and sealed by Jalal Farooq, P.E.  
*(Submitted under NOA No. 20-1202.07)*

**G. OTHERS**

1. Notice of Acceptance No. **19-1015.11**, issued to E.S. Windows, LLC, for their Series "2100" Aluminum Horizontal Sliding Window – S.M.I., approved on 11/07/19 and expiring on 02/10/25.

  
Manuel Pérez, P.E.  
Product Control Examiner  
NOA No. 23-0731.07  
Expiration Date: February 10, 2025  
Approval Date: August 31, 2023

**E.S. Windows, LLC**

**NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED**

**2. NEW EVIDENCE SUBMITTED**

**A. DRAWINGS**

1. Drawing No. **W04-101**, titled “Series-2100 Alum. Horiz. Sliding Wdw. (S.M.I)”, sheets 1 through 8 of 8, dated 11/26/04, with revision **I** dated 07/06/23, prepared by Al-Farooq Corporation, signed and sealed by Jalal Farooq, P.E.

**B. TESTS**

1. None.

**C. CALCULATIONS**

1. None.

**D. QUALITY ASSURANCE**

1. Miami-Dade Department of Regulatory and Economic Resources (RER)

**E. MATERIAL CERTIFICATIONS**


1. Notice of Acceptance No. **22-1116.01** issued to **Kuraray America, Inc.** for their “**SentryGlas® (Clear and White) Glass Interlayers**” dated 12/15/22, expiring on 07/04/28.
2. Notice of Acceptance No. **20-0915.22** issued to **Kuraray America, Inc.** for their “**Trosifol® Ultraclear, Clear and Color PVB Glass Interlayers**” dated 11/19/20, expiring on 07/08/24.

**F. STATEMENTS**

1. Statement letter of conformance, complying with **FBC 7<sup>th</sup> Edition (2020)**, with **FBC 8<sup>th</sup> Edition (2023)**, and of no financial interest, dated July 14, 2023, issued by Al-Farooq Corporation, signed and sealed by Jalal Farooq, P.E..

**G. OTHERS**

1. Notice of Acceptance No. **20-1202.07**, issued to E.S. Windows, LLC, for their Series “2100” Aluminum Horizontal Sliding Window – S.M.I., approved on 03/04/21 and expiring on 02/10/25.

  
Manuel Pérez, P.E.  
Product Control Examiner  
NOA No. 23-0731.07  
Expiration Date: February 10, 2025  
Approval Date: August 31, 2023

THESE WINDOWS ARE RATED FOR SMALL MISSILE IMPACT.  
MIAMI-DADE COUNTY APPROVED IMPACT RESISTANT SHUTTERS  
REQUIRED FOR INSTALLATIONS UP TO 30 FT. OF GRADE.  
SHUTTERS NOT REQD. FOR INSTALLATIONS ABOVE 30 FT. OF GRADE.

### SERIES-2100 ALUM HORIZ. SLIDING WINDOW

DESIGN LOAD RATINGS FOR THESE WINDOWS TO BE AS PER  
CHARTS SHOWN ON SHEET 2.

APPROVAL APPLIES TO SINGLE UNITS OR SIDE BY SIDE COMBINATIONS  
OF H.R./H.R. OR H.R. WITH OTHER WINDOW TYPES IN MODULES OF  
TWO OR MORE WINDOWS USING MIAMI-DADE COUNTY APPROVED  
MULLIONS IN BETWEEN.

LOWER DESIGN PRESSURE FROM WINDOWS OR MULLION APPROVAL WILL  
APPLY TO ENTIRE SYSTEM.

THIS PRODUCT HAS BEEN DESIGNED AND TESTED TO COMPLY WITH THE  
REQUIREMENTS OF THE 2020 (7TH EDITION)/2023 (8TH EDITION) FLORIDA  
BUILDING CODE INCLUDING HIGH VELOCITY HURRICANE ZONE (HVHZ).

1BY OR 2BY WOOD BUCKS & BUCK FASTENERS BY OTHERS, MUST BE  
DESIGNED AND INSTALLED ADEQUATELY TO TRANSFER APPLIED PRODUCT  
LOADS TO THE BUILDING STRUCTURE.

ANCHORS SHALL BE CORROSION RESISTANT, SPACED AS SHOWN ON DETAILS  
AND INSTALLED PER MANUF'S INSTRUCTIONS. SPECIFIED EMBEDMENT TO BASE  
MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO.

A LOAD DURATION INCREASE IS USED IN DESIGN OF ANCHORS INTO WOOD ONLY.


ALL SHIMS TO BE HIGH IMPACT, NON-METALLIC AND NON-COMPRESSIBLE.

MATERIALS INCLUDING BUT NOT LIMITED TO STEEL/METAL SCREWS, THAT  
COME INTO CONTACT WITH OTHER DISSIMILAR MATERIALS SHALL MEET THE  
REQUIREMENTS OF THE 2020/2023 FLORIDA BLDG. CODE & ADOPTED STANDARDS.


THIS PRODUCT APPROVAL IS GENERIC AND DOES NOT PROVIDE INFORMATION  
FOR A SITE SPECIFIC PROJECT, i.e. LIFE SAFETY OF THIS PRODUCT, ADEQUACY  
OF STRUCTURE RECEIVING THIS PRODUCT AND SEALING AROUND OPENING FOR  
WATER INFILTRATION RESISTANCE ETC.

CONDITIONS NOT SHOWN IN THIS DRAWING ARE TO BE ANALYZED SEPARATELY,  
AND TO BE REVIEWED BY BUILDING OFFICIAL.


DESIGN LOADS SHOWN ARE BASED ON 'ALLOWABLE STRESS DESIGN (ASD)'.



TYPICAL ELEVATION



GLASS TYPE 'A'



GLASS TYPE 'B'

GLAZING OPTIONS

**PRODUCT REVISED**  
As complying with the Florida  
Building Code


NOA-No. **23-0731.07**

Expiration Date: **02/10/2025**

By: *Manuel Perez*

Miami-Dade Product Control

**LAMINATED GLASS**  
**SMALL MISSILE IMPACT**



JUL 07 2023

SERIES-2100 ALUM HORIZ. SLIDING WDW. (S.M.I.)

**E.S. WINDOWS, LLC**  
3550 N.W. 49 STREET  
MIAMI, FL. 33142  
TEL. (305) 638-5151 FAX. (305) 638-5158

revisions:	no	date	by	description
	E	03.05.12		UPDATED TO 2010 FBC
	F	09.16.14		UPDATED TO 2014 FBC
	G	10.09.17		UPDATED TO 2017 FBC
	H	11.05.20		UPDATED TO 2020 FBC
	I	07.06.23		UPDATED TO 2023 FBC

date: 11-26-04  
scale: 1/2"=1'-0"  
dr. by: TARIQ  
chk. by:

drawing no.

**W04-101**

sheet 1 of 8


**AL-FAROOQ CORPORATION**  
ENGINEERS & PRODUCT DEVELOPMENT  
9360 SUNSET DRIVE, SUITE 220  
MIAMI, FLORIDA 33173  
TEL. (305) 264-8100 FAX. (305) 262-6978  
(C.A.N. 3538)

COMP-ANL\W04-101ES



DESIGN LOAD CAPACITY - PSF (XO OR OX SIZES)										
WINDOW DIMS. WIDTH    HEIGHT		A	STD. ANCHOR SPACING				ADDL. ANCHOR			
			GLASS TYPE 'A'		GLASS TYPE 'B'		GLASS TYPE 'A'		GLASS TYPE 'B'	
WIDTH	HEIGHT	A	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)
			EXT.(+)	INT.(-)	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)
26-1/2"	26" (2)	3	82.0	108.0	82.0	82.0	-	-	-	-
37"		4	82.0	108.0	82.0	82.0	-	-	-	-
53-1/8"		6	82.0	108.0	82.0	82.0	-	-	-	-
74"		8	82.0	108.0	82.0	82.0	-	-	-	-
26-1/2"	38-3/8" (3)	3	82.0	108.0	82.0	82.0	-	-	-	-
37"		4	82.0	108.0	82.0	82.0	-	-	-	-
53-1/8"		6	82.0	108.0	82.0	82.0	-	-	-	-
74"		8	82.0	108.0	82.0	82.0	-	-	-	-
26-1/2"	50-5/8" (4)	3	82.0	108.0	82.0	82.0	-	-	-	-
37"		4	82.0	108.0	82.0	82.0	-	-	-	-
53-1/8"		6	82.0	108.0	82.0	82.0	-	-	-	-
74"		8	82.0	108.0	82.0	82.0	-	-	-	-
26-1/2"	63" (4)	3	82.0	108.0	82.0	82.0	-	-	-	-
37"		4	82.0	108.0	82.0	82.0	-	-	-	-
53-1/8"		6	82.0	92.5	82.0	82.0	82.0	108.0	-	-
74"		8	75.3	75.3	75.3	75.3	82.0	82.0	82.0	82.0
24"	24" (2)	3	82.0	108.0	82.0	82.0	-	-	-	-
36"		4	82.0	108.0	82.0	82.0	-	-	-	-
48"		6	82.0	108.0	82.0	82.0	-	-	-	-
60"		6	82.0	108.0	82.0	82.0	-	-	-	-
66"		6	82.0	108.0	82.0	82.0	-	-	-	-
72"		8	82.0	108.0	82.0	82.0	-	-	-	-
24"	36" (3)	3	82.0	108.0	82.0	82.0	-	-	-	-
36"		4	82.0	108.0	82.0	82.0	-	-	-	-
48"		6	82.0	108.0	82.0	82.0	-	-	-	-
60"		6	82.0	108.0	82.0	82.0	-	-	-	-
66"		6	82.0	108.0	82.0	82.0	-	-	-	-
72"		8	82.0	108.0	82.0	82.0	-	-	-	-
24"	48" (4)	3	82.0	108.0	82.0	82.0	-	-	-	-
36"		4	82.0	108.0	82.0	82.0	-	-	-	-
48"		6	82.0	108.0	82.0	82.0	-	-	-	-
60"		6	82.0	108.0	82.0	82.0	-	-	-	-
66"		6	82.0	108.0	82.0	82.0	-	-	-	-
72"		8	82.0	108.0	82.0	82.0	-	-	-	-
24"	60" (4)	3	82.0	108.0	82.0	82.0	-	-	-	-
36"		4	82.0	108.0	82.0	82.0	-	-	-	-
48"		6	82.0	106.5	82.0	82.0	82.0	108.0	-	-
60"		6	82.0	91.7	82.0	82.0	82.0	108.0	-	-
66"		6	82.0	86.6	82.0	82.0	82.0	108.0	-	-
72"		8	82.0	82.7	82.0	82.0	82.0	108.0	-	-
24"	66" (5)	3	82.0	108.0	82.0	82.0	-	-	-	-
36"		4	82.0	108.0	82.0	82.0	-	-	-	-
48"		6	82.0	93.3	82.0	82.0	82.0	108.0	-	-
60"		6	79.6	79.6	79.6	79.6	82.0	108.0	82.0	82.0
66"		6	74.8	74.8	74.8	74.8	76.7	108.0	76.7	82.0
66"		6	74.8	74.8	74.8	74.8	76.7	108.0	76.7	82.0


A = NO. OF ANCHORS PER HEAD & SILL  
( ) = NO. OF ANCHORS PER JAMB



ALL EXTERIOR(+) LOADS SHOWN ON THIS SHEET ARE  
FOR WINDOWS WITH APPLIED RISER AT FRAME SILL  
FOR SILL WITHOUT RISER LIMIT EXT.(+) LOADS TO 73.3 PSF  
SEE DETAIL 'B' ON SHEET 3.

DESIGN LOAD CAPACITY - PSF (XOX SIZES)										
WINDOW DIMS. WIDTH    HEIGHT		A	STD. ANCHORS		ADDL. ANCHOR					
			GLASS 'A' & 'B'		GLASS 'A' & 'B'					
WIDTH	HEIGHT	A	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)
			EXT.(+)	INT.(-)	EXT.(+)	INT.(-)				
74"	26" (2)	9	82.0	82.0	-	-	-	-	-	-
106-1/4"		12	82.0	82.0	-	-	-	-	-	-
111"		12	82.0	82.0	-	-	-	-	-	-
74"	38-3/8" (3)	9	82.0	82.0	-	-	-	-	-	-
106-1/4"		12	82.0	82.0	-	-	-	-	-	-
111"		12	82.0	82.0	-	-	-	-	-	-
74"	50-5/8" (4)	9	82.0	82.0	-	-	-	-	-	-
106-1/4"		12	82.0	82.0	-	-	-	-	-	-
111"		12	82.0	82.0	-	-	-	-	-	-
74"	63" (4)	9	82.0	82.0	-	-	-	-	-	-
106-1/4"		12	77.1	77.1	82.0	82.0	-	-	-	-
111"		12	75.3	75.3	82.0	82.0	-	-	-	-
72"	24" (2)	9	82.0	82.0	-	-	-	-	-	-
84"		9	82.0	82.0	-	-	-	-	-	-
96"		9	82.0	82.0	-	-	-	-	-	-
108"		12	82.0	82.0	-	-	-	-	-	-
72"	36" (3)	9	82.0	82.0	-	-	-	-	-	-
84"		9	82.0	82.0	-	-	-	-	-	-
96"		9	82.0	82.0	-	-	-	-	-	-
108"		12	82.0	82.0	-	-	-	-	-	-
72"	48" (4)	9	82.0	82.0	-	-	-	-	-	-
84"		9	82.0	82.0	-	-	-	-	-	-
96"		9	82.0	82.0	-	-	-	-	-	-
108"		12	82.0	82.0	-	-	-	-	-	-
72"	60" (4)	9	82.0	82.0	-	-	-	-	-	-
84"		9	82.0	82.0	-	-	-	-	-	-
96"		9	82.0	82.0	-	-	-	-	-	-
108"		12	82.0	82.0	-	-	-	-	-	-
72"	66" (5)	9	82.0	82.0	-	-	-	-	-	-
84"		9	82.0	82.0	-	-	-	-	-	-
96"		9	76.3	76.3	78.6	82.0	-	-	-	-
108"		12	82.0	82.0	-	-	-	-	-	-


A = NO. OF ANCHORS PER HEAD & SILL  
( ) = NO. OF ANCHORS PER JAMB



OPERATING VENTS TO BE 1/3 OF THE WINDOW WIDTH

DESIGN LOAD CAPACITY - PSF (XOX SIZES)										
WINDOW DIMS. WIDTH    HEIGHT		A	STD. ANCHORS							
			GLASS 'A' & 'B'		GLASS 'A' & 'B'					
WIDTH	HEIGHT	A	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)
			EXT.(+)	INT.(-)	EXT.(+)	INT.(-)				
74"	26" (2)	8	82.0	82.0	-	-	-	-	-	-
106-1/4"		11	82.0	82.0	-	-	-	-	-	-
111"		12	82.0	82.0	-	-	-	-	-	-
74"	38-3/8" (3)	8	82.0	82.0	-	-	-	-	-	-
106-1/4"		11	82.0	82.0	-	-	-	-	-	-
111"		12	82.0	82.0	-	-	-	-	-	-
74"	50-5/8" (4)	8	82.0	82.0	-	-	-	-	-	-
74"		8	82.0	82.0	-	-	-	-	-	-
74"	63" (4)	8	82.0	82.0	-	-	-	-	-	-
74"		8	82.0	82.0	-	-	-	-	-	-
72"	24" (2)	8	82.0	82.0	-	-	-	-	-	-
84"		8	82.0	82.0	-	-	-	-	-	-
96"		9	82.0	82.0	-	-	-	-	-	-
108"		11	82.0	82.0	-	-	-	-	-	-
72"	36" (3)	8	82.0	82.0	-	-	-	-	-	-
84"		8	82.0	82.0	-	-	-	-	-	-
96"		9	82.0	82.0	-	-	-	-	-	-
108"		11	82.0	82.0	-	-	-	-	-	-
72"	48" (4)	8	82.0	82.0	-	-	-	-	-	-
84"		8	82.0	82.0	-	-	-	-	-	-
96"		9	82.0	82.0	-	-	-	-	-	-
72"	60" (4)	8	82.0	82.0	-	-	-	-	-	-
72"		8	82.0	82.0	-	-	-	-	-	-


A = NO. OF ANCHORS PER HEAD & SILL  
( ) = NO. OF ANCHORS PER JAMB



OPERATING VENTS TO BE 1/4 OF THE WINDOW WIDTH

NOTE:  
GLASS CAPACITIES ON THIS SHEET ARE  
BASED ON ASTM E1300-09 (3 SEC. GUSTS)  
AND FLORIDA BUILDING COMMISSION  
DECLARATORY STATEMENT DCA05-DEC-219

**PRODUCT REVISED**  
As complying with the Florida  
Building Code  
NOA-No. **23-0731.07**  
Expiration Date: **02/10/2025**  
By: *Manuel Perez*  
Miami-Dade Product Control




**afC**  
**AL-FAROOQ CORPORATION**  
ENGINEERS & PRODUCT DEVELOPMENT  
9360 SUNSET DRIVE, SUITE 220  
MIAMI, FLORIDA 33173  
TEL. (305) 264-8100 FAX. (305) 262-6978  
COMP-ANL\W04-101ES

SERIES-2100 ALUM. HORIZ. SLIDING WDW. (S.M.I.)  
**E.S. WINDOWS, LLC**  
3550 N.W. 49 STREET  
MIAMI, FL. 33142  
TEL. (305) 638-5151 FAX. (305) 638-5158

revisions:	no.	date	by	description
	E	03.05.12		UPDATED TO 2010 FBC
	F	09.16.14		UPDATED TO 2014 FBC
	G	10.09.17		UPDATED TO 2017 FBC
	H	11.05.20		UPDATED TO 2020 FBC
	I	07.06.23		NO CHANGE THIS SHEET

date: 11-26-04  
scale: 1/2"=1'-0"  
dr. by: TARIQ  
chk. by:  
drawing no.  
**W04-101**  
sheet 2 of 8



WOOD BUCKS AND METAL STRUCTURE NOT BY 'E.S. WINDOWS'  
MUST SUSTAIN LOADS IMPOSED BY GLAZING SYSTEM  
AND TRANSFER THEM TO THE BUILDING STRUCTURE.

**TYPICAL ANCHORS:** SEE ELEV. FOR SPACING  
**1/4" DIA. ULTRACON+ BY 'DEWALT'** (Fu=164 KSI, Fy=148 KSI)  
INTO 2BY WOOD BUCKS OR WOOD STRUCTURES  
1-1/2" MIN. PENETRATION INTO WOOD (HEAD/SILL/JAMBS)  
THRU 1BY BUCKS INTO CONC. OR BLOCKS  
1-1/4" MIN. EMBED INTO CONCRETE (HEAD/SILL/JAMBS)  
1-1/4" MIN. EMBED INTO BLOCKS (JAMBS)  
DIRECTLY INTO CONCRETE OR BLOCKS  
1-1/4" MIN. EMBED INTO CONCRETE (HEAD/SILL/JAMBS)  
1-1/4" MIN. EMBED INTO BLOCKS (JAMBS)

**#14 SMS OR SELF DRILLING SCREWS** (GRADE 2 CRS)  
INTO MIAMI-DADE COUNTY APPROVED MULLIONS  
OR  
INTO METAL STRUCTURES (HEAD/SILL/JAMBS)  
(3) THREADS MIN. PENETRATION BEYOND SUBSTRATE  
ALUMINUM: 1/8" THK. MIN. (6063-T5 MIN.)  
STEEL: 1/8" THK. MIN. (Fy = 36 KSI MIN.)  
(STEEL IN CONTACT WITH ALUMINUM TO BE PLATED OR PAINTED)


**TYPICAL EDGE DISTANCE**  
INTO CONCRETE AND MASONRY = 2-1/2" MIN.  
INTO WOOD STRUCTURE = 1" MIN.  
INTO METAL STRUCTURE = 3/4" MIN.  
WOOD AT HEAD, SILL OR JAMBS SG = 0.55 MIN.  
CONCRETE AT HEAD, SILL OR JAMBS f'c = 3000 PSI MIN.  
C-90 HOLLOW/FILLED BLOCK AT JAMBS f'm = 2000 PSI MIN.

**SEALANTS:**  
FRAME AND VENT CORNERS AND INSTALLATION SCREWS AT SILL  
SEALED WITH WHITE/ALUMINUM COLORED SILICONE.

**WEEPHOLES:**  
W1 = 1-13/16" X 1/4" WEEPHOLES AT 3" FROM EACH END  
WITH PLASTIC BAFFLE  
W2 = 1/4" WEEPHOLE AT TOP & BOTTOM RAIL 1" FROM EACH END

**PRODUCT REVISED**  
As complying with the Florida  
Building Code  
NOA-No. **23-0731.07**  
Expiration Date: **02/10/2025**  
By: *Manuel Perez*  
Miami-Dade Product Control

JUL 07 2023



**af c**  
**AL-FAROOQ CORPORATION**  
ENGINEERS & PRODUCT DEVELOPMENT  
9360 SUNSET DRIVE, SUITE 220  
MIAMI, FLORIDA 33173  
TEL. (305) 264-8100 FAX. (305) 262-6978  
COMP-ANL\W04-101ES

**REVISIONS:**

no	date	by	description
E	03.05.12		NO CHANGE THIS SHEET
F	09.16.14		UPDATED TO 2014 FBC
G	10.09.17		UPDATED TO 2017 FBC
H	11.05.20		UPDATED TO 2020 FBC
I	07.06.23		NO CHANGE THIS SHEET




**AL-FAROOQ CORPORATION**  
ENGINEERS & PRODUCT DEVELOPMENT  
9360 SUNSET DRIVE, SUITE 220  
MIAMI, FLORIDA 33173  
TEL. (305) 264-8100 FAX. (305) 262-6978  
COMP-ANL\W04-101ES

**E.S. WINDOWS, LLC**  
3550 N.W. 49 STREET  
MIAMI, FL. 33142  
TEL. (305) 638-5151 FAX. (305) 638-5158

date:	11-26-04
scale:	1/2" = 1"
dr. by:	TARIQ
chk. by:	

drawing no.	W04-101
sheet	3 of 8






ITEM	PART #	QUANTITY	DESCRIPTION	MATERIAL	MANF./SUPPLIER/REMARKS
1	ES1003	1	FRAME HEAD	6063-T6	-
2	ES2012	1	FRAME SILL	6063-T6	-
3	ES2003	1	FRAME JAMB	6063-T6	-
5	ES1005	1/ VENT	FIXED RAIL (AT SPRING LATCHES)	6063-T6	-
5A	ES1051	1/ VENT	FIXED RAIL (AT SWEEP LATCHES)	6063-T6	-
6	ES2004	1/ VENT	H.D. VENT MEETING RAIL (AT SPRING LATCHES)	6063-T6	-
6A	ES1053	1/ VENT	H.D. VENT MEETING RAIL (AT SWEEP LATCHES)	6063-T6	-
6.1	ES-2004A	1/ VENT	H.D. VENT MEETING RAIL (AT SPRING LATCHES)	6063-T6	ALTERNATE TO 6
6A.1	ES-1053A	1/ VENT	H.D. VENT MEETING RAIL (AT SWEEP LATCHES)	6063-T6	ALTERNATE TO 6A
7	ES1007	2/ VENT	TOP AND BOTTOM RAIL	6063-T5	-
8	ES1006	1/ VENT	JAMB STILE	6063-T5	-
9	ES1103	AS REQD.	GLAZING BEAD	6063-T6	-
10	ES2002	1	SILL TRACK INSERT	6063-T5	-
11	ES2011	AS REQD.	STD. SILL RISER	6063-T5	-
12	ES1009	2/ VENT	SPRING LOADED VENT LATCH	6063-T6	AT 8" FROM ENDS
12A	SL203	2/ VENT	SWEEP LATCH	ZAMAK	AT 11" FROM ENDS, BY INTERLOCK
12B	#8 X 1"	2/ LATCH	LATCH INSTALLATION SCREWS	-	FH SMS
13	ES1012	1/ LATCH	VENT LATCH SPRING	ST. STEEL	-
14	C1B251N	AS REQD.	FOAM FILLED FABRIC W'STRIPPING	-	SCHLEGEL
14A	W23221NG	AS REQD.	FIN SEAL PILE W'STRIPPING	-	ULTRAFAB
15	#8 X 1"	AS REQD.	FRAME/VENT ASSEMBLY SCREWS	CRS	P.H. SMS
16	#10 X 4"	2/ VENT	FIX. RAIL SILL SCREWS	CRS	P.H. SMS
17	W2321NG	AS REQD.	VENT & FIX. RAIL W'STRIPPING	-	ULTRAFAB
18	W23291NG	AS REQD.	FRAME JAMB W'STRIPPING	-	ULTRAFAB
19	WPHL-100	2	BAFFLE	-	M & M PLASTICS
20	#6 X 1/2"	2/ BAFFLE	BAFFLE SCREW	-	F.H. SMS
21	ES1104	AS REQD.	GLAZING GASKET	NEOPRENE	-
22	ES2007	4/ VENT	ROLLER HOUSING & GUIDE	PLASTIC	-
23	ES2006	2/ VENT	ROLLER	BRASS/ST. ST.	-
24	ES2005	2/ VENT	ROLLER PIN	ST. STEEL	-
25	-	1/ WEEP	OPEN CELL FOAM PAD	-	1" X 3/4" X 1" LONG
26	-	1/ VENT	5/16" BOX SCREEN	-	OPTIONAL
27	ES1505	-	FLUSH FRAME ADAPTER	6063-T5	OPTIONAL
28	27-372	2/ LITE	SETTING BLOCK, 7/16" X 3/16" X 3-1/2" LONG	EPDM	DUROMETER 75±5 SHORE A

**PRODUCT REVISED**  
As complying with the Florida  
Building Code  
NOA-No. **23-0731.07**  
Expiration Date: **02/10/2025**  
By: *Manuel Perez*  
Miami-Dade Product Control

JUL 07 2023



revisions:

no	date	description
E	03.05.12	NO CHANGE THIS SHEET
F	09.16.14	UPDATED TO 2014 FBC
G	10.09.17	UPDATED TO 2017 FBC
H	11.05.20	UPDATED TO 2020 FBC
I	07.06.23	NO CHANGE THIS SHEET

date: 11-26-04

scale: 1/2" = 1"

dr. by: TARIQ

chk. by:






drawing no.  
**W04-101**  
sheet 4 of 8

**AL-FAROOQ CORPORATION**  
ENGINEERS & PRODUCT DEVELOPMENT  
9360 SUNSET DRIVE, SUITE 220  
MIAMI, FLORIDA 33173  
TEL. (305) 264-8100 FAX. (305) 262-6978  
(C.A.N. 3538)

series-2100 ALUM. HORIZ. SLIDING WDW. (S.M.I.)  
**E.S. WINDOWS, LLC**  
3550 N.W. 49 STREET  
MIAMI, FL. 33142  
TEL. (305) 638-5151 FAX. (305) 638-5158


COMP-ANL\W04-101ES





VENTS WITH  
SPRING LOADED LATCHES

**PRODUCT REVISED**  
As complying with the Florida Building Code  
NOA-No. **23-0731.07**  
Expiration Date: **02/10/2025**  
By: *Manuel Torres*  
Miami-Dade Product Control







JUL 07 2023

**AL-FAROOQ CORPORATION**  
ENGINEERS & PRODUCT DEVELOPMENT  
9360 SUNSET DRIVE, SUITE 220  
MIAMI, FLORIDA 33173  
TEL. (305) 264-8100 FAX. (305) 262-6978  
C.A.N. 3538

SERIES-2100 ALUM. HORIZ. SLIDING WDW. (S.M.I.)  
**E.S. WINDOWS, LLC**  
3550 N.W. 49 STREET  
MIAMI, FL. 33142  
TEL. (305) 638-5151 FAX. (305) 638-5158


no	date	by	description
E	03.05.12		NO CHANGE THIS SHEET
F	09.16.14		UPDATED TO 2014 FBC
G	10.09.17		UPDATED TO 2017 FBC
H	11.05.20		UPDATED TO 2020 FBC
I	07.06.23		NO CHANGE THIS SHEET

date: 11-26-04  
scale: 1/2" = 1"  
dr. by: TARIQ  
chk. by:  
drawing no.  
**W04-101**  
sheet 5 of 8



**PRODUCT REVISED**  
 As complying with the Florida  
 Building Code  
 NOA-No. **23-0731.07**  
 Expiration Date: **02/10/2025**  
 By: *Manuel Torres*  
 Miami-Dade Product Control

VENTS WITH  
 SWEEP LATCHES



SERIES-2100 ALUM. HORIZ. SLIDING WDW. (S.M.I.)

**E.S. WINDOWS, LLC**  
 3550 N.W. 49 STREET  
 MIAMI, FL. 33142  
 TEL. (305) 638-5151 FAX. (305) 638-5158

**AL-FAROOQ CORPORATION**  
 ENGINEERS & PRODUCT DEVELOPMENT  
 9360 SUNSET DRIVE, SUITE 220  
 MIAMI, FLORIDA 33173 (C.A.N. 3538)  
 TEL. (305) 264-8100 FAX. (305) 262-6978





COMP-ANL\W04-101ES

no	date	by	description
E	03.05.12		NO CHANGE THIS SHEET
F	09.16.14		UPDATED TO 2014 FBC
G	10.09.17		UPDATED TO 2017 FBC
H	11.05.20		UPDATED TO 2020 FBC
I	07.06.23		NO CHANGE THIS SHEET


date: 11-26-04  
 scale: 1/2" = 1"  
 dr. by: TARIQ  
 chk. by:

drawing no.  
**W04-101**  
 sheet 6 of 8

JUL 01 2023



**PRODUCT REVISED**  
 As complying with the Florida Building Code  
 NOA-No. **23-0731.07**  
 Expiration Date: **02/10/2025**  
 By: *Manuel Perez*  
 Miami-Dade Product Control



JUL 07 2023

**AL-FAROOQ CORPORATION**  
 ENGINEERS & PRODUCT DEVELOPMENT  
 9360 SUNSET DRIVE, SUITE 220  
 MIAMI, FLORIDA 33173 (C.A.N. 3538)  
 TEL. (305) 264-8100 FAX. (305) 262-6978  
 COMP-ANL\W04-101ES


SERIES-2100 ALUM. HORIZ. SLIDING WDW. (S.M.I.)

**E.S. WINDOWS, LLC**  
 3550 N.W. 49 STREET  
 MIAMI, FL. 33142  
 TEL. (305) 638-5151 FAX. (305) 638-5158


revisions:	no.	date	by	description
	E	03.05.12		NO CHANGE THIS SHEET
	F	09.16.14		UPDATED TO 2014 FBC
	G	10.09.17		UPDATED TO 2017 FBC
	H	11.05.20		UPDATED TO 2020 FBC
	I	07.06.23		NO CHANGE THIS SHEET

date: 11-26-04	scale: 1/2" = 1"	dr. by: TARIQ	chk. by:
drawing no. <b>W04-101</b>			
sheet 7 of 8			







VENT TOP/BOTTOM CORNERS



FIXED MTG. RAIL CORNER



FRAME TOP CORNER




FRAME BOTTOM CORNER

**PRODUCT REVISED**  
As complying with the Florida  
Building Code

NOA-No. **23-0731.07**

Expiration Date: **02/10/2025**

By: *Manuel Perez*  
Miami-Dade Product Control



JUL 07 2023

**af c**  
**AL-FAROOQ CORPORATION**  
ENGINEERS & PRODUCT DEVELOPMENT  
9360 SUNSET DRIVE, SUITE 220  
MIAMI, FLORIDA 33173 (C.A.N. 3538)  
TEL. (305) 264-8100 FAX. (305) 262-6978  
COMP-ANL\W04-101ES

SERIES-2100 ALUM. HORIZ. SLIDING WDW. (S.M.I.)  
**E.S. WINDOWS, LLC**  
3550 N.W. 49 STREET  
MIAMI, FL. 33142  
TEL. (305) 638-5151 FAX. (305) 638-5158

revisions:		no.	date	by	description
	E	03.05.12			NO CHANGE THIS SHEET
	F	09.16.14			NO CHANGE THIS SHEET
	G	10.09.17			UPDATED TO 2017 FBC
	H	11.05.20			UPDATED TO 2020 FBC
	I	07.06.23			NO CHANGE THIS SHEET

date:	11-26-04
scale:	1/2" = 1"
dr. by:	TARIQ
chk. by:	

drawing no.	W04-101
sheet	8 of 8