

MIAMI-DADE COUNTY PRODUCT CONTROL SECTION

11805 SW 26 Street, Room 208 Miami, Florida 33175-2474 T (786) 315-2590 F (786) 315-2599

www.miamidade.gov/building

DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER) BOARD AND CODE ADMINISTRATION DIVISION

NOTICE OF ACCEPTANCE (NOA)

Loren Cook Company 2015 E. Dale Street Springfield, MO 65803

SCOPE: This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER-Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Models "ACRU, VCR, ACSC and ACW" Aluminum Rooftop and Wall Mounted Fans – L.M.I.

APPROVAL DOCUMENT: Drawing No. **SD080717-12**, titled "ACRU/VCR/ACSC/ACW Power Ventilator Hurricane Rated", sheet 1 through 12 of 12, dated 05/05/14, with revision G dated 11/06/2023, prepared by manufacturer, signed and sealed by Jerry T. Miller, P.E. bearing the Miami-Dade County Product Control Revision stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Section.

MISSILE IMPACT RATING: Large and Small Missile Impact Resistant

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, manufacturing address, model number, the positive and negative design pressure rating, indicate impact rated if applicable, installation instruction drawing reference number, approval number (NOA), the applicable test standards, and the statement reading 'Miami-Dade County Product Control Approved' is to be located on the door's side track, bottom angle, or inner surface of a panel.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official. This NOA **renews** and **revises NOA No. 17-0925.02** and consists of this page 1 and evidence page E-1, E-2 and E-3, as well as approval document mentioned above.

The submitted documentation was reviewed by Carlos M. Utrera, P.E.

MIAMI-DADE COUNTY
APPROVED

NOA No. 23-0815.03 Expiration Date: November 13, 2028 Approval Date: November 22, 2023

Page 1

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA's

Α. **DRAWINGS**

- 1. Manufacturer's die drawings and sections. (Submitted under NOA No. 08-0424.03)
- Drawing No. SD080717-12, titled "ACRU/VCR/ACSC/ACW Power Ventilator 2. Hurricane Rated", sheets 1 through 12 of 12, dated 05/05/14, with revision G, prepared by manufacturer, signed and sealed by Bradley F. Skidmore, P.E. (Submitted under NOA No. 17-0925.02)

B. **TESTS**

- Test report on: 1) Large Missile Impact Test per FBC, TAS 201-94 1. along with marked up drawings and installation diagram of Models ACRU 70 and ACRU 300 Wall Mount Ventilators, prepared by Intertek, Test Report No. H1597.01-801-18R1, dated 08/21/17 and revision dated 12/06/17, signed and sealed by Tyler Westerling, P.E.
 - (Submitted under NOA No. 17-0925.02)
- 2. Test reports on: 1) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94 2) Large Missile Impact Test per FBC, TAS 201-94 along with marked-up drawings and installation diagram of Models ACW 70 and ACW 245 Wall Mount Ventilators, prepared by Intertek, Test Report No. H1597.02-801-18R1, dated 08/21/17 and revision dated 12/06/17, signed and sealed by Tyler Westerling, P.E. (Submitted under NOA No. 17-0925.02)
- 3. Test reports on: 1) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94 2) Large Missile Impact Test per FBC, TAS 201-94 along with marked-up drawings and installation diagram of Model ACRU/VCR 300 Rooftop Ventilator with 48" High Roof Curb, prepared by Intertek-ATI, Test Report No. **D7025.01-801-18**, dated 08/11/14, signed and sealed by Tyler Westerling, P.E. (Submitted under NOA No. 16-1108.05)
- 4. Test reports on: 1) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94 2) Large Missile Impact Test per FBC, TAS 201-94 along with marked-up drawings and installation diagram of Models ACRU 70 and ACRU 300 Rooftop Ventilators, prepared by Intertek-ATI, Test Report No. G1591.01-801-18, dated 09/22/16, signed and sealed by Shawn G. Collins, P.E. (Submitted under NOA No. 14-1218.04)

Carlos M. Utrera, P.E. **Product Control Examiner** NOA No. 23-0815.03

Expiration Date: November 13, 2028 Approval Date: November 22, 2023

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

- 1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA'S (CONTINUED)
- B. TESTS (CONTINUED)
 - 5. Test reports on: 1) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
 - 2) Large Missile Impact Test per FBC, TAS 201-94
 - 3) Cyclic Wind Pressure Loading per FBC, TAS 203-94

along with marked-up drawings and installation diagram of Series/Models 300 ACRU/VCR, metal roof vent, prepared by Architectural Testing, Inc., Test Report No. **79142.01-801-18**, dated 03/03/08, signed and sealed by Jeffrey T. Kaminski, P.E. (Submitted under NOA No. 08-0424.03)

C. CALCULATIONS

- 1. Wind loads and anchor capacity calculations dated 09/12/17, prepared by manufacturer, signed and sealed by Bradley F. Skidmore, P.E. (Submitted under NOA No. 17-0925.02)
- D. QUALITY ASSURANCE
 - 1. Miami-Dade Department of Regulatory and Economic Resources (RER)
- E. MATERIAL CERTIFICATIONS
 - 1. None.
- F. STATEMENTS
 - 1. Statement letter of conformance, complying with **FBC** 6th **Edition (2017)** dated 09/20/17, issued by manufacturer, signed and sealed by Bradley F. Skidmore, P.E. (Submitted under NOA No. 17-0925.02)
 - 2. Statement letter of no financial interest dated 09/20/17, issued by manufacturer, signed and sealed by Bradley F. Skidmore, P.E. (Submitted under NOA No. 17-0925.02)

G. OTHERS

1. Notice of Acceptance No. 16-1108.05, issued to Loren Cook Company for their Series ACRU, VCR, ACSC and ACW Aluminum Rooftop and Wall Mounted Fans, approved on 12/15/16 and expiring on 11/13/18.

Carlos M. Utrera, P.E. Product Control Examiner NOA No. 23-0815.03

Expiration Date: November 13, 2028 Approval Date: November 22, 2023

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

2. EVIDENCE SUBMITTED UNDER NOA # 21-0405.05 AND NEW

A. DRAWINGS

- 1. Drawing No. **SD080717-12**, titled "ACRU/VCR/ACSC/ACW Power Ventilator Hurricane Rated", sheet 1 through 12 of 12, dated 05/05/14, with revision G dated 11/06/2023, prepared by manufacturer, signed and sealed by Jerry T. Miller, P.E.
- B. TESTS
 - 1. None.

C. CALCULATIONS

1. None.

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER).

E. MATERIAL CERTIFICATIONS

1. None.


F. STATEMENTS

- 1. Statement letter of conformance with the 8th edition (2023) of the FBC, issued by Miller Engineering, dated 07/28/2023, signed and sealed by Jerry T. Miller, P.E.
- 2. Statement letter of no financial interest, issued by Miller Engineering, dated 11/08/2023, signed and sealed by Jerry T. Miller, P.E.
- **3.** Statement letter of conformance, complying with 7th edition (2020) of the FBC, issued by manufacturer, dated March 19, 2021, signed and sealed by Bradley F. Skidmore, P.E.

Carlos M. Utrera, P.E. Product Control Examiner NOA No. 23-0815.03

Expiration Date: November 13, 2028 Approval Date: November 22, 2023

| Size | Туре | А | В | С | D | T Sq. | NOMINAL WEIGHT |
|--------|----------------|----------|----------|----------|---|----------|-------------------|
| 70 | DIRECT | 10-3/4 | 17–1/8 | 13-3/8 | 2 | 18 | 20 |
| 70 | TALL DIRECT | 10-3/4 | 17-1/8 | 14-3/8 | 2 | 18 | 21 |
| 90 | DIRECT | 13-1/4 | 21-1/8 | 16-3/8 | 2 | 18 | 28 |
| 90 | TALL DIRECT | 13-1/4 | 21-1/8 | 17-3/8 | 2 | 18 | 29 |
| 100 | DIRECT | 13-1/4 | 21-1/8 | 16-3/8 | 2 | 18 | 30 |
| 101 | TALL DIRECT | 13-1/4 | 21-1/8 | 20-3/16 | 2 | 18 | 31 |
| 70-100 | BELT | 12-1/2 | 23-9/16 | 21-1/8 | 2 | 18 | 50 |
| 120 | BELT/DIRECT | 19-1/16 | 28-7/16 | 26-7/8 | 2 | 20 | 81 |
| 135 | BELT/DIRECT | 19-1/16 | 28-7/16 | 27-1/4 | 2 | 20 | 86 |
| 150 | BELT/DIRECT | 20-15/16 | 32-7/8 | 30-1/4 | 2 | 24 | 102 |
| | HP BELT/DIRECT | 20-15/16 | 32-7/8 | 27-1/2 | 2 | 24 | 100 |
| 165 | BELT/DIRECT | 20-15/16 | 32-7/8 | 30-3/4 | 2 | 24 | 108 |
| | HP BELT/DIRECT | 20-15/16 | 32-7/8 | 27-3/4 | 2 | 24 | 106 |
| | XP BELT/DIRECT | 20-15/16 | 32-7/8 | 26-11/16 | 2 | 24 | 104 |
| 180 | BELT/DIRECT | 24-13/16 | 37-11/16 | 35-7/8 | 3 | 30 | 125 |
| | HP BELT/DIRECT | 24-13/16 | 37-11/16 | 33-3/8 | 3 | 30 | 123 |
| | XP BELT/DIRECT | 24-13/16 | 37-11/16 | 31-9/16 | 3 | 30 | 121 |
| 195 | BELT/DIRECT | 24-13/16 | 37-11/16 | 36-3/8 | 3 | 30 | 135 |
| | HP BELT/DIRECT | 24-13/16 | 37-11/16 | 33-1/2 | 3 | 30 | 133 |
| | XP BELT/DIRECT | 24-13/16 | 37-11/16 | 32-1/8 | 3 | 30 | 131 |
| 210 | BELT/DIRECT | 25-15/16 | 43-5/8 | 38-3/8 | 3 | 30 | 190 |
| | HP BELT/DIRECT | 25-15/16 | 43-5/8 | 35-3/8 | 3 | 30 | 186 |
| | XP BELT/DIRECT | 25-15/16 | 43-5/8 | 32-3/4 | 3 | 30 | 182 |
| 225 | BELT/DIRECT | 25-15/16 | 43-5/8 | 38-1/8 | 3 | 30 | 212 |
| | HP BELT/DIRECT | 25-15/16 | 43-5/8 | 35-1/2 | 3 | 30 | 208 |
| | XP BELT/DIRECT | 25-15/16 | 43-5/8 | 33-5/16 | 3 | 30 | 204 |
| 245 | BELT/DIRECT | 28-1/2 | 47-5/8 | 41-1/16 | 3 | 30 | 234 |
| | HP BELT/DIRECT | 28-1/2 | 47-5/8 | 37-5/16 | 3 | 30 | 230 |
| | XP BELT/DIRECT | 28-1/2 | 47-5/8 | 34-1/16 | 3 | 30 | 226 |
| 270 | BELT/DIRECT | 28-1/2 | 47-5/8 | 41-1/16 | 3 | 36 | 256 |
| | HP BELT/DIRECT | 28-1/2 | 47-5/8 | 37-5/16 | 3 | 36 | 252 |
| | XP BELT/DIRECT | 28-1/2 | 47-5/8 | 35 | 3 | 36 | 248 |
| 300 | BELT/DIRECT | 33-7/8 | 52-5/8 | 49-15/16 | 3 | 36 | 306 |
| | HP BELT/DIRECT | 33-7/8 | 52-5/8 | 45-15/16 | 3 | 36 | 300 |
| | XP BELT/DIRECT | 33-7/8 | 52-5/8 | 41-7/16 | 3 | 36 | 294 |



DESIGN PRESSURE: +150 PSF / -150 PSF

IMPACT RATING: LARGE MISSLE IMPACT RESISTANT

DESIGN TESTING AND INSTALLATION CONFORMS TO FLORIDA BUILDING CODE

ALL DIMENSIONS IN INCHES/ALL WEIGHTS IN POUNDS



JERRY TRAVIS MILLER- ENGINEER

| MAT'L | _ | | | | | | |
|------------------------------------|---|-----|-------|-------|----|--|--|
| DRAWN | _ | BFS | 05/0 | 05/14 | | | |
| DESIGNE | R | BFS | SHEET | 1 OF | 12 | | |
| DO NOT SCALE DRAWING | | | | | | | |
| TOLERANCES LINLESS OTHERWISE NOTED | | | | | | | |

LOREN COOK CO. MANUFACTURERS OF AIR MOVING EQUIPMENT SPRINGFIELD, MISSOURI

REV.

Miami-Dade Product Control


DECIMAL .XX=±.063" .XXX=±.010" .XXXX=±.001" ANGULAR

FRACTIONAL <u>≤</u>12"=±1/16" >12" THRU 96"=±1/8" >96" THRU 144"=±1/4" >144"=±3/8"


(NC)=NO INSPECTION REQ'D

ACRU/VCR/ACSC/ACW POWER VENTILATOR HURRICANE RATED DRAWING NO. SIZE

SD080717-12



ATTACHMENT OF CURB TO ROOF STRUCTURE



| | FASTENER TABLE | | | | | | |
|--------------|---|---|--|--|--|--|--|
| UNIT SIZE | MINIMUM NUMBER OF FASTENERS PER SIDE TO ATTACH UNIT TO CURB | MINIMUM NUMBER OF FASTENERS PER SIDE TO ATTACH CURB TO ROOF STRUCTURE | | | | | |
| 70 | 5 | 5 | | | | | |
| 90 | 5 | 5 | | | | | |
| 70–100 | 5 | 5 | | | | | |
| 101 | 5 | 5 | | | | | |
| 120 | 5 | 6 | | | | | |
| 135 | 5 | 6 | | | | | |
| 150 | 6 | 7 | | | | | |
| 165 | 6 | 7 | | | | | |
| 180 | 8 | 8 | | | | | |
| 195 | 8 | 8 | | | | | |
| 210 | 8 | 9 | | | | | |
| 225 | 8 | 9 | | | | | |
| 245 | 8 | 10 | | | | | |
| 270 | 9 | 10 | | | | | |
| 300 | 9 | 14 | | | | | |

PRODUCT REVISED
as complying with the Florida
Building Code
NOA-No. 23-0815.03

Expiration Date 11/13/2028

By Huns

Miami-Dade Product Control



NOTES:

1) ACRU/VCR/ACW POWER VENTILATOR AS REFERRED TO HEREIN REFERS TO ALL LOREN COOK MODEL POWER VENTILATORS INCLUDING BOTH DIRECT DRIVE AND BELT DRIVE TYPE UNITS WHICH ARE CONSTRUCTED WITH THE SAME OUTER HOUSING COMPONENTS. THE FULL RANGE OF MODELS WOULD BE:

ACRUD, ACRUD-HP, ACRUD-XP ACRUB, ACRUB-HP, ACRUB-XP VCRD, VCRD-HP, VCRD-XP VCR, VCR-XP, VCR-HP ACSC, ACSC-HP, ACSC-XP

- ACWD, ACWD-HP, ACWD-XP, ACWDEC, ACWDEC-HP, ACWDEC-XP, ACWB, ACWB-HP, ACWB-XP
- 2) THIS APPROVAL IS FOR THE STRUCTURAL CAPACITY OF THE EXTERIOR HOUSING ONLY, IT DOES NOT INCLUDE ANY INTERIOR MECHANISM OR ELECTRICAL PART.
- 3) THIS PRODUCT HAS NOT BEEN TESTED FOR WATER PENETRATION ACCORDING TO FLORIDA BUILDING CODE TAS 100(A) WIND DRIVEN RAIN TEST. IT CANNOT BE INSTALLED WITHIN THE RIDGE AREA FBC 1523.6.5.2.13
- 4) UNIT IS TO INCLUDE A CURB CAP BASE TO FACILITATE MOUNTING OF THE UNIT TO A CURB. THE CURB WILL BE ADEQUATELY ATTACHED TO THE BUILDING STRUCTURE TO SUSTAIN ALL FORCES WHICH MAY BE PRODUCED BY THE PRESCRIBED ENVIROMENTAL FORCES EXERTED ON THE FAN AND CURB. THE CURB MUST BE ATTACHED TO A STRUCTURAL MEMBER OF THE BUILDING.

CONCRETE DECK: CURB IS TO BE ATTACHED WITH WEDGE TYPE CONCRETE ANCHOR — MINIMUM 3/8" DIAMETER CARBON STEEL — HILTI KWIK BOLT 3 OR EQUAL.

MINIMUM 2-1/2" OF ENGAGEMENT IN 2000 PSI MINIMUM CONCRETE.


MINIMUM DECK THICKNESS IS 4". SEE TABLE FOR MINIMUM QUANTITY OF ANCHORS REQUIRED PER CURB SIDE.


STEEL ROOF STRUCTURE: CURB IS TO BE ATTACHED WITH SELF—DRILLING STEEL SCREW OF MINIMUM NOMINAL SIZE OF #12. THE SCREW SHALL PASS THROUGH STEEL STRUCTURE AT LEAST 1/2". SEE TABLE FOR MINIMUM QUANTITY OF SCREWS REQUIRED PER CURB SIDE.


WOOD ROOF STRUCTURE: CURB IS TO BE ATTACHED WITH STEEL LAG BOLTS NOMINAL SIZE OF 5/16" DIAMETER OR LARGER. WOOD IS TO BE 4" NOMINAL SIZE OR GREATER. THE BOLT SHALL HAVE A MINIMUM OF 3" OF THREAD ENGAGEMENT AND SHALL BE AT LEAST 1-1/2" FROM MATERIAL EDGE. SEE TABLE FOR MINIMUM QUANTITY OF BOLTS REQUIRED PER CURB SIDE.

- 5) THE CURB SHALL BE CONSTRUCTED OF G-90 GALVANIZED STEEL OR 3003-H24 ALUMINUM OR STAINLESS STEEL. THE CURB MATERIAL THICKNESS SHALL BE 18 GA (.0470") OR GREATER. THE CURB HEIGHT SHALL NOT EXCEED 48".
- 6) THE ACRU/VCR POWER VENTILATOR SHALL BE ATTACHED TO THE CURB WITH ONE OF THE FOLLOWING METHODS INSTALLED ON ALL FOUR SIDES OF THE CURB CAP OR THRU USE OF THE ACCESSORY HINGED BASE. THE FASTENERS SHALL BE 2" FROM EACH CORNER OF THE FAN BASE. THE DISTANCE BETWEEN FASTENERS SHALL BE 5-1/2" OR LESS. THE QUANTITY OF FASTENERS INTO EACH CURB SIDED SHALL EQUAL OR EXCEED THE QUANTITY SHOWN IN THE FASTENER TABLE (AT LEFT).
 -) #12 X 2" HEX WASHER HEAD SELF-DRILLING SCREW
 -) ALTERNATE FASTENER .25" HEX HEAD BOLT AND WASHER WITH COMPANION NUT INSTALLED ON THE INTERIOR OF THE CURB.
- 7) ALL FASTENERS ARE TO BE HIGH QUALITY CORROSION RESISTANT STEEL OR STAINLESS STEEL.
- 8) ANY GAP BETWEEN THE CURB AND CURB CAP SHALL BE FILLED BY THE INSTALLING CONTRACTOR WITH A SUITABLE CORROSION RESISTANT MATERIAL THAT ALLOWS THE FASTENERS TO BE INSTALLED WITHOUT CAUSING EXCESSIVE DISTORTION OF THE UNIT FLANGES.
- 9) THE INSTALLER IS RESPONSIBLE FOR CHECKING THAT ALL FASTENERS ARE PROPERLY INSTALLED AND ALL ACCESS PANELS ARE IN PLACE BEFORE PUTTING THE UNIT INTO SERVICE.
- 10) ALL FASTENERS AND ACCESS PANELS MUST BE PROPERLY INSTALLED AFTER MAINTENANCE OPERATIONS FOR UNIT TO MAINTAIN CODE COMPLIANCE.

| MAT'L - | | | | J Loren Cook | ද _ක ු | |
|--------------------|-------|----------------------------------|------------------------------------|-------------------------|----------------------|--|
| DRAWN | BFS | 05/05/14 | MANUFACTURERS OF AIR MOVING EQUIPM | | | |
| DESIGNER | BFS | SHEET 2 OF 12 | 12/10 | ® SPRINGFIELD, MISSOURI | | |
| DONO T SCALDRAWING | | | ACRU/VCR/ACSC/ACW | | | |
| TOLERAN CE | SUN L | ESS TOHERWISE NOTED | , , , , | | | |
| DECIMAL | | <u>FRACTIONAL</u> ≤12"=±1/16" | | 1 POWER VENTILATOR | | |
| .XX=±.063 | | | | RICANE RATED | | |
| .XXX=±.010" | | 12" THRU 96"=±1/8" | | | | |
| .XXXX=±.001" | >9 | 6" THRU 144"=±1/4" | SIZE | DRAWING NO. | REV. | |
| ANGULAR | | >144"=±3/8" | В | SD080717-12 | G | |
| ±2° | (NC) | =NO INSPECTION REQ'D | | 30000/1/-12 | G | |







Expiration Date 11/13/2028

By Miami-Dade Product Control

210-225 43 45-1/8 10 .050 44 37-1/4 180-195 39-3/8 38-1/4 10 .040 32-1/2 34-5/8 8-1/2 33-1/2 150-165 .040 8-1/2120-135 30-1/8 28 .040 29 25-1/8 6-1/2100 23 .040 24 С Ε В D UNIT Α SIZE DIM DIM DIM DIM DIM

| MAT'L | D | THICK | 1100-0 | ALUM | | |
|----------------------|---|-------|--------|-------|----|--|
| DRAWN | 1 | BFS | 05/0 | 05/14 | | |
| DESIGNE | R | BFS | SHEET | 4 OF | 12 | |
| DO NOT SCALE DRAWING | | | | | | |

| DO NOT SCALE DRAWING | | | | | | | |
|----------------------|--------------------------|--|--|--|--|--|--|
| TOLERANCES (| JNLESS OTHERWISE NOTED | | | | | | |
| DECIMAL | <u>FRACTIONAL</u> | | | | | | |
| .XX=±.063" | <u>≤</u> 12"=±1/16" | | | | | | |
| .XXX=±.010" | >12" THRU 96"=±1/8" | | | | | | |
| XXXX=±.001" | >96" THRU 144"=±1/4" | | | | | | |
| ANGULAR | >144"=±3/8" | | | | | | |
| ±2* | (NC)=NO INSPECTION REQ'D | | | | | | |




LOREN COOK CO.

MANUFACTURERS OF AIR MOVING EQUIPMENT

SPRINGFIELD, MISSOURI

| ACRI | J/VCR/ACSC/ACW | |
|------|----------------|------|
| POW | ER VENTILATÓR | |
| HURF | RICANE RATED | |
| SIZE | DRAWING NO. | REV. |
| | | |


B SD080717-12 G



| 300 | 22 | 39-1/32 | 0.050 |
|-------------|--------|----------|-----------|
| 270 | 16-1/4 | 35-17/32 | 0.040 |
| 245 | 16-1/4 | 32-17/32 | 0.040 |
| 210-225 | 16-1/4 | 29-17/32 | 0.040 |
| 120-135 | 13 | 20-1/32 | 0.040 |
| 70-100 BELT | 8-1/2 | 16-13/32 | 0.040 |
| UNIT | А | В | THICKNESS |
| SIZE | DIM | DIM | MATERIAL |

Expiration Date 11/13/2028

By Miami-Dade Product Control



ALUMINUM: SY MIN=17KSI

| / r | 1 1011111 — 1 | 1 C | IVITIA | _0 | A |
|-----|---------------|-----|--------|----|---------|
| Т | | AB | EE TAI | SE | MAT'L |
|] [| 05/14 | 3 | BFS | 1 | DRAWN |
|] L | T 5 OF 12 | 3 | BFS | R | DESIGNE |
| _ | WING | SC | NOT S | DΩ | |

| DO | NOT SO | CALE DRAWING |
|----------------|--------|----------------------|
| TOLERANCES | UNLES | S OTHERWISE NOTED |
| DECIMAL | | <u>FRACTIONAL</u> |
| .XX=±.063 | | ≤12"=±1/16" |
| .XXX=±.010" | | 12" THRU 96"=±1/8" |
| XXXX=±.001" | >9 | 6" THRU 144"=±1/4" |
| ANGULAR | | >144"=±3/8" |
| ±2° | (NC) | =NO INSPECTION REQ'D |





LOREN COOK CO.

MANUFACTURERS OF AIR MOVING EQUIPMENT
SPRINGFIELD, MISSOURI

ACRU/VCR/ACSC/ACW
POWER VENTILATOR
HURRICANE RATED

| SIZE | DRAWING NO. | REV. |
|------|-------------|------|
| В | SD080717-12 | G |





SECTION A-A

PRODUCT REVISED
as complying with the Florida
Building Code
NOA-No. 23-0815.03

Expiration Date 11/13/2028

By Miami-Dade Product Control

90-100 EXTRA DEEP 13-7/16 3-9/16 2-7/16 10 13-7/16 7-3/4 3-9/16 2-7/16 90-100 10-5/8 7-1/2 3-1/4 1-7/8 70 EXTRA DEEP 10-5/8 6-1/23-1/470 1-7/8 В С UNIT D Α

DIRECT DRIVE

DIM

DIM

DIM

DIM

SIZE

JERRY TRAVIS MILLER- ENGINEER
FLORIDA LICENSE #89925
FLORIDA STATE CERTIFICATE
OF AUTHORITY #RY34386
ALUMINUM



ALUMINUM: SY MIN=17KSI

| | 1 1411111 171131 | 141. | / LOWINGO | |
|-----|---------------------|---------|--------------|----|
| | O ALUM .064 THICK | 100-0 | MAT'L 1 | M |
| | 05/05/14 | BFS | DRAWN | |
| | SHEET 6 OF 12 | BFS | DESIGNER | D |
| | SCALE DRAWING | NOT S | DO | |
| _ A | SS OTHERWISE NOTED | S UNLES | TOLERANCE | |
| Ρ | FRACTIONAL | | DECIMAL | |
| ы | <u>≤</u> 12"=±1/16" | | .XX=±.063 | |
| 11 | >12" THRU 96"=±1/8" | l l | .XXX=±.010 | |
| S | 96" THRU 144"=±1/4" | ' >9 | .XXXX=±.001" | .X |
| | >144"=+3/8" | _ | | |

(NC)=NO INSPECTION REQ'D

| 1 | > | |
|---|---------------------------------------|---|
| ı | -1/1 | |
| ı | \\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\ | _ |
| ı | | |
| ı | 14/NAV 1 | |
| ı | | _ |
| | | |

LOREN COOK CO.

MANUFACTURERS OF AIR MOVING EQUIPMENT


SPRINGFIELD, MISSOURI

ACRU/VCR/ACSC/ACW POWER VENTILATOR

HURRICANE RATED

SIZE DRAWING NO. REV.

B SD080717-12 G



| 300 | 14-3/4 | 52 | 31-3/8 | 19-13/16 | 0.080 | 54 |
|---------|--------|--------|--------|----------|-------|--------|
| 270 | 12-1/4 | 47 | 28-3/8 | 15-11/32 | 0.080 | 49 |
| 245 | 12-1/4 | 47 | 25-7/8 | 15-11/32 | 0.080 | 49 |
| 210-225 | 11 | 43 | 23-3/8 | 14-5/16 | 0.080 | 45 |
| 180-195 | 10-3/8 | 37-1/4 | 19-3/8 | 12-1/2 | 0.080 | 39-1/4 |
| 150-165 | 9-1/2 | 32-1/2 | 15-7/8 | 10-9/16 | 0.064 | 34-1/2 |
| 120-135 | 8-1/4 | 28 | 12-7/8 | 8-3/4 | 0.064 | 30 |
| 100 | 5-7/16 | 23 | 10-1/8 | 7-5/16 | 0.064 | 25 |
| UNIT | DIM | DIM | DIM | DIM | DIM | DIM |
| SIZE | Α | В | С | D | E | F |

Expiration Date 11/13/2028

By Miami-Dade Product Control

JERRY TRAVIS MILLER- ENGINEER
FLORIDA LICENSE #89925
FLORIDA STATE CERTIFICATE
OF AUTHORITY #RY34386

No 89925

STATE OF

ALUMINUM: SY MIN=17KSI

| | | | | _ |
|---------|----|--------|----------------|---|
| MAT'L | 30 | 003-0 | ALUM "E" THICK | |
| DRAWN | I | BFS | 05/05/14 | |
| DESIGNE | R | BFS | SHEET 7 OF 12 | |
| | DO | NOT SO | CALE DRAWING | r |

DO NOT SCALE DRAWING

TOLERANCES UNLESS OTHERWISE NOTED

DECIMAL

YV-+ 063"

FRACTIONAL

YV-+ 063"

C12"=+1/16'



LOREN COOK CO.


MANUFACTURERS OF AIR MOVING EQUIPMENT

SPRINGFIELD, MISSOURI

ACRU/VCR/ACSC/ACW POWER VENTILATOR HURRICANE RATED

SIZE DRAWING NO. REV.

B SD080717-12 G



| 300 | 1 | 7 | 3/8-16 | LOWER | 8 |
|-------------------|-----|-------|---------|----------|----------|
| 270 | 1 | 6 1/8 | 3/8-16 | LOWER | 8 |
| 245 | 1 | 6 1/8 | 3/8-16 | LOWER | 4 |
| 225 | 3/4 | 4 7/8 | 5/16-18 | LOWER | 4 |
| 210 | 3/4 | 4 7/8 | 5/16-18 | LOWER | 4 |
| 195 | 3/4 | 4 1/2 | 5/16-18 | LOWER | 4 |
| 180 | 3/4 | 4 1/2 | 5/16-18 | LOWER | 4 |
| 165 | 3/4 | 3 1/8 | 5/16-18 | LOWER | 4 |
| 150 | 3/4 | 3 1/8 | 5/16-18 | LOWER | 4 |
| 135 | 3/4 | 2 1/4 | 5/16-18 | LOWER | 4 |
| 120 | 3/4 | 2 1/4 | 5/16-18 | LOWER | 4 |
| 70-100 | 3/4 | 2 1/2 | 5/16-18 | LOWER | 4 |
| UNIT | А | В | С | POST | POST |
| SIZE | DIM | DIM | DIM | LOCATION | QUANTITY |
| ACRU/VCR/ACSC/ACW | | | | | |

Expiration Date <u>1</u>1/13/2028

Stun Miami-Dade Product Control JERRY TRAVIS MILLER- ENGINEER FLORIDA LICENSE #89925 FLORIDA STATE CERTIFICATE



ALUMINUM: SY MIN=35KSI

| | MAT'L | ØA 6005-T6 OR 6105-T5 | | | | | |
|---|----------------------|-----------------------|-------|-------------------|--|--|--|
| | DRAWN | | BFS | 05/05/14 | | | |
| | DESIGNER | | BFS | SHEET 8 OF 12 | | | |
| Ξ | DO NOT SCALE DRAWING | | | | | | |
| = | TOLERAI | NCES | UNLES | S OTHERWISE NOTED | | | |
| | DECIMAL EDACTIONAL | | | | | | |

≤12"=±1/16" >12" THRU 96"=±1/8" >96" THRU 144"=±1/4" .XX=±.063" .XXX=±.010" .XXXX=±.001" >144"=±3/8" ANGULAR ±2*


(NC)=NO INSPECTION REQ'D

| • | \square |
|---|-----------|
| | |
| • | |
| | |

LOREN COOK CO. MANUFACTURERS OF AIR MOVING EQUIPMENT SPRINGFIELD, MISSOURI

ACRU/VCR/ACSC/ACW POWER VENTILATOR HURRICANE RATED SIZE DRAWING NO.

REV. SD080717-12



225 17-1/4 3-1/2 22 3 30 .080 210 16-1/2 3-1/2 20-15/16 3 30 .080 14-1/8 3 3 30 .080 195 19 13-1/2 1-1/23 30 180 16-1/2 .080 165 11-7/82-1/22 24 .064 16 2 150 10 - 3/42-1/215 24 .064 2 9-3/8 2 13 20 .064 135 2 120 8-9/16 2 12 20 .064 UNIT В С D F Α SIZE DIM DIM DIM DIM DIM DIM



PRODUCT REVISED
as complying with the Florida
Building Code
NOA-No. 23-0815.03

Expiration Date 11/13/2028

By Miami-Dade Product Control


ALUMINUM: SY MIN=17KSI

| MAT'L | 30 | 3003-H14 ALUM. "F" GA. | | | |
|--------------|------------|------------------------|----------------------|--|--|
| DRAWN | DRAWN | | 05/05/14 | | |
| DESIGNE | DESIGNER | | SHEET 9 OF 12 | | |
| | DO | NOT S | CALE DRAWING | | |
| TOLERA | NCES | UNLES | S OTHERWISE NOTED | | |
| <u>DECIM</u> | DECIMAL | | FRACTIONAL | | |
| .xx=±. | .XX=±.063" | | ≤12"=±1/16" | | |
| .XXX=±.010" | | | >12" THRU 96"=±1/8" | | |
| .XXXX=±.001" | | >9 | >96" THRU 144"=±1/4" | | |
| ANGULAR | | | >144"=±3/8" | | |
| ±2° | | (NC) | =NO INSPECTION REQ'D | | |


LOREN COOK CO.

MANUFACTURERS OF AIR MOVING EQUIPMENT
SPRINGFIELD, MISSOURI

| _ | | | | | | | |
|---|-------------------|---------------|---|--|--|--|--|
| | ACRU/VCR/ACSC/ACW | | | | | | |
| | POW | ER VENTILATOR | | | | | |
| | HUR | RICANE RATED | | | | | |
| | SIZE | DRAWING NO. | - | | | | |
| | В | SD080717-12 | | | | | |







Expiration Date 11/13/2028

By Miami-Dade Product Control

| 300 | 36 | 3 | .080 |
|------|----------|-----|------|
| 270 | 36 | 3 | .080 |
| 245 | 30 | 3 | .080 |
| UNIT | А | В | С |
| SIZE | T-SQUARE | DIM | DIM |



JERRY TRAVIS MILLER- ENGINEER

ALUMINUM: SY MIN=17KSI

| | MAT'L | 3 | 003-H | I14 AL. "C" THICK | Г |
|----|----------------------|---|-------|-------------------|---|
| | DRAWN | | BFS | 05/05/14 | |
| | DESIGNE | R | BFS | SHEET 10 OF 12 | |
| Y. | DO NOT SCALE DRAWING | | | | |


| TOLERANCES | JNLESS OTHERWISE NOTED |
|-------------|--------------------------|
| DECIMAL | FRACTIONAL |
| .XX=±.063" | <u>≤</u> 12"=±1/16" |
| .XXX=±.010" | >12" THRU 96"=±1/8" |
| XXXX=±.001" | >96" THRU 144"=±1/4" |
| ANGULAR | >144"=±3/8" |
| ±2° | (NC)=NO INSPECTION REQ'D |

| | _ |
|-----|---|
| 1/0 | ® |

Loren Cook Co. MANUFACTURERS OF AIR MOVING EQUIPMENT SPRINGFIELD, MISSOURI

ACRU/VCR/ACSC/ACW POWER VENTILATOR HURRICANE RATED


DRAWING NO. REV. SD080171-12



| WALL MOUNT ACRU/VCR FASTENER TABLE 1 | | | | | |
|--------------------------------------|-----------------------|--------------------------------|--|--|--|
| | | MINIMUM NUMBER OF FASTENERS | | | |
| | MINIMUM NUMBER OF | PER SIDE TO ATTACH CURB TO | | | |
| UNIT SIZE | FASTENERS PER SIDE TO | WALL STRUCTURE | | | |
| | ATTACH UNIT TO CURB | 5/16 LAG OR OR 5/16-18 GRADE 2 | | | |
| | | HEX BOLT | | | |
| 70 | 5 | 5 | | | |
| 80 | 5 | 5 | | | |
| 90 | 5 | 5 | | | |
| 100 | 5 | 5 | | | |
| 120 | 5 | 6 | | | |
| 135 | 5 | 6 | | | |
| 150 | 6 | 7 | | | |
| 165 | 6 | 7 | | | |
| 180 | 8 | 8 | | | |
| 195 | 8 | 8 | | | |
| 210 | 8 | 9 | | | |
| 225 | 8 | 9 | | | |
| 245 | 8 | 10 | | | |
| 270 | 9 | 10 | | | |
| 300 | 9 | 14 | | | |


| ACW FASTENER TABLE 2 WALL MOUNT |
|---------------------------------|
|---------------------------------|

| UNIT SIZE | BOLT SIZE | NUMBER OF BOLTS IN | | | |
|-----------|-----------|--------------------|--|--|--|
| UNIT SIZE | BOLT SIZE | ROUND WALL BASE | | | |
| 70 | 3/8 | 4 | | | |
| 90 | 3/8 | 4 | | | |
| 100 | 3/8 | 4 | | | |
| 101 | 3/8 | 4 | | | |
| 120 | 3/8 | 4 | | | |
| 135 | 3/8 | 4 | | | |
| 150 | 3/8 | 8 | | | |
| 165 | 3/8 | 8 | | | |
| 180 | 3/8 | 8 | | | |
| 195 | 3/8 | 8 | | | |
| 210 | 3/8 | 8 | | | |
| 225 | 3/8 | 8 | | | |
| 245 | 3/8 | 8 | | | |



ACRU SIZE 300 SHOWN NOTES:

- 1. THE ACRU/VCR POWER VENTILATOR SHALL BE ATTACHED TO THE CURB WITH ONE OF THE FOLLOWING METHODS INSTALLED ON ALL FOUR SIDES OF THE CURB CAP. THE FASTENER SHALL BE 2" FROM EACH CORNER OF THE FAN BASE. THE DISTANCE BETWEEN FASTENERS SHALL BE 5-1/2" OR LESS. THE QUANTITY OF FASTENERS INTO EACH CURB SIDE SHALL EQUAL OR EXCEED THE QUANTITY SHOWN IN THE FASTENER TABLE 1.
 - A) #12 X 2" HEX WASHER HEAD SELF-DRILLING SCREW
 - B) ALTERNATE FASTENERS- .25" HEX HEAD BOLT AND WASHER WITH COMPANION NUT INSTALLED ON THE INTERIOR OF THE CURB.
- 2. THE WALL CURB SHALL BE FASTENED TO THE WALL STRUCTURE USING THREADED FASTENERS IN THE QUANTITY INDICATED IN THE TABLE 1 ON SIDE OF THE CURB. THE MINIMUM NOMINAL DIAMETER OF THE THREADED FASTENERS SHALL BE 5/16" (5/16 LAG BOLT INTO WOOD OR 5/16-18 GRADE 2 BOLT INTO 1/8" STEEL) AND THESE FASTENERS SHALL BE INSTALLED AND TIGHTENED APPROPRIATE FOR THE WALL STRUCTURE.
- 3. THE ACW POWER VENTILATOR SHALL BE ATTACHED TO THE WALL STRUCTURE USING THE SIZE AND QUANTITY OF BOLTS INDICATED IN THE ACW FASTENER TABLE 2. THESE FASTENERS (3/8 LAG OR 3/8-16 GRADE 2 BOLT) SHALL BE INSTALLED WITH THE APPROPRIATE WASHER AND TIGHTENED AS REQUIRED FOR THE WALL STRUCTURE.
- 4. ALL FASTENERS ARE TO BE HIGH QUALITY CORROSION RESISTANT STEEL OR STAINLESS STEEL.



ACW SIZE 245 SHOWN PRODUCT REVISED
as complying with the Florida
Building Code
NOA-No. 23-0815.03

Expiration Date 11/13/2028

By Miami-Dade Product Control



WALL MOUNT

| DRAWN ACCEPTED BY | | - | | | п | Loren C | 700V | | |
|--|--|----------------------------|--|----------------------|----|-------------|-----------------------|------|--|
| | | AGL | | 7/13/2017 | | | MANUFACTURERS OF | | |
| | | BF | S | SHEET 12 OF 12 | | | SPRINGFIELD, MISSOURI | | |
| DO NOT SCALE DRAWING | | | ACRU/VCR/ACSC/ACW | | | | | | |
| TOLERANCES UNLESS OTHERWISE NOTED | | | OTHERWISE NOTED | - ACKO/VCK/ACSC/ACVV | | | | | |
| DECIMAL .XX = ± .063" .XXX = ± .010" .XXXX = ± .010" .XXXX = ± .001" ANGULAR ± 2° | | FRACTIONAL | | POW | ER | VENTILATO |)R | | |
| | | 10" | ≤12" = ± 1/16" >12" THRU 96" = ± 1/8" >96 THRU 144" = ± 1/4" >144" = ± 3/8" | HURRICANE RATED | | | | | |
| | | J I | | SIZE | | DRAWING NO. | | REV | |
| | | : | | - 144 - 1370 | | | CD000747 | 7 40 | |
| | | (NC) = NO INSPECTION REQ'D | | B | | SD080717 | -12 | G | |

4

3

2

1