



DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)
BOARD AND CODE ADMINISTRATION DIVISION

MIAMI-DADE COUNTY
PRODUCT CONTROL SECTION

11805 SW 26 Street, Room 208
Miami, Florida 33175-2474
T (786) 315-2590 F (786) 315-2599

www.miamidade.gov/economy

NOTICE OF ACCEPTANCE (NOA)

Nucor Corp. (Nucor Buildings Group)
305 Industrial Parkway
Waterloo, IN 46793

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER- Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein and has been designed to comply with the High Velocity Hurricane Zone of the Florida Building Code.

DESCRIPTION: 0.024" (min.) Structural Loc-Seam 360 Steel Roof Panel

APPROVAL DOCUMENT: Drawing No. MD-LOC, titled "Loc Seam 360 roof Panels", sheets 1 through 6 of 6, prepared by Bala Sockalingam, P.E., last revision #1 dated July 21, 2023, signed and sealed by Bala Sockalingam, P.E. on July 21, 2023, bearing the Miami-Dade County Product Control Revision stamp with the Notice of Acceptance number and the expiration date by the Miami-Dade County Product Control Section.

MISSILE IMPACT RATING: Large and Small Missile Impact Resistant

LABELING: Each panel shall bear a permanent label with the manufacturer's name or logo, Eufaula, AL or Swansea, SC and the following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA **revises** NOA # **22-1019.01** and consists of this page 1, evidence submitted pages E-1 and E-2 as well as approval document mentioned above.

The submitted documentation was reviewed by **Helmy A. Makar, P.E., M.S.**



Helmy A. Makar

NOA No. 23-0821.12
Expiration Date: 04/13/2028
Approval Date: 10/05/2023

Nucor Corp. (Nucor Buildings Group)

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA #22-1019.01

A. DRAWINGS

1. *Drawing No. MD-LOC, titled "Loc Seam 360 roof Panels", sheets 1 through 6 of 6, prepared by Bala Sockalingam, P.E., last revision dated September 07, 2022, signed and sealed by Bala Sockalingam, P.E. on March 01, 2023.*

B. TESTS

1. *Test report on Accelerated Weathering Testing of Coating 2000 hours per ASTM G152, prepared by PPG Industrial Coil Coatings.*
2. *Test report on Salt Spray Testing of Coating 1000 hours per ASTM B117-95, prepared by PPG Industrial Coil Coatings.*
3. *Test report for Uniform Static Air Pressure on 24 ga. Loc-Seam 360 Roof Panel, prepared by Force Engineering & Testing, per TAS 125-03 per ASTM E 1592-05, Report No. 534-0047T-22A-D, dated September 12, 2022, signed and sealed by Johnathan Green, P.E.*
4. *Susceptibility to leakage test in accordance with FM 4471, Appendix G on 24 ga. Loc-Seam 360 Roof Panel, prepared by FET, Report No. T272-22, dated August 09, 2022, signed and sealed by Daniel G. Farabaugh, P.E.*
5. *Wind Driven Rain Test in accordance with Miami-Dade County Protocol TAS 100-95 on 24 ga. Loc-Seam 360 Roof Panel, prepared by FET, Report No. T274-22, dated August 15, 2022, signed and sealed by Daniel G. Farabaugh, P.E.*
6. *Impact test per TAS 201-94, test report #534-0047T-22E, dated September 12, 2022, signed and sealed by Johnathan Green, P.E.*

C. CALCULATIONS

1. *Calculations titled "Loc-Seam 360, 24 ga. Roof Panel Calculations", dated March 01, 2023, pages 1 through 3 of 3, prepared by Bala Sockalingam, P.E., signed and sealed by Bala Sockalingam, P.E.*

D. QUALITY ASSURANCE


1. *By Miami Dade County Department of Regulatory and Economic Resources*

E. MATERIAL CERTIFICATIONS

1. *None.*

F. STATEMENTS

1. *Florida Building Code, 2020 Edition, compliance letter, dated September 21, 2022, prepared by Bala Sockalingam, P.E., signed and sealed by Bala Sockalingam P.E. on September 21, 2022*



Helmy A. Makar, P.E., M.S.
Product Control Section Supervisor
NOA No. 23-0821.12
Expiration Date: 04/13/2028
Approval Date: 10/05/2023

Nucor Corp. (Nucor Buildings Group)

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

2. NEW EVIDENCE SUBMITTED

A. DRAWINGS

1. *Drawing No. MD-LOC, titled "Loc Seam 360 roof Panels", sheets 1 through 6 of 6, prepared by Bala Sockalingam, P.E., last revision #1 dated July 21, 2023, signed and sealed by Bala Sockalingam, P.E. on July 21, 2023.*

B. TESTS

1. *None.*

C. CALCULATIONS

1. *None.*

D. QUALITY ASSURANCE

1. *By Miami Dade County Department of Regulatory and Economic Resources*

E. MATERIAL CERTIFICATIONS

1. *None.*

F. STATEMENTS

1. *Florida Building Code, 2020 Edition and 2023 Edition, compliance letter, dated July 21, 2023, prepared by Bala Sockalingam, P.E., signed and sealed by Bala Sockalingam P.E. on July 21, 2023.*




Helmy A. Makar, P.E., M.S.
Product Control Section Supervisor

NOA No. 23-0821.12

Expiration Date: 04/13/2028



Approval Date: 10/05/2023



NOTES:


- 1) MATERIAL IS ASTM A-792
AZ55 FOR GALVALUME
AZ50 FOR PAINTED
- 2) SWAGE IS THE PROCESS OF CRIMPING PANEL TO NARROW IT ALLOWING IT TO NEST INSIDE ANOTHER PANEL
- 3) SWAGE & DIMPLES ARE ON THE LOW SIDE OF THE UP-SLOPE PANEL ONLY.
- 4) PANEL COLORS: ALL STANDARD PVDF COLORS & GM.

NO.		REVISION		MADE CKD. DATE	
LOC SEAM 360 ROOF PANEL					
<p>BALA SOCKALINGAM LICENSE No. 62240 STATE OF FLORIDA PROFESSIONAL ENGINEER</p>					
ENGINEER'S NAME: BALA SOCKALINGAM PH. D., P.E.		ENGINEER'S STATE REGISTRATION NUMBER: 62240		<p>NUCOR CORP 305 INDUSTRIAL PARKWAY WATERLOO, IN 46793 PHONE: (260) 837-7891 FAX (260) 837-7884</p>	
DATE 09-01-22		DATE 09-07-22		<p>NUCOR BUILDINGS GROUP DRAWING #: MD-LOC SEAM 360 24 GA. Pg. 2 of 6</p>	
SCALE: NOT TO SCALE		DRAWN BY: EGB		CHECKED BY: SLF	
<p>For Dade County Office Use Only</p> <p>PRODUCT REVISED as complying with the Florida Building Code Acceptance No. 23-0821.12 Expiration Date 04/13/2028 By: <i>H. G. A. Miller</i> Miami Dade Product Control</p>					



PART "A"


PART A MATERIAL = G90 GALVANIZED, GRADE 50
50,000 PSI ASTM A653
THICKNESS = 0.048" ± 0.002"





EXTRUDED HOLE TO REST ON PURLIN WHEN INSTALLED. EXTRUSION WILL BE SUFFICIENT TO HOLD MATERIAL APART TO AVOID BINDING WHEN CLIPS ARE SCREWED DOWN.

SECTION "A-A"

NOTES:
ALL DIMENSIONS ± .020 UNLESS NOTED
WGT. = 0.238#




PART "B" PERFORATIONS




PART "B"

PART B MATERIAL = G90 GALVANIZED, GRADE 50
50,000 PSI ASTM A653
THICKNESS = 0.026" ± 0.002"




CLIP ASSEMBLY



NO.	REVISION	MADE	CK'D.	DATE


LOC SEAM 360 ROOF PANEL





ENGINEER'S NAME: BALA SOCKALINGAM PH. D., P.E.	ENGINEER'S STATE REGISTRATION NUMBER: 41467
DATE 09-01-22	DATE 09-07-22
DRAWN BY: EGB	CHECKED BY: SLF
NUCOR CORP NUCOR BUILDINGS GROUP 305 INDUSTRIAL PARKWAY WATERLOO, IN 46793 PHONE: (260) 837-7891 FAX: (260) 837-7884	
DRAWING #: MD-LOC SEAM 360 24 GA. Pg. 3 of 6	

For Dade County Office Use Only

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 23-0821.12
Expiration Date 04/13/2028
By Hely A. M...
Miami Dade Product Control



- NOTE: ALL AREAS ON ALUMINUM COATED PANELS THAT REQUIRE MASTIC SHOULD BE WIPED CLEAN WITH A MILD ALL PURPOSE DETERGENT CLEANER BEFORE MASTIC APPLICATION.
- 1) WHEN ENDLAPS ARE REQUIRED THE LOWER 6 INCHES OF THE UPPER PANEL ARE SWAGED, WHICH ALLOWS FOR A BETTER LAP ON TO THE LOWER RECEIVING PANEL. THIS LAP WILL OCCUR APPROXIMATELY 12 INCHES UPSLOPE FROM A PURLIN OR JOIST RUN.
 - 2) PRIOR TO SETTING THE SWAGED PANEL, INSTALL THE BACKUP PLATE ONTO THE LOWER RECEIVING PANEL AS SHOWN.
 - 3) NEXT INSTALL A PIECE OF PRE-CUT TAPE MASTIC ACROSS THE WIDTH OF THE UNDERSIDE OF THE SWAGED PANEL BEGINNING AND ENDING AT THE VERTICAL SEAMS (LEGS). ALSO APPLY TUBE CAULK ON THE MALE AND FEMALE RIBS OF THE SWAGED PANEL AS SHOWN IN DETAIL ABOVE.
 - 4) NEXT APPLY TUBE CAULK ALONG BOTH PANEL RIBS OF THE LOWER RECEIVING PANEL AS SHOWN IN THE ENDLAP CAULKING DETAIL.
 - 5) INSTALL THE UPPER SWAGED PANEL. BOW PANEL IN THE MIDDLE DURING INSTALLATION TO AVOID SWIPING CAULK FROM THE VERTICAL LEGS OF THE PANEL AT THE ENDLAP.
 - 6) NEXT SECURE THE LAP WITH (5) ROOF FASTENERS IN THE PRE-DIMPLED LOCATIONS.
 - 7) HAND SEAM PANEL RIBS TOGETHER AT ENDLAP PRIOR TO MECHANICALLY SEAMING.



NO.		MADE		CKD.		DATE	
REVISION							

LOC SEAM 360 ROOF PANEL

BALA SOCKALINGAM
LICENSE
No. 62240
STATE OF FLORIDA
PROFESSIONAL ENGINEER


ENGINEER'S NAME: BALA SOCKALINGAM PH. D., P.E.
DATE: 09-01-22
SCALE: NOT TO SCALE
DRAWN BY: EGB
CHECKED BY: SLF
ENGINEER'S STATE REGISTRATION NUMBER: 62240

305 INDUSTRIAL PARKWAY
WATERLOO, IN 46793 PHONE: (260) 837-7891 FAX: (260) 837-7884
NUCOR CORP
NUCOR BUILDINGS GROUP


REVISION NUMBER: 0
DRAWING #: MD-LOC SEAM 360 24 GA. Pg. 4 of 6

For Dade County Office Use Only



PRODUCT REVISED
as complying with the Florida Building Code
Acceptance No. 23-0821.12
Expiration Date 04/13/2028
By: H. G. A. M. W.
Miami Dade Product Control




BASIC EAVE DETAIL
BASIC EAVE DETAIL w/ WALL PANELS
SEE WALL SHEETING ERECTION NOTES FOR WALL PANEL FASTENER LOCATIONS




EAVE GUTTER DETAIL
EAVE GUTTER DETAIL w/ WALL PANELS
SEE WALL SHEETING ERECTION NOTES FOR WALL PANEL FASTENER LOCATIONS



RAKE SCULPTURED DETAIL
RAKE SCULPTURED DETAIL w/ WALL PANELS
SEE WALL SHEETING ERECTION NOTES FOR WALL PANEL FASTENER LOCATIONS



RIDGE TRIM DETAIL
RIDGE TRIM DETAIL



HIGH EAVE SCULPTURED DETAIL
HIGH EAVE SCULPTURED DETAIL w/ WALL PANELS
SEE WALL SHEETING ERECTION NOTES FOR WALL PANEL FASTENER LOCATIONS

NO.		REVISION		MADE		CK'D.		DATE	

LOC SEAM 360 ROOF PANEL

BALA SOCKALINGAM
LICENSE
No. 62240
STATE OF FLORIDA
PROFESSIONAL ENGINEER


ENGINEER'S NAME:	BALA SOCKALINGAM PH. D., P.E.
ENGINEER'S STATE REGISTRATION NUMBER:	62240
DATE	09-01-22
SCALE: NOT TO SCALE	
DRAWN BY:	ECB
CHECKED BY:	SLF
<p>NUCOR CORP 305 INDUSTRIAL PARKWAY WATERLOO, IN 46793 PHONE: (260) 837-7891 FAX (260) 837-7884</p> <p>NUCOR BUILDINGS GROUP</p>	
DRAWING #:	MD-LOC SEAM 360 24 GA. Pg. 5 of 6
REVISION NUMBER	0

For Dade County Office Use Only

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 23-0821.12
Expiration Date 04/13/2028
By Hedy A. Mabin
Miami Dade Product Control


VALLEY CONDITION ERECTION NOTES

- 1) INSTALL THE EAVE ANGLES AND EAVE PLATES AS SHOWN AT RIGHT. CAULK THE EAVE PLATES AT THE CORNER WITH TUBE CAULK.
- 2) AFTER THE INSTALLATION OF THE EAVE ANGLES AND EAVE PLATES, AND BEFORE THE ROOF PANEL INSTALLATION, START AT THE LOW EAVE AND PLACE THE INSULATION PAN IN THE VALLEY AND FASTEN WITH (1) FASTENER AT EACH PURLIN. FIELD MITER THE INSULATION PAN AT THE EAVE PLATE. LAP THE INSULATION PANS 2" AND FASTEN WITH (4) FASTENERS.
- 3) INSTALL THE INSULATION OVER THE INSULATION PAN. FASTEN WITH SCREWS AND INSULATION WASHERS AS REQUIRED.
- 4) BEFORE ROOF PANEL INSTALLATION, START AT THE LOW EAVE AND PLACE THE HAT CHANNEL SECTIONS ON BOTH SIDES OF THE VALLEY, 1'-8" FROM THE CENTERLINE AS SHOWN. FASTEN TO EACH PURLIN WITH (2) FASTENERS.
- 5) CENTER THE VALLEY PLATE OVER THE HAT SECTIONS. AT THE EAVE & RIDGE, EXTEND THE PLATE TO THE EDGE OF THE ROOF PANEL, FIELD CUTTING AS REQUIRED. FASTEN VALLEY PLATE TO HAT CHANNEL INSIDE PANEL RIB WITH (1) FASTENER AS SHOWN BELOW. LAP THE VALLEY PLATE 2" & FASTEN WITH (2) FASTENERS.
- 6) PLACE THE DIVERTER FLASH OVER THE VALLEY PLATE AND TEMPORARILY FASTEN WITH (1) SCREW AT THE OUTSIDE CORNERS OF THE VALLEY PLATE. (DO NOT USE THE VALLEY AS A WALKWAY OR A WORK PLATFORM).
- 7) INSTALL 2 1/4" TAPE MASTIC ON THE DIVERTER FLASH 7 1/2" FROM THE CENTER OF THE PLATE AS SHOWN. DO NOT REMOVE PAPER BACKING UNTIL READY TO SET PANEL. ALSO APPLY A BEAD OF BUTYL TUBE CAULK FOR THE FLAT OF THE PANEL ALONG THE TAPE MASTIC.
- 8) INSTALL THE ROOF PANELS - CUTTING ENDS AT THE ANGLE REQUIRED. CUT PANELS 7" FROM THE CENTER OF THE VALLEY PLATE. (NOTE: KEEP METAL SHAVINGS OUT OF MASTIC AND PANEL SIDELAP.) REMOVE TEMPORARY DIVERTER FASTENER IF NEEDED.
- 9) BEFORE THE NEXT PANEL IS INSTALLED, APPLY A 3" PIECE OF TAPE MASTIC AND A BEAD OF TUBE CAULK TO THE MALE SIDE OF THE PANEL FROM THE LOW END OF THE PANEL UP 12" TO ENSURE WEATHERTIGHTNESS, AS SHOWN IN THE SEALANT DETAIL.
- 10) FASTEN WITH SCREWS, 3" O.C. OVER THE TAPE MASTIC, (8 1/4" FROM THE CENTER OF THE DIVERTER FLASH TO THE CENTER OF THE FASTENERS). TAKE SPECIAL CARE AT THIS POINT TO MAINTAIN PANEL MODULARITY.




INSULATION PAN, EAVE PLATE, AND HAT CHANNEL DETAIL AT LOW EAVE CORNER

SEE ERECTION NOTES 1, 2, 3 AND 4




VALLEY PLATE AND DIVERTER FLASH DETAIL AT LOW EAVE CORNER

SEE ERECTION NOTES 5, 6 AND 7




LOC SEAM 360 VALLEY FINAL ASSEMBLY DETAIL




SEALANT DETAIL AT VALLEY

SEE ERECTION NOTES 5, 6, 7 AND 8



SEALANT DETAIL AT LOW END OF PANELS


SEE ERECTION NOTE 9



ROOF PANEL CUT DETAIL

NO.	REVISION	MADE	CK'D	DATE

LOC SEAM 360 ROOF PANEL



ENGINEER'S NAME:	BALA SOCKALINGAM PH. D., P.E.
ENGINEER'S STATE REGISTRATION NUMBER:	62240
DATE	09-01-22
SCALE: NOT TO SCALE	09-07-22
DRAWN BY:	ECB
CHECKED BY:	SLF
DATE	09-07-22
FOR Dade County Office Use Only	

NUCOR CORP
NUCOR BUILDINGS GROUP
305 INDUSTRIAL PARKWAY
WATERLOO, IN 46793 PHONE: (260) 837-7891 FAX: (260) 837-7884

DRAWING #: MD-LOC SEAM 360 24 GA. Pg. 6 of 6
REVISION NUMBER 0

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 23-9821-12
Expiration Date 04/13/2028
By H. G. A. M. M.
Miami Dade Product Control