



DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)
BOARD AND CODE ADMINISTRATION DIVISION

NOTICE OF ACCEPTANCE (NOA)

MIAMI-DADE COUNTY
PRODUCT CONTROL SECTION
11805 SW 26 Street, Room 208
Miami, Florida 33175-2474
T (786) 315-2590 F (786) 315-2599
www.miamidade.gov/building

Eurotech Industries, Inc.
4201 NE 12th Terrace
Ft. Lauderdale, FL 33334

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER-Product Control Section to be used in Miami-Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami-Dade County) and/ or the AHJ (in areas other than Miami-Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Outswing Aluminum Casement Window – L.M.I.

APPROVAL DOCUMENT: Drawing No. **W03-80**, titled "Aluminum Casement Window (L.M.I.)", sheets 1 through 5 of 5, dated 09/05/03, with revision **J** dated 06/15/23, prepared by Al-Farooq Corporation, signed and sealed by Jalal Farooq, P.E., bearing the Miami-Dade County Product Control Renewal stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Section.

MISSILE IMPACT RATING: Large and Small Missile Impact Resistant

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state, model/series, and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/ or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.


ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA **renews NOA No. 23-0622.06** and consists of this page 1 and evidence pages E-1, E-2 and E-3, as well as approval document mentioned above.

The submitted documentation was reviewed by **Manuel Perez, P.E.**




2/29/24

NOA No. 24-0205.06
Expiration Date: February 05, 2025
Approval Date: March 07, 2024
Page 1

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA's

A. DRAWINGS

1. Manufacturer's die drawings and sections.
(Submitted under NOA No. 06-1019.03)
2. Drawing No. **W03-80**, titled "Aluminum Casement Window (L.M.I.)", sheets 1 through 5 of 5, dated 09/05/03, with revision **J** dated 06/15/23, prepared by Al-Farooq Corporation, signed and sealed by Jalal Farooq, P.E.
(Submitted under NOA No. 23-0622.06)

B. TESTS


1. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94
2) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94
3) Water Resistance Test, per FBC, TAS 202-94
4) Forced Entry Test, per FBC 2411.3.2.1 (b) and TAS 202-94
along with marked-up drawings and installation diagram of aluminum casement windows mulled side-by-side Test Report No. **HETI-03-1315** dated 05/12/03, and of a single aluminum casement window Test Report No. **HETI-03-1317** dated 05/14/03, both prepared by Hurricane Engineering & Testing Inc., signed and sealed by Rafael E. Droz-Seda, P.E.
(Submitted under NOA No. 06-1019.03)
2. Test reports on: 1) Large Missile Impact Test per FBC, TAS 201-94
2) Cyclic Wind Pressure Loading per FBC, TAS 203-94
along with marked-up drawings and installation diagram of aluminum casement windows mulled side-by-side Test Report No. **HETI-03-1829** dated 05/12/03, of a single aluminum casement windows Test Report No. **HETI-03-1822**, dated 01/23/04, both prepared by Hurricane Engineering & Testing Inc., signed and sealed by Rafael E. Droz-Seda, P.E.
(Submitted under NOA No. 06-1019.03)

C. CALCULATIONS

1. Anchor verification calculations, complying with **FBC 7th Edition (2020)**, dated 10/26/20, prepared by Al-Farooq Corporation, signed and sealed by Javad Ahmad, P.E.
(Submitted under NOA No. 21-0113.03)
2. Glazing complies with **ASTM E1300-09**

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER)


Manuel Perez, P.E.
Product Control Examiner
NOA No. 24-0205.06
Expiration Date: February 05, 2025
Approval Date: March 07, 2024

Eurotech Industries, Inc.

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA's (CONTINUED)

E. MATERIAL CERTIFICATIONS


1. Notice of Acceptance No. **22-1116.01** issued to **Kuraray America, Inc.** for their **"SentryGlas® (Clear and White) Glass Interlayers"** dated 12/15/22, expiring on 07/04/28.
2. Notice of Acceptance No. **21-0216.01** issued to **Eastman Chemical Company (MA)** for their **"Saflex PVB Interlayers - Clear and Colored for Glass"** dated 04/29/21, expiring on 05/21/26.

F. STATEMENTS

1. Statement letter of conformance, complying with **FBC 7th Edition (2020)**, with **FBC 8th Edition (2023)** and of no financial interest, dated June 16, 2023, issued by Al-Farooq Corporation, signed and sealed by Jalal Farooq, P.E.
(Submitted under NOA No. 23-0622.06)

G. OTHERS

1. Notice of Acceptance No. **21-0113.03**, issued to Eurotech Industries, Inc., for their Outswing Aluminum Casement Window – L.M.I., approved on 04/08/21 and expiring on 02/05/24.


Manuel Perez, P.E.
Product Control Examiner
NOA No. 24-0205.06

Expiration Date: February 05, 2025
Approval Date: March 07, 2024

Eurotech Industries, Inc.

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

2. NEW EVIDENCE SUBMITTED

A. DRAWINGS

1. None.

B. TESTS

1. None.

C. CALCULATIONS

1. None.

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER)

E. MATERIAL CERTIFICATIONS


1. Notice of Acceptance No. **23-0717.30** issued to **Kuraray America, Inc.** for their “**SentryGlas® (Clear and White) Glass Interlayers**” dated 08/31/23, expiring on 07/04/28.
2. Notice of Acceptance No. **23-0713.18** issued to **Eastman Chemical Company (MA)** for their “**Saflex PVB Interlayers - Clear and Colored for Glass**” dated 08/17/23, expiring on 05/21/26.


F. STATEMENTS

1. Statement letter of conformance, complying with **FBC 8th Edition (2023)** and of no financial interest, dated February 1st, 2024, issued by Al-Farooq Corporation, signed and sealed by Jalal Farooq, P.E.
2. Letter from consultant requesting a 1-year extension to allow time to perform verification test, dated 02/01/24 issued by Al-Farooq Corporation, signed and sealed by Jala Farooq, P.E.
3. Testing agreement letter, dated 01/31/24 between American Test Lab of South Florida (ATL) and Eurotech Industries, Inc., issued by ATL and signed by Tony Porcello, President.

G. OTHERS


1. Notice of Acceptance No. **23-0622.06**, issued to Eurotech Industries, Inc., for their Outswing Aluminum Casement Window – L.M.I., approved on 07/20/23 and expiring on 02/05/24.
2. This is a one-year approval, subjected to successful verification test, the final approval will be issued for a total of 5 years.


Manuel Perez, P.E.
Product Control Examiner
NOA No. 24-0205.06
Expiration Date: February 05, 2025
Approval Date: March 07, 2024




TYPICAL ANCHORS
(1) PER HINGE

TYPICAL ANCHORS
(1) PER HINGE



TYPICAL ANCHORS
(1) PER HINGE




TYPICAL ELEVATIONS


ALUMINUM CASEMENT WINDOW (IMPACT)

DESIGN LOAD RATING FOR THESE WINDOWS TO BE AS PER CHARTS SHOWN ON SHEET 2.

APPROVAL APPLIES TO SINGLE VENT WINDOWS OR DUAL VENT WINDOWS USING INTEGRAL IMPOST.



ALSO SIDE BY SIDE COMBINATIONS OF CASEMENT/CASEMENT OF TWO OR MORE WINDOWS USING APPROVED MULLIONS.



THIS PRODUCT HAS BEEN DESIGNED AND TESTED TO COMPLY WITH THE REQUIREMENTS OF THE 2020 (7TH EDITION)/2023 (8TH EDITION) FLORIDA BUILDING CODE INCLUDING HIGH VELOCITY HURRICANE ZONE (HVHZ).

1BY OR 2BY WOOD BUCKS & BUCK FASTENERS BY OTHERS, MUST BE DESIGNED AND INSTALLED ADEQUATELY TO TRANSFER APPLIED PRODUCT LOADS TO THE BUILDING STRUCTURE.

ANCHORS SHALL BE CORROSION RESISTANT, SPACED AS SHOWN ON DETAILS AND INSTALLED PER MANUF'S INSTRUCTIONS. SPECIFIED EMBEDMENT TO BASE MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO.

A LOAD DURATION INCREASE IS USED IN DESIGN OF ANCHORS INTO WOOD ONLY.

ALL SHIMS TO BE HIGH IMPACT, NON-METALLIC AND NON-COMPRESSIBLE.

MATERIALS INCLUDING BUT NOT LIMITED TO STEEL/METAL SCREWS, THAT COME INTO CONTACT WITH OTHER DISSIMILAR MATERIALS SHALL MEET THE REQUIREMENTS OF THE 2020/2023 FLORIDA BLDG. CODE & ADOPTED STANDARDS.

THIS PRODUCT APPROVAL IS GENERIC AND DOES NOT PROVIDE INFORMATION FOR A SITE SPECIFIC PROJECT, i.e. LIFE SAFETY OF THIS PRODUCT, ADEQUACY OF STRUCTURE RECEIVING THIS PRODUCT AND SEALING AROUND OPENING FOR WATER INFILTRATION RESISTANCE ETC.

CONDITIONS NOT SHOWN IN THIS DRAWING ARE TO BE ANALYZED SEPARATELY, AND TO BE REVIEWED BY BUILDING OFFICIAL.

DESIGN LOADS SHOWN ARE BASED ON 'ALLOWABLE STRESS DESIGN (ASD)'.

PRODUCT RENEWED

As complying with the Florida Building Code

NOA-No. **24-0205.06**

Expiration Date: **02/05/2025**

By: *Manuel Perez*

Miami-Dade Product Control

THESE WINDOWS ARE RATED FOR LARGE & SMALL MISSILE IMPACT. SHUTTERS ARE NOT REQUIRED.

PRODUCT REVISED


As complying with the Florida Building Code

NOA-No. **23-0622.06**

Expiration Date: **02/05/2024**

By: *Manuel Perez*

Miami-Dade Product Control



ALUMINUM CASEMENT WINDOW (L.M.I.)

Eurotech Industries Inc.

4201 N.E. 12th Terrace
Oakland Park, Florida 33334

Tel. (954) 630-9967 Fax. (954) 630-0217

AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
9360 SUNSET DRIVE, SUITE 220
MIAMI, FLORIDA 33173 (C.A.N. 3538)
TEL. (305) 264-8100 FAX. (305) 262-6978

COMP-ANL\W03-80EWD

no	date	by	description
G	12.03.15	REV.	PER PER COMMENTS
H	01.31.18	UPDATED TO	2017 FBC
I	11.05.20	UPDATED TO	2020 FBC
J	06.15.23	UPDATED TO	2023 FBC

date:	09-05-03
scale:	1/2"=1'-0"
dr. by:	TARIQ
chk. by:	


drawing no.

W03-80

sheet 1 of 5

DESIGN LOAD CAPACITY - PSF FOR (X) SIZES					
WINDOW DIMS.		GLASS TYPE 'A'		GLASS TYPE 'B'	
WIDTH	HEIGHT	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)
19-1/8"	26"	75.0	75.0	75.0	90.0
26-1/2"		75.0	75.0	75.0	90.0
37"		75.0	75.0	75.0	90.0
19-1/8"	38-3/8"	75.0	75.0	75.0	90.0
26-1/2"		75.0	75.0	75.0	90.0
37"		75.0	75.0	75.0	90.0
19-1/8"	50-5/8"	75.0	75.0	75.0	90.0
26-1/2"		75.0	75.0	75.0	90.0
37"		75.0	75.0	75.0	90.0
19-1/8"	63"	75.0	75.0	75.0	90.0
26-1/2"		75.0	75.0	75.0	90.0
37"		75.0	75.0	75.0	90.0
19-1/8"	74"	75.0	75.0	75.0	90.0
26-1/2"		75.0	75.0	75.0	90.0
37"		75.0	75.0	75.0	90.0
19-1/8"	78"	75.0	75.0	75.0	90.0
26-1/2"		75.0	75.0	75.0	90.0
19-1/8"	84"	75.0	75.0	75.0	90.0
26-1/2"		67.2	75.0	67.2	90.0
18"	24"	75.0	75.0	75.0	90.0
24"		75.0	75.0	75.0	90.0
30"		75.0	75.0	75.0	90.0
36"		75.0	75.0	75.0	90.0
18"	36"	75.0	75.0	75.0	90.0
24"		75.0	75.0	75.0	90.0
30"		75.0	75.0	75.0	90.0
36"		75.0	75.0	75.0	90.0
18"	48"	75.0	75.0	75.0	90.0
24"		75.0	75.0	75.0	90.0
30"		75.0	75.0	75.0	90.0
36"		75.0	75.0	75.0	90.0
18"	60"	75.0	75.0	75.0	90.0
24"		75.0	75.0	75.0	90.0
30"		75.0	75.0	75.0	90.0
36"		75.0	75.0	75.0	90.0
18"	72"	75.0	75.0	75.0	90.0
24"		75.0	75.0	75.0	90.0
30"		75.0	75.0	75.0	90.0
36"		75.0	75.0	75.0	90.0
18"	80"	75.0	75.0	75.0	90.0
24"		75.0	75.0	75.0	90.0
30"		69.9	75.0	69.9	90.0

NOTE:
GLASS CAPACITIES ON THIS SHEET ARE
BASED ON ASTM E1300-09 (3 SEC. GUSTS)
AND FLORIDA BUILDING COMMISSION
DECLARATORY STATEMENT DCA05-DEC-219




DESIGN LOAD CAPACITY - PSF FOR (XX) SIZES							
WINDOW DIMS.		GLASS TYPE 'A' & 'B'					
		1" MIN. EDGE DIST.				2-1/2" EDGE DIST.	
		2 ANCHOR AT EACH SIDE OF IMPOST		3 ANCHORS AT EACH SIDE OF IMPOST		2 ANCHORS AT EACH SIDE OF IMPOST	
WIDTH	HEIGHT	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)	EXT.(+)	INT.(-)
26-1/2"	26"	75.0	75.0	-	-	75.0	75.0
37"		75.0	75.0	-	-	75.0	75.0
53-1/8"		75.0	75.0	-	-	75.0	75.0
74"		75.0	75.0	-	-	75.0	75.0
26-1/2"	38-3/8"	75.0	75.0	-	-	75.0	75.0
37"		75.0	75.0	-	-	75.0	75.0
53-1/8"		75.0	75.0	-	-	75.0	75.0
74"		75.0	75.0	-	-	75.0	75.0
26-1/2"	50-5/8"	75.0	75.0	-	-	75.0	75.0
37"		75.0	75.0	-	-	75.0	75.0
53-1/8"		75.0	75.0	-	-	75.0	75.0
74"		64.5	64.5	75.0	75.0	75.0	75.0
26-1/2"	63"	75.0	75.0	-	-	75.0	75.0
37"		75.0	75.0	-	-	75.0	75.0
53-1/8"		72.2	72.2	75.0	75.0	75.0	75.0
74"		51.8	51.8	75.0	75.0	75.0	75.0
24"	24"	75.0	75.0	-	-	75.0	75.0
36"		75.0	75.0	-	-	75.0	75.0
48"		75.0	75.0	-	-	75.0	75.0
60"		75.0	75.0	-	-	75.0	75.0
72"		75.0	75.0	-	-	75.0	75.0
24"	36"	75.0	75.0	-	-	75.0	75.0
36"		75.0	75.0	-	-	75.0	75.0
48"		75.0	75.0	-	-	75.0	75.0
60"		75.0	75.0	-	-	75.0	75.0
72"		75.0	75.0	-	-	75.0	75.0
24"	48"	75.0	75.0	-	-	75.0	75.0
36"		75.0	75.0	-	-	75.0	75.0
48"		75.0	75.0	-	-	75.0	75.0
60"		75.0	75.0	-	-	75.0	75.0
72"		69.9	69.9	75.0	75.0	75.0	75.0
24"	60"	75.0	75.0	-	-	75.0	75.0
36"		75.0	75.0	-	-	75.0	75.0
48"		75.0	75.0	-	-	75.0	75.0
60"		67.1	67.1	75.0	75.0	75.0	75.0
72"		55.9	55.9	75.0	75.0	75.0	75.0

PRODUCT RENEWED
As complying with the Florida
Building Code
NOA-No. **24-0205.06**
Expiration Date: **02/05/2025**
By: *Manuel Perez*
Miami-Dade Product Control

PRODUCT REVISED
As complying with the Florida
Building Code
NOA-No. **23-0622.06**
Expiration Date: **02/05/2024**
By: *Manuel Perez*
Miami-Dade Product Control

JUN 10 2023



AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
9360 SUNSET DRIVE, SUITE 220
MIAMI, FLORIDA 33173 (C.A.N. 3538)
TEL. (305) 264-8100 FAX. (305) 262-6978
COMP-ANL\W03-80EWD

ALUMINUM CASEMENT WINDOW (L.M.I.)



Eurotech Industries Inc.
4201 N.E. 12th Terrace
Oakland Park, Florida 33334
Tel. (954) 630-9967 Fax. (954) 630-0217

Revisions:

no	date	by	description
G	12.03.15		REV. PER PER COMMENTS
H	01.31.18		UPDATED TO 2017 FBC
I	11.05.20		UPDATED TO 2020 FBC
J	06.15.23		NO CHANGE THIS SHEET

date: 09-05-03
scale: 1/2" = 1"
dr. by: TARIQ
chk. by:


drawing no.
W03-80
sheet 2 of 5



WOOD BUCKS AND METAL STRUCTURE NOT BY 'EUROTECH' MUST SUSTAIN LOADS IMPOSED BY GLAZING SYSTEM AND TRANSFER THEM TO THE BUILDING STRUCTURE.

SEALANTS:

ALL FRAME AND VENT CORNERS AND INSTALLATION SCREWS SEALED WITH CLEAR/ALUMINUM COLORED SILICONE.



TYPICAL ANCHORS: SEE ELEV. FOR SPACING

- 1/4" DIA. ULTRACON+ BY 'DEWALT'** (Fu=164 KSI, Fy=148 KSI)
 - INTO WOOD STRUCTURES
 - 2" MIN. PENETRATION INTO WOOD (HEAD/SILL/JAMBS)
 - THRU 1BY BUCKS INTO CONC. OR BLOCKS
 - 1-1/4" MIN. EMBED INTO CONCRETE (HEAD/SILL/JAMBS)
 - 1-1/4" MIN. EMBED INTO BLOCKS (JAMBS)
 - DIRECTLY INTO CONCRETE OR BLOCKS
 - 2" MIN. EMBED INTO CONCRETE (HEAD/SILL)
 - 1-1/4" MIN. EMBED INTO CONC. OR BLOCKS (JAMBS)


- 1/4" DIA. TEKS OR SELF-DRILLING SCREWS** (GRADE 5 CRS)
 - INTO METAL STRUCTURES (HEAD/SILL/JAMBS)
 - (3) THREADS MIN. TO EXTEND BEYOND METAL THICKNESS
 - ALUMINUM: 1/8" THK. MIN. (6063-T5 MIN.)
 - STEEL: 1/8" THK. MIN. (Fy = 36 KSI MIN.)
 - (STEEL IN CONTACT WITH ALUMINUM TO BE PLATED OR PAINTED)

- #12 SMS OR SELF-DRILLING SCREWS** (GRADE 2 CRS)
 - INTO MIAMI-DADE COUNTY APPROVED MULLIONS (NO SHIMS)
 - (3) THREADS MIN. TO EXTEND BEYOND METAL THICKNESS
 - ALUMINUM: 1/8" THK. MIN. (6063-T5 MIN.) (NO SHIMS)
 - STEEL: 1/8" THK. MIN. (Fy = 36 KSI MIN.) (NO SHIMS)
 - (STEEL IN CONTACT WITH ALUMINUM TO BE PLATED OR PAINTED)

CRITICAL EDGE DISTANCE

- INTO CONCRETE AND BLOCKS = 1" MIN. (SEE CHART SHEET 2)
- INTO CONCRETE AND BLOCKS = 2-1/2" MIN. (SEE CHART SHEET 2)
- INTO WOOD STRUCTURE = 1" MIN.
- INTO METAL STRUCTURE = 3/4" MIN.


- WOOD AT HEAD, SILL OR JAMBS SG = 0.55 MIN.
- CONCRETE AT HEAD, SILL OR JAMBS f'c = 3000 PSI MIN.
- C-90 HOLLOW/FILLED BLOCK AT JAMBS f'm = 2000 PSI MIN.



PRODUCT RENEWED
As complying with the Florida Building Code
NOA-No. **24-0205.06**
Expiration Date: **02/05/2025**
By: *Manuel Perez*
Miami-Dade Product Control

PRODUCT REVISED
As complying with the Florida Building Code
NOA-No. **23-0622.06**
Expiration Date: **02/05/2024**
By: *Manuel Perez*
Miami-Dade Product Control

JUN 15 2023



AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
9360 SUNSET DRIVE, SUITE 220
MIAMI, FLORIDA 33173
TEL. (305) 264-8100 FAX. (305) 262-6978
(C.A.N. 3538)

COMP-ANL\W03-80EWD

ALUMINUM CASEMENT WINDOW (L.M.I.)

Eurotech Industries Inc.
4201 N.E. 12th Terrace
Oakland Park, Florida 33334
Tel. (954) 630-9967 Fax. (954) 630-0217


date: 09-05-03
scale: 1/2" = 1"
dr. by: TARIQ
chk. by:

no	date	by	description
G	12.03.15	REV.	PER RER COMMENTS
H	01.31.18	UPDATED TO	2017 FBC
I	11.05.20	UPDATED TO	2020 FBC
J	06.15.23	NO CHANGE	THIS SHEET


drawing no.
W03-80

sheet 3 of 5

revisions:



SINGLE VENT WINDOWS



DUAL VENT WINDOWS

MIAMI-DADE COUNTY
APPR'D MULLION
SEE SEPARATE NOA

TYPICAL ANCHORS
SEE ELEV.
FOR SPACING

af c
AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
9360 SUNSET DRIVE, SUITE 220
MIAMI, FLORIDA 33173
TEL. (305) 264-8100 FAX. (305) 262-6978
(C.A.N. 3538)

ALUMINUM CASEMENT WINDOW (L.M.I.)

Eurotech Industries Inc.

4201 N.E. 12th Terrace

Oakland Park, Florida 33334

Tel. (954) 630-9967 Fax. (954) 630-0217


revisions:	no	date	by	description
	G	12.03.15	REV.	PER PER COMMENTS
	H	01.31.18	REV.	UPDATED TO 2017 FBC
	I	11.05.20	REV.	UPDATED TO 2020 FBC
	J	06.15.23	REV.	NO CHANGE THIS SHEET

date:	09-05-03
scale:	1/2" = 1"
dr. by:	TARIQ
chk. by:	










drawing no.
W03-80
sheet 4 of 5

PRODUCT RENEWED
As complying with the Florida
Building Code
NOA-No. **24-0205.06**
Expiration Date: **02/05/2025**
By: *Manuel Perez*
Miami-Dade Product Control

PRODUCT REVISED
As complying with the Florida
Building Code
NOA-No. **23-0622.06**
Expiration Date: **02/05/2024**
By: *Manuel Perez*
Miami-Dade Product Control




ITEM	PART #	QUANTITY	DESCRIPTION	MATERIAL	MANF./SUPPLIER/REMARKS
1	ER001	4	WINDOW FRAME	6063-T6	-
2	ER008	4	VENT	6063-T6	-
3	ER003	1	CENTER POST	6063-T6	-
4	ER002	AS REQD.	GLAZING BEAD	6063-T6	-
5	ER004	OPTIONAL	WINDOW SCREEN	6063-T6	-
6	2801	AS REQD.	WEDGE GASKET	-	-
7	-	AS REQD.	FRAME WEATHERSTRIPPING	VINYL	-
9	0150X	3/ VENT	HINGES	-	GIESSE, ATTACHED W/ (3) #12 X 7/16" MS
10	24.25.32.300	2/ VENT	LEVER TYPE FACE MOUNT LOCK, 7" FROM TOP & BOTTOM	STEEL	TRUTH, ATTACHED W/ (2) #8 X 3/8" PH SMS
11	-	2/ VENT	LOCK KEEPERS, AT VENT STILE FACING LOCK	STEEL	ATTACHED W/ (2) #8 X 3/4" PH SDS
12	10579.32	1	ROTO OPERATOR	STEEL	TRUTH, ATTACHED W/ (2) #10 X 1/2" SS SMS
13	1103	1/ CORNER	CLIP-ON CORNER JOINT	ALUMINUM	GIESSE
14	-	2/ LOCK	LOCK INSTALLATION SCREWS	-	#8 X 3/8" PH SMS
15	485	AS REQD.	T-POST CONNECTOR	-	GIESSE



PRODUCT RENEWED
As complying with the Florida Building Code
NOA-No. **24-0205.06**
Expiration Date: **02/05/2025**
By: *Manuel Perez*
Miami-Dade Product Control

PRODUCT REVISED
As complying with the Florida Building Code
NOA-No. **23-0622.06**
Expiration Date: **02/05/2024**
By: *Manuel Perez*
Miami-Dade Product Control

JUN 10 2023



AL-FAROOQ CORPORATION
ENGINEERS & PRODUCT DEVELOPMENT
9360 SUNSET DRIVE, SUITE 220
MIAMI, FLORIDA 33173
TEL. (305) 264-8100 FAX. (305) 262-6978
(C.A.N. 3538)

ALUMINUM CASEMENT WINDOW (L.M.I.)
Eurotech Industries Inc.
4201 N.E. 12th Terrace
Oakland Park, Florida 33334
Tel. (954) 630-9967 Fax. (954) 630-0217

no	date	by	description
G	12.03.15		NO CHANGE THIS SHEET
H	01.31.18		UPDATED TO 2017 FBC
I	11.05.20		UPDATED TO 2020 FBC
J	06.15.23		NO CHANGE THIS SHEET

date: 09-05-03
scale: 1/2" = 1"
dr. by: TARIQ
chk. by:

drawing no.
W03-80
sheet 5 of 5

COMP-ANL\W03-80EWD