

#### DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER) BOARD AND CODE ADMINISTRATION DIVISION NOTICE OF ACCEPTANCE (NOA)

#### Wanessa-Sue, Inc. 5056 Inez Road Kingman, AZ 86409

**SCOPE:** This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER-Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

## **DESCRIPTION:** Airlight Insulated Steel/EPS Building Wall Panel System

**APPROVAL DOCUMENT:** Drawing No. **AD18-22**, titled "Airlight Building Panel System", sheets 1 through 5 of 5, dated 05/31/21, with revision R2 dated 12/04/23, prepared by MCY Engineering, Inc., signed and sealed by Yiping Wang, P.E. bearing the Miami-Dade County Product Control Renewal stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Section.

# **MISSILE IMPACT RATING: Large and Small Missile Impact Resistant**

**LABELING:** A permanent label with the manufacturer's name or logo, manufacturing plant's city and state, model/series, and the statement reading 'Miami-Dade County Product Control Approved' is to be located on each panel..

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official. This NOA renews NOA No. 23-1206.03 and consists of this page 1 and evidence pages E-1 and E-2, as well as approval document mentioned above.

The submitted documentation was reviewed by Manuel Perez, P.E.



NOA No. 24-0926.01 Expiration Date: December 19, 2029 Approval Date: October 17, 2024 Page 1

# NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

#### 1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA's

#### A. DRAWINGS

- 1. Manufacturer's die drawings and sections. *(Submitted under NOA No. 18-1031.01)*
- Drawing No. AD18-22, titled "Airlight Building Panel System", sheets 1 through 5 of 5, dated 05/31/21, with revision R2 dated 12/04/23, prepared by MCY Engineering, Inc., signed and sealed by Yiping Wang, P.E. (Submitted under NOA No. 23-1206.03)

#### **B. TESTS**

- 1. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94
  - 2) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94
  - 3) Water Resistance Test, per FBC, TAS 202-94
  - 4) Large Missile Impact Test per FBC, TAS 201-94
  - 5) Cyclic Wind Pressure Loading per FBC, TAS 203-94

along with marked-up drawings and installation diagram of the insulated wall panels, prepared by Fenestration Testing Laboratory, Inc., Test Report No. **10092**, dated 06/22/18, signed and sealed by Idalmis Ortega, P.E. *(Submitted under NOA No. 18-1031.01)* 

## C. CALCULATIONS

 Anchorage calculations dated 06/26/18, prepared by MCY Engineering, Inc., signed and sealed by Yiping Wang, P.E. (Submitted under NOA No. 18-1031.01)

## D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER)

## **E. MATERIAL CERTIFICATIONS**

1. None.

## F. STATEMENTS

Statement letter of conformance, complying with FBC 8<sup>th</sup> Edition (2023) and of no financial interest, dated 12/05/23, issued by MCY Engineering, Inc., signed and sealed by Yiping Wang, P.E.
(Submitted under NOA No. 22, 1206, 02)

(Submitted under NOA No. 23-1206.03)

## G. OTHERS

1. Notice of Acceptance No. 21-0601.07, issued to Wanessa-Sue, Inc. for their Airlight Insulated Steel/EPS Building Wall Panel System, approved on 07/29/21 and expiring on 12/19/24.

Manuel Perez, P.E. **Product Control Examiner** NOA No. 24-0926.01

NOA No. 24-0926.01 Expiration Date: December 19, 2029 Approval Date: October 17, 2024

## NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

#### 2. NEW EVIDENCE SUBMITTED

#### A. DRAWINGS

1. None.

#### **B. TESTS**

- 1. None.
- C. CALCULATIONS
  - 1. None.

## D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER)

## E. MATERIAL CERTIFICATIONS

1. None.

#### F. STATEMENTS

1. Statement letter of conformance, complying with **FBC 8<sup>th</sup> Edition (2023)** and of no financial interest, dated 09/30/24, issued by MCY Engineering, Inc., signed and sealed by Yiping Wang, P.E.

## G. OTHERS

1. Notice of Acceptance No. 23-1206.03, issued to Wanessa-Sue, Inc. for their Airlight Insulated Steel/EPS Building Wall Panel System, approved on 02/01/24 and expiring on 12/19/24.

Manuel Perez, P.E. Product Control Examiner NOA No. 24-0926.01 Expiration Date: December 19, 2029 Approval Date: October 17, 2024

# WANESSA-SUE,INC. AIRLIGHT BUILDING PANEL SYSTEM LARGE & SMALL MISSILE IMPACT

#### GENERAL NOTES:

- THIS PRODUCT HAS BEEN DESIGNED AND TESTED TO COMPLY WITH THE REQUIREMENTS OF THE 8TH EDITION FLORIDA BUILDING CODE (2023) OUTSIDE OF THE HIGH VELOCITY HURRICANE ZONE (HVHZ).
- PANELS RATED FOR LARGE MISSILE IMPACT.
- THESE PANELS ARE APPROVED FOR AIR AND WATER INFILTRATION.
- ANCHORS SHALL BE AS LISTED, SPACED AS SHOWN ON DETAILS. ANCHORS EMBEDMENT TO BASE MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO.
- ANCHORING OR LOADING CONDITIONS NOT SHOWN IN THESE DETAILS ARE NOT PART OF THIS APPROVAL.
- MATERIALS INCLUDING BUT NOT LIMITED TO STEEL / METAL SCREWS THAT COME INTO CONTACT WITH OTHER DISSIMILAR MATERIALS SHALL MEET THE REQUIREMENTS OF THE 8TH EDITION FLORIDA BUILDING CODE (2023) SECTION AS APPLICABLE.
- METAL STRUCTURES NOT BY WANESSA-SUE TO BE DESIGNED TO SUPPORT TO TRANSFER SUCH LOADS TO THE BUILDING MAIN STRUCTURE.
- ULTIMATE LOAD OBTAINED FROM ASCE 7-22, MULTIPLY BY O.G SHALL BE LESS THAN OR EQUAL TO MAX. DESIGN LOAD IN THIS DOCUMENT. THE DESIGN LOADS SHOWN IN THIS DOCUMENT ARE ALLOWABLE DESIGN LOADS.
- MANUFACTURER'S LABEL SHALL BE LOCATED ON A READILY VISIBLE LOCATION IN ACCORDANCE WITH SECTION 1709.9.3 OF FLORIDA BUILDING CODE LABELING TO COMPLY WITH SECTION 1709.9.2.

#### TYPICAL ANCHORS: (REFER TO ELEVATION FOR SPACING)

- $\frac{\text{TYPE A} }{\text{INTO CONCRETE}} \qquad \frac{3/8" \text{ DIA. POWERS WEDGE BOLT}}{\text{INTO CONCRETE}} (F_{U} = 100 \text{ KSI}, F_{Y} = 65 \text{ KSI})$   $\frac{1}{\text{INTO CONCRETE}} \text{ WITH 2-1/2" MIN. EMBED.}$
- TYPE B -3/8 I G BOLT WITH WASHER AND NUTS<br/>INTO METAL STRUCTURE<br/>STEEL: I/8" MIN. (Fy=36 KSI MIN.)<br/>ALUMINUM: I/8" MIN. THK. (6063-T5 MIN.)

#### TYPICAL EDGE DISTANCE

INTO CONCRETE =2-1/4" MIN. INTO METAL STRUCTURE = 1 " MIN.

CONCRETE fc'=2000 PSI MIN.

ABBREVIATIONS AND SYMBOLS			as comply Building C NOA-No.
	- WITH - WITHOUT - ON CENTER - TYPICAL	X XX SHEET NUMBER	Expiration By Miami-Dad
			MIAN









