

CHECKLIST #0135 FOR THE APPROVAL OF: METAL ROOF SYSTEMS (STRUCTURAL)

- Basic Requirements Checklist.
- One set of the manufacturer's 'approval document' including:
 - a. Details of all sections with dimensions and thickness.
 - b. Assembly details including connections at eaves, ridges and seam, and
 - c. Fastener diagram.
- Calculations verifying all data as follow:
 - a. Deflections shall not exceed L/240,
 - b. Physical properties of the roof panel derived from the test data,
 - c. Fasteners spacing and size, and
 - d. Provision for diaphragm action shall be indicated.
- One set of manufacturer's design drawings marked and verified by the testing laboratory.

The following current laboratory tests and test reports in compliance with protocol TAS 301.

- Accelerated Testing of coating for 2000 hours per ASTM G23.
- Salt Spray Testing of coating for 1000 hours per ASTM B117.
- Uniform static air positive & negative pressure difference per TAS 125-03. See note #2.
- □ Wind Driven Rain Test per TAS100-95 for slopes 2:12 and greater or <u>FM4471 App. G</u> for slopes less than 2:12. If system is to include a valley assembly TAS100-95 shall be required in addition to <u>FM4471 App. G</u>. See note # 3.
- □ Impact test per TAS201-94. Only for thickness less than 22 gage.

Notes:

- 1. System must be tested with the same approved fastener; no change in configuration washer and/or diameter will be accepted.
- 2. Calculated corner pressure and corresponding panel span shall be verified with an uplift test on one specimen following TAS125-03.
- 3. If system approval is to include horizontal joints, two horizontal joints shall be incorporated in TAS100-95 and one horizontal joint in FM4471 App. G of the test specimens.