

## SBD – CM REVIEW FORM (REVISED)

<b>To:</b> Business Opportunity Support Division – Construction	
<b>From:</b> SBD CM Vivian Forhat-Diaz	
<b>Department:</b> WASD	<b>Contact:</b> William Diaz
<b>Date:</b> 11/07/14	<b>RESUBMITTAL:</b> No

<b>PROJECT NUMBER:</b>	RPQ P0153
<b>PROJECT TITLE:</b>	One Year Countywide Contract for Rehabilitation of Sanitary Sewer by the Cured-in-Place Pipe Lining Method for PSIP projects
<b>PROJECT LOCATION:</b>	Various Locations Countywide

**SCOPE OF WORK/DESCRIPTION:** Project include furnishing all labor, materials and equipment for rehabilitating defects in 8 through 36-inch diameter gravity sanitary sewer pipes by the cured-in-place pipe lining method, at various and different locations anywhere within Miami-Dade County. This work includes supplementary cleaning of the affected existing gravity sanitary sewers, isolating the reach of sewer to be repaired, inspecting it with closed circuit television (CCTV), and then installing a cured-in-place pipe liner and re-inspecting the repaired reach with CCTV. The work in the sewer shall be accomplished through the manholes, without disturbing the street surface or adjacent property or any utility, except when performing excavated point repairs of sewers. Work also includes bypass pumping of sewage or plugging and monitoring, if needed, and other appurtenant and miscellaneous related items and work for a completed Project.

**SPECIAL REQUIREMENTS:** **Prime Contractor** must possess a General Engineering or Pipelines Engineering or Underground Utility and Excavation License and must have a minimum of two (2) installation crews and equipment in order to complete the work in a timely fashion. **Prime Contractor** must have been regularly and successfully engaged in the commercial installation of the liner product for a minimum One (1) year, and has successfully performed an aggregate amount of at least 150 repairs of pipes 8 through 27 inches in diameter in subaqueous conditions. This requirement is based on the standard NASSCO recommend for this particular product application.

TRADES/SUBTRADES	AMOUNT	COMMENTS
		<b>PRIME</b>
Cured-in-place 8" through 36" Pipe lining.	\$ 510,830.00	Must meet special requirements.
By-pass Pumping of Sewage	\$ 3,400.00	
Maintenance of Traffic	\$ 10,000.00	
<b>Base Estimate Total</b>	<b>\$ 524,230.00</b>	
Contingency Allowance (10% Base)	\$ 52,423.00	
<b>Total Cost</b>	<b>\$ 576,653.00</b>	

Small Business Development Signature: *Vivian Forhat-Diaz* Date: 11/10/14

\*Trades/Subtrades identified for possible subcontracting opportunities by SBD CM  
 WASD is recommending **No Measure** for CSBE participation.