



## TEMPORARY FOR TEST PROCEDURE

### CATEGORY 15-ELEVATOR

Two affidavits are required to be signed and notarized	<input type="checkbox"/>
The permit is only valid for 180 days and cannot be extended	<input type="checkbox"/>
A new permit and inspection must be obtained if additional time is required. An inspection may not be required if the electrical category 001 has already been finalized (additional category 15 must be added to the master for each T/T permit)	<input type="checkbox"/>
The fee is calculated per elevator service	<input type="checkbox"/>
The Department only inspects the service feeding the elevator. The actual elevator is inspected by ISD	<input type="checkbox"/>
The elevator is sometimes permitted to be fed from a temporary construction service when FPL cannot provide immediate service or when the building electrical service is not ready to be energized	<input type="checkbox"/>
A rough inspection shall be performed on all systems and equipment to be energized prior to the T/T	<input type="checkbox"/>
A T/T inspection is conducted like a final inspection but only for the systems to be energized.	<input type="checkbox"/>
The strict control and safeguarding of all energized equipment is the responsibility of the electrical contractor	<input type="checkbox"/>
A T/T is for testing only. The elevator shall not be utilized for any other purposes	<input type="checkbox"/>



# TEMPORARY FOR TEST PROCEDURE

## CATEGORY 26-SERVICE

The permit is only valid for 30 days and cannot be extended	<input type="checkbox"/>
A new permit and inspection must be obtained if additional time is required. An inspection may not be required if the electrical category 001 has already been finalized (additional cat. 26 must be added to master for each T/T)	<input type="checkbox"/>
A T/T may be obtained for residential uses if the final electrical category 001 inspection has been approved or if required for climate control (Example: Wood floors & Cabinets)	<input type="checkbox"/>
A rough inspection should be performed on all systems and equipment to be energized prior to a "temp. for test" inspection.	<input type="checkbox"/>
The fee is calculated per individual service using fee code G031 per service	<input type="checkbox"/>
Additional systems or equipment may be energized as the hob progresses and as approved by the electrical inspector	<input type="checkbox"/>
The strict control and safeguarding of all energized equipment is the responsibility of the electrical contractor	<input type="checkbox"/>
FP&L requires for all meters to be energized	<input type="checkbox"/>