

Memorandum



Date: 7/6/2017

To: Gary Hartfield, Division Director
Small Business Development Division
Internal Services Department

From: Joanne Menoher Case, Contracts Administrator
Parks, Recreation and Open Spaces Department

Joanne Menoher Case

Subject: Amelia Earhart Park – Pedestrian Bridge Replacement - Project No. 213001-15-004

We respectfully request that you review the attached recommendation for CSBE and SBE Construction goals.

General Descriptions of Work:

Furnish all labor, equipment, and materials required to comply with the intent of the work described in the contract documents including but not limited to: The removal and disposal of an existing pre-fabricated pedestrian steel bridge system and the procurement, coordination, transportation, storage, and installation/erection of a new aluminum pedestrian bridge (arched truss prefabricated aluminum bridge, anchoring, decking, railing, vertical pickets, etc.); professional engineering, services are required for the preparation of the bridge shop drawings, structural calculations, and building permits approvals, as required by RER (process #C2016040813) and the Structural General Notes. Professional Land Surveying services are required: before, during and after bridge installation (for elevations, slopes, dimensions, clearances, camber, foundation locations, bearing plates, as-built information, etc.). A Quality Assurance Plan is required; Site work demolition, new asphalt and new bollards and a work area staging plan is to be submitted for Owner's approval.

Estimated Total Cost: \$177,150.00

Miami-Dade County Parks, Recreation and Open Spaces Department (PROS) is requesting that the General Engineer or General Contractor be in business at least five years, having completed at least two projects similar in size and scope to the subject project.

Due to the specific nature in the scope of the work involved, PROS respectfully requests that SBD considers a 1.2% SBE-Cons for Paving or a No-Measure. An analysis of the CSBE Program Ordinance 97-52 as amended, and I.O 3-22 has been conducted and requests use of the 7360 Contract to ensure sufficient participation of Contractors experienced with bridge installation.

Thank you in advance for your cooperation.

Attachments: Exhibit "A" Construction Breakdown
Exhibit "B" General Conditions / Site Work Breakdown

PARK NAME: Amelia Earhart
 PROJECT TITLE: Pedestrian Bridge Replacement
 Cost Estimate Prepared by: Parks, Recreation and Open Spaces

Date: 7/6/2017 Exhibit A
 P & R #: 213001-15-004
 WKO No.:

ITEM #	TASK DESCRIPTION	TOTALS	%
1	GENERAL REQUIREMENTS	\$10,084.00	5.9%
2	SITework	\$1,950.00	1.1%
3	CONCRETE	\$0.00	0.0%
4	MASONRY	\$0.00	0.0%
5	METAL	\$0.00	0.0%
6	WOOD AND PLASTIC	\$0.00	0.0%
7	THERMAL AND MOISTURE PROTECTION	\$0.00	0.0%
8	DOORS AND WINDOWS	\$0.00	0.0%
9	FINISHES	\$0.00	0.0%
10	SPECIALTIES	\$124,052.96	72.1%
11	EQUIPMENT	\$0.00	0.0%
12	FURNISHINGS	\$0.00	0.0%
13	SPECIAL CONSTRUCTION	\$0.00	0.0%
14	CONVEYING SYSTEMS (NOT USED)	\$0.00	0.0%
15	PLUMBING, HEATING, A/C	\$0.00	0.0%
16	ELECTRICAL	\$0.00	0.0%
	DIVISION SUBTOTAL	\$136,086.96	79%
	OVERHEAD AND PROFIT (15%)	\$20,413.04	11.86%
	BASE ESTIMATE (B.E.)	\$156,500.00	
	(10%)CONTINGENCY ALLOWANCE (..10 * B.E.)	\$15,650.00	9.09%
	BASE ESTIMATE (B.E.) + CONTINGENCY ALLOWANCE	\$172,150.00	100.00%
	DEDICATED ALLOWANCE	\$5,000.00	
TOTAL ESTIMATED CONSTRUCTION COST		\$177,150.00	

PARK NAME: Ameila Earhart

P & R #: 213001-15-004

PRELIMINARY BREAKDOWN

EXHIBIT "B"

A. General Requirements

- 1 Performance Bond
- 2 Insurances
- 3 Project Supervision
- 4 Surveyor
- 5 Equipment/Mobilization
- 6 Temporary Utilities
- 7 Trash removal/Clean up
- 8 Project records as-built



Total

\$10,084.00

B. Site Work

- 1 Asphalt Restoration around scope
- 2
- 3
- 4
- 5
- 6 Sod
- 7
- 8

\$1,600.00

0.20%

\$350.00

0.93%

Total

\$1,950.00