

## SBD – CM REVIEW FORM

<b>To:</b> Business Opportunity Support Division – Construction	
<b>From:</b> SBD CM Vivian Forhat-Diaz	
<b>Company:</b> HUNT – Miami Dolphin Stadium	<b>Contact:</b> Marsha Jackman
<b>Date:</b> 10/06/2014	<b>RESUBMITTAL:</b> No

<b>PROJECT NUMBER:</b>	BP- 21
<b>PROJECT TITLE:</b>	Auger Cast-in-place Piles
<b>PROJECT LOCATION:</b>	Miami Dolphins Stadium

**SCOPE OF WORK/DESCRIPTION:** The Scope is to provide auger cast-in-place piles and test pile program including all Cast-in-place concrete materials, grout, aggregate, admixtures, etc. all reinforcing materials, centering devices, reinforcing materials, required for this scope of work are to the responsibility of this subcontractor. Provide all testing equipment, Osterberg Cell (O-cell) load testing materials, and reports for a tension load test(s); all necessary materials and equipment to perform a lateral load test(s) as required by the Langan "Technical Specification for Augered cast-in-place (ACIP) pile installation and load test program" Cut off all piles to the elevation as per Contract Documents and disposal of cut-off section. Provide Jet-grouting, "cut-off curtain" and/or localized ground treatment at all existing footings as per the Langan "Geotechnical Engineering Study Report". Contractor shall accept the Site preparation and shall make any and all additional stone placement or other modifications to facilitate the placement of crane(s), shoring, etc.; provide any additional access roads, staging areas, crane mats, temporary stone, ice removal, water removal, temporary protection, barricades, signage, dust control, protection of existing utilities to remain, safety precautions and/or procedures as required for the completion of this Work and the necessary removals, maintain the Site surface and restore, to like condition, the Site following the completion of each construction sequence area of its work.

**SPECIAL REQUIREMENTS:** Prime must have five (5) years' experience with auger cast pile work and have had three (3) prior jobs with auger cast piles at least 85' long and must have sufficient in-house engineering and equipment capabilities to produce the foundation system specified as well as perform a load test on select piles.

TRADES/SUBTRADES	AMOUNT	COMMENTS
		<b>PRIME</b>
Drilling Equipment	\$2,080,000.00	General Contractor License. Must meet Special requirements.
Furnish & Install Concrete & Grout	\$485,000.00	
Furnish & Install Reinforcement	\$400,000.00	
Permeation Grouting	\$515,000.00	
		<b>Concrete Contractor</b>
Furnish & Install Concrete & Grout	\$245,000.00	*Possible Subcontracting opportunities
Furnish & Install Reinforcement	\$230,000.00	
Permeation Grouting	\$45,000.00	
<b>Bid Package Total Cost</b>	<b>\$4,000,000.00</b>	

Small Business Development Signature: *Vivian Forhat-Diaz* Date: 10/06/14

\*Trades/Subtrades identified for possible subcontracting opportunities by SBD CM  
**HUNT Construction Group** is recommending 13% for CSBE participation.