



March 4, 2015

Project No: **BP #50 – General Contractor for South Club**

The above-referenced contract is being considered for small business contract measures. **PLEASE NOTE THAT YOUR PARTICIPATION IN THE AVAILABILITY TO BID PROCESS IS VITAL IN ORDER FOR MEASURES/GOALS TO BE PLACED ON THIS PROJECT.** If you are interested in participating as a SBE-Construction firm to perform work in connection with this project and meet the requirements listed in this letter, please complete and return the attached Verification of Availability to Bid by **TOMORROW: THURSDAY, MARCH 5, 2015 at 1:00 P.M. (DUE TO THE NATURE OF THE PROJECT).** It is asked that all pages are returned completed in its entirety. Failure to do so will result in this Verification of Availability to Bid Letter not being considered.

Please review the enclosed description of the project. **TIME IS OF THE ESSENCE.**

The letter of availability may be sent via facsimile transmission to **(305) 375-3160** or via email to **kellyd@miamidade.gov**. If you have any questions, please contact me at (305) 375-3147.

Sincerely,

Kelly Duncombe
Miami-Dade County Internal Services Dept.
Small Business Development Division
111 NW 1st St. 19 Floor Miami, FL 33176
305-375-3147 (P) 305-375-3160 (F)
kellyd@miamidade.gov

miamidade.gov
Delivering Excellence Every Day

<http://www.miamidade.gov/internalservices/small-business.asp>

VERIFICATION OF AVAILABILITY TO BID

CONTRACT TITLE: **General Contractor for South Club**

PROJECT NUMBER: **BP #50**

SEE ATTACHED: **Project Description, Qualifications; License Requirements, Etc.**

Contractor Qualifications Questionnaire

This questionnaire will assist SBD in identifying the qualified contractors that “comply” to perform the aforementioned scope of work. Indicate yes “Y” or no “N” on the empty line on the left side of this questionnaire and forward it completely filled out to this e-mail address: kellyd@miamidade.gov or via fax (305) 375-3160 attention Ms. Kelly Duncombe. (you may select more than one option)

_____ Prime has experience working on projects with a similar size and scope to this project, meets the requirements as indicated in the attached document and can perform the work as required.

_____ Prime DOES NOT have experience completing projects with similar size and scope as this project and DOES NOT meet the requirements as indicated in the attached document.

Similar contracts (Name of Project and Owner)	Project Completion Date	Contract Amount	Project Contact Person & Telephone for Verification

I certify that to the best of my knowledge all the information provided is verifiable and correct.

COMPANY NAME: _____

NAME OF REPRESENTATIVE: _____

TITLE: _____ **SIGNATURE:** _____

TELEPHONE NUMBER: _____ **E-MAIL ADDRESS:** _____



HUNT Construction Group, Inc. - An AECOM Company
2 Oakwood Blvd., Suite 125
Hollywood, Florida 33020
Phone: (305) 325-0577 Fax: (305) 325-0766
www.aecom.com
www.huntconstructiongroup.com

Bid Package Breakdown

SUPPLEMENTAL INFORMATION

For Specialty Contractor

BP #50

Date: February 3, 2015

BP Name: General Contractor for South Club

Bid Package Description: Perform all interior work of the South Club

Specific Requirements and Scope:

This scope includes all the interior work for the South Club including all finishes, mechanical, electrical and plumbing. The firms bidding this work as a Prime will need to have the ability to perform the work and/or contract and manage firms subcontracted to them.

Specific Skills Required:

Bidder must have sufficient experience in this type of work as proven in comparable projects. Bidder must be familiar with fast track performance of project and understand that the design is ongoing. Bidder must have the financial capability to have the funds available to handle the project due to the fast track nature.

Risks Associated with this Package:

Work must be completed within the time frames established so as to not hold up the other trades.

Firms must have a good safety record.

Experience and Licenses Required:

Subcontractor must have five(5) years of experience performing this type of work including the magnitude and schedule conformance.

Schedule/Performance and Manpower Requirements:

Contractor must have the manpower capability to adhere to the fast track schedule while maintaining high quality work.

Subcontractor must have the manpower available to perform this work in the time frame allotted in this fast pace project.

Participants in this package must be responsive to the direction and schedule needs and must be flexible to provide manpower as needed and when needed.



HUNT Construction Group, Inc. - An AECOM Company
2 Oakwood Blvd., Suite 125
Hollywood, Florida 33020
Phone: (305) 325-0577 Fax: (305) 325-0765
www.aecom.com
www.huntconstructiongroup.com

Insurance Required:

Subcontractor must be able to be enrolled in an OCIP program or be able to provide insurance limits of the project.

General Liability insurance will be required. (\$5M per occurrence)

Bonding required:

A 100% Payment and Performance Bond will be required (from an A rated size VIII or better).

Contracting Required:

Bidder must be able to execute the Hunt Subcontractor Agreement.

Bidder must have home office support that can maintain reporting requirements of the Construction Manager (SBD, CWP, Safety)

Bidder must have a clean record with regards to legal claims.

Due to the complexity of the bid package, contractor must have experience in managing and contracting lower tier subcontractors.

Programs Required:

SBD (CSBE) and CWP

The Stadium aspires to have at least 70% of the project's workers be residents of Miami-Dade County, 20% of which are from the County's Community Development Block Grant (CDBG) eligible areas.

The Stadium also aspires to hire a minimum of 10% of the project's workers from Miami – Gardens. Labor residing in zip codes 33056, 33055, 33054, 33169 and 33014 should be given first preference for hire.

The project also aspires to utilize as many local firms as reasonably practical and aspires to have at least 35% of the firms hired as subcontractors be firms located within Miami-Dade County.

Attachment II

Subcontractor's Scope of Work

A. General Description of the Scope of Work:

Subcontractor shall perform the Subcontract Work generally described below (and as further described in the Contract Documents) to provide the following:

BP#50 General Contractors – South Club

The intent of this Attachment II is to describe and clarify the Work required under this Agreement. It is the responsibility of this Subcontractor to provide the **South Club Work** associated with the Miami Dolphins Stadium Renovations project in accordance with the Contract Documents and as described below.

B. Payment and Performance Bonds:

Bonds will be required: Yes No

Bonds will be furnished in accordance with the provisions of Attachment VI.

C. Specific Requirements:

1. Subcontractor shall provide (furnish and install) all Work described by the following specification sections necessary for the proper completion of this Scope of Work as further clarified by this Attachment II:

- 01 10 00 SUMMARY
- 01 23 00 ALTERNATES
- 01 25 00 SUBSTITUTION REQUESTS
- 01 26 00 CONTRACT MODIFICATION PROCEDURES
- 01 31 00 PROJECT MANAGEMENT AND COORDINATION
- 01 33 00 SUBMITTAL PROCEDURES
- 01 40 00 QUALITY REQUIREMENTS
- 01 50 00 TEMPORARY FACILITIES AND CONTROLS
- 06 60 00 EXECUTION
- 01 74 19 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL
- 01 78 23 OPERATION AND MAINTENANCE DATA
- 01 78 39 PROJECT RECORD DOCUMENTS
- 02 41 19 SELECTIVE DEMOLITION
- 03 01 30 MAINTENANCE OF CAST IN PLACE CONCRETE
- 03 10 00 CONCRETE FORMWORK
- 05 40 00 COLD FORMED METAL FRAMING
- 05 50 00 METAL FABRICATIONS
- 06 10 00 ROUGH CARPENTRY
- 06 16 00 SHEATHING
- 06 40 23 INTERIOR ARCHITECTURAL WOODWORK
- 06 41 13 WOOD VENEER FACED ARCHITECTURAL CABINETS

Attachment II

Subcontractor's Scope of Work

- 06 41 16 PLASTIC-LAMINAT-FACED ARCHITECTURAL CABINETS
- 06 42 16 FLUSH WOOD PANELING
- 06 64 00 PLASTIC PANELING
- 07 19 00 WATER REPELLENTS
- 07 21 00 THERMAL INSULATION
- 07 81 00 APPLIED FIREPROFFING
- 07 84 13 PENETRATION FIRESTOPPING
- 07 92 00 JOINT SEALANTS
- 07 95 00 EXPANSION CONTROL
- 08 11 13 HOLLOW METAL DOORS AND FRAMES
- 08 14 16 FLUSH WOOD DOORS
- 08 31 13 ACCESS DOORS AND FRAMES
- 08 41 13 ALUMINUM-FRAMED INTERIOR ENTRANCES AND STOREFRONTS
- 08 41 26 ALL-GLASS ENTRANCES AND STOREFRONTS
- 08 42 13 ALUMINUM FRAMED ENTRANCES
- 08 44 13 GLAZED ALUMINUM CURTAIN WALLS
- 08 45 13 ETFE TRANSPARENT ASSEMBLIES
- 08 71 00 DOOR HARDWARE
- 08 80 00 GLAZING
- 08 81 13 DECORATIVE GLASS GLAZING
- 08 83 00 MIRRORS
- 08 91 19 FIXED LOUVERS
- 09 22 16 NON-STRUCTURAL METAL FRAMING
- 09 24 00 CEMENT PLASTERING (STUCCO)
- 09 29 00 GYPSUM BOARD
- 09 30 13 CERAMIC TILES
- 09 30 33 STONE TILING
- 09 51 13 ACOUSTICAL PANEL CEILINGS
- 09 65 13 RESILENT BASE AND ACCESSORIES
- 09 68 13 TILE CARPENTING
- 09 69 00 ACCESS FLOORING
- 09 93 00 STAINING AND TRANSPARENT FINISHING
- 09 96 00 HIGH PERFORMANCE COATINGS
- 10 21 13.15 STAINLESS STEEL TOILET COMPARTMENTS
- 10 22 39 FOLDING PANEL PARTITIONS
- 10 22 39.13 FOLDING GLASS PANEL WALL ASSEMBLIES
- 10 26 00 WALL AND DOOR PROTECTION
- 10 28 00 TOILET BATH AND LAUNDRY ACCESSORIES
- 10 44 16 FIRE EXTINGUISHERS
- 10 73 16 PREMANUFACTURED SUNSHADE CANOPIES
- 14 91 00 FACILITY CHUTES
- 11 24 30 FALL ARREST PROTECTION SYSTEMS
- 11 40 00 FOOD SERVICE EQUIPMENT
- 12 34 50 SOLID COMPOSITE EXTERIOR CASEWORK
- 12 36 23.13 PLASTIC-LAMINATE-CLAD COUNTERTOPS
- 12 36 40 STONE COUNTERTOPS
- 12 36 61 SIMULATED STONE COUNTERTOPS

Attachment II

Subcontractor's Scope of Work

- 21 12 00 FIRE-SUPPRESSION STANDPIPES
- 21 13 13 WET-PIPE SPRINKLER SYSTEMS
- 22 05 16 EXPANSION FITTINGS AND LOOPS FOR PLUMBING PIPING
- 22 05 23 GENERAL DUTY VALVES FOR PLUMBING PIPING
- 22 05 29 HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT
- 22 05 33 IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT
- 22 07 00 PLUMBING INSULATION
- 22 11 16 DOMESTIC WATER PIPING
- 22 13 16 SANITARY WASTE AND VENT PIPING
- 23 05 00 COMMON WORK RESULTS FOR HVAC
- 23 05 16 EXPANSION FITTINGS AND LOOPS FOR HVAC PIPING
- 23 05 19 METERS AND GAGES FOR HVAC PIPING
- 23 05 23 GENERAL DUTY VALVES FOR HVAC PIPING
- 23 05 29 HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT
- 23 05 48 VIBRATION CONTROLS FOR HVAC PIPING AND EQUIPMENT
- 23 05 53 IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT
- 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC
- 23 07 00 HVAC INSULATION
- 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC
- 23 09 93 SEQUENCE OF OPERATIONS FOR HVAC CONTROLS
- 23 11 23 FACILITY NATURAL GAS-PIPING
- 23 23 00 REFRIGERANT PIPING
- 23 25 00 HVAC WATER TREATMENT
- 23 29 13 ENCLOSED CONTROLLERS
- 23 29 23 VARIABLE FREQUENCY MOTOR CONTROLLERS
- 23 31 13 METAL DUCTS
- 23 31 16 NONMETAL DUCTS
- 23 31 19 HVAC CASINGS
- 23 33 00 AIR DUCT ACCESSORIES
- 23 34 16 CENTRIFUGAL HVAC FANS
- 23 36 00 AIR TERMINAL UNITS
- 23 17 13 DIFFUSERS, REGISTERS AND GRILLES
- 23 51 00 BREECHINGS, CHIMNEYS, AND STACKS
- 23 73 13 MODULAR INDOOR CENTRAL STATION AIR HANDLING UNITS
- 23 81 26 SPLIT SYSTEM AIR CONDITIONERS
- 23 82 19 BLOWER FAN COIL UNITS
- 26 00 00 APPENDIX A FIXTURE CUTS
- 26 05 00 COMMON WORK RESULTS FOR ELECTRICAL
- 26 05 19 ELECTRICAL POWER CONDUCTORS AND CABLES
- 26 05 26 GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS
- 26 05 33 RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS
- 26 05 36 CABLE TRAYS FOR ELECTRICAL SYSTEMS
- 26 05 48 VIBRATION CONTROLS FOR ELECTRICAL SYSTEMS
- 26 05 53 IDENTIFICATION FOR ELECTRICAL SYSTEMS
- 26 22 00 LOW-VOLTAGE TRANSFORMERS
- 26 24 13 SWITCHBOARDS
- 26 24 16 PANEL BOARDS

Attachment II

Subcontractor's Scope of Work

- 26 25 50 DOCKING STATION
- 26 27 26 WIRING DEVICES
- 26 28 13 FUSES
- 26 28 16 ENCLOSED SWITCHED AND CIRCUIT BREAKERS
- 26 29 13 ENCLOSED CONTROLLERS
- 26 29 23 VARIABLE FREQUENCY MOTOR CONTROLLERS
- 26 33 53 UNINTERRUPTIBLE POWER SUPPLY
- 26 36 00 TRANSFER SWITCHES
- 26 41 13 ENHANCED LIGHTING
- 27 20 00 BROADCAST CABLING
- 28 31 11 DIGITAL, ADDRESSABLE FIRE-ALARM SYSTEM

2. The intent of the bid package is for a General Contractor to furnish and install all components, including but not limited to walls, floors, ceilings, MEP, Fire Protection, Food Service, systems, finishes, supports and accessories [unless specifically excluded otherwise and defined here within], for a complete build-out of the club spaces, as identified in accordance with the Contract Documents. General Contractor will be responsible for all trades necessary to complete this Work in an expedited manner, in time for the 2015 football season.
3. The 'white box' will be provided by Others. General Contractor will be required to complete construction of 'white box' [i.e. blocking, and club space side of drywall].
4. The Work of this General Contractor Package shall include but not be limited to the following:

SOUTH CLUB

- a) Furnish and install AR-102 Interface carpet tile at reception area as specified.
- b) Furnish and install concrete tile, porcelain tile and grout at central bar. All substrates shall comply with moisture emissions value recommendation by the TCNA and manufacturer. This statement shall apply to all areas that are to receive tiles throughout the club spaces.
- c) Furnish and install at the wine room, conference room, wine cellar, wine display, east private dining faux wood porcelain tile complete.
- d) Furnish and install at the north corridor color epoxy stripped pattern.
- e) Furnish and install at the south extension penny tile and concrete tile.
- f) Furnish, install and coordinate recessed in new slab for tile.
- g) Furnish and install at east elevation 4x4 ceramic tile to wall.
- h) Furnish and install at both restrooms porcelain mosaic tile.
- i) Furnish and install at the east dining/action station porcelain and concrete tiles as specified by Architects material and finish schedule.
- j) Furnish and install Concrete Masonry Units (see structural detail) with rebar and grout.
- k) Furnish and install at men's and women's restrooms porcelain tile complete.
- l) Furnish and install stone pavers at central as specified on finish schedule.
- m) Furnish and install all base trim at for tiled areas.
- n) Furnish and install running bond Ceramic subway tile at restrooms.
- o) Furnish and install mill work (build bar) and finish according to Architect finish schedule.
- p) Furnish and install chair rails.
- q) Furnish and install wood slats and beams.

Attachment II

Subcontractor's Scope of Work

- r) Furnish and install double sided wine wall at south elevation.
- s) Furnish and install bead board at south elevations.
- t) Furnish and install all framing to ceilings and walls and mirrors. Framing shall include provisions for recessed fire extinguisher units. Framing shall include additional support for overhead fixtures, fans, and television locations as applicable.
- u) Furnish and install new windows, demo existing wall 11.1 D & E
- v) Remove existing viewing windows infill with metal framing and gypsum board to match adjacent wall for full extents.
- w) Furnish and install tube steel for televisions at bar
- x) Furnish and install batt insulation, sound attenuation insulation as specified.
- y) Furnish and Install gypsum board to ceilings to include application tape and joint compound, sanding (level 5 finish) and ready for applied coatings.
- z) Furnish and install at speakeasy tin ceiling tile at south elevation and north as indicated to include led lighting.
- aa) Furnish and install movable decorative screen.
- bb) Furnish and install at south elevation stucco finish as indicated.
- cc) Furnish and install at north elevation video wall (exclude TV's).
- dd) Furnish and install painted board and batten w/painted base.
- ee) Furnish and install all wood beams and painted wood shutters.
- ff) Furnish and install built-in banquette with wood base at north elevation speakeasy.
- gg) Furnish and install wall covering at north elevation speakeasy.
- hh) Furnish and install decorative metal panels at elevator.
- ii) Furnish and install painted bead board ceiling at north elevation speakeasy.
- jj) Furnish and install wood paneled bar tie at North elevation speakeasy.
- kk) Furnish and install concrete tile to face at bar.
- ll) Furnish and install all cased openings at east elevation.
- mm) Furnish and install marble counter top at west elevation.
- nn) Furnish and install applied molding and apply paint as specified. Reference finish schedule for finishes.
- oo) Furnish and install primer and 2 finish coats to gypsum surfaces as indicated in Finish schedule.
- pp) Furnish and install all associated millwork as indicated.
- qq) Furnish and install foot rail at bar (s).
- rr) Furnish and install chair rails and finish according to Architects finish schedule.
- ss) Furnish and install all millwork and build bar to include associated shelving and lighting. Provide specified finishes.
- tt) Furnish and install all wood beams. Finish as specified by Architects Finish Schedule.
- uu) Furnish and install all wood panels and molding, panels and molding are painted unless otherwise specified
- vv) Furnish and install mesh screen panels.
- ww) Furnish and install all millwork niche to include all glass shelves.
- xx) Furnish and install wall coverings at the lounge area.
- yy) Furnish and install back lit barrisol panels at designated areas.
- zz) Furnish and install wood doors, metal doors, frames and hardware, and glass doors and partitions as indicated in schedule. Doors shall be painted/coated as indicated in finish schedule.

Attachment II

Subcontractor's Scope of Work

- aaa) Furnish and install automatic closing devices to doors at rated walls. See Architectural/Structural for rated walls and Fire Protection Plans. To include 2010 FBC and Life Safety Requirements.
- bbb) Furnish and install all associated hardware, coordinate with Dolphins security.
- ccc) Furnish and install all locks and provide keys to Hunt.
- ddd) Furnish and install all blocking for TV mounting.
- eee) Furnish and install pull out trash drawers.
- fff) Furnish and install all Architectural columns as indicated (non-structural) and finish according to Architects Finish Schedule.
- ggg) Furnish and install hot and cold water supply lines, shut off valves, escutcheon covers for piping and supply to all toilets and faucets and kitchen sinks.
- hhh) Furnish and install all motioned sensor faucets, motion sensor toilets and motion sensor urinals.
- iii) Furnish and install bathroom vanity and sinks as indicated in drawings.
- jjj) Furnish and install ADA compliant sinks at men's and women's restrooms.
- kkk) Furnish and install all restroom partitions which are to be white powder coated.
- lll) Furnish and install Corian countertops at restrooms.
- mmm) Furnish and install lacquered wood louver doors at men's and women's restrooms.
- nnn) Furnish and install automatic hand dryer(s) as indicated.
- ooo) Furnish and install recessed metal towel dispenser. Include all accessories.
- ppp) Furnish and install all waste piping in slab and drains as dictated in drawings to include drains strainer covers.
- qqq) Furnish and install garbage disposal units as indicated.
- rrr) Furnish and install painted glass feature wall.
- sss) Furnish and install blocking as required for handicap grab bars at men's and women's restrooms.
- ttt) Furnish and install mirrors at men's and women's restrooms to include ADA wall mounted vanity and sconces.
- uuu) Furnish and install all in slab and above slab electrical conduit runs. Saw cutting will be required. Pour back floor openings with concrete or Architect approved material.
- vvv) Furnish and install electrical power to all food service equipment, lighting and receptacles as indicated for the entire East Club which includes restrooms. Panel boards are provided to the space by others. Electrical Subcontractor by the GC will connect to the panels.
- www) Furnish and install all receptacle covers, see Architectural/Electrical for color types as they vary.
- xxx) Furnish and install all wiring, conduit and boxes for fans overhead and wall sconces and ceiling mounted fixtures, and other decorative lighting as specified.
- yyy) Furnish and install emergency lighting, exit signs per NEC 70, Life safety and 2010 FBC.
- zzz) Furnish and install signage.
- aaaa) Furnish and install all "performance stage" wiring for overhead lights and receptacles/rough in and finish fixtures.
- bbbb) Furnish and install all floor mounted receptacles complete, to include covers and verify all elevations for areas to receive tile or other flooring types for a flush installation.
- cccc) Furnish and install all HVAC duct work, hangers and supports for the complete space, source tie in from the nearest HVAC handling unit.
- dddd) Furnish and install all duct insulation as specified in drawings.

Attachment II

Subcontractor's Scope of Work

- eeee) Furnish and install dampers and diffusers GC does not need to have duct fire sensors (provided and installed by others).
 - ffff) Furnish and install temperature control devices.
5. General Contractor shall provide underground MEP to tie-in point of MEP Infrastructure systems [Point of connection shall be established by BMS Contractor]; General Contractor will tie-in to this location.
 6. General Contractor shall provide all Overhead/wall empty conduit/box rough-in of base building systems, including the following:
 - o Fire alarm (wiring / devices / testing by others)
 - o Audio (wiring / speakers / equipment by others)
 - o Communications (IT) Systems (wiring / devices / equipment by others)
 - o Security (wiring / devices / hardware / equipment by others)
 - o Interface of lighting control with BMS (Building Management System)
 7. General Contractor shall provide Test and Balance Work.
 8. General Contractor shall be required to perform any and all Work associated with underground work. General Contractor shall be responsible to avoid damage to existing components and utilities, and shall provide means to verify, i.e. x-ray of slabs prior to cutting/demolition. General Contractor shall be responsible to restore existing components that may be disrupted during construction.
 9. General Contractor shall provide any and all demolition and or prep work to any existing/remaining components, confirm and/or make safe/confirm utility shut-off. General Contractor shall attend a pre-bid walk-thru of the spaces where the construction will occur.
 10. General Contractors shall provide all materials, compliant with any specific testing i.e. NOA, etc. as required.
 11. Within 1 week of contract award, General Contractor shall provide a listing of all subcontractors who will perform the Work.
 12. General Contractor will work with the Project Team to expedite submittals, procurement, and installation. General Contractor shall provide on-site full-time Project Management, Project Engineering, and Superintendent support for the duration of the Work. Project Team shall attend daily coordination meetings to work thru any and all issues, including to expedite submittal review.
 13. General Contractor shall ensure that all Applicable Codes and Standards are adhered to for the installation of all components.
 14. General Contractor shall cooperate fully with the Construction Manager and other key trades to ensure obtaining the Certificate of Occupancies in an expeditious manner.
 15. General Contractor shall provide all necessary and/or required cutting, excavation, dewatering, stabilization, backfill and concrete pour back of slabs.
 16. General Contractor shall review work areas which precede their installation and shall advise Construction Manager, in writing, of any condition whose defect exceeds industry standards. Contractor shall patch minor cracks, holes and depressions/imperfections for preparation of existing surfaces. Proceeding with work shall indicate acceptance of work areas and/or substrate.
 17. General Contractor shall comply with all necessary field conditions before installation which includes but not limited to temperature, humidity and ventilation limitations. General Contractor shall test substrate and areas, as necessary, for containment of moisture and moisture vapor emission, pH, and alkalinity levels that would be detrimental to the installation of this subcontractor's materials to ensure compliance with the contract documents and manufacturer's installation recommendations. General Contractor shall provide any required

Attachment II

Subcontractor's Scope of Work

- etching and/or applied materials to floor surfaces per manufacturer's recommendations to address moisture condition when prepping floors for scheduled finishes.
18. General Contractor shall coordinate all work with other subcontractors and Owner for cutouts and FF&E.
 19. General Contractor acknowledges that ceiling heights may vary based on conditions in the field, and information will be provided and considered at no additional costs to this Contractor's scope.
 20. General Contractor shall provide proper transitions of its scope of work between existing and new surfaces [similar/dissimilar surfaces].
 21. General Contractor shall furnish and install fire stopping and fire safing, including but not limited to at top of wall terminations for drywall walls and where the subcontractor's work abuts the work of others, in accordance with the Contract Documents.
 22. Provide all block outs as required by other trades. Frame and finish around each block out as required and necessary to provide complete, structural, finished work. Coordinate size of openings with other subcontractors and Construction Manager.
 23. General Contractor shall furnish and install all necessary blocking, sheathing, and/or metal strapping to support wall mounted equipment and accessories, as required whether or not indicated on the drawings, for items including but not limited to all casework, toilet partitions and accessories, food service equipment and shelving, TV brackets, etc. for fixtures, TV mounting brackets, toilet partitions, toilet accessories, wall-mounted door stops, handrails, all projection screens, food service and laundry equipment, fire extinguisher cabinets, acoustical panels, millwork & cabinets, and any other concealed backing for proper support of all wall mounted items. This includes any backing as shown to be required in the Contract Documents as well as submittals by other trades.
 24. General Contractor shall furnish and install access panels in walls and/or ceilings where required.
 25. General Contractor shall coordinate with MEP trades such that holes in walls or ceilings are properly sized to receive finish devices.
 26. General Contractor understands that, on a continuous basis, Subcontractor will neatly stack, store, and protect all materials. Masonry mortar and Drywall mud will be scraped up each day and the floors in the area will be left broom cleaned.
 27. General Contractor shall clean/remove any efflorescence from CMU bloc that may develop over the course of the project.
 28. General Contractor is responsible for distribution of water and electric from a source located on site. General Contractor shall be responsible to provide necessary electric and water if source is not adequate.
 29. General Contractor shall furnish and install partition types as shown on the partition type schedule and the Life Safety Plan in accordance with the Contract Documents.
 30. General Contractor shall furnish and install rated walls, complete even if there are discrepancies between Life Safety and Architectural Plans.
 31. General Contractor shall furnish and install all bracing as required for wall support.
 32. General Contractor shall provide permanent identification of all fire rated walls as required.
 33. The Contract Documents may not show partition tags at every wall. General Contractor shall assume that when a wall or series of walls encloses a room, changes direction, or extends out from the wall, that is the same partition type unless another partition tag is indicated. This Subcontractor shall assume that walls not designed for type are the work of this Subcontract.
 34. General Contractor shall provide acoustical sealants at areas under this Subcontract [including minor fire caulking of existing conditions], sealant within this subcontractor's work between

Attachment II

Subcontractor's Scope of Work

- this subcontractor's work and in-place construction in accordance with the Contract Documents.
35. General Contractor shall provide all Acoustical/Thermal Insulation were required for this contractor's assemblies, in accordance with the Contract Documents.
 36. General Contractor shall install all sealants within the work of this subcontract and to dissimilar materials, including but not limited to door frames, etc.
 37. General Contractor shall provide control joints complete as specified or as required under general drywall construction practice to complete the wall system.
 38. General Contractor shall provide all gypsum finishing. Subcontractor shall provide texture of drywall surfaces in accordance with the Contract Documents. Texture must be of a consistent volume and thickness. General Contractor acknowledges that the finish of the drywall will not be considered complete until Construction Manager [Hunt] agrees the finish is acceptable to be primed and painted. Construction Manager will conduct a pre-painting walk-through with its Subcontractor and the Painting Subcontractor prior to start of painting scope.
 39. General Contractor shall not fasten or support its work to any ductwork, mechanical, or electrical components.
 40. General Contractor shall provide cement plaster and/or stucco system, complete as required by the Contract Documents.
 41. General Contractor shall engineer, furnish and install all cold formed metal framing as defined to be included in this Subcontractor's scope, including all studs, channels, clips, ties, stiffeners, bridging, and accessories for a complete installation. When required by the Contract Documents or applicable codes, all engineering and shop drawings shall be provided by a Professional Engineer licensed in the State of Florida.
 42. General Contractor's work will be scheduled to follow most HVAC, plumbing, fire protection, electrical, and special systems work. General Contractor shall erect work tight to such existing in-place work. General Contractor shall thoroughly review Construction Drawings to understand work crossing its partitions and ceilings. HVAC, plumbing, fire protection, electrical, and special systems subcontractors shall provide required sealant, fire stopping, and fire safing around their work through stud partitions. This contractor is responsible for maintaining the specified separation between such in-place work and partitions. Any separation wider than allowable for proper sealant, fire stopping, and fire safing work shall be the responsibility of this General Contractor.
 43. Drawing references made are for clarification only and are not intended to limit the scope or quantity of the work included in this Subcontract.
 44. Where an omission may occur in the Contract Documents, General Contractor is to include a finish similar to adjacent areas.
 45. General Contractor shall protect all smoke alarms and all other systems that could activate during this Subcontractor's work. Subcontractor shall be responsible for all costs associated with activated alarms due to this Subcontractor's Work.
 46. All work is to be scheduled so as to protect other trades from potentially intense fumes and/or dust, and afford the activities of other trades to continue unimpeded.
 47. General Contractor shall provide supplemental exhaust and/or circulating fans to mitigate odors and/or dust throughout installation of this work scope.
 48. General Contractor shall provide and install necessary materials to properly protect surfaces from damage and wear during construction operations until accepted by the Owner. This shall include protection of all adjacent finishes, since many adjacent finishes cannot be cleaned if exposed to traffic coatings, concrete stain, paint, sealers, etc. Any adjacent finishes permanently damaged by any Work of this Subcontractor will be removed and replaced at this subcontractor's cost.

Attachment II

Subcontractor's Scope of Work

49. Any surfaces that are disturbed or damaged by General Contractor's work shall be properly cleaned and/or repaired to ensure continuity and integrity between surfaces.
50. Removal of all temporary protection installed by this General Contractor shall be removed by this General Contractor.
51. Provide attic stock as specified in the Contract Documents.
52. General Contractor shall provide 3 stages of final clean for the Club spaces, including, rough clean, final clean, and 'fluff and buff', as directed by Hunt Construction Group.

D. Exclusions

1. The following items are specifically excluded from the Work of this Subcontract.
 - a. Fire Protection System (Sprinklers and Fire Alarm).
 - b. MEP Infrastructure to club space vicinity [i.e. nearest AHU].
 - c. Food Service Hood exhaust (Grease Duct, Scrubbers, etc.).
 - d. Beer and Soda Conduit.
 - e. Food Service Electrical and Plumbing connections.
 - f. 200/300 level Suites
 - g. All Rails
 - h. FF&E [loose furnishings].
 - i. Chairs
 - j. ADA Signage
 - k. Throw rugs
 - l. Televisions
 - m. Kitchen supplies
 - n. Fabric for Banquet Seating
 - o. Artwork mirrors (not to be confused with standard mirrors)
 - p. Grab bars, paper towel waste receptacles, women's paper towel disposals, women's sanitary napkins/tampon vending machine.
 - q. HM Frame, Door, and Hardware at the 'white box' walls.
 - r. Toilet Accessories Materials, listed as Owner furnished.

E. Unit Prices

1. Hunt reserves the right to modify (add or remove) the Work in accordance with the following Unit Prices at the costs noted. Unit prices are valid throughout the duration of the project and include all burden, overhead, markup, taxes, profit, etc.
 - a. NONE.