

SBD – CM REVIEW FORM (REVISED)

To: Business Opportunity Support Division – Construction	
From: SBD CM Vivian Forhat-Diaz	
Department: WASD	Contact: Leo Vargas
Date: 01/22/14	RESUBMITTAL: No

PROJECT NUMBER:	RPQ P0130
PROJECT TITLE:	One Year Countywide Contract for Rehabilitation of Sanitary Sewer by the Cured-in-Place Pipe Lining Method
PROJECT LOCATION:	Various Locations County wide

SCOPE OF WORK/DESCRIPTION: Includes all labor, materials, tools, equipment required for rehabilitating defects in 8 through 27 inch diameter gravity sanitary sewer pipes by the cured-in-place pipe lining method. The work includes supplementary cleaning of the affected existing gravity sanitary sewers, insulating the reach of sewer to be repaired, inspecting it with closed circuit television (CCTV), installing a cured-in-place pipe liner and re-inspecting the repaired reach with CCTV.

SPECIAL REQUIREMENTS: Contractors must possess a Florida General Contractor, State of Florida Underground Utility / Excavation Contractor, Miami-Dade County General Contractor, Miami-Dade County General Engineering Contractor, Miami-Dade County Pipeline Contractor license. Prime must have a minimum of 5 years' experience performing pipeline installations and/or Cured-in-Place repairs for Miami-Dade County's WASD. Additionally, Contractor must submit proof that the firm has been regularly and successfully engaged in the installation of the liner product for a minimum of one (1) year, and has successfully performed an aggregate amount of at least 100,000 linear feet of sanitary sewer repairs of 6 through 24 inches or larger in diameter in sub-aqueous conditions. Further, Contractors must submit proof that the liner system submitted must have a documented minimum amount of 500,000 linear feet of any pipe diameter of successful wastewater installation in the United States

TRADES/SUBTRADES	AMOUNT	COMMENTS
PRIME		
Cured-in-place 8" dia. Pipe lining up to 24' deep	\$2,100,000.00	Must meet special requirements. Primary scope of work includes all line items noted. No ancillary work that can be sub-contracted.
Cured-in-place 10" dia. Pipe lining up to 24' deep	\$160,000.00	
Cured-in-place 12" dia. Pipe lining up to 24' deep	\$105,000.00	
Cured-in-place 15" dia. Pipe lining up to 24' deep	\$74,000.00	
Cured-in-place 18" dia. Pipe lining up to 24' deep	\$45,000.00	
Cured-in-place 21" dia. Pipe lining up to 24' deep	\$20,000.00	
Cured-in-place 24" dia. Pipe lining up to 24' deep	\$24,000.00	
Cured-in-place 27" dia. Pipe lining up to 24' deep	\$30,000.00	
Reinstatement service laterals	\$112,000.00	
Sealing Lateral connections	\$280,000.00	
Cured-in-place any dia. In easement areas	\$22,500.00	
Bypass pumping of sewage	\$10,000.00	
Maintenance of traffic	\$10,000.00	

Small Business Development Signature: *Vivian Forhat Diaz* Date: 01/22/14

***Trades/Subtrades identified for possible subcontracting opportunities by SBD CM**
WASD is recommending No Measure for CSBE participation.

PROJECT NUMBER: RPQ #P0130 (Continuation)

BASE SUB-TOTAL	\$2,992,500.00	
CONTINGENCY/ALLOWANCE		
Contingency	\$299,250.00	
Uniformed off-duty Officers	\$35,000.00	
Cleaning & Pre-work video inspection	\$2,000.00	
Cured-in-place lining repairs in excess of quantities above	\$100,000.00	
Reimbursement of construction related permit fees	\$15,000.00	
TOTAL ESTIMATED COST	\$3,443,750.00	

WASD is recommending **No Measure** for **CSBE** participation.