



PROJECT: COURTSIDE FAMILY APARTMENTS

Current Builders Disclaimer: The scope of work below may not be all inclusive but is offered only as an aide to the subcontractor in providing a proposal for the referenced project. Subcontractor warrants that he has thoroughly reviewed the contract documents and by submitting his proposal includes all work for his trade regardless of its exclusion from this scope provided to the subcontractor.

SECTION: 05-5200 Handrails and Railing

Subcontractor's Information

Firm:
Phone: Fax:
Contact Person:

SCOPE OF WORK

DESCRIPTION	Quantity	Unit	Cost	Y	N	Remarks
GENERAL CONDITIONS						
Mobilization / Demobilization		LS				
Sales Tax per Miami / Broward / Palm Beach counties		LS				
Permit & Permit Fees		LS				Fees = \$
Attached pre-qualification form must be filled out						
Handrails and Railings						
Supply, Deliver & Install Following Items:						
Balcony Railings						
44" High welded aluminum patio and balcony railing consisting of 2" square posts core drilled, (1) 2-5/8" by 1-1/2" top cap, (1) 2" x 1" bottom channel, 3/4" square picket with the geometric overlay. Detail A8.0/3 is excluded.		LF				
All layout is by this subcontractor						
Stair Handrails						
42" high welded aluminum stair railing consisting of 2" square posts core drilled with (1) 2-5/8" x 1-1/2" top cap, (1) 2" x 1" bottom channel and 3/4" square picket with (1) line 1-1/2" of OD continuous handgrip and wall mounted handgrip. (2) line cane markers and handicap loops.		LF				
General						
Powder coated finish in black, white, or bronze						
Provide 6 sets of signed and sealed shop drawings and calculations for all fabricated products						
All layout is by this subcontractor						
Miami Dade Responsible Wages (see attached wage scale)						
TOTAL QUOTE						
Proposed Alternates:						
Revised Quote:						
REVISIONAL TERMINATE QUOTE						