

White Jr., Tyrone (ISD)

Subject: ***Verification of Availability*** 05-5200 HANDRAILS AND RAILING

Good afternoon,

SBD has received a request to determine if certified SBE-Construction firms are available and interested to perform work related to brand new Courtside Family Apartments. Please see the attached pre-qualification form and advise if your firm can perform the "HANDRAILS AND RAILING" work listed on the form. **This project is time sensitive, so the deadline for your firm's response is 2:30 PM tomorrow, March 27, 2015.**

Can you firm perform the attached "HANDRAILS AND RAILING" work?

Yes **No**

Name of Firm: _____

Contact Person: _____

Phone Number: _____

Tyrone White

Contract Certification Specialist

Small Business Development Division

Miami-Dade County Internal Services Department

111 NW 1st Street, 19th Floor, Miami, FL 33128

☎ Office: (305) 375-3123 | 📠 Fax: (305) 375-3160

Email: twj@miamidade.gov



"Help stimulate Miami's economy by supporting Small Businesses"



PROJECT: COURTSIDE FAMILY APARTMENTS

Current Builders Disclaimer: The scope of work below may not be all inclusive but is offered only as an aide to the subcontractor in providing a proposal for the referenced project. Subcontractor warrants that he has thoroughly reviewed the contract documents and by submitting his proposal includes all work for his trade regardless of its exclusion from this scope provided to the subcontractor.

SECTION: 05-5200 Handrails and Railing

Subcontractor's Information

Firm:
Phone: Fax:
Contact Person:

SCOPE OF WORK

DESCRIPTION	Quantity	Unit	Unit Price	Total Price	Y	N	Remarks
GENERAL CONDITIONS							
Mobilization / Demobilization		LS					
Sales Tax per Miami / Broward / Palm Beach counties		LS					
Permit & Permit Fees		LS					Fees = \$
Attached pre-qualification form must be filled out							
Handrails and Railings							
Supply, Deliver & Install Following Items:							
Balcony Railings							
44" High welded aluminum patio and balcony railing consisting of 2" square posts core drilled, (1) 2-5/8" by 1-1/2" top cap, (1) 2" x 1" bottom channel, 3/4" square picket with the geometric overlay. Detail A8.0/3 is excluded. All layout is by this subcontractor		LF					
Stair Handrails							
42" high welded aluminum stair railing consisting of 2" square posts core drilled with (1) 2-5/8" x 1-1/2" top cap, (1) 2" x 1" bottom channel and 3/4" square picket with (1) line 1-1/2" of OD continuous handgrip and wall mounted handgrip. (2) line cane markers and handicap loops.		LF					
General							
Powder coated finish in black, white, or bronze							
Provide 6 sets of signed and sealed shop drawings and calculations for all fabricated products							
All layout is by this subcontractor							
Miami Dade Responsible Wages (see attached wage scale)							
TOTAL QUOTE							
Proposed Alternates:							
Revised Quote:							
REVISED ALTERNATE QUOTE							