ADAP.	Adapter
A.R.V.	Air Release Valve
ASPH.	Asphalt
A.C.P.	Asbestos Cement Pipe
Ave.	Avenue
℄	Base Line
B.J.	Break Joint
B.	Bell
B.O.	Blow–Off
BOT.	Bottom
BUTT. V.	Butterfly Valve
℄	Center Line
C.V.	Check Valve
COR.	Corner
C.B.	Catch Basin
C.C.	Center to Center
C.I.P.	Cast Iron Pipe
CONN.	Connection
CONC.	Concrete
COND.	Conduit
CONT.	Contract
C.B. #	Core Boring #
C.M.P.	Corrugated Metal Pipe
CORP. STOP	Corporation Stop
CU. YD.	Cubic Yard
DET.	Detail
D.I.P.	Ductile Iron Pipe
DWG.	Drawing
DIV.	Division
DWY.	Driveway
E.	East
EL.	Elevation
ELEC.	Electric
E.O.P.	Edge of Pavement
EXIST.	Existing
F.B.	Full Bevel
F.B. #	Field Book No.
F.H.	Fire Hydrant
FLG.	Flanged – Flange
F.O.	Flanged Outlet
FTG.	Footing
F.M.	Force Main
F.V.O.	Flushing Valve Outlet
GALV.	Galvanized
G.I.A.	Galvinized Iron Pipe
G.	Gas
G.V.	Gate Valve
GA.	Gauge

ITEM	CROSS REF.	SPEC. REF.

MIAMI-DADE COUNTY
Delivering Excellence Every Day
WATER & SEWER DEPARTMENT

ISSUE DATE	APPROVED BY
06/01/2008	V.F.C.

STANDARD DETAIL

ABBREVIATIONS FOR DEPARTMENT'S PROJECTS

A
10.0