




Sheet Number: 4.5

**Product Specifications**

Miami-Dade Water & Sewer Department  
 Address: 3071 SW 38th Ave, Miami, FL 33146  
 Phone: (305) 665-7477  
 Email: WASD-STANDARDS@miamidade.gov

**Sewer Check Valve**



**Minimum Standards**

- AWWA C508
- ANSI B16.1 Class 125
- ANSI/ASTM A123, A153
- MDWASD Specifications: Sections 40 05 58 (15100), 40 05 65.23 (15115)

**Other Requirements**

- Iron Body Bronze Mounted
- Clapper Hinge Pin 316 Stainless Steel
- Body and Clapper Seating Surface – Metal to Metal or Resilient to Metal
- Cushioned Check Valves are required for high heads (75ft TDH and above)

**Applications**

- Sewer

**PRE-APPROVED MANUFACTURER**

- |   |                         |
|---|-------------------------|
| 1) American Flow Control / American-Darling | 2) Golden Anderson (GA) |
| 3) APCO / DeZURIK                           | 4) Mueller              |
| 5) Clow / M&H / Kennedy                     | 6) VSI Waterworks       |

**Issue Date:**

4/4/2016

**Revised Date:**

5/5/2022

**APPROVED PRODUCTS / MODELS**

SIZE	MANUFACTURER	MODEL	SUBMITTED
4" - 12"	American Flow Control / American-Darling	Series 600 or 50 line	<input type="checkbox"/>
4" - 24"	APCO / DeZURIK	SERIES 6000, Swing Check Valve	<input type="checkbox"/>
4" - 30"	Clow / M&H / Kennedy	59, 106, 159, 259	<input type="checkbox"/>
4" - 30"	Golden Anderson (GA)	GA Series 340 Swing Check Valves	<input type="checkbox"/>
4" - 30"	Golden Anderson (GA)	GA Series 350 Air Cushioned Check Valves	<input type="checkbox"/>
4" - 30"	Mueller	Series 2600	<input type="checkbox"/>
4" - 16"	VSI Waterworks	Swing Check valves Series CVI	<input type="checkbox"/>

**SIZES FURNISHED:**

- |                              |                              |                                |
|------------------------------|------------------------------|--------------------------------|
| <input type="checkbox"/> 4"  | <input type="checkbox"/> 12" | <input type="checkbox"/> 20"   |
| <input type="checkbox"/> 6"  | <input type="checkbox"/> 14" | <input type="checkbox"/> 24"   |
| <input type="checkbox"/> 8"  | <input type="checkbox"/> 16" | <input type="checkbox"/> 30"   |
| <input type="checkbox"/> 10" | <input type="checkbox"/> 18" | <input type="checkbox"/> Other |

**COMMENTS:**

---



---



---

**Approved by:** MDWASD Departmental Standards, Specifications, and Product Committee

**Revision History**

3-7-2019: Updated Model Numbers for GA Check Valves; Updated Requirements to allow resilient to metal;

6-24-2021: Updated American Flow Control to American Flow Control / American-Darling and APCO to APCO / DeZURIK

5-5-2022: Added VSI Waterworks, Series CVI