



September 30, 2022

RFI NO. 3 - CLARIFICATION

Project Title: **Roadway Improvements to SW 268 St from SW 139 Ave to SW 119 Ave**
Project No.: **20210224 (Capital)**

Disregard in its entirety answer provided on question from Ms. Hamill Andrade, Ric-Man International, Inc.; dated September 20, 2022, 8:27 A.M. and replace with the following:

QUESTION: 1) PDF 39 – Page 51 of 131 – Section F. Lining and Coatings 1.a states: “In saltwater intrusion areas where the installation is subject to groundwater variation, the Department shall require the use of VBio Enhanced Polyethylene Encasement and ductile iron pipe with a zinc basecoat under the asphaltic topcoat...” Is this Polywrap required on this project? And is so, on what portions of project?

RESPONSE: 1)The project area currently lies within a Saltwater intrusion zone. For this reason, V-Bio Enhanced Polyethylene Encasement is required for all proposed water main installations as called out on sheet P-3 & P-4. Please refer to item WS-1050-11-0019, For furnishing & Install polyethylene encasement as directed by the Engineer.

END OF CLARIFICATION FOR RFI No. 3

Sincerely,

Alfredo E. Muñoz, P.E.
Chief, Capital Improvements Division
Department of Transportation and Public Works (DTPW)

AM:kf

C:

Jean Bernard Philippeaux, DTPW
Fernando Mardones, DTPW
Jacqueline Fussell

Rene Idarraga, P.E., DTPW
Marcia Martin, ISD

Clerk of the Board
Project File