

APPENDIX "F" TO SPECIAL PROVISIONS
STRUCTURES LOAD RATING CALCULATIONS

LOAD RATING CALCULATIONS

FOR

Project Number:

PW Project No. 20200315, EDP-MT-20200315

Rehabilitation Design

For

**Matheson Hammock Park Road (Bridge No.874294) over
Matheson Hammock Canal**

MIAMI-DADE

DEPARTMENT OF TRANSPORTATION AND PUBLIC WORKS

1/18/2022

THIS LOAD RATING IS PROVIDED AT THIS TIME FOR
INFORMATION ONLY. A FORMAL COMPLETE LOAD
RATING OF THE EXISTING "AS-BUILT"
REHABILITATED BRIDGE WILL BE PROVIDED AFTER
CONSTRUCTION TO CONFIRM THAT THE CURRENT
BRIDGE POSTING CAN BE REMOVED.

Table of Contents

1.0	LOAD RATING SUMMARY	3
2.0	EXISTING BRIDGE	4
3.0	BRIDGE CONFIGURATION.....	4
4.0	ANALYSIS APPROACH.....	4
	EVALUATION OF REHABILITATED BRIDGE (REPAIRED CONDITION)	5
5.0	REFERENCES.....	5
6.0	CONCLUSIONS	5
APPENDICES		8
	APPENDIX A – AASHTOWARE BRR BRIDGE RATING INPUT	8
	APPENDIX B – AASHTOWARE BRR BRIDGE RATING OUTPUT	166
	APPENDIX C – SONOVOID SLAB UNIT STRENGTHENING – CFRP EVALUATION.....	224
	APPENDIX D – LRFR BRIDGE RATING MATHCAD QUCIK CHECK	246
	APPENDIX E – AS-BUILT BRIDGE PLANS.....	249
	APPENDIX F – FDOT BRIDGE INSPECTION REPORT AND SUBSEQUENT INTERIM REPORTS	263
	APPENDIX G – STRUCTURAL TECHNOLOGIES, LLC., PRELIMINARY BRIDGE REPAIR RECOMMENDATIONS	427

Bridge No.	874294	Analysis Method:	LRFR-LRFD	FDOT Bridge Load Rating Summary Form (Page 1 of 1)
Location	Matheson Hammock Road over Matheson Hammock Canal			
Description	Simply-supported 30'-40'-30', Prestressed voided slab beams 36"x17"			

Rating Type	Rating Type	Gross Axle Weight (tons)	Moment/Shear/Service		Dead Load Factor	Live Load Factor	Live Load Distrib. Factor (axles)	Rating Factor	Span No. - Girder No., Interior/Exterior, %Span Length	RF- Weight (tons)
Level	Vehicle	Weight	Member Type	Limit	DC	LL	LLDF	RF	Governing Location	RATING
Inventory	HL93	36	Prestressed	Strength, Moment	1.25/0.90	1.75	0.256	0.700	Span 2 - Slab Unit 2-8, 0.5L	25.2
Operating	HL93	36	Prestressed	Strength, Moment	1.25/0.90	1.35	0.256	0.908	Span 2 - Slab Unit 2-8, 0.5L	32.7
Permit	FL120	60	Prestressed	Strength, Moment	1.25/0.90	1.35	0.256	0.833	Span 2 - Slab Unit 2-8, 0.5L	50.0
Permit Max Span	FL120	60	Prestressed	Strength, Moment	1.25/0.90	1.35	0.256	0.833	Span 2 - Slab Unit 2-8, 0.5L	50.0
Legal	SU2	17	Prestressed	Strength, Moment	1.25/0.90	1.35	0.256	1.896	Span 2 - Slab Unit 2-8, 0.5L	32.2
	SU3	33	Prestressed	Strength, Moment	1.25/0.90	1.35	0.256	1.009	Span 2 - Slab Unit 2-8, 0.5L	33.3
	SU4	35	Prestressed	Strength, Moment	1.25/0.90	1.35	0.256	1.000	Span 2 - Slab Unit 2-8, 0.5L	35.0
	C3	28	Prestressed	Strength, Moment	1.25/0.90	1.35	0.256	1.768	Span 2 - Slab Unit 2-8, 0.5L	49.5
	C4	36.7	Prestressed	Strength, Moment	1.25/0.90	1.35	0.256	1.251	Span 2 - Slab Unit 2-8, 0.5L	45.9
	C5	40	Prestressed	Strength, Moment	1.25/0.90	1.35	0.256	1.213	Span 2 - Slab Unit 2-8, 0.5L	48.5
	ST5	40	Prestressed	Strength, Moment	1.25/0.90	1.35	0.256	1.258	Span 2 - Slab Unit 2-8, 0.5L	50.3
Emergency Vehicle (EV)	EV2	28.75	Member Type	Limit Test	NA	NA				-1
	EV3	43	Member Type	Limit Test	NA	NA				-1

Original Design Load	HS20 or HS20-S16-44	Performed by:	Yves R. Amisial, E.I.	Date:	01/04/22
Rating Type, Analysis	LRFR-LRFD	Checked by:	Maria A. Pena, PE	Date:	01/07/22
Distribution Method	AASHTO Formula	<p><i>This item has been digitally signed and sealed by</i></p> <p>Sybille Bayard, PE</p> <p>2021.09.13 11:30:02 - 4'00'</p> <p><i>on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.</i></p> <p><i>CONSOR Engineers, LLC.</i></p> <p><i>10651 N Kendall Drive, Suite #117</i></p> <p><i>Miami, FL 33176</i></p> <p><i>Certificate of Authorization: 6876</i></p> <p><i>Sybille Bayard, PE No. 56038</i></p> <p>sbayard@consoreng.com</p>			
Impact Factor	33.0% (axle loading)				
FL120 Gov. Span Length	40.0 (feet)				
Minimum Span Length	30.0 (feet)				
Recommended Posting	At/Above legal loads. Posting Not Required.				
Recommended SU Posting	99 (tons)				
Recommended C Posting	99 (tons)				
Recommended ST5 Posting	99 (tons)				
Owner	02 County Highway Agency				
Location	Neither interstate traffic nor within 1 mile reasonable access to an interstate				
EV Posting	No. EV posting is not recommended. The FAST Act does not apply	<p><i>P.E. Seal</i></p> <p>Comments:</p>			
Floor Beam Present?	No				
Segmental Bridge?	No				
Project No. & Reason	432907-1-72-02 Deterioration				
Plans Status	Built				

This 04-13-2021 summary follows the FDOT Bridge Load Rating Manual (BLRM), and the FDOT BMS Coding Guide.

*Recommended SU Posting levels for Florida SU trucks adequately restricts AASHTO SU trucks; see BLRM Chapter 7.

fdot.gov/maintenance/LoadRating.shtm

Introduction

Bridge 874294, constructed in 1967, carries Matheson Hammock Road over Matheson Hammock Canal in Miami-Dade County. According to the the latest NBIS inspection report dated 04/06/2020 and subsequent interim reports, the ADT for this section of roadway is around 736 vehicles per day with a truck percentage of 1%.

Bridge Configuration

The bridge superstructure consists of three simply-supported prestressed concrete 17"x36" sonovoid slab units. There is evidence at the bridge site of reflective longitudinal cracks in the asphalt wearing surface across the bridge indicating that the slab units are acting independently due to possible deterioration or broken transverse post-tensioned cables. The span configuration is 30.0 feet – 40.0 feet – 30.0 feet, with 11 prestressed slab units in each span. A variable asphalt wearing surface is present along the bridge spans.

Analysis Approach

This current load rating was performed using Load and Resistance Factor Rating (LRFR) methodology from the AASHTOWare Bridge Rating (Version 6.8.4) software. The previous load rating was performed on January 13, 2020 using LRFR methodology and Smart Bridge Suite Version 3.1 software. Since the most recent inspection (performed on 4/26/2021 by Marlin Engineering, Inc.) rated the deck and superstructure as "3 Serious", and the substructure as "4 Poor", this current load rating was performed using a Condition Factor of 0.85 for signification deteriorated prestressed slab units, and a Condition Factor of 0.90 for non-deteriorated prestressed slab units per AASHTO MBE Table 6A.4.2.3-1.

Moreover, given the damage sustained by the controlling interior slab units 2-8 and 2-9 in span no. 2 (severed strand), and as per the 2007 Revision to Publication 238 Bridge Safety Inspection Manual from the Pennsylvania Department of Transportation, under section 6.6.3.3.1I, the following conservative assumptions were considered in the analysis:

"Load ratings of beams with deteriorated and/or damaged prestressing strands are to be based on the following procedures:

- Visually observed strands + 25% - Deduct 100% of all exposed strands plus an additional 25% (125% of the total area of the exposed strands) from capacity calculations.*
- Strands adjacent to or intersecting a crack shall be considered ineffective in the region immediately adjacent to the crack.*
- If significant strand loss is noted (>20%), especially for fascia beams, contact BQAD for further instructions.*
- For beams with no exposed strands but which appear to have internal damage (as evidenced by bottom flange cracking with rust and/or delamination), contact BQAD for further instructions.*
- For fascia beams with Capacity/Dead Load < 1.5 or an Operating Rating < 1.5 based on a conventional analysis, an analysis that considers biaxial stresses will be performed by BQAD.*
- These analysis methods may also be applicable to other pre-stressed box beam bridges"*

Therefore, a load rating analysis was performed to evaluate the existing capacity of the slab units within all three spans and provide recommendations for repair and strengthening as needed.

Evaluation of Rehabilitated Bridge (Repaired Condition)

Additional analysis was conducted to evaluate the existing slab units assuming the replacement of the transverse post-tensioning system and the repair of cracks, delamination and spalls noted in the inspection report. The slab units were analyzed as integral, assuming a live load distribution factor in accordance with the AASHTO LRFD, Section 4.6.2.2.

The following assumptions were made:

1. Assume a condition factor of 0.9 for all slab units.

For Slab Units 2-8 and 2-9 assume 100% section loss of a total of 7 strands in addition to the condition factor of 0.9.

References

This current load rating was performed in accordance with the following manuals, specifications, and software:

- FDOT Structures Manual, January 2021 (SM) (Volume 1 - Structures Design Guidelines - (SDG))
- AASHTO LRFD Bridge Design Specifications, 9th Edition (AASHTO)
- FDOT Bridge Load Rating Manual, January 2021 (BLRM)
- The Manual for Bridge Evaluation, 3rd Edition 2018 (MBE) with 2019 Interims
- PCI Design Handbook, 8th Edition (PCI)
- AASHTOWare Bridge Rating, Version 6.8.4.
- Commonwealth of Pennsylvania Department of Transportation, Revision to Publication 238 Bridge Safety Inspection Manual, 2007.

It should be noted that the 2021 BLRM uses the 9th Edition of the AASHTO LRFD design specifications, and that AASHTOWare Bridge Rating Version 6.8.4 uses the 8th Edition of the AASHTO LRFD design specifications. However, since this bridge uses normal weight concrete and does not have prestressed slab units subjected to significant torsion, the applicable portions of the design codes have not changed between the two editions. Therefore, the software still meets the BLRM requirements for evaluating flexure and shear.

Conclusions

Rehabilitated Bridge (Repaired Condition)

The complete evaluation of all non-deteriorated slab units and repaired deteriorated slab units is shown in Appendix B. The interior and exterior slab units were both evaluated for vehicular live loads. By observations, the SU4 legal truck is the controlling live load; the resulting LRFR rating factors are summarized in the table below.

SUMMARY OF LRFR LOAD RATING RESULTS – SONOVOID SLAB UNITS (w/ Concrete Repairs and Post Tensioning Restored)								
Vehicle	Condition Factor	Member Condition	Live Load Type	Limit State	Controlling Member	Controlling Location (% Span)	Controlling Limit State	Rating Factor
SU 4	0.90	Non-Deteriorated	Axle Load	Legal	Interior Unit (Span 1)	50.0	STRENGTH-I Concrete Flexure	1.387
		Non-Deteriorated			Interior Unit (Span 2)	50.0	STRENGTH-I Concrete Flexure	1.461
		Deteriorated (repaired)			Interior Unit (Unit 1-6 or 1-8)	50.0	STRENGTH-I Concrete Flexure	1.387
		Deteriorated (repaired)			Interior Unit (Unit 2-8 or 2-9)	50.0	STRENGTH-I Concrete Flexure	0.931

Figure 1-4.2 Summary of LRFR Load Rating Results for Rehabilitated Sonovoid Slab Units with Concrete Repairs completed, and Post Tensioning restored.

As indicated above, the deteriorated slab units in Span 2 (2-8 & 2-9) did not achieve a minimum rating factor of 1.0 even when analyzed as integral. Consequently, the remaining capacity that is required to satisfy a minimum LRFR legal rating of 1.0 was computed as a final step in the evaluation process to determine the level of strengthening required to restore the bridge to a non-posted stated, as shown in the table below.

LOAD RATING SUMMARY - (Assuming Post Tensioning)					
Span 2 - INTERIOR Unit 2-8 (LRFR) - SU4					
Location	Condition Factor	Existing Flexural Capacity (kip-ft) **	Existing Shear Capacity (kip) **	Required Flexural Capacity (kip-ft) *	Required Shear Capacity (kip) *
0.00	0.90	135.08	-	-	-
1.12		-	94.16	-	-
1.48		293.46	89.01	-	-
3.85		344.64	70.05	-	-
7.7		344.64	70.05	-	-
11.55		344.64	49.78	-	-
15.4		344.64	38.99	359.34	-
19.25		344.64	-38.35	368.62	-
23.1		344.64	-38.99	359.34	-
26.95		344.64	-53.70	-	-
30.8		344.64	-70.05	-	-
34.65		344.64	-70.05	-	-
37.02		293.46	-89.01	-	-
37.39		-	-94.28	-	-
38.5		108.44	-	-	-


* Minimum Required capacity to meet a minimum Inventory Rating Factor of 1.1, conservatively.

** Existing condition assumes the removal of 7 strands, and 1 exterior stirrup leg to account for the controlling deterioration along the bottom face of the slab units.

Figure 1-4.3 Required Capacity of Rehabilitated Slab Units to satisfy LRFR Legal Rating.

APPENDIX A – AASHTOWARE BrR BRIDGE RATING INPUT

A.1 – SUMMARY OF LOAD RATING PARAMETERS

	Project No:		D210107FL.00	YRA	Date:	9/21/2021
	Bridge No.:		874294	HGD	Date:	9/24/2021
	Feature Carried:		Matheson Hammock Park		Page:	1 of 1

SUMMARY OF DEFICIENCIES

SONOVOID SLABS (UNDERSIDE) - SPAN 1

BEAM NO.	LOCATION	DEFICIENCY
1-1	EB1	Outward location with 1/4" height difference to top of cap
1-6	9-ft from EB1	15" x 6" x 1/2" - spall w/ exposed rebar / minor section loss
	EB1 / East	5'L x 6"W delamination with associated 1/16" cracks
	Pier 2 / East	9'L x 12"W delamination with associated 1/16" cracks
1-7	EB1 / East	24"L x 12"W spall/delamination with associated 1/32" cracks
	Pier 2 / East	7'L x 4"W delamination with associated 1/16" cracks
1-8	EB1 / West	15'L x 15"W delamination with associated 1/4" cracks
	9" from EB1 / West	4' x 6" x 2" - spall
	Pier 2 / East	4'L x 15"W delamination with associated 1/32" cracks
	Pier 2	8'L x 3'W delamination with associated 1/16" cracks
1-9	EB1	36"L x 24"W x 2.5" spall/delamination with exposed stirrup (no loss)
	Pier 2 / West	9'L x 10"W delamination with associated 1/16" cracks

SONOVOID SLABS (UNDERSIDE) - SPAN 2

BEAM NO.	LOCATION	DEFICIENCY
2-6	Pier 2 / East	30"L x 4"W delamination
2-7	Pier 2 / West	24"L x 4"W delamination
	full length	16"W delamination with associated 1/4" cracks
	Pier 2	36"L x full width with associated cracks
2-8	Pier 2 / West	15' x 18"W (average) delamination with associated 1/4" cracks
	Midspan	15'x34"x4" with 7 exposed and corroded transverse rebars w/ 60% section remaining and 5 exposed and corroded strands (3 broken strands) - 0% section remaining
	Pier 3 / West	15' x 18"W (average) delamination with associated 1/4" cracks
	Pier 2 / West	5'L x 5" delamination with associated 1/4" cracks
2-9	Midspan	15'x12"x2" spall/delamination with 2 strands and 7 transverse rebars having up to 90% section remaining

SONOVOID SLABS (UNDERSIDE) - SPAN 3

BEAM NO.	LOCATION	DEFICIENCY
3-6	Pier 3 / East	24"L x 6"W delamination with associated 1/16" crack
	~10' from EB 4 / East	42"L x 8" W with associated 1/16" cracks
3-7	Pier 3	8'L x 15"W delamination with associated cracks
	Midspan	3'L x 30" W
	EB 4	12'L x 36"W unsound repair / hollow sounding
3-8	Pier 3	8'L x 3'W x 1" with associated cracks
	EB4	42" x 30"W unsound repair/ delamination with associated 1/16" cracks
	5.5' from EB 4	74" x 36"W unsound repair/ delamination with associated 1/16" cracks

SUBSTRUCTURE

COMPONENT	LOCATION	DEFICIENCY
PIER CAPS	PIER 2 / South Face	48"L X 17" H X 3/4" Spall / Delamination over column 2-2
	PIER 2 / North Face	20"L x 12" H delamination over column 2-2
	PIER 3 / bottom / North	2~ 30"L x 24"W unsound repairs with 1/64" associated cracks between columns 3-1 and 3-2.
	PIER 3 / top & Bottom / North	3'L x 16" delamination between columns 3-1 and 3-2
COLUMNS	Column 2-2	55"H x 32"W x 4"D spall delamination with exposed longitudinal rebars and 5 stirrups (up to 80% remaining)
	Column 2-2	Delamination (entire column height / circumference) with associated 1/4" cracks
	Columns 2-1, 3-1, 3-2	Delamination (entire length) with associated 1/16" cracks (full height)

SPAN 1 OR 3 - SUPPLEMENTAL CALCULATIONS - LOADING PARAMETERS

Bridge Type: Prestressed Voided Slab Unit - 17"x36"
 Standard Drawing:

Total Superimposed Dead Load:	1.396 k/ft
Bridge Railing/ Guardrail Dead Load:	0.148 k/ft
Curb/Sidewalk Dead Load:	1.248 k/ft
Attached Utility Dead Load:	0.000 k/ft
Asphalt W.S. Dead Load (DW):	0.379 k/ft

Number of Spans = 3
 Structure Length = 100 ft.
 Brg.-to-Brg. Span Length = 28.2917 ft. (Assumed at Centerline of 1/4"x6" wide asbestos graphite pads)
 Analyzed Span Length = 30.00 ft.
 Clear Roadway Width = 26.00 ft.
 Wearing Surface: Yes A 1.0-inch wearing surface is present at the supports, and 1.5-in present at midspan.
 The wearing surface dead loads are calculated by BrR and included in the analysis.

Location	Thickness	Average Thickness		
Begin span	1.00 in	1.167 in	0.040833	4.085469
Mid Span	1.50 in			
End Span	1.00 in			

Bridge Railing/Guardrail: Yes Bridge Railing is present.
 Per SCDOT Load Rating guidance, guardrail dead loads are applied only to fascia beams.
 Curb/Sidewalk: Yes A curbs or sidewalks are present. See below for curb/sidewalk dimensions and dead load calculations.
 Parapet: No No parapets are present.
 Attached Utilities: Yes See below for dead load calculations.

Rail 1 Type: Other Metal Posts and Pipes - Assume 10 lb/ft per SDG Table 2.2-1, Bullet Railing **0.010 k/ft**
 10 lb/ft

Rail 2 Type: Rect. Conc. Beam Rectangular Concrete Beam Guardrail **0.125 k/ft**
 125 lb/ft

Rail Post:	Concrete	Quantity	Length/Height	Shape	Area (Standard shapes per AISC 7-14)	
	150 pcf	3 / span	0.83 ft	Rect. 10x10	100.00 in ²	0.013 k/ft
	150 pcf	2 / span	0.83 ft	Rect. 8x10	80.00 in ²	

Rail Blockout: none


Curb/Sidewalk:	AA	29.0 in				
(South End)	BB	1.0 in				
	CC	10.563 in				0.325 k/ft

- Superstructure is modeled without the sidewalk overhang, that is removing the additional 6" of overhang.
- To account for the actual weight of curb/sidewalk, compute an equivalent Thickness of sidewalk corresponding to a rectangular sidewalk with an equivalent width of:


Equiv. Width of Sidewalk = 24 in (Equivalent width of rectangular sidewalk input in AASHTOWare software)


Equiv. CC = 12.9831 in (Equivalent thickness of rectangular sidewalk input in AASHTOWare software)


Typical Curb/Sidewalk Section



Curb/Sidewalk:	AA	77.0 in				
(North End)	BB	1.0 in				
	CC	11.4 in				0.923 k/ft

 CONSOR	Project No:	D210107FL.00	Calculated by:	YRA	Date:	9/21/2021
	Bridge No.:	874294	Checked by:	MAP	Date:	12/29/2021
	Feature Carried:	Matheson Hammock Road			Page:	1 of 4

 CONSOR	Project No:	D210107FL.00	Calculated by:	YRA	Date:	9/21/2021
	Bridge No.:	874294	Checked by:	MAP	Date:	12/29/2021
	Feature Carried:	Matheson Hammock Road			Page:	2 of 4



- Superstructure is modeled without the sidewalk overhang, that is removing the additional 6" of overhang.
- The 1-ft utility opening will be neglected, leaving 1-ft of additional solid sidewalk material assumed to account for the weight of utilities and attachments at the opening. The resulting width of sidewalk to be input in the software shall be:

Equiv. Width of Sidewalk = 60 in (Equivalent width of rectangular sidewalk input in AASHTOWare software)

- No information is available on the utilities and attachments along the North side of the bridge.
- The Concrete sidewalk will be assumed to be solid at the location of the utility opening to account for the weight of the utilities and attachments, conservatively.
- Assume weight of sidewalk taken by the exterior slab units.

Diaphragm:

Width of Slab Unit = 36 in
Depth of Slab Unit = 17 in
No. of Voids = 2.0000
Diameter of Voids = 10.0000 in

Begin Span					
	Start Dist. From Left End* (FT)	Diaphragm Spacing (FT)	No. of Spaces	Width/ Thickness (IN)	Diaphragm Weight (KIP)
Span 1, Begin	0.00	1.00	1	24.0	0.3272
Span 1, 1/4 Point	1.00	6.25	1	12.0	0.1636
Span 1, 3/4 Point	7.25	15.00	1	12.0	0.1636
Span 1, End	22.25	6.25	1	24.0	0.3272
Span 3, Begin	0.00	1.00	1	24.0	0.3272
Span 3, 1/4 Point	1.00	6.25	1	12.0	0.1636
Span 3, 3/4 Point	7.25	15.00	1	12.0	0.1636
Span 3, End	22.25	6.25	1	24.0	0.3272


LLDF (Post-Tensioned - LFD): (Assuming Members are sufficiently connected to act as a unit, meaning accounting for effective post tensioning)


For Interior/Exterior Slab Units: (Moment & Shear)

[AASHTO LFD 3.23.4.3]

S = 3.0 ft. (Width of precast member)
W = 34.0 ft. (Assumed total width of Bridge Superstructure - ignore opening at the N end sidewalk)
L = 28.291667 ft. (Brg.-to-Brg. Span Length - Span 2)
NL = 2.0 (Number of traffic lanes)
Nb = 11.0 (Number of concrete slab units)
μ = 0.2 (Assumed Poisson's Ratio for concrete slab units)

I = 13330.10 in⁴ (Moment of Inertia of Slab Unit - from BrM software)
J = 14593.77 in⁴ (Saint-Venant Torsion constant - from BrM software)

	Project No:	D210107FL.00	Calculated by:	YRA	Date:	9/21/2021
	Bridge No.:	874294	Checked by:	MAP	Date:	12/29/2021
	Feature Carried:	Matheson Hammock Road			Page:	1 of 4

	Project No:	D210107FL.00	Calculated by:	YRA	Date:	9/21/2021
	Bridge No.:	874294	Checked by:	MAP	Date:	12/29/2021
	Feature Carried:	Matheson Hammock Road			Page:	3 of 4

$$K = [(1 + \mu) \cdot I/J]^{1/2} = 1.04694$$

$$C = \text{if } \left[\frac{W}{L} < 1, K \left(\frac{W}{L} \right), K \right] = 1.04694$$

$$D = (5.75 - 0.5N_L) + 0.7N_L(1 - 0.2C)^2 = 5.6251$$

$$\text{LLDF (INT-M)} = S/D = \boxed{0.5333} \text{ (Live Load Distribution Fraction for Moment)}$$

LLDF (Post-Tensioned - LRFR): (Assuming Members are sufficiently connected to act as a unit, meaning accounting for effective post tensioning)

LLDF(INT - OneLane) =	0.296	(LLDF for One lane loaded for Moment and Shear computed for Interior Slab unit in AASHTOWare BrR in accordance with AASHTO LRFD Tables 4.6.2.2.2b-1 and 4.6.2.2.2d-1)
LLDF(INT - MultiLane) =	0.273	(LLDF for Multi lanes loaded for Moment and Shear computed for Interior Slab unit in AASHTOWare BrR in accordance with AASHTO LRFD Tables 4.6.2.2.2b-1 and 4.6.2.2.2d-1)

For Exterior Slab Units: (Moment)

[AASHTO LRFD Table 4.6.2.2.2d-1]

$$d_{e,G11} = -1.0 \text{ ft.}$$

(Horizontal distance from centerline of exterior web of exterior beam/slab unit along the south end at deck level to interior edge of curb or traffic barrier) - (Ext.web = 5"; outboard of curb) - limited to -1.0 since de computed is = 1.8' per AASHTO LRFD 4.6.2.2.2d.

$$d_{e,G1} = -1.0 \text{ ft.}$$

(Horizontal distance from centerline of exterior web of exterior slab unit along the south end at deck level to interior edge of curb or traffic barrier) - (Ext. web = 5"; outboard of curb) - limited to -1.0 since de computed is = 4.8' per AASHTO LRFD 4.6.2.2.2d.

- One Design Lane Loaded:

$$e_{\text{OneLane}_G1} = 1.125 + \frac{d_{e,G1}}{30} \geq 1.0 = 1.000 \text{ (Correction factor for LL distribution on exterior slab unit G1)}$$

$$e_{\text{OneLane}_{G11}} = 1.125 + \frac{d_{e,G11}}{30} \geq 1.0 = 1.000 \text{ (Correction factor for LL distribution on exterior slab unit G11)}$$

$$\text{LLDF (EXT.G1-M}_{\text{OneLane}}) = e \cdot \text{LLDF(INT - M)} = \boxed{0.2960} \text{ (Live Load Distribution Fraction for Moment for One lane Loaded - Unit G1)}$$

$$\text{LLDF (EXT.G11-M}_{\text{OneLane}}) = e \cdot \text{LLDF(INT - M)} = \boxed{0.2960} \text{ (Live Load Distribution Fraction for Moment for One lane Loaded - Unit G11)}$$


- Two or More Design Lanes Loaded:


$$e_{\text{OneLane}_G1} = 1.04 + \frac{d_{e,G1}}{25} \geq 1.0 = 1.000 \text{ (Correction factor for LL distribution on exterior slab unit G1)}$$

$$e_{\text{OneLane}_{G11}} = 1.04 + \frac{d_{e,G11}}{25} \geq 1.0 = 1.000 \text{ (Correction factor for LL distribution on exterior slab unit G11)}$$

$$\text{LLDF (EXT.-M}_{\text{MultiLane}}) = e \cdot \text{LLDF(INT - M)} = \boxed{0.2730} \text{ (Live Load Distribution Fraction for Moment for Multi-Lanes Loaded - Unit G1)}$$

$$\text{LLDF (EXT.-M}_{\text{MultiLane}}) = e \cdot \text{LLDF(INT - M)} = \boxed{0.2730} \text{ (Live Load Distribution Fraction for Moment for Multi-Lanes Loaded - Unit G11)}$$

	Project No:	D210107FL.00	Calculated by:	YRA	Date:	9/21/2021
	Bridge No.:	874294	Checked by:	MAP	Date:	12/29/2021
	Feature Carried:	Matheson Hammock Road			Page:	1 of 4

	Project No:	D210107FL.00	Calculated by:	YRA	Date:	9/21/2021
	Bridge No.:	874294	Checked by:	MAP	Date:	12/29/2021
	Feature Carried:	Matheson Hammock Road			Page:	4 of 4

For Exterior Slab Units: (Shear)

[AASHTO LRFD Table 4.6.2.2.3b-1]

$$d_{e,G1} = -1.0 \text{ ft.}$$

(Horizontal distance from centerline of exterior web of exterior slab unit along the south end at deck level to interior edge of curb or traffic barrier) - (Ext. web = 5"; outboard of curb) - limited to -1.0 since d_e computed is = 4.8' per AASHTO LRFD 4.6.2.2.2d.

$$d_{e,G11} = -1.0 \text{ ft.}$$

(Horizontal distance from centerline of exterior web of exterior beam/slab unit along the south end at deck level to interior edge of curb or traffic barrier) - (Ext. web = 5"; outboard of curb)

$$b = 36.0 \text{ in.}$$

(Width of precast member)

- One Design Lane Loaded:

$$e_{\text{OneLane}_G1} = 1.25 + \frac{d_{e,G1}}{20} \geq 1.0 = 1.000 \text{ (Correction factor for LL distribution on exterior slab unit G1)}$$

$$e_{\text{OneLane}_{G11}} = 1.25 + \frac{d_{e,G11}}{20} \geq 1.0 = 1.000 \text{ (Correction factor for LL distribution on exterior slab unit G11)}$$

$$\text{LLDF (EXT.G1-M}_{\text{OneLane}}) = e_{\text{OneLane}_{G1}} \cdot \text{LLDF (INT,V)} = 0.2960 \text{ (Live Load Distribution Fraction for Shear for One lane Loaded - Unit G1)}$$

$$\text{LLDF (EXT.G11-M}_{\text{OneLane}}) = e_{\text{OneLane}_{G11}} \cdot \text{LLDF (INT,V)} = 0.2960 \text{ (Live Load Distribution Fraction for Shear for One lane Loaded - Unit G11)}$$

- Two or More Design Lanes Loaded:

$$e_{\text{MultiLane}_{G1}} = 1.0 + \left(\frac{d_{e,G1} + \frac{b}{12} - 2.0}{40} \right)^{0.5} \geq 1.0 = 1.000 \text{ (Correction factor for LL distribution on exterior slab unit G1)}$$

$$e_{\text{MultiLane}_{G11}} = 1.0 + \left(\frac{d_{e,G11} + \frac{b}{12} - 2.0}{40} \right)^{0.5} \geq 1.0 = 1.000 \text{ (Correction factor for LL distribution on exterior slab unit G11)}$$

$$\text{LLDF (EXT.-M}_{\text{MultiLane}}) = e_{\text{MultiLane}_{G1}} \cdot \text{LLDF (INT,V)} = 0.2730 \text{ (Live Load Distribution Fraction for Shear for Multi-Lanes Loaded - Unit G1)}$$

$$\text{LLDF (EXT.-M}_{\text{MultiLane}}) = e_{\text{MultiLane}_{G11}} \cdot \text{LLDF (INT,V)} = 0.2730 \text{ (Live Load Distribution Fraction for Shear for Multi-Lanes Loaded - Unit G11)}$$

LLDF (Exist.Condition - LFD): (Assuming Slab Members acting independently - no effective post tensioning)

$$S = 3.0 \text{ ft.}$$

(Width of precast member)

$$W = 34.0 \text{ ft.}$$

(Assumed total width of Bridge Superstructure - ignore opening at the N end sidewalk)

$$L = 28.291667 \text{ ft.}$$

(Brg.-to-Brg. Span Length - Span 2)

$$NL = 2.0$$

(Number of traffic lanes)

$$Nb = 11.0$$

(Number of concrete slab units)

$$D = 3.0000$$

(Assumed equal to Precast member width since slab unit will behave independently. Therefore, individual unit can be assumed to take on the full wheel load)

$$\text{LLDF (INT - LFD)} = S/D = 1.0000 \text{ (Live Load Distribution Fraction for Moment and Shear)}$$

LLDF (Exist.Condition - LRFR): (Assuming Slab units acting independently - no effective post tensioning)

$$\text{LLDF (INT - OneLane - LRFR)} = 0.5 \times \text{Axle} = 0.5000 \text{ (Live Load Distribution Fraction for Moment and Shear - Half of Axle Load)}$$

$$\text{LLDF (INT - OneLane - LRFR)} = 0.5 \times 1.2 \times \text{Axle} = 0.6000 \text{ (Live Load Distribution Fraction for Moment and Shear - Half of Axle Load)}$$

Analysis Case: A) For the purpose of the Load Rating, the following Cases were assumed for AASHTOWare BrR runs:

- Case 1: Run model to account for the condition where the slab units have been rehabilitated with Post Tensioning.
- Case 2: Run model to account for the existing condition without repairs.

B) Per current inspection report, the following are assumed in the analysis to account for the deterioration of the slab unit 1-8:

- West edge of slab unit intermittently delaminated with efflorescence and corrosion bleed-out and associated spalling.
- Assume a condition factor of 0.85 to account for the analysis of the worst case deteriorated slab unit from spans 1 & 3.

SPAN 2 - SUPPLEMENTAL CALCULATIONS - LOADING PARAMETERS

Bridge Type: **Prestressed Voided Slab Unit - 17"x36"**
Standard Drawing:

Total Superimposed Dead Load:	1.395 k/ft
Bridge Railing/ Guardrail Dead Load:	0.147 k/ft
Curb/Sidewalk Dead Load:	1.248 k/ft
Attached Utility Dead Load:	0.000 k/ft
Asphalt W.S. Dead Load (DW):	0.420 k/ft
Asphalt W.S. Dead Load per Slab Unit (DW):	0.038 k/ft

Number of Spans:	3
Number of Sonovoids:	11
Structure Length:	100 ft.
Brg.-to-Brg. Span Length:	38.5 ft. (Assumed at Centerline of 1/4"x6" wide asbestos graphite pads)
Analyzed Span Length:	40.00 ft.
Clear Roadway Width:	26.00 ft.
Slab Unit Width:	36.00 in.
Wearing Surface:	Yes A 1.0-inch wearing surface is present at the supports, and 1.875-in present at midspan. The wearing surface dead loads are calculated by BrR and included in the analysis.

Location	Thickness	Average Thickness
Begin span	1.00 in	1.292 in
Mid Span	1.88 in	
End Span	1.00 in	

Bridge Railing/Guardrail:	Yes	Bridge Railing is present. Per SCDOT Load Rating guidance, guardrail dead loads are applied only to fascia beams.
Curb/Sidewalk:	Yes	A curbs or sidewalks are present. See below for curb/sidewalk dimensions and dead load calculations.
Parapet:	No	No parapets are present.
Attached Utilities:	Yes	See below for dead load calculations.

Rail 1 Type:	Other	Metal Posts and Pipes - Assume 10 lb/ft per SDG Table 2.2-1, Bullet Railing	0.010 k/ft
	10 lb/ft		

Rail 2 Type:	Rect. Conc. Beam	Rectangular Concrete Beam Guardrail	0.125 k/ft
	125 lb/ft		

Rail Post:	Concrete	Quantity	Length/Height	Shape	Area (Standard shapes per AISC 7-14)	0.012 k/ft
	150 pcf	4 / span	0.83 ft	Rect. 10x10	100.00 in ²	
	150 pcf	2 / span	0.83 ft	Rect. 8x10	80.00 in ²	


Rail Blockout:	none
----------------	------


Curb/Sidewalk:	AA	29.0 in	0.325 k/ft
(South End)	BB	1.0 in	
	CC	10.6 in	


- Superstructure is modeled without the sidewalk overhang, that is removing the additional 6" of overhang.
- To account for the actual weight of curb/sidewalk, compute an equivalent Thickness of sidewalk corresponding to a rectangular
Equiv. Width of Sidewalk = 24 in (Equivalent width of rectangular sidewalk inputted in AASHTOWare software)

Equiv. CC = 12.9831 in (Equivalent thickness of rectangular sidewalk inputted in AASHTOWare software)

Typical Curb/Sidewalk Section



	Project No:	D210107FL.00	Calculated by:	YRA	Date:	9/21/2021
	Bridge No.:	874294	Checked by:	MAP	Date:	12/29/2021
	Feature Carried:	Matheson Hammock Road			Page:	1 of 4

	Project No:	D210107FL.00	Calculated by:	YRA	Date:	9/21/2021
	Bridge No.:	874294	Checked by:	MAP	Date:	12/29/2021
	Feature Carried:	Matheson Hammock Road			Page:	2 of 4

Curb/Sidewalk:	AA	77.0 in
(North End)	BB	1.0 in
	CC	11.4 in

0.923 k/ft

- Superstructure is modeled without the sidewalk overhang, that is removing the additional 6" of overhang.
- The 1-ft utility opening will be neglected, leaving 1-ft of additional solid sidewalk material assumed to account for the weight of utilities and attachments, conservatively.

Equiv. Width of Sidewalk = 60 in (Equivalent width of rectangular sidewalk input in AASHTOWare software)



- No information is available on the utilities and attachments along the North side of the bridge.
- The Concrete sidewalk will be assumed to be solid at the location of the utility opening to account for the weight of the utilities and attachments, conservatively.
- Assume weight of sidewalk taken by the exterior slab units.

Diaphragm:	
Width of Slab Unit =	36 in
Depth of Slab Unit =	17 in
No. of Voids =	2.0000
Diameter of Voids =	10.0000 in

Begin Span					
	Start Dist. From Left End* (FT)	Diaphragm Spacing (FT)	No. of Spaces	Width/ Thickness (FT)	Diaphragm Weight (KIP)
Span 2, Begin	0.00	1.00	1	2.0	0.3272
Span 2, 1/4 Point	1.00	8.96	1	1.0	0.1636
Span 2, 3/4 Point	9.96	20.00	1	1.0	0.1636
Span 2, End	29.9583	8.96	1	2.0	0.3272


LLDF (Post-Tensioned - LFD): (Assuming Members are sufficiently connected to act as a unit, meaning accounting for effective post tensioning)


For Interior Slab Units:

[AASHTO LRFD Table 4.6.2.2.2b-1]

S =	3.0	ft.	(Width of precast member)
W =	34.0	ft.	(Assumed total width of Bridge Superstructure - ignore opening at the N end sidewalk)
L =	38.5	ft.	(Brg.-to-Brg. Span Length - Span 2)
NL =	2.0		(Number of traffic lanes)
Nb =	11.0		(Number of concrete slab units)
μ =	0.2		(Assumed Poisson's Ratio for concrete slab units)
I =	13330.10	in ⁴	(Moment of Inertia of Slab Unit - from BrM software)
J =	14593.77	in ⁴	(Saint-Venant Torsion constant - from BrM software)

$$K = [(1 + \mu) \cdot I/J]^{1/2} = 1.04694$$

	Project No:	D210107FL.00	Calculated by:	YRA	Date:	9/21/2021
	Bridge No.:	874294	Checked by:	MAP	Date:	12/29/2021
	Feature Carried:	Matheson Hammock Road			Page:	1 of 4

	Project No:	D210107FL.00	Calculated by:	YRA	Date:	9/21/2021
	Bridge No.:	874294	Checked by:	MAP	Date:	12/29/2021
	Feature Carried:	Matheson Hammock Road			Page:	3 of 4

$$C = \text{if } \left[\frac{W}{L} < 1, K \left(\frac{W}{L} \right), K \right] = 0.92457$$

$$D = (5.75 - 0.5N_L) + 0.7N_L(1 - 0.2C)^2 = 5.6801$$

$$\text{LLDF (INT - LFD)} = S/D = \boxed{0.5282} \text{ (Live Load Distribution Fraction for Moment and Shear)}$$

For Exterior Slab Units:

[AASHTO LRFD Table 4.6.2.2.2d-1]

$$d_e = \boxed{3.0} \text{ ft. (Width of precast member)}$$

LLDF (Post-Tensioned - LRFR): (Assuming Members are sufficiently connected to act as a unit, meaning accounting for effective post tensioning)

$$\text{LLDF(INT - OneLane)} = \boxed{0.254}$$

(LLDF for One lane loaded for Moment and Shear computed for Interior Slab unit in AASHTOWare BrR in

$$\text{LLDF(INT - MultiLane)} = \boxed{0.256}$$

(LLDF for Multi lanes loaded for Moment and Shear computed for Interior Slab unit in AASHTOWare BrR in

For Exterior Slab Units: (Moment)

[AASHTO LRFD Table 4.6.2.2.2d-1]

$$d_{e,G11} = \boxed{-1.0} \text{ ft. (Horizontal distance from centerline of exterior web of exterior beam/slab unit along the south end at deck}$$

$$d_{e,G1} = \boxed{-1.0} \text{ ft. (Horizontal distance from centerline of exterior web of exterior slab unit along the south end at deck level to}$$

- One Design Lane Loaded:

$$e_{\text{OneLane}_G1} = 1.125 + \frac{d_{e,G1}}{30} \geq 1.0 = 1.000 \text{ (Correction factor for LL distribution on exterior slab unit G1)}$$

$$e_{\text{OneLane}_{G11}} = 1.125 + \frac{d_{e,G11}}{30} \geq 1.0 = 1.000 \text{ (Correction factor for LL distribution on exterior slab unit G11)}$$

$$\text{LLDF (EXT.G1-M}_{\text{OneLane}}) = e_{\text{OneLane}_G1} \cdot \text{LLDF(INT, M)} = \boxed{0.2540} \text{ (Live Load Distribution Fraction for Moment for One lane Loaded - Unit G1)}$$

$$\text{LLDF (EXT.G11-M}_{\text{OneLane}}) = e_{\text{OneLane}_{G11}} \cdot \text{LLDF(INT, M)} = \boxed{0.2540} \text{ (Live Load Distribution Fraction for Moment for One lane Loaded - Unit G11)}$$


- Two or More Design Lanes Loaded:


$$e_{\text{MultiLane}_G1} = 1.04 + \frac{d_{e,G1}}{25} \geq 1.0 = 1.000 \text{ (Correction factor for LL distribution on exterior slab unit G1)}$$

$$e_{\text{MultiLane}_{G11}} = 1.04 + \frac{d_{e,G11}}{25} \geq 1.0 = 1.000 \text{ (Correction factor for LL distribution on exterior slab unit G11)}$$

$$\text{LLDF (EXT.-M}_{\text{MultiLane}}) = e_{\text{MultiLane}_G1} \cdot \text{LLDF(INT, M)} = \boxed{0.2560} \text{ (Live Load Distribution Fraction for Moment for Multi-Lanes Loaded - Unit G1)}$$

$$\text{LLDF (EXT.-M}_{\text{MultiLane}}) = e_{\text{MultiLane}_{G11}} \cdot \text{LLDF(INT, M)} = \boxed{0.2560} \text{ (Live Load Distribution Fraction for Moment for Multi-Lanes Loaded - Unit G11)}$$

	Project No:	D210107FL.00	Calculated by:	YRA	Date:	9/21/2021
	Bridge No.:	874294	Checked by:	MAP	Date:	12/29/2021
	Feature Carried:	Matheson Hammock Road			Page:	1 of 4

	Project No:	D210107FL.00	Calculated by:	YRA	Date:	9/21/2021
	Bridge No.:	874294	Checked by:	MAP	Date:	12/29/2021
	Feature Carried:	Matheson Hammock Road			Page:	4 of 4

For Exterior Slab Units: (Shear)

[AASHTO LRFD Table 4.6.2.2.3b-1]

$d_{e,G1} = -1.0$ ft. (Horizontal distance from centerline of exterior web of exterior slab unit along the south end at deck level to
 $d_{e,G11} = -1.0$ ft. (Horizontal distance from centerline of exterior web of exterior beam/slab unit along the south end at deck
 $b = 36.0$ in. (Width of precast member)

- One Design Lane Loaded:

$$e_{OneLane_G1} = 1.25 + \frac{d_{e,G1}}{20} \geq 1.0 = 1.000 \quad (\text{Correction factor for LL distribution on exterior slab unit G1})$$

$$e_{OneLane_G11} = 1.25 + \frac{d_{e,G11}}{20} \geq 1.0 = 1.000 \quad (\text{Correction factor for LL distribution on exterior slab unit G11})$$

$$LLDF (EXT.G1-M_{OneLane}) = e_{OneLane_G1} \cdot LLDF (INT, V) = 0.2540 \quad (\text{Live Load Distribution Fraction for Shear for One lane Loaded - Unit G1})$$

$$LLDF (EXT.G11-M_{OneLane}) = e_{OneLane_G11} \cdot LLDF (INT, V) = 0.2540 \quad (\text{Live Load Distribution Fraction for Shear for One lane Loaded - Unit G11})$$

- Two or More Design Lanes Loaded:

$$e_{MultiLane_G1} = 1.0 + \left(\frac{d_{e,G1} + \frac{b}{12} - 2.0}{40} \right)^{0.5} \geq 1.0 = 1.000 \quad (\text{Correction factor for LL distribution on exterior slab unit G1})$$

$$e_{MultiLane_G11} = 1.0 + \left(\frac{d_{e,G11} + \frac{b}{12} - 2.0}{40} \right)^{0.5} \geq 1.0 = 1.000 \quad (\text{Correction factor for LL distribution on exterior slab unit G11})$$

$$LLDF (EXT.-M_{MultiLane}) = e_{MultiLane_G1} \cdot LLDF (INT, V) = 0.2560 \quad (\text{Live Load Distribution Fraction for Shear for Multi-Lanes Loaded - Unit G1})$$

$$LLDF (EXT.-M_{MultiLane}) = e_{MultiLane_G11} \cdot LLDF (INT, V) = 0.2560 \quad (\text{Live Load Distribution Fraction for Shear for Multi-Lanes Loaded - Unit G11})$$

LLDF (Exist.Condition - LFD): (Assuming Members acting independently - no effective post tensioning)

$S = 3.0$ ft. (Width of precast member)
 $W = 34.0$ ft. (Assumed total width of Bridge Superstructure - ignore opening at the N end sidewalk)
 $L = 38.5$ ft. (Brg.-to-Brg. Span Length - Span 2)
 $NL = 2.0$ (Number of traffic lanes)
 $Nb = 11.0$ (Number of concrete slab units)
 $D = 3.0000$ (Assumed equal to Precast member width since slab unit will behave independently. Therefore, individual unit can be assumed to take on the full wheel load)

$$LLDF (LFD) = S/D = 1.0000 \quad (\text{Live Load Distribution Fraction for Moment and Shear})$$

LLDF (Exist.Condition - LRFR): (Assuming Slab units acting independently - no effective post tensioning)

$$LLDF (INT - OneLane - LRFR) = 0.5 \times \text{Axle} = 0.5000 \quad (\text{Live Load Distribution Fraction for Moment and Shear - Half of Axle Load})$$

$$LLDF (INT - OneLane - LRFR) = 0.5 \times 1.2 \times \text{Axle} = 0.6000 \quad (\text{Live Load Distribution Fraction for Moment and Shear - Half of Axle Load})$$

Analysis Case: A) For the purpose of the Load Rating, the following Cases were assumed for AASHTOWare BrR runs:

- Case 1: Run model for non deteriorated units to account for the condition where the slab units have been rehabilitated.
- Case 2: Run model for non-deteriorated and deteriorated units to account for the existing condition without repairs.
- Case 3: Run model for deteriorated units to account for the condition where the slab units have been rehabilitated, but no strands have been replaced.

B) Per current inspection report, the following are assumed in the analysis to account for the deterioration of the slab unit 2-8:

- 5 exposed strands, with 3 broken: Remove a total of 5 strands from the bottom layer of strands.
- Assume 50% of the adjacent strands along the same layer have been affected to account for the potential of damage in the adjacent strands. That is: Remove 1 additional strand from the bottom layer of strands.
- Assume 50% of the adjacent strands at the next layer have been affected to account for the potential of damage in the adjacent strands. That is: Remove 1 additional strand from the next layer of strands.
- Per recommendation from "Structural Technologies" on 10/01/2021, assume exterior stirrup leg to be deteriorated. In BrR, use 2 legs of shear reinforcement, conservatively for the critical case.

A.2 – LRFR LOAD RATING ANALYSIS INPUT

Username: BrR

Date: Wednesday, September 22, 2021 11:21:02

Bridge ID 874294D Matheson Hmck Bridge over Matheson Hammock Canal

NBI Structure ID (8): 874294D

Description: Rating by YRA, from As-built plans [LAST UPDATED: 9/22/2021]

DETERIORATED MODEL:

Three spans (30'-40'-30') non-composite PS Concrete voided slab unit superstructure comprised of eleven (11) 17"x36" units. Deck width is 35'-0" out-to-out with a 26'-0" clear roadway width.

Wearing surface is present along the bridge with an average thickness of 1.167" along end spans 1 and 3, and 1.292" for interior span 2.

Per current inspection report, the following controlling cases apply:

- Prestressed slab unit 1-8 displaying severe cracking with corrosion stain along the bottom face of the slab unit.
- Prestressed slab unit 2-8 displaying the worst deterioration: Five (5) exposed strands with three (3) broken.

The load rating analysis for the prestressed voided slab units was initially performed using the Load and Resistance factor Rating methodology in accordance with the AASHTO LRFD Bridge Design Specifications (9th edition, 2020), the Manual for Bridge Evaluation (3rd edition with interims through 2019), and the FDOT Bridge Load Rating Manual (January 2021). However, the resulting design and legal rating factors were less than 1, which granted the need to evaluate the structure using the Load Factor Rating methodology.

Description

Location:	Matheson Hammock Park
Total Length:	100.33 <i>(ft)</i>
Facility Carried:	Matheson Hmk Road
Route Number:	00000
Feature Intersected:	Matheson Hammock Canal
Mi Post:	0.08 <i>(mi)</i>
Units:	US Customary
Year Built:	1967
Recent ADTT:	11
District:	District 6
County:	
Owner:	County Hwy Agency
National Highway System:	0 Not on NHS
Functional Class:	09 Rural Local

Global Reference Point

X Coordinate:	0.000 <i>(ft)</i>
Y Coordinate:	0.000 <i>(ft)</i>
Elevation:	<i>(ft)</i>
Longitude:	80.26 <i>(Degrees)</i>
Latitude:	25.68 <i>(Degrees)</i>

Materials

No steel materials.

Concrete

Name: **Class P (5000)**
Description: Class 5000 cement concrete
Specified compressive strength at 28 days (f'_c): 5.000 (ksi)
Initial specified compressive strength (f'_{ci}): 4.000 (ksi)
Coefficient of thermal expansion: 0.0000060000 (1/F)
Density (for dead loads): 0.150 (kcf)
Density (for modulus of elasticity): 0.145 (kcf)
Std Modulus of elasticity (E_c): 4074.28 (ksi)
LRFD Modulus of elasticity (E_c): 4291.19 (ksi)
Poisson's ratio: 0.200
Modulus of rupture: 0.537 (ksi)
Shear factor: 1.000
Composition of concrete: Normal
Std Initial modulus of elasticity (E_{ci}): 3644.15 (ksi)
LRFD Initial modulus of elasticity (E_{ci}): 3986.55 (ksi)
Splitting tensile strength (f_{ct}): (ksi)

Name: **Class A (3000)**
Description: Class A cement concrete (3000 psi)
Specified compressive strength at 28 days (f'_c): 3.000 (ksi)
Initial specified compressive strength (f'_{ci}): (ksi)
Coefficient of thermal expansion: 0.0000060000 (1/F)
Density (for dead loads): 0.150 (kcf)
Density (for modulus of elasticity): 0.145 (kcf)
Std Modulus of elasticity (E_c): 3150.39 (ksi)
LRFD Modulus of elasticity (E_c): 3617.02 (ksi)
Poisson's ratio: 0.200
Modulus of rupture: 0.416 (ksi)
Shear factor: 1.000
Composition of concrete: Normal
Std Initial modulus of elasticity (E_{ci}): (ksi)
LRFD Initial modulus of elasticity (E_{ci}): (ksi)
Splitting tensile strength (f_{ct}): (ksi)

Reinforcing Steel

Name: **Grade 40**
Description: 40 ksi reinforcing steel
Specified yield strength (F_y): 40.000 (ksi)
Modulus of elasticity (E_s): 29000.00 (ksi)
Ultimate strength (F_u): 70.000 (ksi)
Type: Plain

Prestressing Strand

Name: **7/16" (7W-250) SR**
Description: Stress relieved 7/16"/Seven Wire/fpu = 250

Specified yield strength (Fy):	212.500 (ksi)
Ultimate Tensile strength (Fu):	250.000 (ksi)
Modulus of elasticity (Es):	28500.00 (ksi)
Load per unit length:	0.367 (lb/ft)
Cross sectional area (A):	0.108 (in^2)
Nominal diameter (d):	0.4375 (in)
Transfer length (Std):	21.8750 (in)
Transfer length (LRFD):	26.2500 (in)
Type:	Stress Relieved
Epoxy coated:	FALSE

No timber materials.

Beam Shapes

Steel Shapes

No steel shapes.

Prestressed Shapes

No prestressed I shapes.

Prestressed Box Shapes

Name:	17"x36" PSU
Description:	17"x36" Prestressed Slab Unit for units E thru G
Type:	Circular Void
Nominal Depth:	17.0000 (in)
Depth (d):	17.0000 (in)
Top flange width:	35.0000 (in)
Bottom flange width:	36.0000 (in)
Three-void (D1, D2, D1) shape:	FALSE
Circular void diameter:	10.0000 (in)
Distance to CG of void(s) from bottom:	9.0000 (in)
Number of circular voids:	2
Center to center distance of voids:	16.0000 (in)
Vertical location of shear key:	2.0000 (in)
Shear key height:	6.0000 (in)
Shear key depth:	1.5000 (in)
Nominal load:	457.107 (lb/ft)
Cross sectional area:	438.822 (in^2)
Ixx:	13330.101 (in^4)
CG from bottom:	8.1667 (in)
Bottom Sxx:	1632.246 (in^3)
Top Sxx:	1509.078 (in^3)

Volume/Surface Ratio: 3.175 (in)
 Half Depth Area for Positive Flexure: (in^2)
 Half Depth Area for Negative Flexure: (in^2)
 St. Venant's Torsional Constant: 14593.772 (in^4)

Strand Grid

Row Number	Number of Strands	Vertical Location (in)	Horizontal Spacing (in)
1	16	2.5000	2.0000
2	6	4.5000	2.0000
3	16	14.5000	2.0000

No prestressed U shapes.

No prestressed tee shapes.

Timber Shapes

No timber shapes.

Appurtenances

No concrete railings.

Railings

Name: **Conc Guardrail w/ metal Post and Rail**
 Description: Conc. Post and beam guardrail with post and tube rail mounted
 Effective Wind Height: 36.0000 (in)
 Railing Load: 0.166 (kip/ft)
 Distance From Edge to Centroid: 5.0000 (in)
 Width: 10.0000 (in)

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Factors

Factors - LFD

Name: 2002 AASHTO Std. Specifications

Description: AASHTO Standard Specifications for Highway Bridges, 17th

Edition, 2002

Load Factors

Load Group	Gamma D		(L+I)n	(L+I)p	CF	E	B
Inventory	1.300	1.000	1.670	0.000	1.000	1.000	1.000
Operating	1.300	1.000	1.000	0.000	1.000	1.000	1.000

Load Group	SF	W	WL	LF	R+S+T	EQ	ICE
Inventory	1.000	0.000	0.000	0.000	0.000	0.000	0.000
Operating	1.000	0.000	0.000	0.000	0.000	0.000	0.000

Resistance Factors

Reinforced concrete:

Flexure: 0.900

Reinforced concrete:

Shear: 0.850

Prestressed concrete:

Flexure: 1.000

Prestressed concrete:

Shear: 0.900

Prestressed concrete:

Flexure in Non-P/S Components: 0.900

Steel:

Flexure: 1.000

Steel:

Shear: 1.000

Steel:

Bearing Stiffeners: 1.000

Name: 2002 AASHTO Std. Specifications(CD=0.90)

Description: AASHTO Standard Specifications for Highway Bridges,
17th Edition, 2002

Load Factors

Load Group	Gamma D		(L+I)n	(L+I)p	CF	E	B
Inventory	1.300	1.000	1.670	0.000	1.000	1.000	1.000
Operating	1.300	1.000	1.000	0.000	1.000	1.000	1.000

Load Group	SF	W	WL	LF	R+S+T	EQ	ICE
Inventory	1.000	0.000	0.000	0.000	0.000	0.000	0.000
Operating	1.000	0.000	0.000	0.000	0.000	0.000	0.000

Resistance Factors

Reinforced concrete:

Flexure: 0.810

Reinforced concrete:

Shear: 0.765

Prestressed concrete:

Flexure: 0.900

Prestressed concrete:

Shear: 0.810

Prestressed concrete:

Flexure in Non-P/S Components: 0.810

Steel:
 Flexure: 0.900
 Steel:
 Shear: 0.900
 Steel:
 Bearing Stiffeners: 0.900
 Name: 2002 AASHTO Std. Specifications(CD=0.85)
 Description: AASHTO Standard Specifications for Highway Bridges,
 17th Edition, 2002

Load Factors

Load Group	Gamma D	(L+I)n	(L+I)p	CF	E	B
Inventory	1.300	1.000	1.670	0.000	1.000	1.000
Operating	1.300	1.000	1.000	0.000	1.000	1.000

Load Group	SF	W	WL	LF	R+S+T	EQ	ICE
Inventory	1.000	0.000	0.000	0.000	0.000	0.000	0.000
Operating	1.000	0.000	0.000	0.000	0.000	0.000	0.000

Resistance Factors

Reinforced concrete:
 Flexure: 0.765
 Reinforced concrete:
 Shear: 0.723
 Prestressed concrete:
 Flexure: 0.850
 Prestressed concrete:
 Shear: 0.765
 Prestressed concrete:
 Flexure in Non-P/S Components: 0.765
 Steel:
 Flexure: 0.850
 Steel:
 Shear: 0.850
 Steel:
 Bearing Stiffeners: 0.850

No LRFD Factors specified.

Bridge Alternatives End Span 1 (or 3) - Bridge Alt.

Reference Line

Reference Line Length: (ft)
 Starting Station: (ft)
 Bearing: N 90° 0' 0.00" E
Global Positioning
 Distance: 0.000 (ft)

Offset: 0.000 (ft)
Elevation: (ft)

Structures

Name: Exist. EXT Span 1(or 3) SuperStr
Description:

Structure Alternatives

Name: Exist. END Span 1(or 3) Alt.

Description:

Superstructure Definition: End Span 1 (or 3) - PS Conc PSU

Bridge Alternatives INT Span 2 - Bridge Alt.

Reference Line

Reference Line Length: (ft)
Starting Station: (ft)
Bearing: N 90^ 0' 0.00" E

Global Positioning

Distance: 0.000 (ft)
Offset: 0.000 (ft)
Elevation: (ft)

Structures

Name: Exist. INT Span 2 Superstruct.
Description:

Structure Alternatives

Name: Exist. INT Span 2 Alt.

Description:

Superstructure Definition: INT Span 2 - PS Conc PSU

Superstructure Definition End Span 1 (or 3) - PS Conc PSU

Definition

Units: US Customary
Number of spans: 1
Number of girders: 11

Length

Span (ft)
1 28.2917

Frame Structure Simplified Definition:

Support Frame Connection

1

2

Girder Spacing Display Type: Perpendicular

Average Humidity: 70.000 (%)

Analysis

Default Library Factors

Factor Override

Analysis Module

Analysis Method: ASD

Analysis Module:

Analysis Module Component:

Properties:

Analysis Method: LFD

Analysis Module:

Analysis Module Component:

Properties:

Analysis Method: LRFD

Analysis Module:

Analysis Module Component:

Properties:

Analysis Method: LRFR

Analysis Module:

Analysis Module Component:

Properties:

Analysis Method: Distribution Factors

Analysis Module:

Analysis Module Component:

Properties:

Default rating method: LFD

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Structure Framing Plan Details

Layout

	Skew	
Support	(Degrees)	
1	0.0000	
2	0.0000	
Girder Spacing Orientation:	Perpendicular	

Girder	Girder Spacing	
Bay	Start	End
	(ft)	(ft)

1	3.0000	3.0000
2	3.0000	3.0000
3	3.0000	3.0000
4	3.0000	3.0000
5	3.0000	3.0000
6	3.0000	3.0000
7	3.0000	3.0000
8	3.0000	3.0000
9	3.0000	3.0000
10	3.0000	3.0000

Diaphragms

Girder Bay 1

Girder Bay 2

Girder Bay 3

Girder Bay 4

Girder Bay 5

Girder Bay 6

Girder Bay 7

Girder Bay 8

Girder Bay 9

Girder Bay 10

Structure Typical Section

Deck

Left start width:	18.00	(ft)
Left end width:	18.00	(ft)
Right start width:	15.00	(ft)
Right end width:	15.00	(ft)
Left start overhang:	1.50	(ft)
Left end overhang:	1.50	(ft)

Deck (Cont'd)

Deck concrete:

Total deck thickness: (in)

Deck crack control parameter: (kip/in)

Sustained modular ratio factor: 3.000

Railing

Name	Load Case	Measure To	Measured From	Distance At Start	Distance At End	Front Face Orientation
Conc Guar...	DC1 - R...		Left Ed...	0.00	0.00	Right
Conc Guar...	DC1 - R...		Right E...	0.00	0.00	Left

Sidewalk

Width	Thickness At End	Material	Load Case	Measure to	Measured From	At Start
60.0000	11.4375	Class A...	DC1 - C...		Left Ed...	0.00 ...
24.0000	10.5630	Class A...	DC1 - C...		Right E...	0.00 ...

Lane Position

Offset Left Start: -13.00 (ft)

Offset Left End: -13.00 (ft)

Offset Right Start: 0.00 (ft)
 Offset Right End: 0.00 (ft)
 Offset Left Start: 13.00 (ft)
 Offset Left End: 13.00 (ft)
 Offset Right Start: 0.00 (ft)
 Offset Right End: 0.00 (ft)

Wearing Surface

Wearing surface material: Asphalt
 Description: Asphalt Wearing Surface
 Wearing surface thickness: 1.1670 (in)
 Wearing surface density: 145.000 (pcf)
 Load case: DW - A.W.S.

Load Case Description

Load Case Name	Description	Stage	Type	Time (Days)
DC1 - Railing	DC acting on non-comp...	Non-composite (Sta...		D,DC
DC1 - Curb	DC acting on non-comp...	Non-composite (Sta...		D,DC
DW - A.W.S.	DW acting on long-ter...	Composite (long te...		D,DW

Superstructure Loads

DL Distribution

Stage 1 Dead Load Distribution: Tributary Area
 Stage 2 Dead Load Distribution: Uniformly to All Girders

Stiffener Definitions

Stress Limits

Name: PS Conc Stress Limits

Description:

Concrete material: Class P (5000)
 Initial allowable tension (LFD): 0.190 (ksi)
 Initial allowable compression (LFD): 2.400 (ksi)
 Final allowable slab compression (LFD): (ksi)
 Final allowable tension (LFD): 0.425 (ksi)
 Final allowable DL compression (LFD): 2.000 (ksi)
 Final allowable compression (LFD): 3.000 (ksi)
 Final allowable compression (LL + 1/2(Pe+DL)) (LFD): 2.000 (ksi)
 Initial allowable tension (LRFD): 0.190 (ksi)
 Initial allowable compression (LRFD): 2.600 (ksi)
 Final allowable slab compression (LRFD): (ksi)
 Final allowable tension (LRFD): 0.425 (ksi)
 Final allowable DL compression (LRFD): 2.250 (ksi)
 Final allowable compression (LRFD): 3.000 (ksi)
 Final allowable compression (LL + 1/2(Pe+DL)) (LRFD): 2.000 (ksi)

Prestress Properties

Name: PS Strands Properties

General Pretress Data

Prestressing Strand:	7/16" (7W-250) SR
Loss Method:	AASHTO Approximate
Jacking stress ratio:	0.700
Transfer stress ratio:	
Transfer time:	24.0 <i>(Hours)</i>
AASHTO - Dead load percent:	0.0 <i>(%)</i>

Loss Data - PCI

PCI - Maturity coefficient:	
PCI - Ultimate creep loss:	<i>(ksi)</i>
PCI - Ultimate shrinkage loss:	<i>(ksi)</i>
PCI - Additional time 1:	<i>(Days)</i>
PCI - Additional time 2:	<i>(Days)</i>
PCI - Additional time 3:	<i>(Days)</i>
PCI - Additional time 4:	<i>(Days)</i>
PCI - Additional time 5:	<i>(Days)</i>
PCI - Additional time 6:	<i>(Days)</i>
PCI - Additional time 7:	<i>(Days)</i>
PCI - Additional time 8:	<i>(Days)</i>
PCI - Additional time 9:	<i>(Days)</i>
PCI - Additional time 10:	<i>(Days)</i>

Loss Data - Lump-sum

Lump-sum - Composite loss:	<i>(ksi)</i>
Lump-sum - Continuous loss:	<i>(ksi)</i>
Lump-sum - Final loss:	<i>(ksi)</i>

Shear Reinforcement Definitions - Vertical

Name:	#4 Bent Shear Reinf.
Vertical Reinforcement:	Grade 40
Vertical Rebar:	4
Number of legs (Vertical):	3.00
Inclination angle alpha (Vertical):	90.0 <i>(Degrees)</i>

Shear Reinforcement Definitions - Horizontal

Name:	#3 - 2'-7" long
Reinforcement (Horz. 1):	Grade 40
Rebar (Horz. 1):	3
Number of legs (Horz. 1):	1.00
Inclination angle alpha (Horz. 1):	90.0 <i>(Degrees)</i>
Reinforcement (Horz. 2):	
Rebar (Horz. 2):	
Number of legs (Horz. 2):	
Inclination angle alpha (Horz. 2):	90.0 <i>(Degrees)</i>

Member G1

Link with: None

Description:

Existing:	17"x36" EXT PSU -
Current:	17"x36" EXT PSU -

Number of Spans: 1

Span Number	Span Length (ft)
1	28.291666

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support Number	Horizontal (in)	Vertical (in)	Rotational (Radians)	Load Case Name
1				
2				

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

Elastic

Support Number	X Translation (kip/ft)	Y Translation (kip/ft)	Z Rotation (kip-in/rad)	Override Computed Z Rotation
1				
2				

Member Alternative 17"x36" EXT PSU

Description:

Description

Material Type: Prestressed Concrete
Girder Type: PS Precast Box
Member units: US Customary
Girder property input method: Schedule based
Additional Self Load: (kip/ft)
Additional Self Load %: 1.0 (%)

Analysis Module

Analysis Method: ASD
Analysis Module: AASHTO ASD
Analysis Module Component:

Properties:

Analysis Method: LFD
Analysis Module: AASHTO LFD

Analysis Module Component:

Properties:

Analysis Method: LRFD
Analysis Module: AASHTO LRFD
Analysis Module Component:
Properties:

Analysis Method: LRFR
Analysis Module: AASHTO LRFR
Analysis Module Component:
Properties:

Analysis Method: Distribution Factors
Analysis Module: Legacy BrR Dist Fact
Analysis Module Component:
Properties:

Default rating method: LRFR
LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:

LFD: 2002 AASHTO Std. Specifications(CD=0.85)

ASD Factors

Inventory Operating

Structural steel

Concrete

PS Concrete Comp.

PS Concrete Tens.

PS Moment Cap.

Reinforcement

Bearing Stiffener

Stirrup

Timber NA

Default Materials

Deck concrete: Class A (3000)

Deck reinforcement: Grade 40

Beam concrete: Class P (5000)

Beam reinforcement: Grade 40

Stirrup reinforcement: Grade 40

Prestressing strand: 7/16" (7W-250) SR

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)
 All other limit states: 33.0 (%)

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)

Lanes	Shear	Shear at Supports	Moment	Deflection
Loaded				
1 Lane	0.100	0.100	0.100	0.100
Multi-Lane	0.100	0.100	0.100	0.100

LRFD

Distance	Length	Type	1 Lane	Multi-Lane
(ft)	(ft)			
0.00	28.292	Deflectio...	0.100	0.100
0.00	28.292	Moment	0.100	0.100
0.00	28.292	Shear	0.100	0.100

Shrinkage/Time

Deck curing method: Moist-cured
 Deck drying time: 3.000 (Days)
 Consider deck differential shrinkage loads: FALSE
 Beam Curing method: Steam-cured
 Curing time: 20.00 (Days)
 Service life: 75.00 (Years)
 Analysis time: 54.00 (Years)
 Composite time: 60.00 (Days)
 Continuous time: 45.0 (Days)

Beam Details

Span Details

Span	Prestress Shape Use	Concrete Material n	Prestress Properties	Left Projection	Right Projection
	Projection	Creep		(in) (in)	
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	6.0000	8.5000

Continuous Support Details

Support Number	Support Distance on Left, SL (in)	Support Distance on Right, SR (in)
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance (ft)	Length (ft)
PS Conc Stress Lim...	1	0.000	29.50

Slab Interface

Deck interface type:	Monolithic
Interface width:	(in)
Deck cohesion factor:	0.400 (ksi)
Deck friction factor:	1.400

Continuity Diaphragm

Span	Material	Left Support Distance	Bar	Bar	Right Support Material	Distance
No.	Bar	Bar	Count	Size	Count	Size

Prestressing Force Information

Strand Layout

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance (ft)	Debond Distance (in)	Harp Curvature (in)
1	Left	1	1	Straight/Debonded			
	Right						
1	Left	1	2	Straight/Debonded			
	Right						
1	Left	1	3	Straight/Debonded			
	Right						
1	Left	1	6	Straight/Debonded			
	Right						
1	Left	1	7	Straight/Debonded			
	Right						
1	Left	1	8	Straight/Debonded			
	Right						
1	Left	1	9	Straight/Debonded			
	Right						
1	Left	1	10	Straight/Debonded			
	Right						
1	Left	1	11	Straight/Debonded			
	Right						

1	Left Right	1	14	Straight/Debonded
1	Left Right	1	15	Straight/Debonded
1	Left Right	1	16	Straight/Debonded
1	Left Right	3	1	Straight/Debonded
1	Left Right	3	16	Straight/Debonded

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	6.25	1	1.0000	0.1636
1	7.25...	15.00	1	1.0000	0.1636
1	22.25...	6.25	1	1.0000	0.1636

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Extends into Deck
#4 Bent Shear R...	1	0.21	4	6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	8.0000	FALSE
#4 Bent Shear R...	1	2.88	19	15.0000	FALSE
#4 Bent Shear R...	1	26.62	1	8.0000	FALSE
#4 Bent Shear R...	1	27.29	4	6.0000	FALSE

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Composite Length (ft)
#3 - 2'-7" long	1	0.21	4	6.0000	
#3 - 2'-7" long	1	2.21	1	8.0000	
#3 - 2'-7" long	1	2.88	19	15.0000	
#3 - 2'-7" long	1	26.62	1	8.0000	

#3 - 2'-7" long	1	27.29	4	6.0000
-----------------	---	-------	---	--------

Member G2

Link with: None

Description:

Existing: 17"x36" INT PSU -

Current: 17"x36" INT PSU -

Number of Spans: 1

Span Number	Span Length (ft)
1	28.291666

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support Number	Horizontal (in)	Vertical (in)	Rotational (Radians)	Load Case Name
1				
2				

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

Elastic

Support Number	X Translation (kip/ft)	Y Translation (kip/ft)	Z Rotation (kip-in/rad)	Override Computed Z Rotation
1				
2				

Member Alternative 17"x36" INT PSU

Description:

Description

Material Type: Prestressed Concrete

Girder Type: PS Precast Box

Member units: US Customary

Girder property input method: Schedule based

Additional Self Load: (kip/ft)

Additional Self Load %: 1.0 (%)

Analysis Module

Analysis Method: ASD
Analysis Module: AASHTO ASD
Analysis Module Component:
Properties:

Analysis Method: LFD
Analysis Module: AASHTO LFD
Analysis Module Component:
Properties:

Analysis Method: LRFD
Analysis Module: AASHTO LRFD
Analysis Module Component:
Properties:

Analysis Method: LRFR
Analysis Module: AASHTO LRFR
Analysis Module Component:
Properties:

Analysis Method: Distribution Factors
Analysis Module: Legacy BrR Dist Fact
Analysis Module Component:
Properties:

Default rating method: LRFR
LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:
LFD: 2002 AASHTO Std. Specifications(CD=0.85)

ASD Factors

	Inventory	Operating
Structural steel		
Concrete		
PS Concrete Comp.		
PS Concrete Tens.		
PS Moment Cap.		
Reinforcement		
Bearing Stiffener		
Stirrup		
Timber	NA	

Default Materials

Deck concrete: Class A (3000)
Deck reinforcement: Grade 40
Beam concrete: Class P (5000)

Beam reinforcement: Grade 40
 Stirrup reinforcemt: Grade 40
 Prestressing strand: 7/16" (7W-250) SR

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)

Lanes	Shear	Shear at Supports	Moment	Deflection
Loaded				
1 Lane	0.167	0.167	0.167	0.167
Multi-Lane	0.167	0.167	0.167	0.167

LRFD

Distance	Length	Type	1 Lane	Multi-Lane
(ft)	(ft)			
0.00	28.292	Deflectio...	0.167	0.200
0.00	28.292	Moment	0.167	0.200
0.00	28.292	Shear	0.167	0.200

Shrinkage/Time

Deck curing method: Moist-cured

Deck drying time: 3.000 (Days)

Consider deck differential shrinkage loads: FALSE

Beam Curing method: Steam-cured

Curing time: 20.00 (Days)

Service life: 75.00 (Years)

Analysis time: 54.00 (Years)

Composite time: 60.00 (Days)

Continuous time: 45.0 (Days)

Beam Details

Span Details

Span	Prestress Shape Use	Concrete Material n	Prestress Properties	Left	Right
	Projection	Creep		Projection	
				(in) (in)	
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	6.0000	8.5000

Continuous Support Details

Support Number	Support Distance on Left, SL (in)	Support Distance on Right, SR (in)
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance (ft)	Length (ft)
PS Conc Stress Lim...	1	0.000	29.50

Slab Interface

Deck interface type:	Monolithic
Interface width:	(in)
Deck cohesion factor:	0.400 (ksi)
Deck friction factor:	1.400

Continuity Diaphragm

Span	Material	Left Support Distance	Bar	Bar	Right Support Material	Distance
No.	Bar	Bar	Count	Size	Count	Size

Prestressing Force Information

Strand Layout

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance (ft)	Debond Distance (in)	Harp Curvature (in)
1	Left	1	1	Straight/Debonded			
	Right						
1	Left	1	2	Straight/Debonded			
	Right						
1	Left	1	3	Straight/Debonded			
	Right						
1	Left	1	6	Straight/Debonded			
	Right						
1	Left	1	7	Straight/Debonded			
	Right						
1	Left	1	8	Straight/Debonded			

1	Right	1	9	Straight/Debonded
1	Left Right	1	10	Straight/Debonded
1	Left Right	1	11	Straight/Debonded
1	Left Right	1	14	Straight/Debonded
1	Left Right	1	15	Straight/Debonded
1	Left Right	1	16	Straight/Debonded
1	Left Right	3	1	Straight/Debonded
1	Left Right	3	16	Straight/Debonded

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	6.25	1	1.0000	0.1636
1	7.25...	15.00	1	1.0000	0.1636
1	22.25...	6.25	1	1.0000	0.1636

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Extends into Deck
#4 Bent Shear R...	1	0.21	4	6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	8.0000	FALSE
#4 Bent Shear R...	1	2.88	19	15.0000	FALSE
#4 Bent Shear R...	1	26.62	1	8.0000	FALSE
#4 Bent Shear R...	1	27.29	4	6.0000	FALSE

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Composite Length (ft)
#3 - 2'-7" long	1	0.21	4	6.0000	
#3 - 2'-7" long	1	2.21	1	8.0000	
#3 - 2'-7" long	1	2.88	19	15.0000	
#3 - 2'-7" long	1	26.62	1	8.0000	
#3 - 2'-7" long	1	27.29	4	6.0000	

Member G3

Link with: None

Description:

Existing: 17"x36" INT PSU -

Current: 17"x36" INT PSU -

Number of Spans: 1

Span Number	Span Length (ft)
1	28.291666

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support Number	Horizontal (in)	Vertical (in)	Rotational (Radians)	Load Case Name
1				
2				

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

Elastic

Support Number	X Translation (kip/ft)	Y Translation (kip/ft)	Z Rotation (kip-in/rad)	Override Computed Z Rotation
1				
2				

Member Alternative 17"x36" INT PSU

Description:

Description

Material Type: Prestressed Concrete

Girder Type: PS Precast Box

Member units: US Customary

Girder property input method: Schedule based

Additional Self Load: *(kip/ft)*

Additional Self Load %: 1.0 *(%)*

Analysis Module

Analysis Method: ASD

Analysis Module: AASHTO ASD

Analysis Module Component:

Properties:

Analysis Method: LFD

Analysis Module: AASHTO LFD

Analysis Module Component:

Properties:

Analysis Method: LRFD

Analysis Module: AASHTO LRFD

Analysis Module Component:

Properties:

Analysis Method: LRFR

Analysis Module: AASHTO LRFR

Analysis Module Component:

Properties:

Analysis Method: Distribution Factors

Analysis Module: Legacy BrR Dist Fact

Analysis Module Component:

Properties:

Default rating method: LRFR

LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:

LFD: 2002 AASHTO Std. Specifications(CD=0.85)

ASD Factors

Inventory Operating

Structural steel

Concrete

PS Concrete Comp.

PS Concrete Tens.

PS Moment Cap.

Reinforcement

Bearing Stiffener

Stirrup
Timber NA

Default Materials

Deck concrete: Class A (3000)
Deck reinforcement: Grade 40
Beam concrete: Class P (5000)
Beam reinforcement: Grade 40
Stirrup reinforcement: Grade 40
Prestressing strand: 7/16" (7W-250) SR

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)

Lanes	Shear	Shear at Supports	Moment	Deflection
Loaded				
1 Lane	1.000	1.000	1.000	1.000
Multi-Lane	1.000	1.000	1.000	1.000

LRFD

Distance	Length	Type	1 Lane	Multi-Lane
(ft)	(ft)			
0.00	28.292	Deflectio...	0.500	0.600
0.00	28.292	Moment	0.500	0.600
0.00	28.292	Shear	0.500	0.600

Shrinkage/Time

Deck curing method: Moist-cured

Deck drying time: 3.000 (Days)

Consider deck differential shrinkage loads: FALSE

Beam Curing method: Steam-cured

Curing time: 20.00 (Days)

Service life: 75.00 (Years)

Analysis time: 54.00 (Years)

Composite time: 60.00 (Days)

Continuous time: 45.0 (Days)

Beam Details

Span Details

Span Prestress Shape Concrete Material Prestress Properties Left Right

	Use	n		Projection
	Projection	Creep		
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	(in) (in) 6.0000 8.5000

Continuous Support Details

Support Number	Support Distance on Left, SL (in)	Support Distance on Right, SR (in)
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance (ft)	Length (ft)
PS Conc Stress Lim...	0	-0.750	29.50

Slab Interface

Deck interface type:	Monolithic
Interface width:	(in)
Deck cohesion factor:	0.400 (ksi)
Deck friction factor:	1.400

Continuity Diaphragm

Span	Material	Left Support Distance	Bar	Bar	Right Support Material	Distance
Bar		Bar				
No.			Count	Size	Count	Size

Prestressing Force Information

Strand Layout

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance (ft)	Debond Distance (in)	Harp Curvature (in)
1	Left	1	1	Straight/Debonded			
	Right						
1	Left	1	2	Straight/Debonded			
	Right						
1	Left	1	3	Straight/Debonded			
	Right						

1	Left	1	6	Straight/Debonded
	Right			
1	Left	1	7	Straight/Debonded
	Right			
1	Left	1	8	Straight/Debonded
	Right			
1	Left	1	9	Straight/Debonded
	Right			
1	Left	1	10	Straight/Debonded
	Right			
1	Left	1	11	Straight/Debonded
	Right			
1	Left	1	14	Straight/Debonded
	Right			
1	Left	1	15	Straight/Debonded
	Right			
1	Left	1	16	Straight/Debonded
	Right			
1	Left	3	1	Straight/Debonded
	Right			
1	Left	3	16	Straight/Debonded
	Right			

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	6.25	1	1.0000	0.1636
1	7.25...	15.00	1	1.0000	0.1636
1	22.25...	6.25	1	1.0000	0.1636

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance	Number Spaces	Spacing	Extends into Deck
------------------------	------------	-------------------	------------------	---------	----------------------

#4 Bent Shear R...	1	(ft) 0.21	4	(in) 6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	8.0000	FALSE
#4 Bent Shear R...	1	2.88	19	15.0000	FALSE
#4 Bent Shear R...	1	26.62	1	8.0000	FALSE
#4 Bent Shear R...	1	27.29	4	6.0000	FALSE

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance	Number Spaces	Spacing	Composite Length
		(ft)		(in)	(ft)
#3 - 2'-7" long	1	0.21	4	6.0000	
#3 - 2'-7" long	1	2.21	1	8.0000	
#3 - 2'-7" long	1	2.88	19	15.0000	
#3 - 2'-7" long	1	26.62	1	8.0000	
#3 - 2'-7" long	1	27.29	4	6.0000	

Member G4

Link with: G3

Description:

Existing:

Current:

Number of Spans: 1

Span Number	Span Length
	(ft)
1	28.291666

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member G5

Link with: G3

Description:

Existing:

Current:

Number of Spans: 1

Span Number	Span Length
	(ft)
1	28.291666

Support	Frame Connection
---------	------------------

1
2

Pedestrian load: *(lb/ft)*

Member G6

Link with: G3

Description:

Existing: 17"x36" INT PSU -

Current: 17"x36" INT PSU -

Number of Spans: 1

Span Number	Span Length <i>(ft)</i>
1	28.291666

Support	Frame Connection
1	
2	

Pedestrian load: *(lb/ft)*

Member G7

Link with: G3

Description:

Existing:

Current:

Number of Spans: 1

Span Number	Span Length <i>(ft)</i>
1	28.291666

Support	Frame Connection
1	
2	

Pedestrian load: *(lb/ft)*

Member G8

Link with: G9

Description:

Existing:

Current:

Number of Spans: 1

Span Number	Span Length (ft)
1	28.291666

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member G9

Link with: None

Description:

Existing: 17"x36" INT PSU - w/ Post Tensioning -
 Current: 17"x36" INT PSU - w/ Post Tensioning -
 Number of Spans: 1

Span Number	Span Length (ft)
1	28.291666

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support Number	Horizontal (in)	Vertical (in)	Rotational (Radians)	Load Case Name
1				
2				

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

Elastic

Support Number	X Translation (kip/ft)	Y Translation (kip/ft)	Z Rotation (kip-in/rad)	Override Computed Z Rotation
1				
2				

Member Alternative 17"x36" INT PSU - w/ Post Tensioning

Description:

Description

Material Type: Prestressed Concrete

Girder Type: PS Precast Box

Member units: US Customary

Girder property input method: Schedule based

Additional Self Load: *(kip/ft)*

Additional Self Load %: 1.0 *(%)*

Analysis Module

Analysis Method: ASD

Analysis Module: AASHTO ASD

Analysis Module Component:

Properties:

Analysis Method: LFD

Analysis Module: AASHTO LFD

Analysis Module Component:

Properties:

Analysis Method: LRFD

Analysis Module: AASHTO LRFD

Analysis Module Component:

Properties:

Analysis Method: LRFR

Analysis Module: AASHTO LRFR

Analysis Module Component:

Properties:

Analysis Method: Distribution Factors

Analysis Module: Legacy BrR Dist Fact

Analysis Module Component:

Properties:

Default rating method: LRFR

LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:

LFD: 2002 AASHTO Std. Specifications(CD=0.90)

ASD Factors

Inventory Operating

Structural steel

Concrete

PS Concrete Comp.

PS Concrete Tens.

PS Moment Cap.

Reinforcement

Bearing Stiffener

Stirrup
Timber NA

Default Materials

Deck concrete: Class A (3000)
Deck reinforcement: Grade 40
Beam concrete: Class P (5000)
Beam reinforcement: Grade 40
Stirrup reinforcement: Grade 40
Prestressing strand: 7/16" (7W-250) SR

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)

Lanes	Shear	Shear at Supports	Moment	Deflection
Loaded				
1 Lane	0.533	0.000	0.533	0.182
Multi-Lane	0.533	0.000	0.533	0.364

LRFD

Distance	Length	Type	1 Lane	Multi-Lane
(ft)	(ft)			
0.00	28.292	Moment	0.296	0.273
0.00	28.292	Shear	0.296	0.273
0.00	28.292	Deflectio...	0.109	0.182

Shrinkage/Time

Deck curing method: Moist-cured

Deck drying time: 3.000 (Days)

Consider deck differential shrinkage loads: FALSE

Beam Curing method: Steam-cured

Curing time: 20.00 (Days)

Service life: 75.00 (Years)

Analysis time: 54.00 (Years)

Composite time: 60.00 (Days)

Continuous time: 45.0 (Days)

Beam Details

Span Details

Span Prestress Shape Concrete Material Prestress Properties Left Right

	Use	n		Projection
	Projection	Creep		
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	(in) (in) 6.0000 8.5000

Continuous Support Details

Support Number	Support Distance on Left, SL (in)	Support Distance on Right, SR (in)
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance (ft)	Length (ft)
PS Conc Stress Lim...	0	-0.750	29.50

Slab Interface

Deck interface type:	Monolithic
Interface width:	(in)
Deck cohesion factor:	0.400 (ksi)
Deck friction factor:	1.400

Continuity Diaphragm

Span	Material	Left Support Distance	Bar	Bar	Right Support Material	Distance
No.	Bar	Bar	Count	Size	Count	Size

Prestressing Force Information

Strand Layout

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance (ft)	Debond Distance (in)	Harp Curvature (in)
1	Left	1	1	Straight/Debonded			
	Right						
1	Left	1	2	Straight/Debonded			
	Right						
1	Left	1	3	Straight/Debonded			
	Right						

1		1	6	Straight/Debonded
	Left			
	Right			
1		1	7	Straight/Debonded
	Left			
	Right			
1		1	8	Straight/Debonded
	Left			
	Right			
1		1	9	Straight/Debonded
	Left			
	Right			
1		1	10	Straight/Debonded
	Left			
	Right			
1		1	11	Straight/Debonded
	Left			
	Right			
1		1	14	Straight/Debonded
	Left			
	Right			
1		1	15	Straight/Debonded
	Left			
	Right			
1		1	16	Straight/Debonded
	Left			
	Right			
1		3	1	Straight/Debonded
	Left			
	Right			
1		3	16	Straight/Debonded
	Left			
	Right			

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	6.25	1	1.0000	0.1636
1	7.25...	15.00	1	1.0000	0.1636
1	22.25...	6.25	1	1.0000	0.1636

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance	Number Spaces	Spacing	Extends into Deck
------------------------	------------	-------------------	------------------	---------	----------------------

#4 Bent Shear R...	1	(ft) 0.21	4	(in) 6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	8.0000	FALSE
#4 Bent Shear R...	1	2.88	19	15.0000	FALSE
#4 Bent Shear R...	1	26.62	1	8.0000	FALSE
#4 Bent Shear R...	1	27.29	4	6.0000	FALSE

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance	Number Spaces	Spacing	Composite Length
		(ft)		(in)	(ft)
#3 - 2'-7" long	1	0.21	4	6.0000	
#3 - 2'-7" long	1	2.21	1	8.0000	
#3 - 2'-7" long	1	2.88	19	15.0000	
#3 - 2'-7" long	1	26.62	1	8.0000	
#3 - 2'-7" long	1	27.29	4	6.0000	

Member G10

Link with: G9

Description:

Existing: 17"x36" INT PSU -

Current: 17"x36" INT PSU -

Number of Spans: 1

Span Number	Span Length
	(ft)
1	28.291666

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member G11

Link with: G1

Description:

Existing:

Current:

Number of Spans: 1

Span Number	Span Length
	(ft)
1	28.291666

Support	Frame Connection
---------	------------------

1
2

Pedestrian load: (lb/ft)

Superstructure Definition INT Span 2 - PS Conc PSU

Definition

Units: US Customary

Number of spans: 1

Number of girders: 11

Length

Span (ft)

1 38.5000

Frame Structure Simplified Definition:

Support Frame Connection

1

2

Girder Spacing Display Type: Perpendicular

Average Humidity: 70.000 (%)

Analysis

Default Library Factors

Factor Override

Analysis Module

Analysis Method: ASD

Analysis Module:

Analysis Module Component:

Properties:

Analysis Method: LFD

Analysis Module:

Analysis Module Component:

Properties:

Analysis Method: LRFD

Analysis Module:

Analysis Module Component:

Properties:

Analysis Method: LRFR

Analysis Module:

Analysis Module Component:

Properties:

Analysis Method: Distribution Factors

Analysis Module:

Analysis Module Component:

Properties:

Default rating method: LFD

Impact

Standard Impact Factor

Type:

Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Structure Framing Plan Details

Layout

Skew

Support

(Degrees)

1

0.0000

2

0.0000

Girder Spacing Orientation: Perpendicular

Girder

Girder Spacing

Bay

Start

End

(ft)

(ft)

1

3.0000

3.0000

2

3.0000

3.0000

3

3.0000

3.0000

4

3.0000

3.0000

5

3.0000

3.0000

6

3.0000

3.0000

7

3.0000

3.0000

8

3.0000

3.0000

9

3.0000

3.0000

10

3.0000

3.0000

Diaphragms

Girder Bay 1

Girder Bay 2

Girder Bay 3

Girder Bay 4

Girder Bay 5

Girder Bay 6

Girder Bay 7

Girder Bay 8

Girder Bay 9

Girder Bay 10

Structure Typical Section

Deck

Left start width: 18.00 (ft)

Left end width: 18.00 (ft)

Right start width: 15.00 (ft)

Right end width: 15.00 (ft)

Left start overhang: 1.50 (ft)

Left end overhang: 1.50 (ft)

Deck (Cont'd)

Deck concrete:

Total deck thickness: (in)

Deck crack control parameter: (kip/in)

Sustained modular ratio factor: 3.000

Railing

Name	Load Case	Measure To	Measured From	Distance At Start	Distance At End	Front Face Orientation
Conc Guar...	DC1 - R...		Left Ed...	0.00	0.00	Right
Conc Guar...	DC1 - R...		Right E...	0.00	0.00	Left

Sidewalk

Width	Thickness At End	Material	Load Case	Measure to	Measured From	At Start
60.0000	11.4375	Class A...	DC1 - C...		Left Ed...	0.00 ...
24.0000	10.5630	Class A...	DC1 - C...		Right E...	0.00 ...

Lane Position

Offset Left Start: -13.00 (ft)

Offset Left End: -13.00 (ft)

Offset Right Start: 0.00 (ft)

Offset Right End: 0.00 (ft)

Offset Left Start: 13.00 (ft)

Offset Left End: 13.00 (ft)

Offset Right Start: 0.00 (ft)

Offset Right End: 0.00 (ft)

Wearing Surface

Wearing surface material: Asphalt

Description: Asphalt Wearing Surface

Wearing surface thickness: 1.1670 (in)

Wearing surface density: 145.000 (pcf)

Load case: DW - A.W.S.

Load Case Description

Load Case Name	Description	Stage	Type	Time (Days)
DC1 - Railing	DC acting on non-comp...	Non-composite (Sta...		D,DC
DC1 - Curb	DC acting on non-comp...	Non-composite (Sta...		D,DC
DW - A.W.S.	DW acting on long-ter...	Composite (long te...		D,DW

Superstructure Loads

DL Distribution

Stage 1 Dead Load Distribution: Tributary Area

Stage 2 Dead Load Distribution: Uniformly to All Girders

Stiffener Definitions

Stress Limits

Name: PS Conc Stress Limits

Description:

Concrete material:	Class P (5000)	
Initial allowable tension (LFD):	0.190	(ksi)
Initial allowable compression (LFD):	2.400	(ksi)
Final allowable slab compression (LFD):		(ksi)
Final allowable tension (LFD):	0.425	(ksi)
Final allowable DL compression (LFD):	2.000	(ksi)
Final allowable compression (LFD):	3.000	(ksi)
Final allowable compression (LL + 1/2(Pe+DL)) (LFD):	2.000	(ksi)
Initial allowable tension (LRFD):	0.190	(ksi)
Initial allowable compression (LRFD):	2.600	(ksi)
Final allowable slab compression (LRFD):		(ksi)
Final allowable tension (LRFD):	0.425	(ksi)
Final allowable DL compression (LRFD):	2.250	(ksi)
Final allowable compression (LRFD):	3.000	(ksi)
Final allowable compression (LL + 1/2(Pe+DL)) (LRFD):	2.000	(ksi)

Prestress Properties

Name: **PS Strands Properties**

General Pretress Data

Prestressing Strand:	7/16" (7W-250) SR
Loss Method:	AASHTO Approximate
Jacking stress ratio:	0.700
Transfer stress ratio:	
Transfer time:	24.0 (Hours)
AASHTO - Dead load percent:	0.0 (%)

Loss Data - PCI

PCI - Maturity coefficient:	
PCI - Ultimate creep loss:	(ksi)
PCI - Ultimate shrinkage loss:	(ksi)
PCI - Additional time 1:	(Days)
PCI - Additional time 2:	(Days)
PCI - Additional time 3:	(Days)
PCI - Additional time 4:	(Days)
PCI - Additional time 5:	(Days)
PCI - Additional time 6:	(Days)
PCI - Additional time 7:	(Days)
PCI - Additional time 8:	(Days)
PCI - Additional time 9:	(Days)
PCI - Additional time 10:	(Days)

Loss Data - Lump-sum

Lump-sum - Composite loss:	(ksi)
Lump-sum - Continuous loss:	(ksi)
Lump-sum - Final loss:	(ksi)

Shear Reinforcement Definitions - Vertical

Name:	#4 Bent Shear Reinf.
Vertical Reinforcement:	Grade 40
Vertical Rebar:	4
Number of legs (Vertical):	3.00

Inclination angle alpha (Vertical): 90.0 (Degrees)

Shear Reinforcement Definitions - Horizontal

Name: #3 - 2'-7" long
Reinforcement (Horz. 1): Grade 40
Rebar (Horz. 1): 3
Number of legs (Horz. 1): 1.00
Inclination angle alpha (Horz. 1): 90.0 (Degrees)
Reinforcement (Horz. 2):
Rebar (Horz. 2):
Number of legs (Horz. 2):
Inclination angle alpha (Horz. 2): 90.0 (Degrees)

Member G1

Link with: None

Description:

Existing: 17"x36" EXT PSU -
Current: 17"x36" EXT PSU -
Number of Spans: 1

Span Number	Span Length (ft)
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support Number	Horizontal (in)	Vertical (in)	Rotational (Radians)	Load Case Name
1				
2				

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

Elastic

Support Number	X Translation (kip/ft)	Y Translation (kip/ft)	Z Rotation (kip-in/rad)	Override Computed Z Rotation
1				

Member Alternative 17"x36" EXT PSU

Description:

Description

Material Type: Prestressed Concrete
 Girder Type: PS Precast Box
 Member units: US Customary
 Girder property input method: Schedule based
 Additional Self Load: (kip/ft)
 Additional Self Load %: 1.0 (%)

Analysis Module

Analysis Method: ASD
 Analysis Module: AASHTO ASD
 Analysis Module Component:
 Properties:

Analysis Method: LFD
 Analysis Module: AASHTO LFD
 Analysis Module Component:
 Properties:

Analysis Method: LRFD
 Analysis Module: AASHTO LRFD
 Analysis Module Component:
 Properties:

Analysis Method: LRFR
 Analysis Module: AASHTO LRFR
 Analysis Module Component:
 Properties:

Analysis Method: Distribution Factors
 Analysis Module: Legacy BrR Dist Fact
 Analysis Module Component:
 Properties:

Default rating method: LRFR
 LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:

LFD: 2002 AASHTO Std. Specifications(CD=0.90)

ASD Factors

Inventory Operating

Structural steel

Concrete

PS Concrete Comp.

PS Concrete Tens.

PS Moment Cap.
Reinforcement
Bearing Stiffener
Stirrup
Timber NA

Default Materials

Deck concrete: Class A (3000)
Deck reinforcement: Grade 40
Beam concrete: Class P (5000)
Beam reinforcement: Grade 40
Stirrup reinforcement: Grade 40
Prestressing strand: 7/16" (7W-250) SR

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)

Lanes	Shear	Shear at Supports	Moment	Deflection
Loaded				
1 Lane	0.100	0.100	0.100	0.100
Multi-Lane	0.100	0.100	0.100	0.100

LRFD

Distance (ft)	Length (ft)	Type	1 Lane	Multi-Lane
0.00	38.500	Deflectio...	0.100	0.100
0.00	38.500	Moment	0.100	0.100
0.00	38.500	Shear	0.100	0.100

Shrinkage/Time

Deck curing method: Moist-cured

Deck drying time: 3.000 (Days)

Consider deck differential shrinkage loads: FALSE

Beam Curing method: Steam-cured

Curing time: 20.00 (Days)

Service life: 75.00 (Years)

Analysis time: 54.00 (Years)

Composite time: 60.00 (Days)

Continuous time: 45.0 (Days)

Beam Details

Span Details

Span	Prestress Shape Use	Concrete Material	Prestress Properties	Left Projection	Right
	Projection	Creep		(in) (in)	
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	8.5000	8.5000

Continuous Support Details

Support Number	Support Distance on Left, SL (in)	Support Distance on Right, SR (in)
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance (ft)	Length (ft)
PS Conc Stress Lim...	1	0.000	39.92

Slab Interface

Deck interface type:	Monolithic
Interface width:	(in)
Deck cohesion factor:	0.400 (ksi)
Deck friction factor:	1.400

Continuity Diaphragm

Span	Material	Left Support Distance	Bar	Bar	Right Support	Distance
No.	Bar	Bar	Count	Size	Count	Size

Prestressing Force Information**Strand Layout**

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance (ft)	Debond Distance (in)	Harp Curvature (in)
1	Left	1	1	Straight/Debonded			
	Right						
1	Left	1	2	Straight/Debonded			
	Right						

1		1	3	Straight/Debonded
	Left			
	Right			
1		1	4	Straight/Debonded
	Left			
	Right			
1		1	5	Straight/Debonded
	Left			
	Right			
1		1	6	Straight/Debonded
	Left			
	Right			
1		1	7	Straight/Debonded
	Left			
	Right			
1		1	8	Straight/Debonded
	Left			
	Right			
1		1	9	Straight/Debonded
	Left			
	Right			
1		1	10	Straight/Debonded
	Left			
	Right			
1		1	11	Straight/Debonded
	Left			
	Right			
1		1	12	Straight/Debonded
	Left			
	Right			
1		1	13	Straight/Debonded
	Left			
	Right			
1		1	14	Straight/Debonded
	Left			
	Right			
1		1	15	Straight/Debonded
	Left			
	Right			
1		1	16	Straight/Debonded
	Left			
	Right			
1		2	1	Straight/Debonded
	Left			
	Right			
1		2	2	Straight/Debonded
	Left			
	Right			
1		2	3	Straight/Debonded
	Left			

1	Right	2	4	Straight/Debonded
1	Left Right	2	5	Straight/Debonded
1	Left Right	2	6	Straight/Debonded
1	Left Right	3	1	Straight/Debonded
1	Left Right	3	7	Straight/Debonded
1	Left Right	3	10	Straight/Debonded
1	Left Right	3	16	Straight/Debonded

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	8.96	1	1.0000	0.1636
1	9.96...	20.00	1	1.0000	0.1636
1	29.96...	8.96	1	1.0000	0.1636

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Extends into Deck
#4 Bent Shear R...	1	0.21	4	6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	10.5000	FALSE
#4 Bent Shear R...	1	3.08	27	15.0000	FALSE
#4 Bent Shear R...	1	36.83	1	10.5000	FALSE
#4 Bent Shear R...	1	37.71	4	6.0000	FALSE

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance	Number Spaces	Spacing	Composite Length
------------------------	------------	-------------------	------------------	---------	---------------------

#3 - 2'-7" long	1	(ft) 0.21	4	(in) 6.0000	(ft)
#3 - 2'-7" long	1	2.21	1	10.5000	
#3 - 2'-7" long	1	3.08	27	15.0000	
#3 - 2'-7" long	1	36.83	1	10.5000	
#3 - 2'-7" long	1	37.71	4	6.0000	

Member G2

Link with: None

Description:

Existing: 17"x36" INT PSU -

Current: 17"x36" INT PSU -

Number of Spans: 1

Span Number	Span Length (ft)
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support Number	Horizontal (in)	Vertical (in)	Rotational (Radians)	Load Case Name
1				
2				

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

Elastic

Support Number	X Translation (kip/ft)	Y Translation (kip/ft)	Z Rotation (kip-in/rad)	Override Computed Z Rotation
1				
2				

Member Alternative 17"x36" INT PSU

Description:

Description

Material Type: Prestressed Concrete

Girder Type: PS Precast Box
Member units: US Customary
Girder property input method: Schedule based
Additional Self Load: (kip/ft)
Additional Self Load %: 1.0 (%)

Analysis Module

Analysis Method: ASD
Analysis Module: AASHTO ASD
Analysis Module Component:
Properties:

Analysis Method: LFD
Analysis Module: AASHTO LFD
Analysis Module Component:
Properties:

Analysis Method: LRFD
Analysis Module: AASHTO LRFD
Analysis Module Component:
Properties:

Analysis Method: LRFR
Analysis Module: AASHTO LRFR
Analysis Module Component:
Properties:

Analysis Method: Distribution Factors
Analysis Module: Legacy BrR Dist Fact
Analysis Module Component:
Properties:

Default rating method: LRFR
LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:
LFD: 2002 AASHTO Std. Specifications(CD=0.90)

ASD Factors

Inventory Operating

Structural steel
Concrete
PS Concrete Comp.
PS Concrete Tens.
PS Moment Cap.
Reinforcement
Bearing Stiffener
Stirrup
Timber

NA

Default Materials

Deck concrete: Class A (3000)
Deck reinforcement: Grade 40
Beam concrete: Class P (5000)
Beam reinforcement: Grade 40
Stirrup reinforcement: Grade 40
Prestressing strand: 7/16" (7W-250) SR

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)

Lanes	Shear	Shear at Supports	Moment	Deflection
Loaded				
1 Lane	0.167	0.167	0.167	0.167
Multi-Lane	0.167	0.167	0.167	0.167

LRFD

Distance (ft)	Length (ft)	Type	1 Lane	Multi-Lane
0.00	38.500	Deflectio...	0.167	0.200
0.00	38.500	Moment	0.167	0.200
0.00	38.500	Shear	0.167	0.200

Shrinkage/Time

Deck curing method: Moist-cured
Deck drying time: 3.000 (Days)
Consider deck differential shrinkage loads: FALSE
Beam Curing method: Steam-cured
Curing time: 20.00 (Days)
Service life: 75.00 (Years)
Analysis time: 54.00 (Years)
Composite time: 60.00 (Days)
Continuous time: 45.0 (Days)

Beam Details

Span Details

Span	Prestress Shape Use	Concrete Material n	Prestress Properties	Left Projection	Right Projection
	Projection	Creep			

1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	(in) (in) 8.5000	8.5000
---	---------------------	-----------------------------	------------------	---------------------	--------

Continuous Support Details

Support Number	Support Distance on Left, SL (in)	Support Distance on Right, SR (in)
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance (ft)	Length (ft)
PS Conc Stress Lim...	1	0.000	39.92

Slab Interface

Deck interface type:	Monolithic
Interface width:	(in)
Deck cohesion factor:	0.400 (ksi)
Deck friction factor:	1.400

Continuity Diaphragm

Span	Material	Left Support			Right Support	
Bar	Bar	Distance	Bar	Bar	Material	Distance
No.		Bar	Count	Size	Count	Size

Prestressing Force Information

Strand Layout

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance (ft)	Debond Distance (in)	Harp Curvature (in)
1	Left	1	1	Straight/Debonded			
	Right						
1	Left	1	2	Straight/Debonded			
	Right						
1	Left	1	3	Straight/Debonded			
	Right						
1	Left	1	4	Straight/Debonded			
	Right						

1		1	5	Straight/Debonded
	Left			
	Right			
1		1	6	Straight/Debonded
	Left			
	Right			
1		1	7	Straight/Debonded
	Left			
	Right			
1		1	8	Straight/Debonded
	Left			
	Right			
1		1	9	Straight/Debonded
	Left			
	Right			
1		1	10	Straight/Debonded
	Left			
	Right			
1		1	11	Straight/Debonded
	Left			
	Right			
1		1	12	Straight/Debonded
	Left			
	Right			
1		1	13	Straight/Debonded
	Left			
	Right			
1		1	14	Straight/Debonded
	Left			
	Right			
1		1	15	Straight/Debonded
	Left			
	Right			
1		1	16	Straight/Debonded
	Left			
	Right			
1		2	1	Straight/Debonded
	Left			
	Right			
1		2	2	Straight/Debonded
	Left			
	Right			
1		2	3	Straight/Debonded
	Left			
	Right			
1		2	4	Straight/Debonded
	Left			
	Right			
1		2	5	Straight/Debonded
	Left			

1	Right	2	6	Straight/Debonded
1	Left			
1	Right	3	1	Straight/Debonded
1	Left			
1	Right	3	7	Straight/Debonded
1	Left			
1	Right	3	10	Straight/Debonded
1	Left			
1	Right	3	16	Straight/Debonded
	Left			
	Right			

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	8.96	1	1.0000	0.1636
1	9.95...	20.00	1	1.0000	0.1636
1	29.95...	8.96	1	1.0000	0.1636

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Extends into Deck
#4 Bent Shear R...	1	0.21	4	6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	10.5000	FALSE
#4 Bent Shear R...	1	3.08	27	15.0000	FALSE
#4 Bent Shear R...	1	36.83	1	10.5000	FALSE
#4 Bent Shear R...	1	37.71	4	6.0000	FALSE

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Composite Length (ft)
#3 - 2'-7" long	1	0.21	4	6.0000	
#3 - 2'-7" long	1	2.21	1	10.5000	
#3 - 2'-7" long	1	3.08	27	15.0000	
#3 - 2'-7" long	1	36.83	1	10.5000	
#3 - 2'-7" long	1	37.71	4	6.0000	

Member G3

Link with: None

Description:

Existing: 17"x36" INT PSU - w/ Conc Repair Only -

Current: 17"x36" INT PSU - w/ Conc Repair Only -

Number of Spans: 1

Span Number	Span Length (ft)
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support Number	Horizontal (in)	Vertical (in)	Rotational (Radians)	Load Case Name
1				
2				

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

Elastic

Support Number	X Translation (kip/ft)	Y Translation (kip/ft)	Z Rotation (kip-in/rad)	Override Computed Z Rotation
1				
2				

Member Alternative 17"x36" INT PSU - w/ Conc Repair Only

Description:

Description

Material Type: Prestressed Concrete

Girder Type: PS Precast Box

Member units: US Customary

Girder property input method: Schedule based

Additional Self Load: (kip/ft)

Additional Self Load %: 1.0 (%)

Analysis Module

Analysis Method: ASD
Analysis Module: AASHTO ASD
Analysis Module Component:
Properties:

Analysis Method: LFD
Analysis Module: AASHTO LFD
Analysis Module Component:
Properties:

Analysis Method: LRFD
Analysis Module: AASHTO LRFD
Analysis Module Component:
Properties:

Analysis Method: LRFR
Analysis Module: AASHTO LRFR
Analysis Module Component:
Properties:

Analysis Method: Distribution Factors
Analysis Module: Legacy BrR Dist Fact
Analysis Module Component:
Properties:

Default rating method: LRFR
LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:

LFD: 2002 AASHTO Std. Specifications(CD=0.90)

ASD Factors

Inventory Operating

Structural steel

Concrete

PS Concrete Comp.

PS Concrete Tens.

PS Moment Cap.

Reinforcement

Bearing Stiffener

Stirrup

Timber

NA

Default Materials

Deck concrete: Class A (3000)

Deck reinforcement: Grade 40

Beam concrete: Class P (5000)

Beam reinforcement: Grade 40

Stirrup reinforcemt: Grade 40
 Prestressing strand: 7/16" (7W-250) SR

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)

Lanes	Shear	Shear at Supports	Moment	Deflection
Loaded				
1 Lane	1.000	1.000	1.000	1.000
Multi-Lane	1.000	1.000	1.000	1.000

LRFD

Distance	Length	Type	1 Lane	Multi-Lane
(ft)	(ft)			
0.00	38.500	Deflectio...	0.500	0.600
0.00	38.500	Moment	0.500	0.600
0.00	38.500	Shear	0.500	0.600

Shrinkage/Time

Deck curing method: Moist-cured

Deck drying time: 3.000 (Days)

Consider deck differential shrinkage loads: FALSE

Beam Curing method: Steam-cured

Curing time: 20.00 (Days)

Service life: 75.00 (Years)

Analysis time: 54.00 (Years)

Composite time: 60.00 (Days)

Continuous time: 45.0 (Days)

Beam Details

Span Details

Span	Prestress Shape Use	Concrete Material n	Prestress Properties	Left Projection	Right Projection
	Projection	Creep		(in) (in)	
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	8.5000	8.5000

Continuous Support Details

Support Support Distance Support Distance

Number	on Left, SL (in)	on Right, SR (in)
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance (ft)	Length (ft)
PS Conc Stress Lim...	1	0.000	39.92

Slab Interface

Deck interface type:	Monolithic
Interface width:	(in)
Deck cohesion factor:	0.400 (ksi)
Deck friction factor:	1.400

Continuity Diaphragm

Span	Material	Left Support			Right Support	
Bar	Bar	Distance	Bar	Bar	Material	Distance
No.		Bar	Count	Size	Count	Size

Prestressing Force Information

Strand Layout

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance (ft)	Debond Distance (in)	Harp Curvature (in)
1	Left	1	1	Straight/Debonded			
	Right						
1	Left	1	2	Straight/Debonded			
	Right						
1	Left	1	3	Straight/Debonded			
	Right						
1	Left	1	4	Straight/Debonded			
	Right						
1	Left	1	5	Straight/Debonded			
	Right						
1	Left	1	12	Straight/Debonded			
	Right						

1	Left	1	13	Straight/Debonded
	Right			
1	Left	1	14	Straight/Debonded
	Right			
1	Left	1	15	Straight/Debonded
	Right			
1	Left	1	16	Straight/Debonded
	Right			
1	Left	2	1	Straight/Debonded
	Right			
1	Left	2	2	Straight/Debonded
	Right			
1	Left	2	4	Straight/Debonded
	Right			
1	Left	2	5	Straight/Debonded
	Right			
1	Left	2	6	Straight/Debonded
	Right			
1	Left	3	1	Straight/Debonded
	Right			
1	Left	3	7	Straight/Debonded
	Right			
1	Left	3	10	Straight/Debonded
	Right			
1	Left	3	16	Straight/Debonded
	Right			

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	8.96	1	1.0000	0.1636
1	9.96...	20.00	1	1.0000	0.1636

1	29.95...	8.96	1	1.0000	0.1636
---	----------	------	---	--------	--------

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Extends into Deck
#4 Bent Shear R...	1	0.21	4	6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	10.5000	FALSE
#4 Bent Shear R...	1	3.08	27	15.0000	FALSE
#4 Bent Shear R...	1	36.83	1	10.5000	FALSE
#4 Bent Shear R...	1	37.71	4	6.0000	FALSE

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Composite Length (ft)
#3 - 2'-7" long	1	0.21	4	6.0000	
#3 - 2'-7" long	1	2.21	1	10.5000	
#3 - 2'-7" long	1	3.08	27	15.0000	
#3 - 2'-7" long	1	36.83	1	10.5000	
#3 - 2'-7" long	1	37.71	4	6.0000	

Member G4

Link with: G3

Description:

Existing:

Current:

Number of Spans: 1

Span Number	Span Length (ft)
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member G5

Link with: G3

Description:

Existing:

Current:

Number of Spans: 1

Span Number	Span Length
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member G6

Link with: G3

Description:

Existing:

Current:

Number of Spans: 1

Span Number	Span Length
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member G7

Link with: G3

Description:

Existing:

Current:

Number of Spans: 1

Span Number	Span Length
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member G8

Link with: None

Description:

Existing: 17"x36" INT PSU -
Current: 17"x36" INT PSU -
Number of Spans: 1

Span Number	Span Length (ft)
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support Number	Horizontal (in)	Vertical (in)	Rotational (Radians)	Load Case Name
1				
2				

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

Elastic

Support Number	X Translation (kip/ft)	Y Translation (kip/ft)	Z Rotation (kip-in/rad)	Override Computed Z Rotation
1				
2				

Member Alternative 17"x36" INT PSU

Description:

Description

Material Type: Prestressed Concrete
Girder Type: PS Precast Box
Member units: US Customary
Girder property input method: Schedule based
Additional Self Load: (kip/ft)
Additional Self Load %: 1.0 (%)

Analysis Module

Analysis Method: ASD
Analysis Module: AASHTO ASD
Analysis Module Component:

Properties:

Analysis Method: LFD
Analysis Module: AASHTO LFD
Analysis Module Component:
Properties:

Analysis Method: LRFD
Analysis Module: AASHTO LRFD
Analysis Module Component:
Properties:

Analysis Method: LRFR
Analysis Module: AASHTO LRFR
Analysis Module Component:
Properties:

Analysis Method: Distribution Factors
Analysis Module: Legacy BrR Dist Fact
Analysis Module Component:
Properties:

Default rating method: LRFR
LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:

LFD: 2002 AASHTO Std. Specifications(CD=0.85)

ASD Factors

	Inventory	Operating
Structural steel		
Concrete		
PS Concrete Comp.		
PS Concrete Tens.		
PS Moment Cap.		
Reinforcement		
Bearing Stiffener		
Stirrup		
Timber	NA	

Default Materials

Deck concrete:	Class A (3000)
Deck reinforcement:	Grade 40
Beam concrete:	Class P (5000)
Beam reinforcement:	Grade 40
Stirrup reinforcemt:	Grade 40
Prestressing strand:	7/16" (7W-250) SR

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)

Lanes	Shear	Shear at Supports	Moment	Deflection
Loaded				
1 Lane	1.000	1.000	1.000	1.000
Multi-Lane	1.000	1.000	1.000	1.000

LRFD

Distance	Length	Type	1 Lane	Multi-Lane
(ft)	(ft)			
0.00	38.500	Deflectio...	0.500	0.600
0.00	38.500	Moment	0.500	0.600
0.00	38.500	Shear	0.500	0.600

Shrinkage/Time

Deck curing method: Moist-cured

Deck drying time: 3.000 (Days)

Consider deck differential shrinkage loads: FALSE

Beam Curing method: Steam-cured

Curing time: 20.00 (Days)

Service life: 75.00 (Years)

Analysis time: 54.00 (Years)

Composite time: 60.00 (Days)

Continuous time: 45.0 (Days)

Beam Details

Span Details

Span	Prestress Shape Use	Concrete Material n	Prestress Properties	Left Projection	Right
	Projection	Creep		(in) (in)	
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	8.5000	8.5000

Continuous Support Details

Support Number	Support Distance on Left, SL (in)	Support Distance on Right, SR (in)
-------------------	-----------------------------------------	------------------------------------------

1

Stress Limit Ranges

Stress Limit	Span	Start Distance (ft)	Length (ft)
PS Conc Stress Lim...	1	0.000	39.92

Slab Interface

Deck interface type:	Monolithic
Interface width:	(in)
Deck cohesion factor:	0.400 (ksi)
Deck friction factor:	1.400

Continuity Diaphragm

Span	Material	Left Support Distance	Bar	Bar	Right Support Material	Distance
No.	Bar	Bar	Count	Size	Count	Size

Prestressing Force Information**Strand Layout**

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance (ft)	Debond Distance (in)	Harp Curvature (in)
1	Left	1	1	Straight/Debonded			
	Right						
1	Left	1	2	Straight/Debonded			
	Right						
1	Left	1	3	Straight/Debonded			
	Right						
1	Left	1	4	Straight/Debonded			
	Right						
1	Left	1	5	Straight/Debonded			
	Right						
1	Left	1	12	Straight/Debonded			
	Right						
1	Left	1	13	Straight/Debonded			
	Right						

1	Left	1	14	Straight/Debonded
	Right			
1	Left	1	15	Straight/Debonded
	Right			
1	Left	1	16	Straight/Debonded
	Right			
1	Left	2	1	Straight/Debonded
	Right			
1	Left	2	2	Straight/Debonded
	Right			
1	Left	2	4	Straight/Debonded
	Right			
1	Left	2	5	Straight/Debonded
	Right			
1	Left	2	6	Straight/Debonded
	Right			
1	Left	3	1	Straight/Debonded
	Right			
1	Left	3	7	Straight/Debonded
	Right			
1	Left	3	10	Straight/Debonded
	Right			
1	Left	3	16	Straight/Debonded
	Right			

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	8.96	1	1.0000	0.1636
1	9.96...	20.00	1	1.0000	0.1636
1	29.95...	8.96	1	1.0000	0.1636

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Extends into Deck
#4 Bent Shear R...	1	0.21	4	6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	10.5000	FALSE
#4 Bent Shear R...	1	3.08	27	15.0000	FALSE
#4 Bent Shear R...	1	36.83	1	10.5000	FALSE
#4 Bent Shear R...	1	37.71	4	6.0000	FALSE

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Composite Length (ft)
#3 - 2'-7" long	1	0.21	4	6.0000	
#3 - 2'-7" long	1	2.21	1	10.5000	
#3 - 2'-7" long	1	3.08	27	15.0000	
#3 - 2'-7" long	1	36.83	1	10.5000	
#3 - 2'-7" long	1	37.71	4	6.0000	

Member G9

Link with: G8

Description:

Existing: 17"x36" INT PSU - w/ Conc. Repair + Post Tensioning -

Current: 17"x36" INT PSU - w/ Conc. Repair + Post Tensioning -

Number of Spans: 1

Span Number	Span Length (ft)
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member G10

Link with: None

Description:

Existing: 17"x36" INT PSU - w/ Conc. Repair + Post Tensioning -

Current: 17"x36" INT PSU - w/ Conc. Repair + Post Tensioning -

Number of Spans: 1

Span Number	Span Length (ft)
-------------	---------------------

1 38.500000

Support Frame Connection

1

2

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support Number	Horizontal (in)	Vertical (in)	Rotational (Radians)	Load Case Name
-------------------	--------------------	------------------	-------------------------	----------------

1

2

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

Elastic

Support Number	X Translation (kip/ft)	Y Translation (kip/ft)	Z Rotation (kip-in/rad)	Override Computed Z Rotation
-------------------	---------------------------	---------------------------	----------------------------	---------------------------------

1

2

Member Alternative 17"x36" INT PSU - w/ Conc. Repair + Post Tensioning

Description:

Description

Material Type: Prestressed Concrete

Girder Type: PS Precast Box

Member units: US Customary

Girder property input method: Schedule based

Additional Self Load: (kip/ft)

Additional Self Load %: 1.0 (%)

Analysis Module

Analysis Method: ASD

Analysis Module: AASHTO ASD

Analysis Module Component:

Properties:

Analysis Method: LFD

Analysis Module: AASHTO LFD

Analysis Module Component:

Properties:

Analysis Method: LRFD

Analysis Module: AASHTO LRFD
Analysis Module Component:
Properties:

Analysis Method: LRFR
Analysis Module: AASHTO LRFR
Analysis Module Component:
Properties:

Analysis Method: Distribution Factors
Analysis Module: Legacy BrR Dist Fact
Analysis Module Component:
Properties:

Default rating method: LRFR
LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:

LFD: 2002 AASHTO Std. Specifications(CD=0.90)

ASD Factors

Inventory Operating

Structural steel

Concrete

PS Concrete Comp.

PS Concrete Tens.

PS Moment Cap.

Reinforcement

Bearing Stiffener

Stirrup

Timber NA

Default Materials

Deck concrete: Class A (3000)

Deck reinforcement: Grade 40

Beam concrete: Class P (5000)

Beam reinforcement: Grade 40

Stirrup reinforcement: Grade 40

Prestressing strand: 7/16" (7W-250) SR

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)

Lanes Loaded	Shear	Shear at Supports	Moment	Deflection
1 Lane	0.527	0.000	0.527	0.182
Multi-Lane	0.527	0.000	0.527	0.364

LRFD

Distance (ft)	Length (ft)	Type	1 Lane	Multi-Lane
0.00	38.500	Moment	0.254	0.256
0.00	38.500	Shear	0.254	0.256
0.00	38.500	Deflectio...	0.109	0.182

Shrinkage/Time

Deck curing method: Moist-cured
Deck drying time: 3.000 (Days)
Consider deck differential shrinkage loads: FALSE
Beam Curing method: Steam-cured
Curing time: 20.00 (Days)
Service life: 75.00 (Years)
Analysis time: 54.00 (Years)
Composite time: 60.00 (Days)
Continuous time: 45.0 (Days)

Beam Details

Span Details

Span	Prestress Shape Use	Concrete Material n	Prestress Properties	Left Projection (in)	Right Projection (in)
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	8.5000	8.5000

Continuous Support Details

Support Number	Support Distance on Left, SL (in)	Support Distance on Right, SR (in)
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance (ft)	Length (ft)
PS Conc Stress Lim...	1	0.000	39.92

Slab Interface

Deck interface type: Monolithic
 Interface width: (in)
 Deck cohesion factor: 0.400 (ksi)
 Deck friction factor: 1.400

Continuity Diaphragm

Span	Material	Left Support	Bar	Bar	Right Support	Distance
No.	Bar	Distance	Bar	Count	Material	Count Size

Prestressing Force Information**Strand Layout**

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance (ft)	Debond Distance (in)	Harp Curvature (in)
1	Left	1	1	Straight/Debonded			
1	Right	1	2	Straight/Debonded			
1	Left	1	3	Straight/Debonded			
1	Right	1	4	Straight/Debonded			
1	Left	1	5	Straight/Debonded			
1	Right	1	12	Straight/Debonded			
1	Left	1	13	Straight/Debonded			
1	Right	1	14	Straight/Debonded			
1	Left	1	15	Straight/Debonded			
1	Right	1	16	Straight/Debonded			

1	Right	2	1	Straight/Debonded
1	Left Right	2	2	Straight/Debonded
1	Left Right	2	4	Straight/Debonded
1	Left Right	2	5	Straight/Debonded
1	Left Right	2	6	Straight/Debonded
1	Left Right	3	1	Straight/Debonded
1	Left Right	3	7	Straight/Debonded
1	Left Right	3	10	Straight/Debonded
1	Left Right	3	16	Straight/Debonded

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	8.96	1	1.0000	0.1636
1	9.96...	20.00	1	1.0000	0.1636
1	29.95...	8.96	1	1.0000	0.1636

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Extends into Deck
#4 Bent Shear R...	1	0.21	4	6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	10.5000	FALSE
#4 Bent Shear R...	1	3.08	27	15.0000	FALSE
#4 Bent Shear R...	1	36.83	1	10.5000	FALSE

#4 Bent Shear R...	1	37.71	4	6.0000	FALSE
--------------------	---	-------	---	--------	-------

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance <i>(ft)</i>	Number Spaces	Spacing <i>(in)</i>	Composite Length <i>(ft)</i>
#3 - 2'-7" long	1	0.21	4	6.0000	
#3 - 2'-7" long	1	2.21	1	10.5000	
#3 - 2'-7" long	1	3.08	27	15.0000	
#3 - 2'-7" long	1	36.83	1	10.5000	
#3 - 2'-7" long	1	37.71	4	6.0000	

Member G11

Link with: G1

Description:

Existing:

Current:

Number of Spans: 1

Span Number	Span Length <i>(ft)</i>
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: *(lb/ft)*

Username: BrR

Date: Wednesday, September 22, 2021 10:06:29

Bridge ID 874294 Matheson Hmck Bridge over Matheson Hammock Canal

NBI Structure ID (8): 874294

Description: Rating by YRA, from As-built plans, 9/14/2021

Three spans (30'-40'-30') non-composite PS Concrete voided slab unit superstructure comprised of eleven (11) 17"x36" units. Deck width is 35'-0" out-to-out with a 26'-0" clear roadway width.

Wearing surface is present along the bridge with an average thickness of 1.167" along end spans 1 and 3, and 1.292" for interior span 2.

The load rating analysis for the prestressed voided slab units was initially performed using the Load and Resistance factor Rating methodology in accordance with the AASHTO LRFD Bridge Design Specifications (9th edition, 2020), the Manual for Bridge Evaluation (3rd edition with interims through 2019), and the FDOT Bridge Load Rating Manual (January 2021). However, the resulting design and legal rating factors were less than 1, which granted the need to evaluate the structure using the Load Factor Rating methodology.

Description

Location:	Matheson Hammock Park
Total Length:	100.33 <i>(ft)</i>
Facility Carried:	Matheson Hmk Road
Route Number:	00000
Feature Intersected:	Matheson Hammock Canal
Mi Post:	0.08 <i>(mi)</i>
Units:	US Customary
Year Built:	1967
Recent ADTT:	11
District:	District 6
County:	
Owner:	County Hwy Agency
National Highway System:	0 Not on NHS
Functional Class:	09 Rural Local

Global Reference Point

X Coordinate:	0.000 <i>(ft)</i>
Y Coordinate:	0.000 <i>(ft)</i>
Elevation:	<i>(ft)</i>
Longitude:	80.26 <i>(Degrees)</i>
Latitude:	25.68 <i>(Degrees)</i>

Materials

No steel materials.

Concrete

Name:	Class P (5000)
Description:	Class 5000 cement concrete
Specified compressive strength at 28 days (f _c):	5.000 <i>(ksi)</i>

Initial specified compressive strength (f'ci):	4.000 (ksi)
Coefficient of thermal expansion:	0.0000060000 (1/F)
Density (for dead loads):	0.150 (kef)
Density (for modulus of elasticity):	0.145 (kef)
Std Modulus of elasticity (Ec):	4074.28 (ksi)
LRFD Modulus of elasticity (Ec):	4291.19 (ksi)
Poisson's ratio:	0.200
Modulus of rupture:	0.537 (ksi)
Shear factor:	1.000
Composition of concrete:	Normal
Std Initial modulus of elasticity (Eci):	3644.15 (ksi)
LRFD Initial modulus of elasticity (Eci):	3986.55 (ksi)
Splitting tensile strength (fct):	(ksi)

Name:	Class A (3000)
Description:	Class A cement concrete (3000 psi)
Specified compressive strength at 28 days (f'c):	3.000 (ksi)
Initial specified compressive strength (f'ci):	(ksi)
Coefficient of thermal expansion:	0.0000060000 (1/F)
Density (for dead loads):	0.150 (kef)
Density (for modulus of elasticity):	0.145 (kef)
Std Modulus of elasticity (Ec):	3150.39 (ksi)
LRFD Modulus of elasticity (Ec):	3617.02 (ksi)
Poisson's ratio:	0.200
Modulus of rupture:	0.416 (ksi)
Shear factor:	1.000
Composition of concrete:	Normal
Std Initial modulus of elasticity (Eci):	(ksi)
LRFD Initial modulus of elasticity (Eci):	(ksi)
Splitting tensile strength (fct):	(ksi)

Reinforcing Steel

Name:	Grade 40
Description:	40 ksi reinforcing steel
Specified yield strength (Fy):	40.000 (ksi)
Modulus of elasticity (Es):	29000.00 (ksi)
Ultimate strength (Fu):	70.000 (ksi)
Type:	Plain

Prestressing Strand

Name:	7/16" (7W-250) SR
Description:	Stress relieved 7/16"/Seven Wire/fpu = 250
Specified yield strength (Fy):	212.500 (ksi)
Ultimate Tensile strength (Fu):	250.000 (ksi)
Modulus of elasticity (Es):	28500.00 (ksi)
Load per unit length:	0.367 (lb/ft)
Cross sectional area (A):	0.108 (in^2)
Nominal diameter (d):	0.4375 (in)
Transfer length (Std):	21.8750 (in)
Transfer length (LRFD):	26.2500 (in)

Type:
Epoxy coated:

Stress Relieved
FALSE

No timber materials.

Beam Shapes

Steel Shapes

No steel shapes.

Prestressed Shapes

No prestressed I shapes.

Prestressed Box Shapes

Name: 17"x36" PSU
Description: 17"x36" Prestressed Slab Unit for units E thru G
Type: Circular Void
Nominal Depth: 17.0000 (in)
Depth (d): 17.0000 (in)
Top flange width: 35.0000 (in)
Bottom flange width: 36.0000 (in)
Three-void (D1, D2, D1) shape: FALSE
Circular void diameter: 10.0000 (in)
Distance to CG of void(s) from bottom: 9.0000 (in)
Number of circular voids: 2
Center to center distance of voids: 16.0000 (in)
Vertical location of shear key: 2.0000 (in)
Shear key height: 6.0000 (in)
Shear key depth: 1.5000 (in)
Nominal load: 457.107 (lb/ft)
Cross sectional area: 438.822 (in²)
Ixx: 13330.101 (in⁴)
CG from bottom: 8.1667 (in)
Bottom Sxx: 1632.246 (in³)
Top Sxx: 1509.078 (in³)
Volume/Surface Ratio: 3.175 (in)
Half Depth Area for Positive Flexure: (in²)
Half Depth Area for Negative Flexure: (in²)
St. Venant's Torsional Constant: 14593.772 (in⁴)

Strand Grid

Row Number	Number of Strands	Vertical Location (in)	Horizontal Spacing (in)
1	16	2.5000	2.0000

2	6	4.5000	2.0000
3	16	14.5000	2.0000

No prestressed U shapes.

No prestressed tee shapes.

Timber Shapes

No timber shapes.

Appurtenances

No concrete railings.

Railings

Name: **Conc Guardrail w/ metal Post and Rail**
Description: Conc. Post and beam guardrail with post and tube rail mounted
Effective Wind Height: 36.0000 (in)
Railing Load: 0.166 (kip/ft)
Distance From Edge to Centroid: 5.0000 (in)
Width: 10.0000 (in)

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Factors

Factors - LFD

Name: 2002 AASHTO Std. Specifications

Description: AASHTO Standard Specifications for Highway Bridges, 17th Edition, 2002

Load Factors

Load Group	Gamma D	(L+I)n	(L+I)p	CF	E	B
Inventory	1.300	1.000	1.670	0.000	1.000	1.000
Operating	1.300	1.000	1.000	0.000	1.000	1.000

Load Group	SF	W	WL	LF	R+S+T	EQ	ICE
Inventory	1.000	0.000	0.000	0.000	0.000	0.000	0.000
Operating	1.000	0.000	0.000	0.000	0.000	0.000	0.000

Resistance Factors

Reinforced concrete:

Flexure: 0.900

Reinforced concrete:

Shear: 0.850

Prestressed concrete:

Flexure: 1.000

Prestressed concrete:

Shear: 0.900

Prestressed concrete:

Flexure in Non-P/S Components: 0.900

Steel:

Flexure: 1.000

Steel:

Shear: 1.000

Steel:

Bearing Stiffeners: 1.000

Name: 2002 AASHTO Std. Specifications(CF=0.9)

Description: AASHTO Standard Specifications for Highway Bridges,
17th Edition, 2002Load Factors

Load Group	Gamma D		(L+I)n	(L+I)p	CF	E	B
Inventory	1.300	1.000	1.670	0.000	1.000	1.000	1.000
Operating	1.300	1.000	1.000	0.000	1.000	1.000	1.000

Load Group	SF	W	WL	LF	R+S+T	EQ	ICE
Inventory	1.000	0.000	0.000	0.000	0.000	0.000	0.000
Operating	1.000	0.000	0.000	0.000	0.000	0.000	0.000

Resistance Factors

Reinforced concrete:

Flexure: 0.810

Reinforced concrete:

Shear: 0.765

Prestressed concrete:

Flexure: 0.900

Prestressed concrete:

Shear: 0.810

Prestressed concrete:

Flexure in Non-P/S Components: 0.810

Steel:

Flexure: 0.900

Steel:

Shear: 0.900

Steel:

Bearing Stiffeners: 0.900

Name: 2002 AASHTO Std. Specifications(CF=0.95)

Description: AASHTO Standard Specifications for Highway Bridges,

17th Edition, 2002

Load Factors

Load Group	Gamma	D	(L+I)n	(L+I)p	CF	E	B
Inventory	1.300	1.000	1.670	0.000	1.000	1.000	1.000
Operating	1.300	1.000	1.000	0.000	1.000	1.000	1.000

Load Group	SF	W	WL	LF	R+S+T	EQ	ICE
Inventory	1.000	0.000	0.000	0.000	0.000	0.000	0.000
Operating	1.000	0.000	0.000	0.000	0.000	0.000	0.000

Resistance Factors

Reinforced concrete:

Flexure: 0.855

Reinforced concrete:

Shear: 0.807

Prestressed concrete:

Flexure: 0.950

Prestressed concrete:

Shear: 0.855

Prestressed concrete:

Flexure in Non-P/S Components: 0.855

Steel:

Flexure: 0.950

Steel:

Shear: 0.950

Steel:

Bearing Stiffeners: 0.950

Name: 2002 AASHTO Std. Specifications(CF=0.85)

Description: AASHTO Standard Specifications for Highway Bridges,

17th Edition, 2002

Load Factors

Load Group	Gamma	D	(L+I)n	(L+I)p	CF	E	B
Inventory	1.300	1.000	1.670	0.000	1.000	1.000	1.000
Operating	1.300	1.000	1.000	0.000	1.000	1.000	1.000

Load Group	SF	W	WL	LF	R+S+T	EQ	ICE
Inventory	1.000	0.000	0.000	0.000	0.000	0.000	0.000
Operating	1.000	0.000	0.000	0.000	0.000	0.000	0.000

Resistance Factors

Reinforced concrete:

Flexure: 0.765

Reinforced concrete:

Shear: 0.723

Prestressed concrete:

Flexure: 0.850

Prestressed concrete:

Shear:	0.765
Prestressed concrete:	
Flexure in Non-P/S Components:	0.765
Steel:	
Flexure:	0.850
Steel:	
Shear:	0.850
Steel:	
Bearing Stiffeners:	0.850

No LRFD Factors specified.

Bridge Alternatives End Span 1 (or 3) - Bridge Alt.

Reference Line

Reference Line Length:	(ft)
Starting Station:	(ft)
Bearing:	N 90^ 0' 0.00" E

Global Positioning

Distance:	0.000 (ft)
Offset:	0.000 (ft)
Elevation:	(ft)

Structures

Name:	Exist. EXT Span 1(or 3) SuperStr
Description:	

Structure Alternatives

Name: Exist. END Span 1(or 3) Alt.

Description:

Superstructure Definition: End Span 1 (or 3) - PS Conc PSU

Bridge Alternatives INT Span 2 - Bridge Alt.

Reference Line

Reference Line Length:	(ft)
Starting Station:	(ft)
Bearing:	N 90^ 0' 0.00" E

Global Positioning

Distance:	0.000 (ft)
Offset:	0.000 (ft)
Elevation:	(ft)

Structures

Name:	Exist. INT Span 2 Superstruct.
-------	--------------------------------

Description:

Structure Alternatives

Name: Exist. INT Span 2 Alt.

Description:

Superstructure Definition: INT Span 2 - PS Conc PSU

Superstructure Definition End Span 1 (or 3) - PS Conc PSU

Definition

Units: US Customary

Number of spans: 1

Number of girders: 11

Length

Span (ft)

1 28.2917

Frame Structure Simplified Definition:

Support Frame Connection

1

2

Girder Spacing Display Type: Perpendicular

Average Humidity: 70.000 (%)

Analysis

Default Library Factors

Factor Override

Analysis Module

Analysis Method: ASD

Analysis Module:

Analysis Module Component:

Properties:

Analysis Method: LFD

Analysis Module:

Analysis Module Component:

Properties:

Analysis Method: LRFD

Analysis Module:

Analysis Module Component:

Properties:

Analysis Method: LRFR

Analysis Module:

Analysis Module Component:

Properties:

Analysis Method: Distribution Factors

Analysis Module:

Analysis Module Component:
Properties:

Default rating method: LFD

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Structure Framing Plan Details

Layout

	Skew	
Support	(Degrees)	
1	0.0000	
2	0.0000	
Girder Spacing Orientation:	Perpendicular	

Girder	Girder Spacing	
Bay	Start	End
	(ft)	(ft)
1	3.0000	3.0000
2	3.0000	3.0000
3	3.0000	3.0000
4	3.0000	3.0000
5	3.0000	3.0000
6	3.0000	3.0000
7	3.0000	3.0000
8	3.0000	3.0000
9	3.0000	3.0000
10	3.0000	3.0000

Diaphragms

Girder Bay 1
Girder Bay 2
Girder Bay 3
Girder Bay 4
Girder Bay 5
Girder Bay 6
Girder Bay 7
Girder Bay 8
Girder Bay 9
Girder Bay 10

Structure Typical Section

Deck

Left start width: 18.00 (ft)

Left end width: 18.00 (ft)

Right start width: 15.00 (ft)
 Right end width: 15.00 (ft)
 Left start overhang: 1.50 (ft)
 Left end overhang: 1.50 (ft)

Deck (Cont'd)

Deck concrete:

Total deck thickness: (in)

Deck crack control parameter: (kip/in)

Sustained modular ratio factor: 3.000

Railing

Name	Load Case	Measure To	Measured From	Distance At Start	Distance At End	Front Face Orientation
Conc Guar...	DC1 - R...		Left Ed...	0.00	0.00	Right
Conc Guar...	DC1 - R...		Right E...	0.00	0.00	Left

Sidewalk

Width	Thickness At End	Material	Load Case	Measure to	Measured From	At Start
60.0000	11.4375	Class A...	DC1 - C...		Left Ed...	0.00 ...
24.0000	10.5630	Class A...	DC1 - C...		Right E...	0.00 ...

Lane Position

Offset Left Start: -13.00 (ft)
 Offset Left End: -13.00 (ft)
 Offset Right Start: 0.00 (ft)
 Offset Right End: 0.00 (ft)
 Offset Left Start: 13.00 (ft)
 Offset Left End: 13.00 (ft)
 Offset Right Start: 0.00 (ft)
 Offset Right End: 0.00 (ft)

Wearing Surface

Wearing surface material: Asphalt
 Description: Asphalt Wearing Surface
 Wearing surface thickness: 1.1670 (in)
 Wearing surface density: 145.000 (pcf)
 Load case: DW - A.W.S.

Load Case Description

Load Case Name	Description	Stage	Type	Time (Days)
DC1 - Railing	DC acting on non-comp...	Non-composite (Sta...		D,DC
DC1 - Curb	DC acting on non-comp...	Non-composite (Sta...		D,DC
DW - A.W.S.	DW acting on long-ter...	Composite (long te...		D,DW

Superstructure Loads

DL Distribution

Stage 1 Dead Load Distribution: Tributary Area

Stage 2 Dead Load Distribution: Uniformly to All Girders

Stiffener Definitions

Stress Limits

Name:

PS Conc Stress Limits

Description:

Concrete material: Class P (5000)

Initial allowable tension (LFD): 0.190 (ksi)

Initial allowable compression (LFD): 2.400 (ksi)

Final allowable slab compression (LFD): (ksi)

Final allowable tension (LFD): 0.425 (ksi)

Final allowable DL compression (LFD): 2.000 (ksi)

Final allowable compression (LFD): 3.000 (ksi)

Final allowable compression (LL + 1/2(Pe+DL)) (LFD): 2.000 (ksi)

Initial allowable tension (LRFD): 0.190 (ksi)

Initial allowable compression (LRFD): 2.600 (ksi)

Final allowable slab compression (LRFD): (ksi)

Final allowable tension (LRFD): 0.425 (ksi)

Final allowable DL compression (LRFD): 2.250 (ksi)

Final allowable compression (LRFD): 3.000 (ksi)

Final allowable compression (LL + 1/2(Pe+DL)) (LRFD): 2.000 (ksi)

Prestress Properties

Name:

PS Strands Properties

General Pretress Data

Prestressing Strand: 7/16" (7W-250) SR

Loss Method: AASHTO Approximate

Jacking stress ratio: 0.700

Transfer stress ratio:

Transfer time: 24.0 (Hours)

AASHTO - Dead load percent: 0.0 (%)

Loss Data - PCI

PCI - Maturity coefficient:

PCI - Ultimate creep loss: (ksi)

PCI - Ultimate shrinkage loss: (ksi)

PCI - Additional time 1: (Days)

PCI - Additional time 2: (Days)

PCI - Additional time 3: (Days)

PCI - Additional time 4: (Days)

PCI - Additional time 5: (Days)

PCI - Additional time 6: (Days)

PCI - Additional time 7: (Days)

PCI - Additional time 8: (Days)

PCI - Additional time 9: (Days)

PCI - Additional time 10: (Days)

Loss Data - Lump-sum

Lump-sum - Composite loss: (ksi)

Lump-sum - Continuous loss: (ksi)

Lump-sum - Final loss: (ksi)

Shear Reinforcement Definitions - Vertical

Name:

#4 Bent Shear Reinf.

Vertical Reinforcement:	Grade 40
Vertical Rebar:	4
Number of legs (Vertical):	3.00
Inclination angle alpha (Vertical):	90.0 <i>(Degrees)</i>

Shear Reinforcement Definitions - Horizontal

Name:	#3 - 2'-7" long
Reinforcement (Horz. 1):	Grade 40
Rebar (Horz. 1):	3
Number of legs (Horz. 1):	1.00
Inclination angle alpha (Horz. 1):	90.0 <i>(Degrees)</i>
Reinforcement (Horz. 2):	
Rebar (Horz. 2):	
Number of legs (Horz. 2):	
Inclination angle alpha (Horz. 2):	90.0 <i>(Degrees)</i>

Member G1

Link with: None

Description:

Existing:	17"x36" EXT PSU -
Current:	17"x36" EXT PSU -
Number of Spans:	1

Span	Span Length
Number	<i>(ft)</i>
1	28.291666

Support	Frame Connection
1	
2	

Pedestrian load: *(lb/ft)*

Member Loads

Member Loads - Settlement

Support	Horizontal	Vertical	Rotational	Load Case Name
Number	<i>(in)</i>	<i>(in)</i>	<i>(Radians)</i>	
1				
2				

Support Constraints

General

Support	Support			
Number	Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

Elastic

Support Number	X Translation (kip/ft)	Y Translation (kip/ft)	Z Rotation (kip-in/rad)	Override Computed Z Rotation
1				
2				

Member Alternative 17"x36" EXT PSU

Description:

Description

Material Type: Prestressed Concrete

Girder Type: PS Precast Box

Member units: US Customary

Girder property input method: Schedule based

Additional Self Load: (kip/ft)

Additional Self Load %: 1.0 (%)

Analysis Module

Analysis Method: ASD

Analysis Module: AASHTO ASD

Analysis Module Component:

Properties:

Analysis Method: LFD

Analysis Module: AASHTO LFD

Analysis Module Component:

Properties:

Analysis Method: LRFD

Analysis Module: AASHTO LRFD

Analysis Module Component:

Properties:

Analysis Method: LRFR

Analysis Module: AASHTO LRFR

Analysis Module Component:

Properties:

Analysis Method: Distribution Factors

Analysis Module: Legacy BrR Dist Fact

Analysis Module Component:

Properties:

Default rating method: LRFR

LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:

LFD: 2002 AASHTO Std. Specifications(CF=0.9)

ASD Factors

Inventory Operating

Structural steel

Concrete	
PS Concrete Comp.	
PS Concrete Tens.	
PS Moment Cap.	
Reinforcement	
Bearing Stiffener	
Stirrup	
Timber	NA

Default Materials

Deck concrete:	Class A (3000)
Deck reinforcement:	Grade 40
Beam concrete:	Class P (5000)
Beam reinforcement:	Grade 40
Stirrup reinforcemt:	Grade 40
Prestressing strand:	7/16" (7W-250) SR

Impact

Standard Impact Factor

Type:	Standard - AASHTO
-------	-------------------

LRFD Dynamic Load Allowance

Fatigue and fracture limit states:	15.0 (%)
------------------------------------	----------

All other limit states:	33.0 (%)
-------------------------	----------

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)

Lanes	Shear	Shear at Supports	Moment	Deflection
Loaded				
1 Lane	0.010	0.010	0.010	0.010
Multi-Lane	0.010	0.010	0.010	0.010

LRFD

Distance (ft)	Length (ft)	Type	1 Lane	Multi-Lane
0.00	28.292	Deflectio...	0.010	0.010
0.00	28.292	Moment	0.010	0.010
0.00	28.292	Shear	0.010	0.010

Shrinkage/Time

Deck curing method:	Moist-cured
---------------------	-------------

Deck drying time:	3.000 (Days)
-------------------	--------------

Consider deck differential shrinkage loads:	FALSE
---------------------------------------------	-------

Beam Curing method:	Steam-cured
---------------------	-------------

Curing time:	20.00 (Days)
--------------	--------------

Service life:	75.00 (Years)
---------------	---------------

Analysis time:	54.00 (Years)
----------------	---------------

Composite time:	60.00 (Days)
-----------------	--------------

Continuous time:	45.0 (Days)
------------------	-------------

Beam Details

Span Details

Span	Prestress Shape Use	Concrete Material n	Prestress Properties	Left Projection	Right Projection
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	(in) 6.0000	(in) 8.5000

Continuous Support Details

Support Number	Support Distance on Left, SL (in)	Support Distance on Right, SR (in)
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance (ft)	Length (ft)
PS Conc Stress Lim...	1	0.000	29.50

Slab Interface

Deck interface type:	Monolithic
Interface width:	(in)
Deck cohesion factor:	0.400 (ksi)
Deck friction factor:	1.400

Continuity Diaphragm

Span	Material Bar	Left Support Distance Bar	Bar Count	Bar Size	Right Support Material	Distance
No.						

Prestressing Force Information

Strand Layout

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance (ft)	Debond Distance (in)	Harp Curvature (in)
1	Left Right	1	1	Straight/Debonded			

1	Left	1	2	Straight/Debonded
	Right			
1	Left	1	3	Straight/Debonded
	Right			
1	Left	1	6	Straight/Debonded
	Right			
1	Left	1	7	Straight/Debonded
	Right			
1	Left	1	8	Straight/Debonded
	Right			
1	Left	1	9	Straight/Debonded
	Right			
1	Left	1	10	Straight/Debonded
	Right			
1	Left	1	11	Straight/Debonded
	Right			
1	Left	1	14	Straight/Debonded
	Right			
1	Left	1	15	Straight/Debonded
	Right			
1	Left	1	16	Straight/Debonded
	Right			
1	Left	3	1	Straight/Debonded
	Right			
1	Left	3	16	Straight/Debonded
	Right			

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	6.25	1	1.0000	0.1636
1	7.25...	15.00	1	1.0000	0.1636

1	22.25...	6.25	1	1.0000	0.1636
---	----------	------	---	--------	--------

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Extends into Deck
#4 Bent Shear R...	1	0.21	4	6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	8.0000	FALSE
#4 Bent Shear R...	1	2.88	19	15.0000	FALSE
#4 Bent Shear R...	1	26.63	1	8.0000	FALSE
#4 Bent Shear R...	1	27.29	4	6.0000	FALSE

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Composite Length (ft)
#3 - 2'-7" long	1	0.21	4	6.0000	
#3 - 2'-7" long	1	2.21	1	8.0000	
#3 - 2'-7" long	1	2.88	19	15.0000	
#3 - 2'-7" long	1	26.63	1	8.0000	
#3 - 2'-7" long	1	27.29	4	6.0000	

Member G2

Link with: None

Description:

Existing: 17"x36" INT PSU -

Current: 17"x36" INT PSU -

Number of Spans: 1

Span Number	Span Length (ft)
1	28.291666

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support Number	Horizontal (in)	Vertical (in)	Rotational (Radians)	Load Case Name
1				
2				

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

Elastic

Support Number	X Translation (kip/ft)	Y Translation (kip/ft)	Z Rotation (kip-in/rad)	Override Computed Z Rotation
1				
2				

Member Alternative 17"x36" INT PSU

Description:

Description

Material Type: Prestressed Concrete
Girder Type: PS Precast Box
Member units: US Customary
Girder property input method: Schedule based
Additional Self Load: (kip/ft)
Additional Self Load %: 1.0 (%)

Analysis Module

Analysis Method: ASD
Analysis Module: AASHTO ASD
Analysis Module Component:
Properties:

Analysis Method: LFD
Analysis Module: AASHTO LFD
Analysis Module Component:
Properties:

Analysis Method: LRFD
Analysis Module: AASHTO LRFD
Analysis Module Component:
Properties:

Analysis Method: LRFR
Analysis Module: AASHTO LRFR
Analysis Module Component:
Properties:

Analysis Method: Distribution Factors
Analysis Module: Legacy BrR Dist Fact
Analysis Module Component:
Properties:

Default rating method: LRFR
LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:

LFD: 2002 AASHTO Std. Specifications(CF=0.9)

ASD Factors

Inventory Operating

Structural steel

Concrete

PS Concrete Comp.

PS Concrete Tens.

PS Moment Cap.

Reinforcement

Bearing Stiffener

Stirrup

Timber

NA

Default Materials

Deck concrete: Class A (3000)

Deck reinforcement: Grade 40

Beam concrete: Class P (5000)

Beam reinforcement: Grade 40

Stirrup reinforcemt: Grade 40

Prestressing strand: 7/16" (7W-250) SR

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)

Lanes		Shear at		
Loaded	Shear	Supports	Moment	Deflection
1 Lane	0.167	0.017	0.017	0.017
Multi-Lane	0.167	0.017	0.017	0.017

LRFD

Distance	Length	Type	1 Lane	Multi-Lane
(ft)	(ft)			
0.00	28.292	Deflectio...	0.167	0.200
0.00	28.292	Moment	0.167	0.200
0.00	28.292	Shear	0.167	0.200

Shrinkage/Time

Deck curing method: Moist-cured

Deck drying time: 3.000 *(Days)*
 Consider deck differential shrinkage loads: FALSE
 Beam Curing method: Steam-cured
 Curing time: 20.00 *(Days)*
 Service life: 75.00 *(Years)*
 Analysis time: 54.00 *(Years)*
 Composite time: 60.00 *(Days)*
 Continuous time: 45.0 *(Days)*

Beam Details

Span Details

Span	Prestress Shape Use	Concrete Material n	Prestress Properties	Left Projection <i>(in)</i>	Right Projection <i>(in)</i>
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	6.0000	8.5000

Continuous Support Details

Support Number	Support Distance on Left, SL <i>(in)</i>	Support Distance on Right, SR <i>(in)</i>
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance <i>(ft)</i>	Length <i>(ft)</i>
PS Conc Stress Lim...	1	0.000	29.50

Slab Interface

Deck interface type: Monolithic
 Interface width: *(in)*
 Deck cohesion factor: 0.400 *(ksi)*
 Deck friction factor: 1.400

Continuity Diaphragm

Span	Material	Left Support Distance	Bar	Bar	Right Support Material	Distance
No.	Bar	Bar	Count	Size	Count	Size

Prestressing Force Information

Strand Layout

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance <i>(ft)</i>	Debond Distance <i>(in)</i>	Harp Curvature <i>(in)</i>
1	Left	1	1	Straight/Debonded			
	Right						
1	Left	1	2	Straight/Debonded			
	Right						
1	Left	1	3	Straight/Debonded			
	Right						
1	Left	1	6	Straight/Debonded			
	Right						
1	Left	1	7	Straight/Debonded			
	Right						
1	Left	1	8	Straight/Debonded			
	Right						
1	Left	1	9	Straight/Debonded			
	Right						
1	Left	1	10	Straight/Debonded			
	Right						
1	Left	1	11	Straight/Debonded			
	Right						
1	Left	1	14	Straight/Debonded			
	Right						
1	Left	1	15	Straight/Debonded			
	Right						
1	Left	1	16	Straight/Debonded			
	Right						
1	Left	3	1	Straight/Debonded			
	Right						
1	Left	3	16	Straight/Debonded			
	Right						

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	6.25	1	1.0000	0.1636
1	7.25...	15.00	1	1.0000	0.1636
1	22.25...	6.25	1	1.0000	0.1636

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Extends into Deck
#4 Bent Shear R...	1	0.21	4	6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	8.0000	FALSE
#4 Bent Shear R...	1	2.88	19	15.0000	FALSE
#4 Bent Shear R...	1	26.63	1	8.0000	FALSE
#4 Bent Shear R...	1	27.29	4	6.0000	FALSE

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Composite Length (ft)
#3 - 2'-7" long	1	0.21	4	6.0000	
#3 - 2'-7" long	1	2.21	1	8.0000	
#3 - 2'-7" long	1	2.88	19	15.0000	
#3 - 2'-7" long	1	26.63	1	8.0000	
#3 - 2'-7" long	1	27.29	4	6.0000	

Member G3

Link with: None

Description:

Existing: 17"x36" INT PSU -

Current: 17"x36" INT PSU -

Number of Spans: 1

Span Number	Span Length (ft)
1	28.291666

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support Number	Horizontal (in)	Vertical (in)	Rotational (Radians)	Load Case Name
1				
2				

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

Elastic

Support Number	X Translation (kip/ft)	Y Translation (kip/ft)	Z Rotation (kip-in/rad)	Override Computed Z Rotation
1				
2				

Member Alternative 17"x36" INT PSU

Description:

Description

Material Type: Prestressed Concrete
Girder Type: PS Precast Box
Member units: US Customary
Girder property input method: Schedule based
Additional Self Load: (kip/ft)
Additional Self Load %: 1.0 (%)

Analysis Module

Analysis Method: ASD
Analysis Module: AASHTO ASD
Analysis Module Component:

Properties:

Analysis Method: LFD
Analysis Module: AASHTO LFD
Analysis Module Component:
Properties:

Analysis Method: LRFD
Analysis Module: AASHTO LRFD
Analysis Module Component:
Properties:

Analysis Method: LRFR
Analysis Module: AASHTO LRFR
Analysis Module Component:
Properties:

Analysis Method: Distribution Factors
Analysis Module: Legacy BrR Dist Fact
Analysis Module Component:
Properties:

Default rating method: LRFR
LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:

LFD: 2002 AASHTO Std. Specifications(CF=0.9)

ASD Factors

Inventory Operating

Structural steel

Concrete

PS Concrete Comp.

PS Concrete Tens.

PS Moment Cap.

Reinforcement

Bearing Stiffener

Stirrup

Timber NA

Default Materials

Deck concrete: Class A (3000)

Deck reinforcement: Grade 40

Beam concrete: Class P (5000)

Beam reinforcement: Grade 40

Stirrup reinforcement: Grade 40

Prestressing strand: 7/16" (7W-250) SR

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)

Lanes	Shear	Shear at Supports	Moment	Deflection
Loaded				
1 Lane	1.000	1.000	1.000	1.000
Multi-Lane	1.000	1.000	1.000	1.000

LRFD

Distance (ft)	Length (ft)	Type	1 Lane	Multi-Lane
0.00	28.292	Moment	0.500	0.600
0.00	28.292	Shear	0.500	0.600
0.00	28.292	Deflectio...	0.500	0.600

Shrinkage/Time

Deck curing method: Moist-cured
Deck drying time: 3.000 (Days)
Consider deck differential shrinkage loads: FALSE
Beam Curing method: Steam-cured
Curing time: 20.00 (Days)
Service life: 75.00 (Years)
Analysis time: 54.00 (Years)
Composite time: 60.00 (Days)
Continuous time: 45.0 (Days)

Beam Details

Span Details

Span	Prestress Shape Use	Concrete Material n	Prestress Properties	Left Projection (in)	Right Projection (in)
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	6.0000	8.5000

Continuous Support Details

Support Number	Support Distance on Left, SL (in)	Support Distance on Right, SR (in)
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance (ft)	Length (ft)
PS Conc Stress Lim...	0	-0.750	29.50

Slab Interface

Deck interface type: Monolithic
Interface width: (in)
Deck cohesion factor: 0.400 (ksi)
Deck friction factor: 1.400

Continuity Diaphragm

Left Support

Right Support

Span No.	Material Bar	Distance Bar	Bar Count	Bar Size	Material	Distance
					Count	Size

Prestressing Force Information

Strand Layout

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance (ft)	Debond Distance (in)	Harp Curvature (in)
1	Left	1	1	Straight/Debonded			
	Right						
1	Left	1	2	Straight/Debonded			
	Right						
1	Left	1	3	Straight/Debonded			
	Right						
1	Left	1	6	Straight/Debonded			
	Right						
1	Left	1	7	Straight/Debonded			
	Right						
1	Left	1	8	Straight/Debonded			
	Right						
1	Left	1	9	Straight/Debonded			
	Right						
1	Left	1	10	Straight/Debonded			
	Right						
1	Left	1	11	Straight/Debonded			
	Right						
1	Left	1	14	Straight/Debonded			
	Right						
1	Left	1	15	Straight/Debonded			
	Right						
1	Left	1	16	Straight/Debonded			
	Right						
1		3	1	Straight/Debonded			

1	Left	3	16	Straight/Debonded
	Right			
	Left			
	Right			

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	6.25	1	1.0000	0.1636
1	7.25...	15.00	1	1.0000	0.1636
1	22.25...	6.25	1	1.0000	0.1636

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Extends into Deck
#4 Bent Shear R...	1	0.21	4	6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	8.0000	FALSE
#4 Bent Shear R...	1	2.88	19	15.0000	FALSE
#4 Bent Shear R...	1	26.63	1	8.0000	FALSE
#4 Bent Shear R...	1	27.29	4	6.0000	FALSE

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Composite Length (ft)
#3 - 2'-7" long	1	0.21	4	6.0000	
#3 - 2'-7" long	1	2.21	1	8.0000	
#3 - 2'-7" long	1	2.88	19	15.0000	
#3 - 2'-7" long	1	26.63	1	8.0000	
#3 - 2'-7" long	1	27.29	4	6.0000	

Member G4

Link with: G3

Description:

Existing:

Current:

Number of Spans: 1

Span Span Length

Number *(ft)*
1 28.291666

Support Frame Connection
1
2

Pedestrian load: *(lb/ft)*

Member G5

Link with: G3

Description:

Existing:

Current:

Number of Spans: 1

Span Span Length
Number *(ft)*
1 28.291666

Support Frame Connection
1
2

Pedestrian load: *(lb/ft)*

Member G6

Link with: G3

Description:

Existing:

Current:

Number of Spans: 1

Span Span Length
Number *(ft)*
1 28.291666

Support Frame Connection
1
2

Pedestrian load: *(lb/ft)*

Member G7

Link with: G3

Description:

Existing:
Current:
Number of Spans: 1

Span Number	Span Length (ft)
1	28.291666

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member G8

Link with: G3
Description:

Existing:
Current:
Number of Spans: 1

Span Number	Span Length (ft)
1	28.291666

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member G9

Link with: G3
Description:

Existing:
Current:
Number of Spans: 1

Span Number	Span Length (ft)
1	28.291666

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member G10

Link with: None

Description:

Existing: 17"x36" INT PSU - (w/ Post Tensioning) -

Current: 17"x36" INT PSU - (w/ Post Tensioning) -

Number of Spans: 1

Span Number	Span Length (ft)
1	28.291666

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support Number	Horizontal (in)	Vertical (in)	Rotational (Radians)	Load Case Name
1				
2				

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

Elastic

Support Number	X Translation (kip/ft)	Y Translation (kip/ft)	Z Rotation (kip-in/rad)	Override Computed Z Rotation
1				
2				

Member Alternative 17"x36" INT PSU - (w/ Post Tensioning)

Description:

Description

Material Type: Prestressed Concrete

Girder Type: PS Precast Box

Member units: US Customary

Girder property input method: Schedule based

Additional Self Load: (kip/ft)

Additional Self Load %: 1.0 (%)

Analysis Module

Analysis Method: ASD
Analysis Module: AASHTO ASD
Analysis Module Component:
Properties:

Analysis Method: LFD
Analysis Module: AASHTO LFD
Analysis Module Component:
Properties:

Analysis Method: LRFD
Analysis Module: AASHTO LRFD
Analysis Module Component:
Properties:

Analysis Method: LRFR
Analysis Module: AASHTO LRFR
Analysis Module Component:
Properties:

Analysis Method: Distribution Factors
Analysis Module: Legacy BrR Dist Fact
Analysis Module Component:
Properties:

Default rating method: LRFR
LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:

LFD: 2002 AASHTO Std. Specifications(CF=0.9)

ASD Factors

Inventory Operating

Structural steel

Concrete

PS Concrete Comp.

PS Concrete Tens.

PS Moment Cap.

Reinforcement

Bearing Stiffener

Stirrup

Timber

NA

Default Materials

Deck concrete: Class A (3000)

Deck reinforcement: Grade 40

Beam concrete: Class P (5000)

Beam reinforcement: Grade 40

Stirrup reinforcemt: Grade 40
 Prestressing strand: 7/16" (7W-250) SR

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)

Lanes	Shear	Shear at Supports	Moment	Deflection
Loaded				
1 Lane	0.533	0.000	0.533	0.182
Multi-Lane	0.533	0.000	0.533	0.364

LRFD

Distance	Length	Type	1 Lane	Multi-Lane
(ft)	(ft)			
0.00	28.292	Moment	0.296	0.273
0.00	28.292	Shear	0.296	0.273
0.00	28.292	Deflectio...	0.109	0.182

Shrinkage/Time

Deck curing method: Moist-cured

Deck drying time: 3.000 (Days)

Consider deck differential shrinkage loads: FALSE

Beam Curing method: Steam-cured

Curing time: 20.00 (Days)

Service life: 75.00 (Years)

Analysis time: 54.00 (Years)

Composite time: 60.00 (Days)

Continuous time: 45.0 (Days)

Beam Details

Span Details

Span	Prestress Shape Use	Concrete Material n	Prestress Properties	Left Projection	Right Projection
	Projection	Creep		(in) (in)	
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	6.0000	8.5000

Continuous Support Details

Support Support Distance Support Distance

Number	on Left, SL (in)	on Right, SR (in)
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance (ft)	Length (ft)
PS Conc Stress Lim...	0	-0.750	29.50

Slab Interface

Deck interface type:	Monolithic
Interface width:	(in)
Deck cohesion factor:	0.400 (ksi)
Deck friction factor:	1.400

Continuity Diaphragm

Span	Material	Left Support Distance	Bar	Bar	Right Support Material	Distance
No.	Bar	Bar	Count	Size	Count	Size

Prestressing Force Information

Strand Layout

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance (ft)	Debond Distance (in)	Harp Curvature (in)
1	Left Right	1	1	Straight/Debonded			
1	Left Right	1	2	Straight/Debonded			
1	Left Right	1	3	Straight/Debonded			
1	Left Right	1	6	Straight/Debonded			
1	Left Right	1	7	Straight/Debonded			
1	Left Right	1	8	Straight/Debonded			

1	Left	1	9	Straight/Debonded
	Right			
1	Left	1	10	Straight/Debonded
	Right			
1	Left	1	11	Straight/Debonded
	Right			
1	Left	1	14	Straight/Debonded
	Right			
1	Left	1	15	Straight/Debonded
	Right			
1	Left	1	16	Straight/Debonded
	Right			
1	Left	3	1	Straight/Debonded
	Right			
1	Left	3	16	Straight/Debonded
	Right			

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	6.25	1	1.0000	0.1636
1	7.25...	15.00	1	1.0000	0.1636
1	22.25...	6.25	1	1.0000	0.1636

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Extends into Deck
#4 Bent Shear R...	1	0.21	4	6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	8.0000	FALSE
#4 Bent Shear R...	1	2.88	19	15.0000	FALSE
#4 Bent Shear R...	1	26.63	1	8.0000	FALSE
#4 Bent Shear R...	1	27.29	4	6.0000	FALSE

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Composite Length (ft)
#3 - 2'-7" long	1	0.21	4	6.0000	
#3 - 2'-7" long	1	2.21	1	8.0000	
#3 - 2'-7" long	1	2.88	19	15.0000	
#3 - 2'-7" long	1	26.63	1	8.0000	
#3 - 2'-7" long	1	27.29	4	6.0000	

Member G11

Link with: None

Description:

Existing: 17"x36" EXT PSU (w/ Post Tensioning) -

Current: 17"x36" EXT PSU (w/ Post Tensioning) -

Number of Spans: 1

Span Number	Span Length (ft)
1	28.291666

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support Number	Horizontal (in)	Vertical (in)	Rotational (Radians)	Load Case Name
1				
2				

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

Elastic

Support Number	X Translation (kip/ft)	Y Translation (kip/ft)	Z Rotation (kip-in/rad)	Override Computed Z Rotation
1				
2				

Member Alternative 17"x36" EXT PSU (w/ Post Tensioning)

Description:

Description

Material Type: Prestressed Concrete
Girder Type: PS Precast Box
Member units: US Customary
Girder property input method: Schedule based
Additional Self Load: (kip/ft)
Additional Self Load %: 1.0 (%)

Analysis Module

Analysis Method: ASD
Analysis Module: AASHTO ASD
Analysis Module Component:
Properties:

Analysis Method: LFD
Analysis Module: AASHTO LFD
Analysis Module Component:
Properties:

Analysis Method: LRFD
Analysis Module: AASHTO LRFD
Analysis Module Component:
Properties:

Analysis Method: LRFR
Analysis Module: AASHTO LRFR
Analysis Module Component:
Properties:

Analysis Method: Distribution Factors
Analysis Module: Legacy BrR Dist Fact
Analysis Module Component:
Properties:

Default rating method: LRFR
LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:

LFD: 2002 AASHTO Std. Specifications(CF=0.9)

ASD Factors

Inventory Operating

Structural steel

Concrete

PS Concrete Comp.

PS Concrete Tens.

PS Moment Cap.

Reinforcement

Bearing Stiffener

Stirrup

Timber

NA

Default Materials

Deck concrete: Class A (3000)
Deck reinforcement: Grade 40
Beam concrete: Class P (5000)
Beam reinforcement: Grade 40
Stirrup reinforcement: Grade 40
Prestressing strand: 7/16" (7W-250) SR

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)

Lanes	Shear	Shear at Supports	Moment	Deflection
Loaded				
1 Lane	0.100	0.100	0.100	0.100
Multi-Lane	0.100	0.100	0.100	0.100

LRFD

Distance	Length	Type	1 Lane	Multi-Lane
(ft)	(ft)			
0.00	28.292	Deflectio...	0.100	0.100
0.00	28.292	Moment	0.100	0.100
0.00	28.292	Shear	0.100	0.100

Shrinkage/Time

Deck curing method: Moist-cured

Deck drying time: 3.000 (Days)

Consider deck differential shrinkage loads: FALSE

Beam Curing method: Steam-cured

Curing time: 20.00 (Days)

Service life: 75.00 (Years)

Analysis time: 54.00 (Years)

Composite time: 60.00 (Days)

Continuous time: 45.0 (Days)

Beam Details

Span Details

Span	Prestress Shape	Concrete Material	Prestress Properties	Left	Right
	Use	n			

	Projection	Creep		Projection
				(in) (in)
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	6.0000 8.5000

Continuous Support Details

Support Number	Support Distance on Left, SL (in)	Support Distance on Right, SR (in)
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance (ft)	Length (ft)
PS Conc Stress Lim...	1	0.000	29.50

Slab Interface

Deck interface type:	Monolithic
Interface width:	(in)
Deck cohesion factor:	0.400 (ksi)
Deck friction factor:	1.400

Continuity Diaphragm

Span	Material	Left Support	Bar	Bar	Right Support	
Bar	Bar	Distance	Bar	Bar	Material	Distance
No.		Bar	Count	Size	Count	Size

Prestressing Force Information

Strand Layout

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance (ft)	Debond Distance (in)	Harp Curvature (in)
1	Left	1	1	Straight/Debonded			
	Right						
1	Left	1	2	Straight/Debonded			
	Right						
1	Left	1	3	Straight/Debonded			
	Right						
1	Left	1	6	Straight/Debonded			
	Right						

1	Left Right	1	7	Straight/Debonded
1	Left Right	1	8	Straight/Debonded
1	Left Right	1	9	Straight/Debonded
1	Left Right	1	10	Straight/Debonded
1	Left Right	1	11	Straight/Debonded
1	Left Right	1	14	Straight/Debonded
1	Left Right	1	15	Straight/Debonded
1	Left Right	1	16	Straight/Debonded
1	Left Right	3	1	Straight/Debonded
1	Left Right	3	16	Straight/Debonded

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	6.25	1	1.0000	0.1636
1	7.25...	15.00	1	1.0000	0.1636
1	22.25...	6.25	1	1.0000	0.1636

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Extends into Deck
------------------------	------------	---------------------------	------------------	-----------------	----------------------

#4 Bent Shear R...	1	0.21	4	6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	8.0000	FALSE
#4 Bent Shear R...	1	2.88	19	15.0000	FALSE
#4 Bent Shear R...	1	26.62	1	8.0000	FALSE
#4 Bent Shear R...	1	27.29	4	6.0000	FALSE

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Composite Length (ft)
#3 - 2'-7" long	1	0.21	4	6.0000	
#3 - 2'-7" long	1	2.21	1	8.0000	
#3 - 2'-7" long	1	2.88	19	15.0000	
#3 - 2'-7" long	1	26.62	1	8.0000	
#3 - 2'-7" long	1	27.29	4	6.0000	

Superstructure Definition INT Span 2 - PS Conc PSU

Definition

Units: US Customary

Number of spans: 1

Number of girders: 11

Length

Span (ft)

1 38.5000

Frame Structure Simplified Definition:

Support Frame Connection

1

2

Girder Spacing Display Type: Perpendicular

Average Humidity: 70.000 (%)

Analysis

Default Library Factors

Factor Override

Analysis Module

Analysis Method: ASD

Analysis Module:

Analysis Module Component:

Properties:

Analysis Method: LFD

Analysis Module:

Analysis Module Component:

Properties:

Analysis Method: LRFD

Analysis Module:

Analysis Module Component:

Properties:

Analysis Method: LRFR
Analysis Module:
Analysis Module Component:
Properties:

Analysis Method: Distribution Factors
Analysis Module:
Analysis Module Component:
Properties:

Default rating method: LFD

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Structure Framing Plan Details

Layout

Skew
Support (Degrees)
1 0.0000
2 0.0000
Girder Spacing Orientation: Perpendicular

Girder	Girder Spacing	
Bay	Start	End
	(ft)	(ft)
1	3.0000	3.0000
2	3.0000	3.0000
3	3.0000	3.0000
4	3.0000	3.0000
5	3.0000	3.0000
6	3.0000	3.0000
7	3.0000	3.0000
8	3.0000	3.0000
9	3.0000	3.0000
10	3.0000	3.0000

Diaphragms

Girder Bay 1
Girder Bay 2
Girder Bay 3
Girder Bay 4
Girder Bay 5
Girder Bay 6
Girder Bay 7

Girder Bay 8
 Girder Bay 9
 Girder Bay 10

Structure Typical Section

Deck

Left start width: 18.00 (ft)
 Left end width: 18.00 (ft)
 Right start width: 15.00 (ft)
 Right end width: 15.00 (ft)
 Left start overhang: 1.50 (ft)
 Left end overhang: 1.50 (ft)

Deck (Cont'd)

Deck concrete:
 Total deck thickness: (in)
 Deck crack control parameter: (kip/in)
 Sustained modular ratio factor: 3.000

Railing

Name	Load Case	Measure To	Measured From	Distance At Start	Distance At End	Front Face Orientation
Conc Guar...	DC1 - R...		Left Ed...	0.00	0.00	Right
Conc Guar...	DC1 - R...		Right E...	0.00	0.00	Left

Sidewalk

Width	Thickness At End	Material	Load Case	Measure to	Measured From	At Start
60.0000	11.4375	Class A...	DC1 - C...		Left Ed...	0.00 ...
24.0000	10.5630	Class A...	DC1 - C...		Right E...	0.00 ...

Lane Position

Offset Left Start: -13.00 (ft)
 Offset Left End: -13.00 (ft)
 Offset Right Start: 0.00 (ft)
 Offset Right End: 0.00 (ft)
 Offset Left Start: 13.00 (ft)
 Offset Left End: 13.00 (ft)
 Offset Right Start: 0.00 (ft)
 Offset Right End: 0.00 (ft)

Wearing Surface

Wearing surface material: Asphalt
 Description: Asphalt Wearing Surface
 Wearing surface thickness: 1.1670 (in)
 Wearing surface density: 145.000 (pcf)
 Load case: DW - A.W.S.

Load Case Description

Load Case Name	Description	Stage	Type (Days)	Time
DC1 - Railing	DC acting on non-comp...	Non-composite (Sta...		D,DC
DC1 - Curb	DC acting on non-comp...	Non-composite (Sta...		D,DC
DW - A.W.S.	DW acting on long-ter...	Composite (long te...		D,DW

Superstructure Loads

DL Distribution

Stage 1 Dead Load Distribution: Tributary Area

Stage 2 Dead Load Distribution: Uniformly to All Girders

Stiffener Definitions

Stress Limits

Name:

PS Conc Stress Limits

Description:

Concrete material: Class P (5000)

Initial allowable tension (LFD): 0.190 (ksi)

Initial allowable compression (LFD): 2.400 (ksi)

Final allowable slab compression (LFD): (ksi)

Final allowable tension (LFD): 0.425 (ksi)

Final allowable DL compression (LFD): 2.000 (ksi)

Final allowable compression (LFD): 3.000 (ksi)

Final allowable compression (LL + 1/2(Pe+DL)) (LFD): 2.000 (ksi)

Initial allowable tension (LRFD): 0.190 (ksi)

Initial allowable compression (LRFD): 2.600 (ksi)

Final allowable slab compression (LRFD): (ksi)

Final allowable tension (LRFD): 0.425 (ksi)

Final allowable DL compression (LRFD): 2.250 (ksi)

Final allowable compression (LRFD): 3.000 (ksi)

Final allowable compression (LL + 1/2(Pe+DL)) (LRFD): 2.000 (ksi)

Prestress Properties

Name:

PS Strands Properties

General Pretress Data

Prestressing Strand: 7/16" (7W-250) SR

Loss Method: AASHTO Approximate

Jacking stress ratio: 0.700

Transfer stress ratio:

Transfer time: 24.0 (Hours)

AASHTO - Dead load percent: 0.0 (%)

Loss Data - PCI

PCI - Maturity coefficient:

PCI - Ultimate creep loss: (ksi)

PCI - Ultimate shrinkage loss: (ksi)

PCI - Additional time 1: (Days)

PCI - Additional time 2: (Days)

PCI - Additional time 3: (Days)

PCI - Additional time 4: (Days)

PCI - Additional time 5: (Days)

PCI - Additional time 6: (Days)

PCI - Additional time 7: (Days)

PCI - Additional time 8: (Days)

PCI - Additional time 9: (Days)

PCI - Additional time 10: (Days)
Loss Data - Lump-sum
 Lump-sum - Composite loss: (ksi)
 Lump-sum - Continuous loss: (ksi)
 Lump-sum - Final loss: (ksi)

Shear Reinforcement Definitions - Vertical

Name: **#4 Bent Shear Reinf.**
 Vertical Reinforcement: Grade 40
 Vertical Rebar: 4
 Number of legs (Vertical): 3.00
 Inclination angle alpha (Vertical): 90.0 (Degrees)

Shear Reinforcement Definitions - Horizontal

Name: **#3 - 2'-7" long**
 Reinforcement (Horz. 1): Grade 40
 Rebar (Horz. 1): 3
 Number of legs (Horz. 1): 1.00
 Inclination angle alpha (Horz. 1): 90.0 (Degrees)
 Reinforcement (Horz. 2):
 Rebar (Horz. 2):
 Number of legs (Horz. 2):
 Inclination angle alpha (Horz. 2): 90.0 (Degrees)

Member G1

Link with: None

Description:

Existing: 17"x36" EXT PSU -
 Current: 17"x36" EXT PSU -
 Number of Spans: 1

Span	Span Length
Number	(ft)
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support	Horizontal	Vertical	Rotational	Load Case Name
Number	(in)	(in)	(Radians)	
1				
2				

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

Elastic

Support Number	X Translation (kip/ft)	Y Translation (kip/ft)	Z Rotation (kip-in/rad)	Override Computed Z Rotation
1				
2				

Member Alternative 17"x36" EXT PSU

Description:

Description

Material Type: Prestressed Concrete
Girder Type: PS Precast Box
Member units: US Customary
Girder property input method: Schedule based
Additional Self Load: (kip/ft)
Additional Self Load %: 1.0 (%)

Analysis Module

Analysis Method: ASD
Analysis Module: AASHTO ASD
Analysis Module Component:
Properties:

Analysis Method: LFD
Analysis Module: AASHTO LFD
Analysis Module Component:
Properties:

Analysis Method: LRFD
Analysis Module: AASHTO LRFD
Analysis Module Component:
Properties:

Analysis Method: LRFR
Analysis Module: AASHTO LRFR
Analysis Module Component:
Properties:

Analysis Method: Distribution Factors
Analysis Module: Legacy BrR Dist Fact
Analysis Module Component:
Properties:

Default rating method: LRFR

LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:

LFD:

ASD Factors

	Inventory	Operating
Structural steel		
Concrete		
PS Concrete Comp.		
PS Concrete Tens.		
PS Moment Cap.		
Reinforcement		
Bearing Stiffener		
Stirrup		
Timber	NA	

Default Materials

Deck concrete:	Class A (3000)
Deck reinforcement:	Grade 40
Beam concrete:	Class P (5000)
Beam reinforcement:	Grade 40
Stirrup reinforcement:	Grade 40
Prestressing strand:	7/16" (7W-250) SR

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)				
Lanes		Shear at		
Loaded	Shear	Supports	Moment	Deflection
1 Lane	0.100	0.100	0.100	0.100
Multi-Lane	0.100	0.100	0.100	0.100

LRFD

Distance	Length	Type	1 Lane	Multi-Lane
(ft)	(ft)			
0.00	38.500	Deflectio...	0.100	0.100
0.00	38.500	Moment	0.100	0.100
0.00	38.500	Shear	0.100	0.100

Shrinkage/Time

Deck curing method: Moist-cured
 Deck drying time: 3.000 *(Days)*
 Consider deck differential shrinkage loads: FALSE
 Beam Curing method: Steam-cured
 Curing time: 20.00 *(Days)*
 Service life: 75.00 *(Years)*
 Analysis time: 54.00 *(Years)*
 Composite time: 60.00 *(Days)*
 Continuous time: 45.0 *(Days)*

Beam Details

Span Details

Span	Prestress Shape Use	Concrete Material	Prestress Properties	Left	Right
	Projection	Creep		Projection	
				<i>(in)</i> <i>(in)</i>	
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	8.5000	8.5000

Continuous Support Details

Support Number	Support Distance on Left, SL <i>(in)</i>	Support Distance on Right, SR <i>(in)</i>
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance <i>(ft)</i>	Length <i>(ft)</i>
PS Conc Stress Lim...	1	0.000	39.92

Slab Interface

Deck interface type: Monolithic
 Interface width: *(in)*
 Deck cohesion factor: 0.400 *(ksi)*
 Deck friction factor: 1.400

Continuity Diaphragm

Span	Material	Left Support Distance	Bar	Bar	Right Support Material	Distance
No.	Bar	Bar	Count	Size	Count	Size

Prestressing Force Information

Strand Layout

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance (ft)	Debond Distance (in)	Harp Curvature (in)
1	Left	1	1	Straight/Debonded			
	Right						
1	Left	1	2	Straight/Debonded			
	Right						
1	Left	1	3	Straight/Debonded			
	Right						
1	Left	1	4	Straight/Debonded			
	Right						
1	Left	1	5	Straight/Debonded			
	Right						
1	Left	1	6	Straight/Debonded			
	Right						
1	Left	1	7	Straight/Debonded			
	Right						
1	Left	1	8	Straight/Debonded			
	Right						
1	Left	1	9	Straight/Debonded			
	Right						
1	Left	1	10	Straight/Debonded			
	Right						
1	Left	1	11	Straight/Debonded			
	Right						
1	Left	1	12	Straight/Debonded			
	Right						
1	Left	1	13	Straight/Debonded			
	Right						
1	Left	1	14	Straight/Debonded			
	Right						
1	Left	1	15	Straight/Debonded			

1	Right	1	16	Straight/Debonded
1	Left Right	2	1	Straight/Debonded
1	Left Right	2	2	Straight/Debonded
1	Left Right	2	3	Straight/Debonded
1	Left Right	2	4	Straight/Debonded
1	Left Right	2	5	Straight/Debonded
1	Left Right	2	6	Straight/Debonded
1	Left Right	3	1	Straight/Debonded
1	Left Right	3	7	Straight/Debonded
1	Left Right	3	10	Straight/Debonded
1	Left Right	3	16	Straight/Debonded

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	8.96	1	1.0000	0.1636
1	9.96...	20.00	1	1.0000	0.1636
1	29.96...	8.96	1	1.0000	0.1636

Shear Reinforcement Ranges - Vertical

Shear	Span	Start	Number	Spacing	Extends into
-------	------	-------	--------	---------	--------------

Reinforcement	No	Distance (ft)	Spaces	(in)	Deck
#4 Bent Shear R...	1	0.21	4	6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	10.5000	FALSE
#4 Bent Shear R...	1	3.08	27	15.0000	FALSE
#4 Bent Shear R...	1	36.83	1	10.5000	FALSE
#4 Bent Shear R...	1	37.71	4	6.0000	FALSE

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Composite Length (ft)
#3 - 2'-7" long	1	0.21	4	6.0000	
#3 - 2'-7" long	1	2.21	1	10.5000	
#3 - 2'-7" long	1	3.08	27	15.0000	
#3 - 2'-7" long	1	36.83	1	10.5000	
#3 - 2'-7" long	1	37.71	4	6.0000	

Member G2

Link with: None

Description:

Existing: 17"x36" INT PSU -

Current: 17"x36" INT PSU -

Number of Spans: 1

Span Number	Span Length (ft)
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support Number	Horizontal (in)	Vertical (in)	Rotational (Radians)	Load Case Name
1				
2				

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free

2	Roller	Free	Fixed	Free
<u>Elastic</u>				
Support	X Translation	Y Translation	Z Rotation	Override Computed
Number	(kip/ft)	(kip/ft)	(kip-in/rad)	Z Rotation
1				
2				

Member Alternative 17"x36" INT PSU

Description:

Description

Material Type: Prestressed Concrete

Girder Type: PS Precast Box

Member units: US Customary

Girder property input method: Schedule based

Additional Self Load: (kip/ft)

Additional Self Load %: 1.0 (%)

Analysis Module

Analysis Method: ASD

Analysis Module: AASHTO ASD

Analysis Module Component:

Properties:

Analysis Method: LFD

Analysis Module: AASHTO LFD

Analysis Module Component:

Properties:

Analysis Method: LRFD

Analysis Module: AASHTO LRFD

Analysis Module Component:

Properties:

Analysis Method: LRFR

Analysis Module: AASHTO LRFR

Analysis Module Component:

Properties:

Analysis Method: Distribution Factors

Analysis Module: Legacy BrR Dist Fact

Analysis Module Component:

Properties:

Default rating method: LRFR

LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:

LFD:

ASD Factors

	Inventory	Operating
Structural steel		
Concrete		
PS Concrete Comp.		
PS Concrete Tens.		
PS Moment Cap.		
Reinforcement		
Bearing Stiffener		
Stirrup		
Timber	NA	

Default Materials

Deck concrete:	Class A (3000)
Deck reinforcement:	Grade 40
Beam concrete:	Class P (5000)
Beam reinforcement:	Grade 40
Stirrup reinforcement:	Grade 40
Prestressing strand:	7/16" (7W-250) SR

Impact

Standard Impact Factor

Type:	Standard - AASHTO
-------	-------------------

LRFD Dynamic Load Allowance

Fatigue and fracture limit states:	15.0 (%)
All other limit states:	33.0 (%)

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)				
Lanes		Shear at		
Loaded	Shear	Supports	Moment	Deflection
1 Lane	0.167	0.167	0.167	0.167
Multi-Lane	0.167	0.167	0.167	0.167

LRFD

Distance	Length	Type	1 Lane	Multi-Lane
(ft)	(ft)			
0.00	38.500	Deflectio...	0.167	0.200
0.00	38.500	Moment	0.167	0.200
0.00	38.500	Shear	0.167	0.200

Shrinkage/Time

Deck curing method:	Moist-cured
Deck drying time: 3.000	(Days)
Consider deck differential shrinkage loads:	FALSE
Beam Curing method:	Steam-cured
Curing time: 20.00	(Days)
Service life: 75.00	(Years)

Analysis time: 54.00 *(Years)*
Composite time: 60.00 *(Days)*
Continuous time: 45.0 *(Days)*

Beam Details

Span Details

Span	Prestress Shape Use	Concrete Material n	Prestress Properties	Left Projection	Right
	Projection	Creep		<i>(in)</i> <i>(in)</i>	
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	8.5000	8.5000

Continuous Support Details

Support Number	Support Distance on Left, SL <i>(in)</i>	Support Distance on Right, SR <i>(in)</i>
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance <i>(ft)</i>	Length <i>(ft)</i>
PS Conc Stress Lim...	1	0.000	39.92

Slab Interface

Deck interface type:	Monolithic
Interface width:	<i>(in)</i>
Deck cohesion factor:	0.400 <i>(ksi)</i>
Deck friction factor:	1.400

Continuity Diaphragm

Span	Material Bar	Left Support Distance Bar	Bar Count	Bar Size	Right Support Material	Distance Count	Size
No.							

Prestressing Force Information

Strand Layout

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance <i>(ft)</i>	Debond Distance <i>(in)</i>	Harp Curvature <i>(in)</i>
------	------	---------	----------	--------------	---------------------------	-----------------------------	----------------------------

1		1	1	Straight/Debonded
	Left			
	Right			
1		1	2	Straight/Debonded
	Left			
	Right			
1		1	3	Straight/Debonded
	Left			
	Right			
1		1	4	Straight/Debonded
	Left			
	Right			
1		1	5	Straight/Debonded
	Left			
	Right			
1		1	6	Straight/Debonded
	Left			
	Right			
1		1	7	Straight/Debonded
	Left			
	Right			
1		1	8	Straight/Debonded
	Left			
	Right			
1		1	9	Straight/Debonded
	Left			
	Right			
1		1	10	Straight/Debonded
	Left			
	Right			
1		1	11	Straight/Debonded
	Left			
	Right			
1		1	12	Straight/Debonded
	Left			
	Right			
1		1	13	Straight/Debonded
	Left			
	Right			
1		1	14	Straight/Debonded
	Left			
	Right			
1		1	15	Straight/Debonded
	Left			
	Right			
1		1	16	Straight/Debonded
	Left			
	Right			
1		2	1	Straight/Debonded
	Left			

1	Right	2	2	Straight/Debonded
1	Left Right	2	3	Straight/Debonded
1	Left Right	2	4	Straight/Debonded
1	Left Right	2	5	Straight/Debonded
1	Left Right	2	6	Straight/Debonded
1	Left Right	3	1	Straight/Debonded
1	Left Right	3	7	Straight/Debonded
1	Left Right	3	10	Straight/Debonded
1	Left Right	3	16	Straight/Debonded

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	8.96	1	1.0000	0.1636
1	9.95...	20.00	1	1.0000	0.1636
1	29.95...	8.96	1	1.0000	0.1636

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Extends into Deck
#4 Bent Shear R...	1	0.21	4	6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	10.5000	FALSE
#4 Bent Shear R...	1	3.08	27	15.0000	FALSE
#4 Bent Shear R...	1	36.83	1	10.5000	FALSE

#4 Bent Shear R...	1	37.71	4	6.0000	FALSE
--------------------	---	-------	---	--------	-------

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Composite Length (ft)
#3 - 2'-7" long	1	0.21	4	6.0000	
#3 - 2'-7" long	1	2.21	1	10.5000	
#3 - 2'-7" long	1	3.08	27	15.0000	
#3 - 2'-7" long	1	36.83	1	10.5000	
#3 - 2'-7" long	1	37.71	4	6.0000	

Member G3

Link with: None

Description:

Existing: 17"x36" INT PSU -

Current: 17"x36" INT PSU -

Number of Spans: 1

Span Number	Span Length (ft)
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support Number	Horizontal (in)	Vertical (in)	Rotational (Radians)	Load Case Name
1				
2				

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

Elastic

Support Number	X Translation (kip/ft)	Y Translation (kip/ft)	Z Rotation (kip-in/rad)	Override Computed Z Rotation
1				

Member Alternative 17"x36" INT PSU

Description:

Description

Material Type: Prestressed Concrete
 Girder Type: PS Precast Box
 Member units: US Customary
 Girder property input method: Schedule based
 Additional Self Load: (kip/ft)
 Additional Self Load %: 1.0 (%)

Analysis Module

Analysis Method: ASD
 Analysis Module: AASHTO ASD
 Analysis Module Component:
 Properties:

Analysis Method: LFD
 Analysis Module: AASHTO LFD
 Analysis Module Component:
 Properties:

Analysis Method: LRFD
 Analysis Module: AASHTO LRFD
 Analysis Module Component:
 Properties:

Analysis Method: LRFR
 Analysis Module: AASHTO LRFR
 Analysis Module Component:
 Properties:

Analysis Method: Distribution Factors
 Analysis Module: Legacy BrR Dist Fact
 Analysis Module Component:
 Properties:

Default rating method: LRFR
 LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:

LFD: 2002 AASHTO Std. Specifications(CF=0.9)

ASD Factors

Inventory Operating

Structural steel

Concrete

PS Concrete Comp.

PS Concrete Tens.

PS Moment Cap.
Reinforcement
Bearing Stiffener
Stirrup
Timber NA

Default Materials

Deck concrete: Class A (3000)
Deck reinforcement: Grade 40
Beam concrete: Class P (5000)
Beam reinforcement: Grade 40
Stirrup reinforcement: Grade 40
Prestressing strand: 7/16" (7W-250) SR

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)

Lanes	Shear	Shear at Supports	Moment	Deflection
Loaded				
1 Lane	1.000	1.000	1.000	1.000
Multi-Lane	1.000	1.000	1.000	1.000

LRFD

Distance (ft)	Length (ft)	Type	1 Lane	Multi-Lane
0.00	38.500	Deflectio...	0.500	0.600
0.00	38.500	Moment	0.500	0.600
0.00	38.500	Shear	0.500	0.600

Shrinkage/Time

Deck curing method: Moist-cured

Deck drying time: 3.000 (Days)

Consider deck differential shrinkage loads: FALSE

Beam Curing method: Steam-cured

Curing time: 20.00 (Days)

Service life: 75.00 (Years)

Analysis time: 54.00 (Years)

Composite time: 60.00 (Days)

Continuous time: 45.0 (Days)

Beam Details

Span Details

Span	Prestress Shape Use	Concrete Material	Prestress Properties	Left Projection	Right
	Projection	Creep		(in) (in)	
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	8.5000	8.5000

Continuous Support Details

Support Number	Support Distance on Left, SL (in)	Support Distance on Right, SR (in)
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance (ft)	Length (ft)
PS Conc Stress Lim...	1	0.000	39.92

Slab Interface

Deck interface type:	Monolithic
Interface width:	(in)
Deck cohesion factor:	0.400 (ksi)
Deck friction factor:	1.400

Continuity Diaphragm

Span	Material	Left Support Distance	Bar	Bar	Right Support	Distance
No.	Bar	Bar	Count	Size	Count	Size

Prestressing Force Information**Strand Layout**

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance (ft)	Debond Distance (in)	Harp Curvature (in)
1	Left	1	1	Straight/Debonded			
	Right						
1	Left	1	2	Straight/Debonded			
	Right						

1		1	3	Straight/Debonded
	Left			
	Right			
1		1	4	Straight/Debonded
	Left			
	Right			
1		1	5	Straight/Debonded
	Left			
	Right			
1		1	6	Straight/Debonded
	Left			
	Right			
1		1	7	Straight/Debonded
	Left			
	Right			
1		1	8	Straight/Debonded
	Left			
	Right			
1		1	9	Straight/Debonded
	Left			
	Right			
1		1	10	Straight/Debonded
	Left			
	Right			
1		1	11	Straight/Debonded
	Left			
	Right			
1		1	12	Straight/Debonded
	Left			
	Right			
1		1	13	Straight/Debonded
	Left			
	Right			
1		1	14	Straight/Debonded
	Left			
	Right			
1		1	15	Straight/Debonded
	Left			
	Right			
1		1	16	Straight/Debonded
	Left			
	Right			
1		2	1	Straight/Debonded
	Left			
	Right			
1		2	2	Straight/Debonded
	Left			
	Right			
1		2	3	Straight/Debonded
	Left			

1	Right	2	4	Straight/Debonded
1	Left	2	5	Straight/Debonded
1	Right	2	6	Straight/Debonded
1	Left	3	1	Straight/Debonded
1	Right	3	7	Straight/Debonded
1	Left	3	10	Straight/Debonded
1	Right	3	16	Straight/Debonded

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	8.96	1	1.0000	0.1636
1	9.96...	20.00	1	1.0000	0.1636
1	29.95...	8.96	1	1.0000	0.1636

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Extends into Deck
#4 Bent Shear R...	1	0.21	4	6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	10.5000	FALSE
#4 Bent Shear R...	1	3.08	27	15.0000	FALSE
#4 Bent Shear R...	1	36.83	1	10.5000	FALSE
#4 Bent Shear R...	1	37.71	4	6.0000	FALSE

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance	Number Spaces	Spacing	Composite Length
---------------------	---------	----------------	---------------	---------	------------------

#3 - 2'-7" long	1	(ft) 0.21	4	(in) 6.0000	(ft)
#3 - 2'-7" long	1	2.21	1	10.5000	
#3 - 2'-7" long	1	3.08	27	15.0000	
#3 - 2'-7" long	1	36.83	1	10.5000	
#3 - 2'-7" long	1	37.71	4	6.0000	

Member G4

Link with: G3

Description:

Existing:

Current:

Number of Spans: 1

Span Number	Span Length (ft)
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member G5

Link with: G3

Description:

Existing:

Current:

Number of Spans: 1

Span Number	Span Length (ft)
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member G6

Link with: G3

Description:

Existing:

Current:

Number of Spans: 1

Span Number	Span Length (ft)
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member G7

Link with: G3

Description:

Existing:

Current:

Number of Spans: 1

Span Number	Span Length (ft)
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member G8

Link with: G3

Description:

Existing:

Current:

Number of Spans: 1

Span Number	Span Length (ft)
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member G9

Link with: G3

Description:

Existing:

Current:

Number of Spans: 1

Span Number	Span Length (ft)
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member G10

Link with: None

Description:

Existing: 17"x36" INT PSU - w/ post Tensioning -

Current: 17"x36" INT PSU - w/ post Tensioning -

Number of Spans: 1

Span Number	Span Length (ft)
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support Number	Horizontal (in)	Vertical (in)	Rotational (Radians)	Load Case Name
1				
2				

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

<u>Elastic</u>				
Support	X Translation	Y Translation	Z Rotation	Override Computed
Number	(kip/ft)	(kip/ft)	(kip-in/rad)	Z Rotation
1				
2				

Member Alternative 17"x36" INT PSU - w/ post Tensioning

Description:

Description

Material Type: Prestressed Concrete

Girder Type: PS Precast Box

Member units: US Customary

Girder property input method: Schedule based

Additional Self Load: (kip/ft)

Additional Self Load %: 1.0 (%)

Analysis Module

Analysis Method: ASD

Analysis Module: AASHTO ASD

Analysis Module Component:

Properties:

Analysis Method: LFD

Analysis Module: AASHTO LFD

Analysis Module Component:

Properties:

Analysis Method: LRFD

Analysis Module: AASHTO LRFD

Analysis Module Component:

Properties:

Analysis Method: LRFR

Analysis Module: AASHTO LRFR

Analysis Module Component:

Properties:

Analysis Method: Distribution Factors

Analysis Module: Legacy BrR Dist Fact

Analysis Module Component:

Properties:

Default rating method: LRFR

LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:

LFD: 2002 AASHTO Std. Specifications(CF=0.9)

ASD Factors

Inventory Operating

Structural steel
Concrete
PS Concrete Comp.
PS Concrete Tens.
PS Moment Cap.
Reinforcement
Bearing Stiffener
Stirrup
Timber NA

Default Materials

Deck concrete: Class A (3000)
Deck reinforcement: Grade 40
Beam concrete: Class P (5000)
Beam reinforcement: Grade 40
Stirrup reinforcemt: Grade 40
Prestressing strand: 7/16" (7W-250) SR

Impact

Standard Impact Factor

Type: Standard - AASHTO

LRFD Dynamic Load Allowance

Fatigue and fracture limit states: 15.0 (%)

All other limit states: 33.0 (%)

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)

Lanes	Shear	Shear at Supports	Moment	Deflection
Loaded				
1 Lane	0.527	0.000	0.527	0.182
Multi-Lane	0.527	0.000	0.527	0.364

LRFD

Distance (ft)	Length (ft)	Type	1 Lane	Multi-Lane
0.00	38.500	Moment	0.254	0.256
0.00	38.500	Shear	0.254	0.256
0.00	38.500	Deflectio...	0.109	0.182

Shrinkage/Time

Deck curing method: Moist-cured
Deck drying time: 3.000 (Days)
Consider deck differential shrinkage loads: FALSE
Beam Curing method: Steam-cured
Curing time: 20.00 (Days)
Service life: 75.00 (Years)
Analysis time: 54.00 (Years)
Composite time: 60.00 (Days)

Continuous time: 45.0 *(Days)*

Beam Details

Span Details

Span	Prestress Shape Use	Concrete Material n	Prestress Properties	Left Projection	Right
		Creep		<i>(in)</i>	<i>(in)</i>
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	8.5000	8.5000

Continuous Support Details

Support Number	Support Distance on Left, SL <i>(in)</i>	Support Distance on Right, SR <i>(in)</i>
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance <i>(ft)</i>	Length <i>(ft)</i>
PS Conc Stress Lim...	1	0.000	39.92

Slab Interface

Deck interface type:	Monolithic
Interface width:	<i>(in)</i>
Deck cohesion factor:	0.400 <i>(ksi)</i>
Deck friction factor:	1.400

Continuity Diaphragm

Span	Material Bar	Left Support Distance Bar	Bar Count	Bar Size	Right Support Material	Distance	Count	Size
No.								

Prestressing Force Information

Strand Layout

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance <i>(ft)</i>	Debond Distance <i>(in)</i>	Harp Curvature <i>(in)</i>
1	Left	1	1	Straight/Debonded			

1	Right	1	2	Straight/Debonded
1	Left Right	1	3	Straight/Debonded
1	Left Right	1	4	Straight/Debonded
1	Left Right	1	5	Straight/Debonded
1	Left Right	1	6	Straight/Debonded
1	Left Right	1	7	Straight/Debonded
1	Left Right	1	8	Straight/Debonded
1	Left Right	1	9	Straight/Debonded
1	Left Right	1	10	Straight/Debonded
1	Left Right	1	11	Straight/Debonded
1	Left Right	1	12	Straight/Debonded
1	Left Right	1	13	Straight/Debonded
1	Left Right	1	14	Straight/Debonded
1	Left Right	1	15	Straight/Debonded
1	Left Right	1	16	Straight/Debonded
1	Left Right	2	1	Straight/Debonded
1	Left Right	2	2	Straight/Debonded

1	Left Right	2	3	Straight/Debonded
1	Left Right	2	4	Straight/Debonded
1	Left Right	2	5	Straight/Debonded
1	Left Right	2	6	Straight/Debonded
1	Left Right	3	1	Straight/Debonded
1	Left Right	3	7	Straight/Debonded
1	Left Right	3	10	Straight/Debonded
1	Left Right	3	16	Straight/Debonded

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	8.96	1	1.0000	0.1636
1	9.96...	20.00	1	1.0000	0.1636
1	29.95...	8.96	1	1.0000	0.1636

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Extends into Deck
#4 Bent Shear R...	1	0.21	4	6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	10.5000	FALSE
#4 Bent Shear R...	1	3.08	27	15.0000	FALSE
#4 Bent Shear R...	1	36.83	1	10.5000	FALSE
#4 Bent Shear R...	1	37.71	4	6.0000	FALSE

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Composite Length (ft)
#3 - 2'-7" long	1	0.21	4	6.0000	
#3 - 2'-7" long	1	2.21	1	10.5000	
#3 - 2'-7" long	1	3.08	27	15.0000	
#3 - 2'-7" long	1	36.83	1	10.5000	
#3 - 2'-7" long	1	37.71	4	6.0000	

Member G11

Link with: None

Description:

Existing: 17"x36" EXT PSU -

Current: 17"x36" EXT PSU -

Number of Spans: 1

Span Number	Span Length (ft)
1	38.500000

Support	Frame Connection
1	
2	

Pedestrian load: (lb/ft)

Member Loads

Member Loads - Settlement

Support Number	Horizontal (in)	Vertical (in)	Rotational (Radians)	Load Case Name
1				
2				

Support Constraints

General

Support Number	Support Type	X Translation	Y Translation	Z Rotation
1	Pinned	Fixed	Fixed	Free
2	Roller	Free	Fixed	Free

Elastic

Support Number	X Translation (kip/ft)	Y Translation (kip/ft)	Z Rotation (kip-in/rad)	Override Computed Z Rotation
1				
2				

Member Alternative 17"x36" EXT PSU

Description:

Description

Material Type: Prestressed Concrete

Girder Type: PS Precast Box

Member units: US Customary

Girder property input method: Schedule based

Additional Self Load: (kip/ft)

Additional Self Load %: 1.0 (%)

Analysis Module

Analysis Method: ASD

Analysis Module: AASHTO ASD

Analysis Module Component:

Properties:

Analysis Method: LFD

Analysis Module: AASHTO LFD

Analysis Module Component:

Properties:

Analysis Method: LRFD

Analysis Module: AASHTO LRFD

Analysis Module Component:

Properties:

Analysis Method: LRFR

Analysis Module: AASHTO LRFR

Analysis Module Component:

Properties:

Analysis Method: Distribution Factors

Analysis Module: Legacy BrR Dist Fact

Analysis Module Component:

Properties:

Default rating method: LRFR

LRFD shear computation method: General Procedure

Factors

Factor Override

LRFD:

LFD: 2002 AASHTO Std. Specifications(CF=0.9)

ASD Factors

Inventory Operating

Structural steel

Concrete

PS Concrete Comp.

PS Concrete Tens.

PS Moment Cap.

Reinforcement	
Bearing Stiffener	
Stirrup	
Timber	NA

Default Materials

Deck concrete:	Class A (3000)
Deck reinforcement:	Grade 40
Beam concrete:	Class P (5000)
Beam reinforcement:	Grade 40
Stirrup reinforcemt:	Grade 40
Prestressing strand:	7/16" (7W-250) SR

Impact

Standard Impact Factor

Type:	Standard - AASHTO
-------	-------------------

LRFD Dynamic Load Allowance

Fatigue and fracture limit states:	15.0 (%)
------------------------------------	----------

All other limit states:	33.0 (%)
-------------------------	----------

Live Load Distribution

Standard

D i s t r i b u t i o n F a c t o r (Wheels)

Lanes	Shear	Shear at Supports	Moment	Deflection
Loaded				
1 Lane	0.100	0.100	0.100	0.100
Multi-Lane	0.100	0.100	0.100	0.100

LRFD

Distance	Length	Type	1 Lane	Multi-Lane
(ft)	(ft)			
0.00	38.500	Deflectio...	0.100	0.100
0.00	38.500	Moment	0.100	0.100
0.00	38.500	Shear	0.100	0.100

Shrinkage/Time

Deck curing method:	Moist-cured
Deck drying time: 3.000	(Days)
Consider deck differential shrinkage loads:	FALSE
Beam Curing method:	Steam-cured
Curing time: 20.00	(Days)
Service life: 75.00	(Years)
Analysis time: 54.00	(Years)
Composite time: 60.00	(Days)
Continuous time: 45.0	(Days)

Beam Details

Span Details

Span	Prestress Shape Use	Concrete Material	Prestress Properties	Left Projection	Right Projection
1	17"x36" PSU TRUE	Class P (5000... 6.64...	PS Strands Pr...	(in) 8.5000	(in) 8.5000

Continuous Support Details

Support Number	Support Distance on Left, SL (in)	Support Distance on Right, SR (in)
1		
2		

Stress Limit Ranges

Stress Limit	Span	Start Distance (ft)	Length (ft)
PS Conc Stress Lim...	1	0.000	39.92

Slab Interface

Deck interface type:	Monolithic
Interface width:	(in)
Deck cohesion factor:	0.400 (ksi)
Deck friction factor:	1.400

Continuity Diaphragm

Span	Material	Left Support Distance	Bar	Bar	Right Support Material	Distance
No.	Bar	Bar	Count	Size	Count	Size

Prestressing Force Information**Strand Layout**

Span	Pos.	Row No.	Col. No.	Config. Type	Harp Distance (ft)	Debond Distance (in)	Harp Curvature (in)
1	Left	1	1	Straight/Debonded			
1	Right	1	2	Straight/Debonded			
1	Left	1	3	Straight/Debonded			
	Right						

1	Left Right	1	4	Straight/Debonded
1	Left Right	1	5	Straight/Debonded
1	Left Right	1	6	Straight/Debonded
1	Left Right	1	7	Straight/Debonded
1	Left Right	1	8	Straight/Debonded
1	Left Right	1	9	Straight/Debonded
1	Left Right	1	10	Straight/Debonded
1	Left Right	1	11	Straight/Debonded
1	Left Right	1	12	Straight/Debonded
1	Left Right	1	13	Straight/Debonded
1	Left Right	1	14	Straight/Debonded
1	Left Right	1	15	Straight/Debonded
1	Left Right	1	16	Straight/Debonded
1	Left Right	2	1	Straight/Debonded
1	Left Right	2	2	Straight/Debonded
1	Left Right	2	3	Straight/Debonded

1	2	4	Straight/Debonded
	Left		
	Right		
1	2	5	Straight/Debonded
	Left		
	Right		
1	2	6	Straight/Debonded
	Left		
	Right		
1	3	1	Straight/Debonded
	Left		
	Right		
1	3	7	Straight/Debonded
	Left		
	Right		
1	3	10	Straight/Debonded
	Left		
	Right		
1	3	16	Straight/Debonded
	Left		
	Right		

Deck Profile

Interior Diaphragms

Span	Start Distance (ft)	Spacing (ft)	No of Spaces	Thickness (in)	Weight (kip)
1	0.00...	1.00	1	2.0000	0.3272
1	1.00...	8.96	1	1.0000	0.1636
1	9.96...	20.00	1	1.0000	0.1636
1	29.96...	8.96	1	1.0000	0.1636

Shear Reinforcement Ranges - Vertical

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Extends into Deck
#4 Bent Shear R...	1	0.21	4	6.0000	FALSE
#4 Bent Shear R...	1	2.21	1	10.5000	FALSE
#4 Bent Shear R...	1	3.08	27	15.0000	FALSE
#4 Bent Shear R...	1	36.83	1	10.5000	FALSE
#4 Bent Shear R...	1	37.71	4	6.0000	FALSE

Shear Reinforcement Ranges - Horizontal

Shear Reinforcement	Span No	Start Distance (ft)	Number Spaces	Spacing (in)	Composite Length (ft)
------------------------	------------	---------------------------	------------------	-----------------	-----------------------------

#3 - 2'-7" long	1	0.21	4	6.0000
#3 - 2'-7" long	1	2.21	1	10.5000
#3 - 2'-7" long	1	3.08	27	15.0000
#3 - 2'-7" long	1	36.83	1	10.5000
#3 - 2'-7" long	1	37.71	4	6.0000

APPENDIX B – AASHTOWARE BrR RATING OUTPUT

Bridge Name: Matheson Hmck Bridge over Matheson Hammock Canal
NBI Structure ID: 874294
Bridge ID: 874294

Analyzed By: BrR
Analyze Date: Wednesday, October 06, 2021 15:45:03
Analysis Engine: AASHTO LRFR Engine Version 6.8.4.3002
Analysis Preference Setting: None

Report By: BrR
Report Date: Wednesday, October 06, 2021 15:45:44

Structure Definition Name: End Span 1 (or 3) - PS Conc PSU
Member Name: G10
Member Alternative Name: 17"x36" INT PSU - (w/ Post Tensioning)

Report by Action: ☒ Flexure ☒ Concrete Stresses ☒ Shear ☒ Critical

Detailed Rating Results
17"x36" INT PSU - (w/ Post Tensioning)
HL-93 (US)
Truck + Lane
Impact: With Impact
Lane: Single Lane

Span 1

							Inventory Rating	Inventory Load Rating	Operating Rating	Operating Load Rating
Location										
(ft)	Percent	Limit State	Units	Capacity	DL + Adj-LL*	LL	Factor	(Ton)	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	3564.00	99.000	3564.00
0.00	0.0	Concrete Stresses	ksi	0.70	-0.00	0.00	99.000	3564.00		
1.17	4.1	Shear	kip	129.09	7.72	20.37	3.351	120.64	4.344	156.39
1.69	6.0	Flexure	kip-ft	243.32	13.52	33.69	3.841	138.27	4.979	179.24
1.69	6.0	Shear	kip	118.17	7.42	19.81	3.141	113.07	4.072	146.57
1.69	6.0	Concrete Stresses	ksi	1.63	0.10	0.25	7.736	278.50		
2.83	10.0	Flexure	kip-ft	284.36	21.61	53.30	2.759	99.33	3.577	128.76
2.83	10.0	Shear	kip	92.75	6.76	18.60	2.590	93.25	3.358	120.88
2.83	10.0	Concrete Stresses	ksi	1.63	0.16	0.39	4.700	169.19		
5.66	20.0	Flexure	kip-ft	304.65	38.40	90.83	1.615	58.13	2.093	75.35
5.66	20.0	Shear	kip	85.08	5.11	15.62	2.878	103.61	3.731	134.31
5.66	20.0	Concrete Stresses	ksi	1.63	0.28	0.67	2.527	90.96		
8.49	30.0	Flexure	kip-ft	304.65	50.23	112.61	1.227	44.18	1.591	57.27
8.49	30.0	Shear	kip	59.51	3.30	12.71	2.491	89.69	4.720	169.93
8.49	30.0	Concrete Stresses	ksi	1.63	0.37	0.83	1.907	68.64		
11.32	40.0	Flexure	kip-ft	304.65	57.22	118.63	1.123	40.43	1.456	52.41
11.32	40.0	Shear	kip	54.86	1.65	9.84	3.066	110.39	6.250	225.00
11.32	40.0	Concrete Stresses	ksi	1.63	0.42	0.87	1.736	62.51		
14.15	50.0	Flexure		304.65	59.54	109.11	1.206	43.40	1.563	56.26

14.15	50.0	Shear	kip-ft	-64.58	-0.00	-7.03	5.251	189.03	8.967	322.81
14.15	50.0	Concrete Stresses	ksi	1.63	0.44	0.80	1.861	67.00		
16.98	60.0	Flexure	kip-ft	304.65	57.20	118.63	1.123	40.43	1.456	52.41
16.98	60.0	Shear	kip	-54.87	-1.65	-9.84	3.066	110.38	6.249	224.98
16.98	60.0	Concrete Stresses	ksi	1.63	0.42	0.87	1.737	62.51		
19.80	70.0	Flexure	kip-ft	304.65	50.19	112.61	1.228	44.19	1.591	57.29
19.80	70.0	Shear	kip	-59.53	-3.30	-12.71	2.492	89.71	4.720	169.91
19.80	70.0	Concrete Stresses	ksi	1.63	0.37	0.83	1.907	68.66		
22.63	80.0	Flexure	kip-ft	304.65	38.37	90.83	1.615	58.13	2.093	75.36
22.63	80.0	Shear	kip	-85.08	-5.12	-15.62	2.878	103.60	3.730	134.30
22.63	80.0	Concrete Stresses	ksi	1.63	0.28	0.67	2.527	90.97		
25.46	90.0	Flexure	kip-ft	291.74	21.57	53.30	2.839	102.20	3.680	132.49
25.46	90.0	Shear	kip	-89.88	-6.76	-18.60	2.502	90.07	3.243	116.75
25.46	90.0	Concrete Stresses	ksi	1.63	0.16	0.39	4.701	169.23		
26.81	94.8	Flexure	kip-ft	256.36	11.90	29.83	4.626	166.53	5.996	215.87
26.81	94.8	Shear	kip	-118.33	-7.55	-20.03	3.106	111.81	4.026	144.94
26.81	94.8	Concrete Stresses	ksi	1.63	0.09	0.22	8.804	316.93		
27.11	95.8	Shear	kip	-125.83	-7.72	-20.35	3.262	117.43	4.228	152.22
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	3564.00	99.000	3564.00
28.29	100.0	Concrete Stresses	ksi	0.82	-0.00	0.00	99.000	3564.00		

Detailed Rating Results
17"x36" INT PSU - (w/ Post Tensioning)
HL-93 (US)
Tandem + Lane
Impact: With Impact
Lane: Single Lane

Span 1

Location						Inventory		Operating	
						Rating	Load Rating	Rating	Load Rating
(ft)	Percent	Units	Capacity	LL	Factor		(Ton)	Factor	(Ton)

		Limit State			DL + Adj- LL*					
0.00	0.0	Flexure	kip- ft	88.32	0.00	0.00	99.000	3564.00	99.000	3564.00
0.00	0.0	Concrete Stresses	ksi	0.70	-0.00	0.00	99.000	3564.00		
1.17	4.1	Shear	kip	129.09	7.72	19.93	3.425	123.31	4.440	159.85
1.69	6.0	Flexure	kip-ft	243.32	13.52	33.11	3.907	140.67	5.065	182.34
1.69	6.0	Shear	kip	118.17	7.42	19.47	3.196	115.05	4.143	149.13
1.69	6.0	Concrete Stresses	ksi	1.63	0.10	0.24	7.870	283.33		
2.83	10.0	Flexure	kip-ft	284.36	21.61	52.96	2.777	99.96	3.599	129.57
2.83	10.0	Shear	kip	92.75	6.76	18.48	2.607	93.85	3.379	121.65
2.83	10.0	Concrete Stresses	ksi	1.63	0.16	0.39	4.729	170.26		
5.66	20.0	Flexure	kip- ft	304.65	38.40	93.28	1.572	56.60	2.038	73.37
5.66	20.0	Shear	kip	85.08	5.11	16.06	2.801	100.82	3.630	130.69
5.66	20.0	Concrete Stresses	ksi	1.63	0.28	0.69	2.460	88.57		
8.49	30.0	Flexure	kip- ft	304.65	50.23	120.96	1.143	41.13	1.481	53.32
8.49	30.0	Shear	kip	53.03	3.30	13.69	2.042	73.50	4.381	157.72
8.49	30.0	Concrete Stresses	ksi	1.63	0.37	0.89	1.775	63.90		
11.32	40.0	Flexure	kip- ft	304.65	57.22	135.99	0.980	35.27	1.270	45.71
11.32	40.0	Shear	kip	45.04	1.65	11.37	2.159	77.74	4.245	152.83
11.32	40.0	Concrete Stresses	ksi	1.63	0.42	1.00	1.515	54.53		
14.15	50.0	Flexure	kip- ft	304.65	59.54	138.38	0.951	34.23	1.232	44.37
14.15	50.0	Shear	kip	-44.95	-0.00	-9.11	2.818	101.46	5.444	195.99
14.15	50.0	Concrete Stresses	ksi	1.63	0.44	1.02	1.467	52.83		
16.98	60.0	Flexure	kip- ft	304.65	57.20	135.99	0.980	35.27	1.270	45.72
16.98	60.0	Shear	kip	-45.04	-1.65	-11.37	2.159	77.73	4.245	152.83
16.98	60.0	Concrete Stresses	ksi	1.63	0.42	1.00	1.515	54.53		
19.80	70.0	Flexure	kip- ft	304.65	50.19	120.96	1.143	41.14	1.481	53.33
19.80	70.0	Shear	kip	-53.04	-3.30	-13.69	2.042	73.50	4.381	157.70
19.80	70.0	Concrete Stresses	ksi	1.63	0.37	0.89	1.775	63.92		
22.63	80.0	Flexure		304.65	38.37	93.28	1.572	56.61	2.038	73.38

22.63	80.0	Shear	kip-ft	-85.08	-5.12	-16.06	2.800	100.81	3.630	130.68
22.63	80.0	Concrete Stresses	ksi	1.63	0.28	0.69	2.461	88.58		
25.46	90.0	Flexure	kip-ft	291.74	21.57	52.96	2.857	102.85	3.703	133.32
25.46	90.0	Shear	kip	-89.88	-6.76	-18.48	2.518	90.64	3.264	117.50
25.46	90.0	Concrete Stresses	ksi	1.63	0.16	0.39	4.730	170.30		
26.81	94.8	Flexure	kip-ft	256.36	11.90	29.27	4.715	169.73	6.112	220.02
26.81	94.8	Shear	kip	-118.33	-7.55	-19.65	3.166	113.97	4.104	147.74
26.81	94.8	Concrete Stresses	ksi	1.63	0.09	0.22	8.973	323.03		
27.11	95.8	Shear	kip	-125.83	-7.72	-19.91	3.334	120.01	4.321	155.57
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	3564.00	99.000	3564.00
28.29	100.0	Concrete Stresses	ksi	0.82	-0.00	0.00	99.000	3564.00		

Detailed Rating Results
17"x36" INT PSU - (w/ Post Tensioning)
C 3
Axle Load
Impact: With Impact
Lane: Single Lane

Span 1

							Legal Rating	Legal Load Rating
Location								
(ft)	Percent	Limit State	Units	Capacity	DL + Adj -LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	2772.00
1.17	4.1	Shear	kip	129.09	7.72	11.15	8.238	230.67
1.69	6.0	Flexure	kip-ft	243.32	13.52	18.41	9.462	264.94
1.69	6.0	Shear	kip	118.17	7.42	10.91	7.679	215.03
2.83	10.0	Flexure	kip-ft	284.36	21.61	29.33	6.749	188.96
2.83	10.0	Shear	kip	92.75	6.76	10.37	6.254	175.13
5.66	20.0	Flexure	kip-ft	304.65	38.40	51.10	3.864	108.18
5.66	20.0	Shear	kip	85.08	5.11	9.03	6.703	187.69
8.49	30.0	Flexure	kip-ft	304.65	50.23	65.30	2.849	79.78
8.49	30.0	Shear	kip	85.08	3.30	7.69	8.095	226.66
11.32	40.0	Flexure	kip-ft	304.65	57.22	71.93	2.493	69.81
11.32	40.0	Shear	kip	85.08	1.65	6.36	10.048	281.34
14.15	50.0	Flexure	kip-ft	304.65	59.54	70.99	2.495	69.85

14.15	50.0	Shear	kip	-85.08	-0.00	-5.02	13.040	365.13
16.98	60.0	Flexure	kip-ft	304.65	57.20	71.93	2.493	69.82
16.98	60.0	Shear	kip	-85.08	-1.65	-6.36	10.047	281.31
19.80	70.0	Flexure	kip-ft	304.65	50.19	65.30	2.850	79.80
19.80	70.0	Shear	kip	-85.08	-3.30	-7.69	8.094	226.64
22.63	80.0	Flexure	kip-ft	304.65	38.37	51.10	3.864	108.20
22.63	80.0	Shear	kip	-85.08	-5.12	-9.03	6.702	187.67
25.46	90.0	Flexure	kip-ft	291.74	21.57	29.33	6.944	194.42
25.46	90.0	Shear	kip	-89.88	-6.76	-10.37	6.041	169.14
26.81	94.8	Flexure	kip-ft	256.36	11.90	16.28	11.410	319.48
26.81	94.8	Shear	kip	-118.33	-7.55	-11.01	7.610	213.09
27.11	95.8	Shear	kip	-125.83	-7.72	-11.15	8.018	224.49
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	2772.00

Detailed Rating Results
17"x36" INT PSU - (w/ Post Tensioning)
C 4
Axle Load
Impact: With Impact
Lane: Single Lane

Span 1

							Legal	Legal
							Rating	Load
Location								Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj -LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	3628.35
1.17	4.1	Shear	kip	129.09	7.72	15.66	5.867	215.02
1.69	6.0	Flexure	kip-ft	243.32	13.52	25.63	6.797	249.10
1.69	6.0	Shear	kip	118.17	7.42	15.19	5.516	202.17
2.83	10.0	Flexure	kip-ft	284.36	21.61	40.46	4.892	179.30
2.83	10.0	Shear	kip	92.75	6.76	14.30	4.534	166.17
5.66	20.0	Flexure	kip-ft	304.65	38.40	71.13	2.775	101.72
5.66	20.0	Shear	kip	85.08	5.11	12.57	4.815	176.48
8.49	30.0	Flexure	kip-ft	304.65	50.23	92.01	2.022	74.11
8.49	30.0	Shear	kip	85.08	3.30	10.84	5.745	210.55
11.32	40.0	Flexure	kip-ft	304.65	57.22	103.09	1.739	63.75
11.32	40.0	Shear	kip	85.08	1.65	9.11	7.010	256.93
14.15	50.0	Flexure	kip-ft	304.65	59.54	104.38	1.697	62.18
14.15	50.0	Shear	kip	-85.08	-0.00	-7.38	8.869	325.04
16.98	60.0	Flexure	kip-ft	304.65	57.20	103.09	1.740	63.76
16.98	60.0	Shear	kip	-85.08	-1.65	-9.11	7.010	256.90
19.80	70.0	Flexure	kip-ft	304.65	50.19	92.01	2.022	74.12

19.80	70.0	Shear	kip	-85.08	-3.30	-10.84	5.744	210.53
22.63	80.0	Flexure	kip-ft	304.65	38.37	71.13	2.776	101.73
22.63	80.0	Shear	kip	-85.08	-5.12	-12.57	4.815	176.46
25.46	90.0	Flexure	kip-ft	291.74	21.57	40.46	5.034	184.49
25.46	90.0	Shear	kip	-89.88	-6.76	-14.30	4.379	160.50
26.81	94.8	Flexure	kip-ft	256.36	11.90	22.74	8.167	299.32
26.81	94.8	Shear	kip	-118.33	-7.55	-15.38	5.447	199.65
27.11	95.8	Shear	kip	-125.83	-7.72	-15.65	5.711	209.30
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	3628.35

Detailed Rating Results
17"x36" INT PSU - (w/ Post Tensioning)
C 5
Axle Load
Impact: With Impact
Lane: Single Lane

Span 1

							Legal Rating	Legal Load Rating
Location								
(ft)	Percent	Limit State	Units	Capacity	DL + Adj -LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	3960.00
1.17	4.1	Shear	kip	129.09	7.72	15.73	5.842	233.70
1.69	6.0	Flexure	kip-ft	243.32	13.52	25.93	6.717	268.67
1.69	6.0	Shear	kip	118.17	7.42	15.37	5.451	218.06
2.83	10.0	Flexure	kip-ft	284.36	21.61	41.23	4.802	192.06
2.83	10.0	Shear	kip	92.75	6.76	14.57	4.450	178.00
5.66	20.0	Flexure	kip-ft	304.65	38.40	71.33	2.768	110.72
5.66	20.0	Shear	kip	85.08	5.11	12.61	4.802	192.09
8.49	30.0	Flexure	kip-ft	304.65	50.23	90.30	2.060	82.42
8.49	30.0	Shear	kip	85.08	3.30	10.64	5.854	234.15
11.32	40.0	Flexure	kip-ft	304.65	57.22	98.14	1.827	73.09
11.32	40.0	Shear	kip	85.08	1.65	8.67	7.364	294.57
14.15	50.0	Flexure	kip-ft	304.65	59.54	103.05	1.719	68.74
14.15	50.0	Shear	kip	-85.08	-0.00	-6.71	9.756	390.22
16.98	60.0	Flexure	kip-ft	304.65	57.20	98.14	1.827	73.10
16.98	60.0	Shear	kip	-85.08	-1.65	-8.67	7.364	294.54
19.80	70.0	Flexure	kip-ft	304.65	50.19	90.30	2.061	82.43
19.80	70.0	Shear	kip	-85.08	-3.30	-10.64	5.853	234.13
22.63	80.0	Flexure	kip-ft	304.65	38.37	71.33	2.768	110.73
22.63	80.0	Shear	kip	-85.08	-5.12	-12.61	4.802	192.07
25.46	90.0	Flexure	kip-ft	291.74	21.57	41.23	4.940	197.62

25.46	90.0	Shear	kip	-89.88	-6.76	-14.57	4.298	171.92
26.81	94.8	Flexure	kip-ft	256.36	11.90	22.94	8.096	323.85
26.81	94.8	Shear	kip	-118.33	-7.55	-15.51	5.400	216.01
27.11	95.8	Shear	kip	-125.83	-7.72	-15.72	5.686	227.44
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	3960.00

Detailed Rating Results
17"x36" INT PSU - (w/ Post Tensioning)
FL120 Span < 200ft
Axle Load
Impact: With Impact
Lane: Single Lane

Span 1

							Permit	Permit
Location							Rating	Load Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj -LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	5940.00
1.69	6.0	Flexure	kip-ft	243.32	13.52	40.86	4.618	277.07
2.83	10.0	Flexure	kip-ft	284.36	21.61	64.51	3.324	199.45
5.66	20.0	Flexure	kip-ft	304.65	38.40	109.25	1.958	117.46
8.49	30.0	Flexure	kip-ft	304.65	50.23	134.22	1.502	90.10
11.32	40.0	Flexure	kip-ft	304.65	57.22	139.42	1.393	83.60
14.15	50.0	Flexure	kip-ft	304.65	59.54	125.17	1.533	91.97
16.98	60.0	Flexure	kip-ft	304.65	57.20	139.42	1.394	83.61
19.80	70.0	Flexure	kip-ft	304.65	50.19	134.22	1.502	90.12
22.63	80.0	Flexure	kip-ft	304.65	38.37	109.25	1.958	117.47
25.46	90.0	Flexure	kip-ft	291.74	21.57	64.51	3.420	205.22
26.81	94.8	Flexure	kip-ft	256.36	11.90	36.20	5.560	333.58
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	5940.00

Detailed Rating Results
17"x36" INT PSU - (w/ Post Tensioning)
ST 5
Axle Load
Impact: With Impact
Lane: Single Lane

Span 1

Location							Legal	Legal
							Rating	Load Rating

(ft)	Percent	Limit State	Units	Capacity	DL + Adj -LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	3960.00
1.17	4.1	Shear	kip	129.09	7.72	15.36	5.983	239.30
1.69	6.0	Flexure	kip-ft	243.32	13.52	25.26	6.895	275.80
1.69	6.0	Shear	kip	118.17	7.42	14.97	5.596	223.84
2.83	10.0	Flexure	kip-ft	284.36	21.61	39.92	4.958	198.33
2.83	10.0	Shear	kip	92.75	6.76	14.11	4.595	183.81
5.66	20.0	Flexure	kip-ft	304.65	38.40	67.83	2.911	116.42
5.66	20.0	Shear	kip	85.08	5.11	11.99	5.050	201.99
8.49	30.0	Flexure	kip-ft	304.65	50.23	83.72	2.222	88.89
8.49	30.0	Shear	kip	85.08	3.30	9.86	6.314	252.56
11.32	40.0	Flexure	kip-ft	304.65	57.22	93.25	1.923	76.92
11.32	40.0	Shear	kip	85.08	1.65	7.74	8.252	330.08
14.15	50.0	Flexure	kip-ft	304.65	59.54	93.59	1.892	75.69
14.15	50.0	Shear	kip	-85.08	-0.00	-6.08	10.765	430.60
16.98	60.0	Flexure	kip-ft	304.65	57.20	93.25	1.923	76.93
16.98	60.0	Shear	kip	-85.08	-1.65	-7.74	8.251	330.04
19.80	70.0	Flexure	kip-ft	304.65	50.19	83.72	2.223	88.91
19.80	70.0	Shear	kip	-85.08	-3.30	-9.86	6.313	252.53
22.63	80.0	Flexure	kip-ft	304.65	38.37	67.83	2.911	116.44
22.63	80.0	Shear	kip	-85.08	-5.12	-11.99	5.049	201.97
25.46	90.0	Flexure	kip-ft	291.74	21.57	39.92	5.102	204.07
25.46	90.0	Shear	kip	-89.88	-6.76	-14.11	4.438	177.53
26.81	94.8	Flexure	kip-ft	256.36	11.90	22.37	8.303	332.11
26.81	94.8	Shear	kip	-118.33	-7.55	-15.13	5.538	221.51
27.11	95.8	Shear	kip	-125.83	-7.72	-15.35	5.823	232.91
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	3960.00

Detailed Rating Results
17"x36" INT PSU - (w/ Post Tensioning)
SU 2
Axle Load
Impact: With Impact
Lane: Single Lane

Span 1

							Legal	Legal
Location							Rating	Load Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj -LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	1683.00
1.17	4.1	Shear	kip	129.09	7.72	10.65	8.625	146.63

1.69	6.0	Flexure	kip-ft	243.32	13.52	17.56	9.917	168.59
1.69	6.0	Shear	kip	118.17	7.42	10.41	8.049	136.83
2.83	10.0	Flexure	kip-ft	284.36	21.61	27.92	7.091	120.54
2.83	10.0	Shear	kip	92.75	6.76	9.87	6.572	111.72
5.66	20.0	Flexure	kip-ft	304.65	38.40	48.27	4.090	69.54
5.66	20.0	Shear	kip	85.08	5.11	8.53	7.097	120.64
8.49	30.0	Flexure	kip-ft	304.65	50.23	61.05	3.047	51.81
8.49	30.0	Shear	kip	85.08	3.30	7.19	8.658	147.19
11.32	40.0	Flexure	kip-ft	304.65	57.22	66.26	2.706	46.01
11.32	40.0	Shear	kip	85.08	1.65	5.86	10.907	185.42
14.15	50.0	Flexure	kip-ft	304.65	59.54	63.91	2.771	47.11
14.15	50.0	Shear	kip	-85.08	-0.00	-4.52	14.485	246.24
16.98	60.0	Flexure	kip-ft	304.65	57.20	66.26	2.707	46.01
16.98	60.0	Shear	kip	-85.08	-1.65	-5.86	10.906	185.40
19.80	70.0	Flexure	kip-ft	304.65	50.19	61.05	3.048	51.82
19.80	70.0	Shear	kip	-85.08	-3.30	-7.19	8.657	147.18
22.63	80.0	Flexure	kip-ft	304.65	38.37	48.27	4.091	69.54
22.63	80.0	Shear	kip	-85.08	-5.12	-8.53	7.096	120.63
25.46	90.0	Flexure	kip-ft	291.74	21.57	27.92	7.296	124.03
25.46	90.0	Shear	kip	-89.88	-6.76	-9.87	6.347	107.90
26.81	94.8	Flexure	kip-ft	256.36	11.90	15.54	11.954	203.21
26.81	94.8	Shear	kip	-118.33	-7.55	-10.51	7.973	135.54
27.11	95.8	Shear	kip	-125.83	-7.72	-10.65	8.394	142.71
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	1683.00

Detailed Rating Results
17"x36" INT PSU - (w/ Post Tensioning)
SU 3
Axle Load
Impact: With Impact
Lane: Single Lane

Span 1

							Legal	Legal
Location							Rating	Load Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj -LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	3267.00
1.17	4.1	Shear	kip	129.09	7.72	18.97	4.842	159.80
1.69	6.0	Flexure	kip-ft	243.32	13.52	31.22	5.579	184.12
1.69	6.0	Shear	kip	118.17	7.42	18.50	4.528	149.43
2.83	10.0	Flexure	kip-ft	284.36	21.61	49.37	4.009	132.31
2.83	10.0	Shear	kip	92.75	6.76	17.45	3.716	122.62

5.66	20.0	Flexure	kip-ft	304.65	38.40	84.06	2.349	77.51
5.66	20.0	Shear	kip	85.08	5.11	14.86	4.075	134.48
8.49	30.0	Flexure	kip-ft	304.65	50.23	104.05	1.788	59.01
8.49	30.0	Shear	kip	85.08	3.30	12.26	5.080	167.65
11.32	40.0	Flexure	kip-ft	304.65	57.22	116.56	1.538	50.77
11.32	40.0	Shear	kip	85.08	1.65	9.66	6.609	218.10
14.15	50.0	Flexure	kip-ft	304.65	59.54	118.00	1.501	49.53
14.15	50.0	Shear	kip	-85.08	-0.00	-7.38	8.869	292.67
16.98	60.0	Flexure	kip-ft	304.65	57.20	116.56	1.539	50.77
16.98	60.0	Shear	kip	-85.08	-1.65	-9.66	6.609	218.08
19.80	70.0	Flexure	kip-ft	304.65	50.19	104.05	1.788	59.02
19.80	70.0	Shear	kip	-85.08	-3.30	-12.26	5.080	167.63
22.63	80.0	Flexure	kip-ft	304.65	38.37	84.06	2.349	77.52
22.63	80.0	Shear	kip	-85.08	-5.12	-14.86	4.075	134.46
25.46	90.0	Flexure	kip-ft	291.74	21.57	49.37	4.125	136.14
25.46	90.0	Shear	kip	-89.88	-6.76	-17.45	3.589	118.44
26.81	94.8	Flexure	kip-ft	256.36	11.90	27.65	6.719	221.73
26.81	94.8	Shear	kip	-118.33	-7.55	-18.69	4.482	147.89
27.11	95.8	Shear	kip	-125.83	-7.72	-18.96	4.713	155.53
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	3267.00

Detailed Rating Results
17"x36" INT PSU - (w/ Post Tensioning)

SU 4

Axle Load

Impact: With Impact

Lane: Single Lane

Span 1

							Legal	Legal
Location							Rating	Load Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj -LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	3465.00
1.17	4.1	Shear	kip	129.09	7.72	19.76	4.649	162.71
1.69	6.0	Flexure	kip-ft	243.32	13.52	32.50	5.359	187.56
1.69	6.0	Shear	kip	118.17	7.42	19.26	4.349	152.22
2.83	10.0	Flexure	kip-ft	284.36	21.61	51.35	3.855	134.94
2.83	10.0	Shear	kip	92.75	6.76	18.15	3.573	125.06
5.66	20.0	Flexure	kip-ft	304.65	38.40	87.11	2.266	79.32
5.66	20.0	Shear	kip	85.08	5.11	15.40	3.932	137.62
8.49	30.0	Flexure	kip-ft	304.65	50.23	111.07	1.675	58.63
8.49	30.0	Shear	kip	85.08	3.30	12.64	4.926	172.42

11.32	40.0	Flexure	kip-ft	304.65	57.22	127.15	1.410	49.36
11.32	40.0	Shear	kip	84.27	1.65	9.99	6.330	221.56
14.15	50.0	Flexure	kip-ft	304.65	59.54	127.65	1.387	48.56
14.15	50.0	Shear	kip	-85.08	-0.00	-7.78	8.408	294.29
16.98	60.0	Flexure	kip-ft	304.65	57.20	127.15	1.411	49.37
16.98	60.0	Shear	kip	-84.29	-1.65	-9.99	6.331	221.58
19.80	70.0	Flexure	kip-ft	304.65	50.19	111.07	1.675	58.64
19.80	70.0	Shear	kip	-85.08	-3.30	-12.64	4.926	172.40
22.63	80.0	Flexure	kip-ft	304.65	38.37	87.11	2.267	79.33
22.63	80.0	Shear	kip	-85.08	-5.12	-15.40	3.932	137.61
25.46	90.0	Flexure	kip-ft	291.74	21.57	51.35	3.967	138.84
25.46	90.0	Shear	kip	-89.88	-6.76	-18.15	3.451	120.79
26.81	94.8	Flexure	kip-ft	256.36	11.90	28.79	6.452	225.84
26.81	94.8	Shear	kip	-118.33	-7.55	-19.46	4.304	150.63
27.11	95.8	Shear	kip	-125.83	-7.72	-19.75	4.525	158.36
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	3465.00

Note:

*Adj-LL is only applicable for Permit load rating.

Bridge Name: Matheson Hmck Bridge over Matheson Hammock Canal
NBI Structure ID: 874294
Bridge ID: 874294

Analyzed By: BrR
Analyze Date: Wednesday, October 06, 2021 15:34:40
Analysis Engine: AASHTO LRFR Engine Version 6.8.4.3002
Analysis Preference Setting: None

Report By: BrR
Report Date: Wednesday, October 06, 2021 15:35:19

Structure Definition Name: INT Span 2 - PS Conc PSU
Member Name: G10
Member Alternative Name: 17"x36" INT PSU - w/ post Tensioning

Report by Action: ☒ Flexure ☒ Concrete Stresses ☒ Shear ☒ Critical

Detailed Rating Results
17"x36" INT PSU - w/ post Tensioning
HL-93 (US)
Truck + Lane
Impact: With Impact
Lane: Single Lane

Span 2

							Inventory Rating	Inventory Load Rating	Operating Rating	Operating Load Rating
Location										
(ft)	Percent	Limit State	Units	Capacity	DL + Adj-LL*	LL	Factor	(Ton)	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	182.46	0.00	0.00	99.000	3564.00	99.000	3564.00
0.00	0.0	Concrete Stresses	ksi	1.08	-0.00	0.00	99.000	3564.00		
1.12	2.9	Shear	kip	112.73	10.73	20.86	2.720	97.92	3.526	126.94
1.48	3.8	Flexure	kip-ft	408.30	16.29	30.61	7.243	260.75	9.389	338.01
1.48	3.8	Shear	kip	106.69	10.52	20.57	2.598	93.53	3.368	121.24
1.48	3.8	Concrete Stresses	ksi	2.45	0.12	0.23	12.955	466.37		
3.85	10.0	Flexure	kip-ft	462.73	39.60	73.09	3.231	116.30	4.188	150.76
3.85	10.0	Shear	kip	79.93	9.14	18.70	2.093	75.36	2.714	97.69
3.85	10.0	Concrete Stresses	ksi	2.45	0.29	0.54	5.026	180.94		
7.70	20.0	Flexure	kip-ft	462.73	70.46	124.85	1.715	61.73	2.223	80.02
7.70	20.0	Shear	kip	79.93	6.89	15.71	2.594	93.38	3.363	121.05
7.70	20.0	Concrete Stresses	ksi	2.45	0.52	0.92	2.633	94.80		
11.55	30.0	Flexure	kip-ft	462.73	92.31	156.13	1.271	45.76	1.648	59.32
11.55	30.0	Shear	kip	79.93	4.49	12.85	3.304	118.93	4.283	154.17
11.55	30.0	Concrete Stresses	ksi	2.45	0.68	1.15	1.931	69.51		
15.40	40.0	Flexure	kip-ft	462.73	105.27	172.00	1.100	39.61	1.426	51.34
15.40	40.0	Shear	kip	70.23	2.24	10.26	3.754	135.16	5.567	200.41
15.40	40.0	Concrete Stresses	ksi	2.45	0.77	1.26	1.659	59.71		
19.25	50.0	Flexure	kip-ft	462.73	109.59	171.21	1.087	39.14	1.409	50.74

19.25	50.0	Shear	kip	-71.82	0.00	-7.73	5.308	191.08	7.657	275.64
19.25	50.0	Concrete Stresses	ksi	2.45	0.81	1.26	1.635	58.85		
23.10	60.0	Flexure	kip-ft	462.73	105.27	172.00	1.100	39.61	1.426	51.34
23.10	60.0	Shear	kip	-70.23	-2.24	-10.26	3.754	135.16	5.567	200.41
23.10	60.0	Concrete Stresses	ksi	2.45	0.77	1.26	1.659	59.71		
26.95	70.0	Flexure	kip-ft	480.13	92.31	156.13	1.335	48.06	1.730	62.30
26.95	70.0	Shear	kip	-80.21	-4.49	-12.85	3.316	119.38	4.299	154.75
26.95	70.0	Concrete Stresses	ksi	2.45	0.68	1.15	1.931	69.51		
30.80	80.0	Flexure	kip-ft	462.73	70.46	124.85	1.715	61.73	2.223	80.02
30.80	80.0	Shear	kip	-79.93	-6.89	-15.71	2.594	93.38	3.363	121.05
30.80	80.0	Concrete Stresses	ksi	2.45	0.52	0.92	2.633	94.80		
34.65	90.0	Flexure	kip-ft	462.73	39.60	73.09	3.231	116.30	4.188	150.76
34.65	90.0	Shear	kip	-79.93	-9.14	-18.70	2.093	75.36	2.714	97.69
34.65	90.0	Concrete Stresses	ksi	2.45	0.29	0.54	5.026	180.94		
37.02	96.2	Flexure	kip-ft	408.30	16.29	30.61	7.243	260.75	9.389	338.01
37.02	96.2	Shear	kip	-106.69	-10.52	-20.57	2.598	93.53	3.368	121.24
37.02	96.2	Concrete Stresses	ksi	2.45	0.12	0.23	12.955	466.37		
37.39	97.1	Shear	kip	-112.75	-10.73	-20.87	2.720	97.93	3.526	126.95
38.50	100.0	Flexure	kip-ft	157.45	0.00	0.00	99.000	3564.00	99.000	3564.00
38.50	100.0	Concrete Stresses	ksi	1.08	0.00	0.00	99.000	3564.00		

Detailed Rating Results
17"x36" INT PSU - w/ post Tensioning
HL-93 (US)
Tandem + Lane
Impact: With Impact
Lane: Single Lane

Span 2

Location		Limit State	Units	Capacity	DL + Adj-LL*	LL	Inventory Inventory Operating Operating			
							Rating	Load Rating	Rating	Load Rating
(ft)	Percent						Factor	(Ton)	Factor	(Ton)

0.00	0.0	Flexure	kip-ft	182.46	0.00	0.00	99.000	3564.00	99.000	3564.00
0.00	0.0	Concrete Stresses	ksi	1.08	-0.00	0.00	99.000	3564.00		
1.12	2.9	Shear	kip	112.73	10.73	18.65	3.044	109.57	3.945	142.04
1.48	3.8	Flexure	kip-ft	408.30	16.29	27.43	8.082	290.94	10.476	377.14
1.48	3.8	Shear	kip	106.69	10.52	18.43	2.901	104.43	3.760	135.37
1.48	3.8	Concrete Stresses	ksi	2.45	0.12	0.20	14.455	520.38		
3.85	10.0	Flexure	kip-ft	462.73	39.60	66.60	3.545	127.63	4.596	165.45
3.85	10.0	Shear	kip	79.93	9.14	17.02	2.301	82.82	2.982	107.36
3.85	10.0	Concrete Stresses	ksi	2.45	0.29	0.49	5.516	198.56		
7.70	20.0	Flexure	kip-ft	462.73	70.46	117.65	1.820	65.51	2.359	84.92
7.70	20.0	Shear	kip	79.93	6.89	14.77	2.758	99.29	3.575	128.71
7.70	20.0	Concrete Stresses	ksi	2.45	0.52	0.86	2.795	100.61		
11.55	30.0	Flexure	kip-ft	462.73	92.31	153.13	1.296	46.66	1.680	60.48
11.55	30.0	Shear	kip	79.93	4.49	12.60	3.372	121.38	4.371	157.35
11.55	30.0	Concrete Stresses	ksi	2.45	0.68	1.13	1.969	70.87		
15.40	40.0	Flexure	kip-ft	462.73	105.27	173.06	1.093	39.36	1.417	51.02
15.40	40.0	Shear	kip	69.26	2.24	10.48	3.623	130.44	5.451	196.25
15.40	40.0	Concrete Stresses	ksi	2.45	0.77	1.27	1.648	59.34		
19.25	50.0	Flexure	kip-ft	462.73	109.59	177.43	1.049	37.77	1.360	48.96
19.25	50.0	Shear	kip	-66.70	0.00	-8.43	4.523	162.82	7.025	252.91
19.25	50.0	Concrete Stresses	ksi	2.45	0.81	1.30	1.577	56.78		
23.10	60.0	Flexure	kip-ft	462.73	105.27	173.06	1.093	39.36	1.417	51.02
23.10	60.0	Shear	kip	-69.26	-2.24	-10.48	3.623	130.44	5.451	196.25
23.10	60.0	Concrete Stresses	ksi	2.45	0.77	1.27	1.648	59.34		
26.95	70.0	Flexure	kip-ft	480.13	92.31	153.13	1.361	49.00	1.764	63.52
26.95	70.0	Shear	kip	-80.21	-4.49	-12.60	3.384	121.84	4.387	157.94
26.95	70.0	Concrete Stresses	ksi	2.45	0.68	1.13	1.969	70.87		
30.80	80.0	Flexure	kip-ft	462.73	70.46	117.65	1.820	65.51	2.359	84.92
30.80	80.0	Shear	kip	-79.93	-6.89	-14.77	2.758	99.29	3.575	128.71
30.80	80.0		ksi	2.45	0.52	0.86	2.795	100.61		

		Concrete Stresses								
34.65	90.0	Flexure	kip-ft	462.73	39.60	66.60	3.545	127.63	4.596	165.45
34.65	90.0	Shear	kip	-79.93	-9.14	-17.02	2.301	82.82	2.982	107.36
34.65	90.0	Concrete Stresses	ksi	2.45	0.29	0.49	5.516	198.56		
37.02	96.2	Flexure	kip-ft	408.30	16.29	27.43	8.082	290.94	10.476	377.14
37.02	96.2	Shear	kip	-106.69	-10.52	-18.43	2.901	104.43	3.760	135.37
37.02	96.2	Concrete Stresses	ksi	2.45	0.12	0.20	14.455	520.38		
37.39	97.1	Shear	kip	-112.75	-10.73	-18.65	3.044	109.58	3.946	142.05
38.50	100.0	Flexure	kip-ft	157.45	0.00	0.00	99.000	3564.00	99.000	3564.00
38.50	100.0	Concrete Stresses	ksi	1.08	0.00	0.00	99.000	3564.00		

Detailed Rating Results
17"x36" INT PSU - w/ post Tensioning
C 3
Axle Load
Impact: With Impact
Lane: Single Lane

Span 2

							Legal Rating	Legal Load Rating
Location								
(ft)	Percent	Limit State	Units	Capacity	DL + Adj- LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	182.46	0.00	0.00	99.000	2772.00
1.12	2.9	Shear	kip	112.73	10.73	11.46	6.669	186.74
1.48	3.8	Flexure	kip-ft	408.30	16.29	16.68	17.893	501.00
1.48	3.8	Shear	kip	106.69	10.52	11.27	6.382	178.70
3.85	10.0	Flexure	kip-ft	462.73	39.60	38.88	8.175	228.91
3.85	10.0	Shear	kip	79.93	9.14	10.10	5.218	146.10
7.70	20.0	Flexure	kip-ft	462.73	70.46	63.23	4.558	127.63
7.70	20.0	Shear	kip	79.93	6.89	8.21	6.680	187.05
11.55	30.0	Flexure	kip-ft	462.73	92.31	81.45	3.280	91.85
11.55	30.0	Shear	kip	79.93	4.49	7.05	8.107	226.99
15.40	40.0	Flexure	kip-ft	462.73	105.27	91.86	2.773	77.64
15.40	40.0	Shear	kip	79.93	2.24	5.89	10.068	281.90
19.25	50.0	Flexure	kip-ft	462.73	109.59	91.12	2.750	77.00
19.25	50.0	Shear	kip	79.93	0.00	4.73	12.989	363.70
23.10	60.0	Flexure	kip-ft	462.73	105.27	91.86	2.773	77.64
23.10	60.0	Shear	kip	-79.93	-2.24	-5.89	10.068	281.90

26.95	70.0	Flexure	kip-ft	480.13	92.31	81.45	3.445	96.45
26.95	70.0	Shear	kip	-80.21	-4.49	-7.05	8.137	227.84
30.80	80.0	Flexure	kip-ft	462.73	70.46	63.23	4.558	127.63
30.80	80.0	Shear	kip	-79.93	-6.89	-8.21	6.680	187.05
34.65	90.0	Flexure	kip-ft	462.73	39.60	38.88	8.175	228.91
34.65	90.0	Shear	kip	-79.93	-9.14	-10.10	5.218	146.10
37.02	96.2	Flexure	kip-ft	408.30	16.29	16.68	17.893	501.00
37.02	96.2	Shear	kip	-106.69	-10.52	-11.27	6.382	178.70
37.39	97.1	Shear	kip	-112.75	-10.73	-11.46	6.670	186.75
38.50	100.0	Flexure	kip-ft	157.45	0.00	0.00	99.000	2772.00

Detailed Rating Results
17"x36" INT PSU - w/ post Tensioning
C 4
Axle Load
Impact: With Impact
Lane: Single Lane

Span 2

Location							Legal Rating	Legal Load Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj- LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	182.46	0.00	0.00	99.000	3628.35
1.12	2.9	Shear	kip	112.73	10.73	16.06	4.756	174.32
1.48	3.8	Flexure	kip-ft	408.30	16.29	23.41	12.747	467.17
1.48	3.8	Shear	kip	106.69	10.52	15.83	4.547	166.63
3.85	10.0	Flexure	kip-ft	462.73	39.60	55.34	5.744	210.50
3.85	10.0	Shear	kip	79.93	9.14	14.37	3.666	134.35
7.70	20.0	Flexure	kip-ft	462.73	70.46	93.36	3.087	113.13
7.70	20.0	Shear	kip	79.93	6.89	12.12	4.524	165.81
11.55	30.0	Flexure	kip-ft	462.73	92.31	114.05	2.343	85.86
11.55	30.0	Shear	kip	79.93	4.49	9.87	5.790	212.19
15.40	40.0	Flexure	kip-ft	462.73	105.27	126.11	2.020	74.03
15.40	40.0	Shear	kip	79.93	2.24	8.19	7.244	265.51
19.25	50.0	Flexure	kip-ft	462.73	109.59	128.76	1.946	71.32
19.25	50.0	Shear	kip	79.93	0.00	6.69	9.192	336.87
23.10	60.0	Flexure	kip-ft	462.73	105.27	126.11	2.020	74.03
23.10	60.0	Shear	kip	-79.93	-2.24	-8.19	7.244	265.51
26.95	70.0	Flexure	kip-ft	480.13	92.31	114.05	2.460	90.16
26.95	70.0	Shear	kip	-80.21	-4.49	-9.87	5.811	212.98
30.80	80.0	Flexure	kip-ft	462.73	70.46	93.36	3.087	113.13
30.80	80.0	Shear	kip	-79.93	-6.89	-12.12	4.524	165.81

34.65	90.0	Flexure	kip-ft	462.73	39.60	55.34	5.744	210.50
34.65	90.0	Shear	kip	-79.93	-9.14	-14.37	3.666	134.35
37.02	96.2	Flexure	kip-ft	408.30	16.29	23.41	12.747	467.17
37.02	96.2	Shear	kip	-106.69	-10.52	-15.83	4.547	166.63
37.39	97.1	Shear	kip	-112.75	-10.73	-16.06	4.757	174.33
38.50	100.0	Flexure	kip-ft	157.45	0.00	0.00	99.000	3628.35

Detailed Rating Results
17"x36" INT PSU - w/ post Tensioning
C 5
Axle Load
Impact: With Impact
Lane: Single Lane

Span 2

							Legal	Legal
Location							Rating	Load Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj-LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	182.46	0.00	0.00	99.000	3960.00
1.12	2.9	Shear	kip	112.73	10.73	16.08	4.750	190.02
1.48	3.8	Flexure	kip-ft	408.30	16.29	23.46	12.722	508.90
1.48	3.8	Shear	kip	106.69	10.52	15.86	4.538	181.51
3.85	10.0	Flexure	kip-ft	462.73	39.60	55.39	5.739	229.54
3.85	10.0	Shear	kip	79.93	9.14	14.39	3.663	146.51
7.70	20.0	Flexure	kip-ft	462.73	70.46	92.41	3.119	124.75
7.70	20.0	Shear	kip	79.93	6.89	12.00	4.571	182.83
11.55	30.0	Flexure	kip-ft	462.73	92.31	114.81	2.327	93.08
11.55	30.0	Shear	kip	79.93	4.49	9.94	5.751	230.04
15.40	40.0	Flexure	kip-ft	462.73	105.27	128.28	1.986	79.42
15.40	40.0	Shear	kip	79.93	2.24	8.24	7.203	288.14
19.25	50.0	Flexure	kip-ft	462.73	109.59	132.83	1.886	75.46
19.25	50.0	Shear	kip	79.93	0.00	6.32	9.727	389.09
23.10	60.0	Flexure	kip-ft	462.73	105.27	128.28	1.986	79.42
23.10	60.0	Shear	kip	-79.93	-2.24	-8.24	7.203	288.14
26.95	70.0	Flexure	kip-ft	480.13	92.31	114.81	2.444	97.75
26.95	70.0	Shear	kip	-80.21	-4.49	-9.94	5.773	230.90
30.80	80.0	Flexure	kip-ft	462.73	70.46	92.41	3.119	124.75
30.80	80.0	Shear	kip	-79.93	-6.89	-12.00	4.571	182.83
34.65	90.0	Flexure	kip-ft	462.73	39.60	55.39	5.739	229.54
34.65	90.0	Shear	kip	-79.93	-9.14	-14.39	3.663	146.51
37.02	96.2	Flexure	kip-ft	408.30	16.29	23.46	12.722	508.90
37.02	96.2	Shear	kip	-106.69	-10.52	-15.86	4.538	181.51

37.39	97.1	Shear	kip	-112.75	-10.73	-16.08	4.751	190.03
38.50	100.0	Flexure	kip-ft	157.45	0.00	0.00	99.000	3960.00

Detailed Rating Results
17"x36" INT PSU - w/ post Tensioning
FL120 Span < 200ft
Axle Load
Impact: With Impact
Lane: Single Lane

Span 2

							Permit	Permit
							Rating	Load
Location								Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj-LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	182.46	0.00	0.00	99.000	5940.00
1.48	3.8	Flexure	kip-ft	408.30	16.29	35.85	9.016	540.99
3.85	10.0	Flexure	kip-ft	462.73	39.60	85.33	4.036	242.14
7.70	20.0	Flexure	kip-ft	462.73	70.46	144.69	2.158	129.47
11.55	30.0	Flexure	kip-ft	462.73	92.31	179.27	1.615	96.87
15.40	40.0	Flexure	kip-ft	462.73	105.27	196.07	1.407	84.45
19.25	50.0	Flexure	kip-ft	462.73	109.59	193.35	1.404	84.24
23.10	60.0	Flexure	kip-ft	462.73	105.27	196.07	1.407	84.45
26.95	70.0	Flexure	kip-ft	480.13	92.31	179.27	1.695	101.73
30.80	80.0	Flexure	kip-ft	462.73	70.46	144.69	2.158	129.47
34.65	90.0	Flexure	kip-ft	462.73	39.60	85.33	4.036	242.14
37.02	96.2	Flexure	kip-ft	408.30	16.29	35.85	9.016	540.99
38.50	100.0	Flexure	kip-ft	157.45	0.00	0.00	99.000	5940.00

Detailed Rating Results
17"x36" INT PSU - w/ post Tensioning
ST 5
Axle Load
Impact: With Impact
Lane: Single Lane

Span 2

							Legal	Legal
							Rating	Load
Location								Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj-LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	182.46	0.00	0.00	99.000	3960.00

1.12	2.9	Shear	kip	112.73	10.73	14.69	5.201	208.03
1.48	3.8	Flexure	kip-ft	408.30	16.29	21.47	13.898	555.92
1.48	3.8	Shear	kip	106.69	10.52	14.52	4.957	198.29
3.85	10.0	Flexure	kip-ft	462.73	39.60	51.52	6.170	246.79
3.85	10.0	Shear	kip	79.93	9.14	13.38	3.938	157.51
7.70	20.0	Flexure	kip-ft	462.73	70.46	88.86	3.243	129.72
7.70	20.0	Shear	kip	79.93	6.89	11.54	4.753	190.12
11.55	30.0	Flexure	kip-ft	462.73	92.31	112.03	2.385	95.39
11.55	30.0	Shear	kip	79.93	4.49	9.70	5.894	235.75
15.40	40.0	Flexure	kip-ft	462.73	105.27	125.93	2.023	80.91
15.40	40.0	Shear	kip	79.93	2.24	7.86	7.549	301.96
19.25	50.0	Flexure	kip-ft	462.73	109.59	128.11	1.956	78.24
19.25	50.0	Shear	kip	79.93	0.00	6.02	10.217	408.69
23.10	60.0	Flexure	kip-ft	462.73	105.27	125.93	2.023	80.91
23.10	60.0	Shear	kip	-79.93	-2.24	-7.86	7.549	301.96
26.95	70.0	Flexure	kip-ft	480.13	92.31	112.03	2.504	100.17
26.95	70.0	Shear	kip	-80.21	-4.49	-9.70	5.916	236.64
30.80	80.0	Flexure	kip-ft	462.73	70.46	88.86	3.243	129.72
30.80	80.0	Shear	kip	-79.93	-6.89	-11.54	4.753	190.12
34.65	90.0	Flexure	kip-ft	462.73	39.60	51.52	6.170	246.79
34.65	90.0	Shear	kip	-79.93	-9.14	-13.38	3.938	157.51
37.02	96.2	Flexure	kip-ft	408.30	16.29	21.47	13.898	555.92
37.02	96.2	Shear	kip	-106.69	-10.52	-14.52	4.957	198.28
37.39	97.1	Shear	kip	-112.75	-10.73	-14.69	5.201	208.05
38.50	100.0	Flexure	kip-ft	157.45	0.00	0.00	99.000	3960.00

Detailed Rating Results
17"x36" INT PSU - w/ post Tensioning
SU 2
Axle Load
Impact: With Impact
Lane: Single Lane

Span 2

							Legal	Legal
Location							Rating	Load Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj-LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	182.46	0.00	0.00	99.000	1683.00
1.12	2.9	Shear	kip	112.73	10.73	9.87	7.737	131.52
1.48	3.8	Flexure	kip-ft	408.30	16.29	14.44	20.659	351.20
1.48	3.8	Shear	kip	106.69	10.52	9.77	7.369	125.27
3.85	10.0	Flexure	kip-ft	462.73	39.60	34.85	9.121	155.07

3.85	10.0	Shear	kip	79.93	9.14	9.05	5.822	98.97
7.70	20.0	Flexure	kip-ft	462.73	70.46	60.77	4.742	80.62
7.70	20.0	Shear	kip	79.93	6.89	7.89	6.950	118.15
11.55	30.0	Flexure	kip-ft	462.73	92.31	77.77	3.436	58.41
11.55	30.0	Shear	kip	79.93	4.49	6.73	8.491	144.34
15.40	40.0	Flexure	kip-ft	462.73	105.27	85.84	2.968	50.45
15.40	40.0	Shear	kip	79.93	2.24	5.57	10.644	180.94
19.25	50.0	Flexure	kip-ft	462.73	109.59	84.98	2.949	50.13
19.25	50.0	Shear	kip	79.93	0.00	4.41	13.927	236.76
23.10	60.0	Flexure	kip-ft	462.73	105.27	85.84	2.968	50.45
23.10	60.0	Shear	kip	-79.93	-2.24	-5.57	10.644	180.94
26.95	70.0	Flexure	kip-ft	480.13	92.31	77.77	3.608	61.33
26.95	70.0	Shear	kip	-80.21	-4.49	-6.73	8.523	144.88
30.80	80.0	Flexure	kip-ft	462.73	70.46	60.77	4.742	80.62
30.80	80.0	Shear	kip	-79.93	-6.89	-7.89	6.950	118.15
34.65	90.0	Flexure	kip-ft	462.73	39.60	34.85	9.122	155.07
34.65	90.0	Shear	kip	-79.93	-9.14	-9.05	5.822	98.97
37.02	96.2	Flexure	kip-ft	408.30	16.29	14.44	20.659	351.20
37.02	96.2	Shear	kip	-106.69	-10.52	-9.77	7.369	125.27
37.39	97.1	Shear	kip	-112.75	-10.73	-9.88	7.737	131.54
38.50	100.0	Flexure	kip-ft	157.45	0.00	0.00	99.000	1683.00

Detailed Rating Results
17"x36" INT PSU - w/ post Tensioning
SU 3
Axle Load
Impact: With Impact
Lane: Single Lane

Span 2

							Legal	Legal
Location							Rating	Load
(ft)	Percent	Limit	Units	Capacity	DL + Adj- LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	182.46	0.00	0.00	99.000	3267.00
1.12	2.9	Shear	kip	112.73	10.73	18.08	4.225	139.42
1.48	3.8	Flexure	kip-ft	408.30	16.29	26.43	11.289	372.52
1.48	3.8	Shear	kip	106.69	10.52	17.87	4.026	132.87
3.85	10.0	Flexure	kip-ft	462.73	39.60	63.47	5.008	165.27
3.85	10.0	Shear	kip	79.93	9.14	16.49	3.197	105.48
7.70	20.0	Flexure	kip-ft	462.73	70.46	109.61	2.629	86.76
7.70	20.0	Shear	kip	79.93	6.89	14.24	3.853	127.16
11.55	30.0	Flexure	kip-ft	462.73	92.31	138.43	1.930	63.69

11.55	30.0	Shear	kip	79.93	4.49	11.98	4.770	157.41
15.40	40.0	Flexure	kip-ft	462.73	105.27	156.17	1.631	53.83
15.40	40.0	Shear	kip	79.93	2.24	9.73	6.094	201.11
19.25	50.0	Flexure	kip-ft	462.73	109.59	159.70	1.569	51.78
19.25	50.0	Shear	kip	79.93	0.00	7.48	8.215	271.09
23.10	60.0	Flexure	kip-ft	462.73	105.27	156.17	1.631	53.83
23.10	60.0	Shear	kip	-79.93	-2.24	-9.73	6.094	201.11
26.95	70.0	Flexure	kip-ft	480.13	92.31	138.43	2.027	66.89
26.95	70.0	Shear	kip	-80.21	-4.49	-11.98	4.788	158.00
30.80	80.0	Flexure	kip-ft	462.73	70.46	109.61	2.629	86.76
30.80	80.0	Shear	kip	-79.93	-6.89	-14.24	3.853	127.16
34.65	90.0	Flexure	kip-ft	462.73	39.60	63.47	5.008	165.27
34.65	90.0	Shear	kip	-79.93	-9.14	-16.49	3.196	105.48
37.02	96.2	Flexure	kip-ft	408.30	16.29	26.43	11.289	372.52
37.02	96.2	Shear	kip	-106.69	-10.52	-17.87	4.026	132.87
37.39	97.1	Shear	kip	-112.75	-10.73	-18.08	4.225	139.43
38.50	100.0	Flexure	kip-ft	157.45	0.00	0.00	99.000	3267.00

Detailed Rating Results
17"x36" INT PSU - w/ post Tensioning
SU 4
Axle Load
Impact: With Impact
Lane: Single Lane

Span 2

							Legal	Legal
Location							Rating	Load Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj-LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	182.46	0.00	0.00	99.000	3465.00
1.12	2.9	Shear	kip	112.73	10.73	18.95	4.032	141.10
1.48	3.8	Flexure	kip-ft	408.30	16.29	27.70	10.774	377.09
1.48	3.8	Shear	kip	106.69	10.52	18.72	3.843	134.50
3.85	10.0	Flexure	kip-ft	462.73	39.60	66.43	4.785	167.47
3.85	10.0	Shear	kip	79.93	9.14	17.26	3.054	106.89
7.70	20.0	Flexure	kip-ft	462.73	70.46	114.49	2.517	88.10
7.70	20.0	Shear	kip	79.93	6.89	14.87	3.689	129.12
11.55	30.0	Flexure	kip-ft	462.73	92.31	147.43	1.812	63.43
11.55	30.0	Shear	kip	79.93	4.49	12.48	4.580	160.30
15.40	40.0	Flexure	kip-ft	462.73	105.27	168.68	1.510	52.85
15.40	40.0	Shear	kip	79.93	2.24	10.10	5.877	205.68
19.25	50.0	Flexure	kip-ft	462.73	109.59	171.55	1.461	51.12

19.25	50.0	Shear	kip	79.93	0.00	7.71	7.976	279.15
23.10	60.0	Flexure	kip-ft	462.73	105.27	168.68	1.510	52.85
23.10	60.0	Shear	kip	-79.93	-2.24	-10.10	5.877	205.68
26.95	70.0	Flexure	kip-ft	480.13	92.31	147.43	1.903	66.61
26.95	70.0	Shear	kip	-80.21	-4.49	-12.48	4.597	160.90
30.80	80.0	Flexure	kip-ft	462.73	70.46	114.49	2.517	88.10
30.80	80.0	Shear	kip	-79.93	-6.89	-14.87	3.689	129.12
34.65	90.0	Flexure	kip-ft	462.73	39.60	66.43	4.785	167.47
34.65	90.0	Shear	kip	-79.93	-9.14	-17.26	3.054	106.89
37.02	96.2	Flexure	kip-ft	408.30	16.29	27.70	10.774	377.09
37.02	96.2	Shear	kip	-106.69	-10.52	-18.72	3.843	134.50
37.39	97.1	Shear	kip	-112.75	-10.73	-18.95	4.032	141.12
38.50	100.0	Flexure	kip-ft	157.45	0.00	0.00	99.000	3465.00

Note:

*Adj-LL is only applicable for Permit load rating.

Bridge Name: Matheson Hmck Bridge over Matheson Hammock Canal
NBI Structure ID: 874294D
Bridge ID: 874294D

Analyzed By: BrR
Analyze Date: Wednesday, October 06, 2021 11:44:40
Analysis Engine: AASHTO LRFR Engine Version 6.8.4.3002
Analysis Preference Setting: None

Report By: BrR
Report Date: Wednesday, October 06, 2021 11:45:40

Structure Definition Name: End Span 1 (or 3) - PS Conc PSU
Member Name: G9
Member Alternative Name: 17"x36" INT PSU - w/ Conc Repair + Post Tensioning

Report by Action: ☒ Flexure ☒ Concrete Stresses ☒ Shear ☒ Critical

Detailed Rating Results
17"x36" INT PSU - w/ Conc Repair + Post Tensioning
HL-93 (US)
Truck + Lane
Impact: With Impact
Lane: Single Lane

Span 1

							Inventory Rating	Inventory Load Rating	Operating Rating	Operating Load Rating
Location										
(ft)	Percent	Limit State	Units	Capacity	DL + Adj-LL*	LL	Factor	(Ton)	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	3564.00	99.000	3564.00
0.00	0.0	Concrete Stresses	ksi	0.70	-0.00	0.00	99.000	3564.00		
1.17	4.1	Shear	kip	129.09	7.72	20.37	3.351	120.64	4.344	156.39
1.69	6.0	Flexure	kip-ft	243.32	13.52	33.69	3.841	138.27	4.979	179.24
1.69	6.0	Shear	kip	118.17	7.42	19.81	3.141	113.07	4.072	146.57
1.69	6.0	Concrete Stresses	ksi	1.63	0.10	0.25	7.736	278.50		
2.83	10.0	Flexure	kip-ft	284.36	21.61	53.30	2.759	99.33	3.577	128.76
2.83	10.0	Shear	kip	92.75	6.76	18.60	2.590	93.25	3.358	120.88
2.83	10.0	Concrete Stresses	ksi	1.63	0.16	0.39	4.700	169.19		
5.66	20.0	Flexure	kip-ft	304.65	38.40	90.83	1.615	58.13	2.093	75.35
5.66	20.0	Shear	kip	85.08	5.11	15.62	2.878	103.61	3.731	134.31
5.66	20.0	Concrete Stresses	ksi	1.63	0.28	0.67	2.527	90.96		
8.49	30.0	Flexure	kip-ft	304.65	50.23	112.61	1.227	44.18	1.591	57.27
8.49	30.0	Shear	kip	59.51	3.30	12.71	2.491	89.69	4.720	169.93
8.49	30.0	Concrete Stresses	ksi	1.63	0.37	0.83	1.907	68.64		
11.32	40.0	Flexure	kip-ft	304.65	57.22	118.63	1.123	40.43	1.456	52.41
11.32	40.0	Shear	kip	54.86	1.65	9.84	3.066	110.39	6.250	225.00
11.32	40.0	Concrete Stresses	ksi	1.63	0.42	0.87	1.736	62.51		
14.15	50.0	Flexure		304.65	59.54	109.11	1.206	43.40	1.563	56.26

14.15	50.0	Shear	kip-ft	-64.58	-0.00	-7.03	5.251	189.03	8.967	322.81
14.15	50.0	Concrete Stresses	ksi	1.63	0.44	0.80	1.861	67.00		
16.98	60.0	Flexure	kip-ft	304.65	57.20	118.63	1.123	40.43	1.456	52.41
16.98	60.0	Shear	kip	-54.87	-1.65	-9.84	3.066	110.38	6.249	224.98
16.98	60.0	Concrete Stresses	ksi	1.63	0.42	0.87	1.737	62.51		
19.80	70.0	Flexure	kip-ft	304.65	50.19	112.61	1.228	44.19	1.591	57.29
19.80	70.0	Shear	kip	-59.53	-3.30	-12.71	2.492	89.71	4.720	169.91
19.80	70.0	Concrete Stresses	ksi	1.63	0.37	0.83	1.907	68.66		
22.63	80.0	Flexure	kip-ft	304.65	38.37	90.83	1.615	58.13	2.093	75.36
22.63	80.0	Shear	kip	-85.08	-5.12	-15.62	2.878	103.60	3.730	134.30
22.63	80.0	Concrete Stresses	ksi	1.63	0.28	0.67	2.527	90.97		
25.46	90.0	Flexure	kip-ft	291.74	21.57	53.30	2.839	102.20	3.680	132.49
25.46	90.0	Shear	kip	-89.88	-6.76	-18.60	2.502	90.07	3.243	116.75
25.46	90.0	Concrete Stresses	ksi	1.63	0.16	0.39	4.701	169.23		
26.81	94.8	Flexure	kip-ft	256.36	11.90	29.83	4.626	166.53	5.996	215.87
26.81	94.8	Shear	kip	-118.33	-7.55	-20.03	3.106	111.81	4.026	144.94
26.81	94.8	Concrete Stresses	ksi	1.63	0.09	0.22	8.804	316.93		
27.11	95.8	Shear	kip	-125.83	-7.72	-20.35	3.262	117.43	4.228	152.22
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	3564.00	99.000	3564.00
28.29	100.0	Concrete Stresses	ksi	0.82	-0.00	0.00	99.000	3564.00		

Detailed Rating Results
17"x36" INT PSU - w/ Conc Repair + Post Tensioning
HL-93 (US)
Tandem + Lane
Impact: With Impact
Lane: Single Lane

Span 1

Location						Inventory		Operating	
						Rating	Load Rating	Rating	Load Rating
(ft)	Percent	Units	Capacity	LL	Factor		(Ton)	Factor	(Ton)

		Limit State			DL + Adj- LL*					
0.00	0.0	Flexure	kip- ft	88.32	0.00	0.00	99.000	3564.00	99.000	3564.00
0.00	0.0	Concrete Stresses	ksi	0.70	-0.00	0.00	99.000	3564.00		
1.17	4.1	Shear	kip	129.09	7.72	19.93	3.425	123.31	4.440	159.85
1.69	6.0	Flexure	kip-ft	243.32	13.52	33.11	3.907	140.67	5.065	182.34
1.69	6.0	Shear	kip	118.17	7.42	19.47	3.196	115.05	4.143	149.13
1.69	6.0	Concrete Stresses	ksi	1.63	0.10	0.24	7.870	283.33		
2.83	10.0	Flexure	kip-ft	284.36	21.61	52.96	2.777	99.96	3.599	129.57
2.83	10.0	Shear	kip	92.75	6.76	18.48	2.607	93.85	3.379	121.65
2.83	10.0	Concrete Stresses	ksi	1.63	0.16	0.39	4.729	170.26		
5.66	20.0	Flexure	kip- ft	304.65	38.40	93.28	1.572	56.60	2.038	73.37
5.66	20.0	Shear	kip	85.08	5.11	16.06	2.801	100.82	3.630	130.69
5.66	20.0	Concrete Stresses	ksi	1.63	0.28	0.69	2.460	88.57		
8.49	30.0	Flexure	kip- ft	304.65	50.23	120.96	1.143	41.13	1.481	53.32
8.49	30.0	Shear	kip	53.03	3.30	13.69	2.042	73.50	4.381	157.72
8.49	30.0	Concrete Stresses	ksi	1.63	0.37	0.89	1.775	63.90		
11.32	40.0	Flexure	kip- ft	304.65	57.22	135.99	0.980	35.27	1.270	45.71
11.32	40.0	Shear	kip	45.04	1.65	11.37	2.159	77.74	4.245	152.83
11.32	40.0	Concrete Stresses	ksi	1.63	0.42	1.00	1.515	54.53		
14.15	50.0	Flexure	kip- ft	304.65	59.54	138.38	0.951	34.23	1.232	44.37
14.15	50.0	Shear	kip	-44.95	-0.00	-9.11	2.818	101.46	5.444	195.99
14.15	50.0	Concrete Stresses	ksi	1.63	0.44	1.02	1.467	52.83		
16.98	60.0	Flexure	kip- ft	304.65	57.20	135.99	0.980	35.27	1.270	45.72
16.98	60.0	Shear	kip	-45.04	-1.65	-11.37	2.159	77.73	4.245	152.83
16.98	60.0	Concrete Stresses	ksi	1.63	0.42	1.00	1.515	54.53		
19.80	70.0	Flexure	kip- ft	304.65	50.19	120.96	1.143	41.14	1.481	53.33
19.80	70.0	Shear	kip	-53.04	-3.30	-13.69	2.042	73.50	4.381	157.70
19.80	70.0	Concrete Stresses	ksi	1.63	0.37	0.89	1.775	63.92		
22.63	80.0	Flexure		304.65	38.37	93.28	1.572	56.61	2.038	73.38

22.63	80.0	Shear	kip-ft	-85.08	-5.12	-16.06	2.800	100.81	3.630	130.68
22.63	80.0	Concrete Stresses	ksi	1.63	0.28	0.69	2.461	88.58		
25.46	90.0	Flexure	kip-ft	291.74	21.57	52.96	2.857	102.85	3.703	133.32
25.46	90.0	Shear	kip	-89.88	-6.76	-18.48	2.518	90.64	3.264	117.50
25.46	90.0	Concrete Stresses	ksi	1.63	0.16	0.39	4.730	170.30		
26.81	94.8	Flexure	kip-ft	256.36	11.90	29.27	4.715	169.73	6.112	220.02
26.81	94.8	Shear	kip	-118.33	-7.55	-19.65	3.166	113.97	4.104	147.74
26.81	94.8	Concrete Stresses	ksi	1.63	0.09	0.22	8.973	323.03		
27.11	95.8	Shear	kip	-125.83	-7.72	-19.91	3.334	120.01	4.321	155.57
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	3564.00	99.000	3564.00
28.29	100.0	Concrete Stresses	ksi	0.82	-0.00	0.00	99.000	3564.00		

Detailed Rating Results
17"x36" INT PSU - w/ Conc Repair + Post Tensioning
C 3
Axle Load
Impact: With Impact
Lane: Single Lane

Span 1

							Legal Rating	Legal Load Rating
Location								
(ft)	Percent	Limit State	Units	Capacity	DL + Adj -LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	2772.00
1.17	4.1	Shear	kip	129.09	7.72	11.15	8.238	230.67
1.69	6.0	Flexure	kip-ft	243.32	13.52	18.41	9.462	264.94
1.69	6.0	Shear	kip	118.17	7.42	10.91	7.679	215.03
2.83	10.0	Flexure	kip-ft	284.36	21.61	29.33	6.749	188.96
2.83	10.0	Shear	kip	92.75	6.76	10.37	6.254	175.13
5.66	20.0	Flexure	kip-ft	304.65	38.40	51.10	3.864	108.18
5.66	20.0	Shear	kip	85.08	5.11	9.03	6.703	187.69
8.49	30.0	Flexure	kip-ft	304.65	50.23	65.30	2.849	79.78
8.49	30.0	Shear	kip	85.08	3.30	7.69	8.095	226.66
11.32	40.0	Flexure	kip-ft	304.65	57.22	71.93	2.493	69.81
11.32	40.0	Shear	kip	85.08	1.65	6.36	10.048	281.34
14.15	50.0	Flexure	kip-ft	304.65	59.54	70.99	2.495	69.85

14.15	50.0	Shear	kip	-85.08	-0.00	-5.02	13.040	365.13
16.98	60.0	Flexure	kip-ft	304.65	57.20	71.93	2.493	69.82
16.98	60.0	Shear	kip	-85.08	-1.65	-6.36	10.047	281.31
19.80	70.0	Flexure	kip-ft	304.65	50.19	65.30	2.850	79.80
19.80	70.0	Shear	kip	-85.08	-3.30	-7.69	8.094	226.64
22.63	80.0	Flexure	kip-ft	304.65	38.37	51.10	3.864	108.20
22.63	80.0	Shear	kip	-85.08	-5.12	-9.03	6.702	187.67
25.46	90.0	Flexure	kip-ft	291.74	21.57	29.33	6.944	194.42
25.46	90.0	Shear	kip	-89.88	-6.76	-10.37	6.041	169.14
26.81	94.8	Flexure	kip-ft	256.36	11.90	16.28	11.410	319.48
26.81	94.8	Shear	kip	-118.33	-7.55	-11.01	7.610	213.09
27.11	95.8	Shear	kip	-125.83	-7.72	-11.15	8.018	224.49
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	2772.00

Detailed Rating Results
17"x36" INT PSU - w/ Conc Repair + Post Tensioning
C 4
Axle Load
Impact: With Impact
Lane: Single Lane

Span 1

							Legal	Legal
							Rating	Load
Location								Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj -LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	3628.35
1.17	4.1	Shear	kip	129.09	7.72	15.66	5.867	215.02
1.69	6.0	Flexure	kip-ft	243.32	13.52	25.63	6.797	249.10
1.69	6.0	Shear	kip	118.17	7.42	15.19	5.516	202.17
2.83	10.0	Flexure	kip-ft	284.36	21.61	40.46	4.892	179.30
2.83	10.0	Shear	kip	92.75	6.76	14.30	4.534	166.17
5.66	20.0	Flexure	kip-ft	304.65	38.40	71.13	2.775	101.72
5.66	20.0	Shear	kip	85.08	5.11	12.57	4.815	176.48
8.49	30.0	Flexure	kip-ft	304.65	50.23	92.01	2.022	74.11
8.49	30.0	Shear	kip	85.08	3.30	10.84	5.745	210.55
11.32	40.0	Flexure	kip-ft	304.65	57.22	103.09	1.739	63.75
11.32	40.0	Shear	kip	85.08	1.65	9.11	7.010	256.93
14.15	50.0	Flexure	kip-ft	304.65	59.54	104.38	1.697	62.18
14.15	50.0	Shear	kip	-85.08	-0.00	-7.38	8.869	325.04
16.98	60.0	Flexure	kip-ft	304.65	57.20	103.09	1.740	63.76
16.98	60.0	Shear	kip	-85.08	-1.65	-9.11	7.010	256.90
19.80	70.0	Flexure	kip-ft	304.65	50.19	92.01	2.022	74.12

19.80	70.0	Shear	kip	-85.08	-3.30	-10.84	5.744	210.53
22.63	80.0	Flexure	kip-ft	304.65	38.37	71.13	2.776	101.73
22.63	80.0	Shear	kip	-85.08	-5.12	-12.57	4.815	176.46
25.46	90.0	Flexure	kip-ft	291.74	21.57	40.46	5.034	184.49
25.46	90.0	Shear	kip	-89.88	-6.76	-14.30	4.379	160.50
26.81	94.8	Flexure	kip-ft	256.36	11.90	22.74	8.167	299.32
26.81	94.8	Shear	kip	-118.33	-7.55	-15.38	5.447	199.65
27.11	95.8	Shear	kip	-125.83	-7.72	-15.65	5.711	209.30
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	3628.35

Detailed Rating Results
17"x36" INT PSU - w/ Conc Repair + Post Tensioning
C 5
Axle Load
Impact: With Impact
Lane: Single Lane

Span 1

Location							Legal Rating	Legal Load Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj -LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	3960.00
1.17	4.1	Shear	kip	129.09	7.72	15.73	5.842	233.70
1.69	6.0	Flexure	kip-ft	243.32	13.52	25.93	6.717	268.67
1.69	6.0	Shear	kip	118.17	7.42	15.37	5.451	218.06
2.83	10.0	Flexure	kip-ft	284.36	21.61	41.23	4.802	192.06
2.83	10.0	Shear	kip	92.75	6.76	14.57	4.450	178.00
5.66	20.0	Flexure	kip-ft	304.65	38.40	71.33	2.768	110.72
5.66	20.0	Shear	kip	85.08	5.11	12.61	4.802	192.09
8.49	30.0	Flexure	kip-ft	304.65	50.23	90.30	2.060	82.42
8.49	30.0	Shear	kip	85.08	3.30	10.64	5.854	234.15
11.32	40.0	Flexure	kip-ft	304.65	57.22	98.14	1.827	73.09
11.32	40.0	Shear	kip	85.08	1.65	8.67	7.364	294.57
14.15	50.0	Flexure	kip-ft	304.65	59.54	103.05	1.719	68.74
14.15	50.0	Shear	kip	-85.08	-0.00	-6.71	9.756	390.22
16.98	60.0	Flexure	kip-ft	304.65	57.20	98.14	1.827	73.10
16.98	60.0	Shear	kip	-85.08	-1.65	-8.67	7.364	294.54
19.80	70.0	Flexure	kip-ft	304.65	50.19	90.30	2.061	82.43
19.80	70.0	Shear	kip	-85.08	-3.30	-10.64	5.853	234.13
22.63	80.0	Flexure	kip-ft	304.65	38.37	71.33	2.768	110.73
22.63	80.0	Shear	kip	-85.08	-5.12	-12.61	4.802	192.07
25.46	90.0	Flexure	kip-ft	291.74	21.57	41.23	4.940	197.62

25.46	90.0	Shear	kip	-89.88	-6.76	-14.57	4.298	171.92
26.81	94.8	Flexure	kip-ft	256.36	11.90	22.94	8.096	323.85
26.81	94.8	Shear	kip	-118.33	-7.55	-15.51	5.400	216.01
27.11	95.8	Shear	kip	-125.83	-7.72	-15.72	5.686	227.44
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	3960.00

Detailed Rating Results
17"x36" INT PSU - w/ Conc Repair + Post Tensioning
FL120 Span < 200ft
Axle Load
Impact: With Impact
Lane: Single Lane

Span 1

							Permit	Permit
Location							Rating	Load Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj -LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	5940.00
1.69	6.0	Flexure	kip-ft	243.32	13.52	40.86	4.618	277.07
2.83	10.0	Flexure	kip-ft	284.36	21.61	64.51	3.324	199.45
5.66	20.0	Flexure	kip-ft	304.65	38.40	109.25	1.958	117.46
8.49	30.0	Flexure	kip-ft	304.65	50.23	134.22	1.502	90.10
11.32	40.0	Flexure	kip-ft	304.65	57.22	139.42	1.393	83.60
14.15	50.0	Flexure	kip-ft	304.65	59.54	125.17	1.533	91.97
16.98	60.0	Flexure	kip-ft	304.65	57.20	139.42	1.394	83.61
19.80	70.0	Flexure	kip-ft	304.65	50.19	134.22	1.502	90.12
22.63	80.0	Flexure	kip-ft	304.65	38.37	109.25	1.958	117.47
25.46	90.0	Flexure	kip-ft	291.74	21.57	64.51	3.420	205.22
26.81	94.8	Flexure	kip-ft	256.36	11.90	36.20	5.560	333.58
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	5940.00

Detailed Rating Results
17"x36" INT PSU - w/ Conc Repair + Post Tensioning
ST 5
Axle Load
Impact: With Impact
Lane: Single Lane

Span 1

							Legal	Legal
Location							Rating	Load Rating

(ft)	Percent	Limit State	Units	Capacity	DL + Adj -LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	3960.00
1.17	4.1	Shear	kip	129.09	7.72	15.36	5.983	239.30
1.69	6.0	Flexure	kip-ft	243.32	13.52	25.26	6.895	275.80
1.69	6.0	Shear	kip	118.17	7.42	14.97	5.596	223.84
2.83	10.0	Flexure	kip-ft	284.36	21.61	39.92	4.958	198.33
2.83	10.0	Shear	kip	92.75	6.76	14.11	4.595	183.81
5.66	20.0	Flexure	kip-ft	304.65	38.40	67.83	2.911	116.42
5.66	20.0	Shear	kip	85.08	5.11	11.99	5.050	201.99
8.49	30.0	Flexure	kip-ft	304.65	50.23	83.72	2.222	88.89
8.49	30.0	Shear	kip	85.08	3.30	9.86	6.314	252.56
11.32	40.0	Flexure	kip-ft	304.65	57.22	93.25	1.923	76.92
11.32	40.0	Shear	kip	85.08	1.65	7.74	8.252	330.08
14.15	50.0	Flexure	kip-ft	304.65	59.54	93.59	1.892	75.69
14.15	50.0	Shear	kip	-85.08	-0.00	-6.08	10.765	430.60
16.98	60.0	Flexure	kip-ft	304.65	57.20	93.25	1.923	76.93
16.98	60.0	Shear	kip	-85.08	-1.65	-7.74	8.251	330.04
19.80	70.0	Flexure	kip-ft	304.65	50.19	83.72	2.223	88.91
19.80	70.0	Shear	kip	-85.08	-3.30	-9.86	6.313	252.53
22.63	80.0	Flexure	kip-ft	304.65	38.37	67.83	2.911	116.44
22.63	80.0	Shear	kip	-85.08	-5.12	-11.99	5.049	201.97
25.46	90.0	Flexure	kip-ft	291.74	21.57	39.92	5.102	204.07
25.46	90.0	Shear	kip	-89.88	-6.76	-14.11	4.438	177.53
26.81	94.8	Flexure	kip-ft	256.36	11.90	22.37	8.303	332.11
26.81	94.8	Shear	kip	-118.33	-7.55	-15.13	5.538	221.51
27.11	95.8	Shear	kip	-125.83	-7.72	-15.35	5.823	232.91
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	3960.00

Detailed Rating Results
17"x36" INT PSU - w/ Conc Repair + Post Tensioning
SU 2
Axle Load
Impact: With Impact
Lane: Single Lane

Span 1

							Legal	Legal
Location							Rating	Load Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj -LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	1683.00
1.17	4.1	Shear	kip	129.09	7.72	10.65	8.625	146.63

1.69	6.0	Flexure	kip-ft	243.32	13.52	17.56	9.917	168.59
1.69	6.0	Shear	kip	118.17	7.42	10.41	8.049	136.83
2.83	10.0	Flexure	kip-ft	284.36	21.61	27.92	7.091	120.54
2.83	10.0	Shear	kip	92.75	6.76	9.87	6.572	111.72
5.66	20.0	Flexure	kip-ft	304.65	38.40	48.27	4.090	69.54
5.66	20.0	Shear	kip	85.08	5.11	8.53	7.097	120.64
8.49	30.0	Flexure	kip-ft	304.65	50.23	61.05	3.047	51.81
8.49	30.0	Shear	kip	85.08	3.30	7.19	8.658	147.19
11.32	40.0	Flexure	kip-ft	304.65	57.22	66.26	2.706	46.01
11.32	40.0	Shear	kip	85.08	1.65	5.86	10.907	185.42
14.15	50.0	Flexure	kip-ft	304.65	59.54	63.91	2.771	47.11
14.15	50.0	Shear	kip	-85.08	-0.00	-4.52	14.485	246.24
16.98	60.0	Flexure	kip-ft	304.65	57.20	66.26	2.707	46.01
16.98	60.0	Shear	kip	-85.08	-1.65	-5.86	10.906	185.40
19.80	70.0	Flexure	kip-ft	304.65	50.19	61.05	3.048	51.82
19.80	70.0	Shear	kip	-85.08	-3.30	-7.19	8.657	147.18
22.63	80.0	Flexure	kip-ft	304.65	38.37	48.27	4.091	69.54
22.63	80.0	Shear	kip	-85.08	-5.12	-8.53	7.096	120.63
25.46	90.0	Flexure	kip-ft	291.74	21.57	27.92	7.296	124.03
25.46	90.0	Shear	kip	-89.88	-6.76	-9.87	6.347	107.90
26.81	94.8	Flexure	kip-ft	256.36	11.90	15.54	11.954	203.21
26.81	94.8	Shear	kip	-118.33	-7.55	-10.51	7.973	135.54
27.11	95.8	Shear	kip	-125.83	-7.72	-10.65	8.394	142.71
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	1683.00

Detailed Rating Results
17"x36" INT PSU - w/ Conc Repair + Post Tensioning
SU 3
Axle Load
Impact: With Impact
Lane: Single Lane

Span 1

							Legal	Legal
Location							Rating	Load Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj -LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	3267.00
1.17	4.1	Shear	kip	129.09	7.72	18.97	4.842	159.80
1.69	6.0	Flexure	kip-ft	243.32	13.52	31.22	5.579	184.12
1.69	6.0	Shear	kip	118.17	7.42	18.50	4.528	149.43
2.83	10.0	Flexure	kip-ft	284.36	21.61	49.37	4.009	132.31
2.83	10.0	Shear	kip	92.75	6.76	17.45	3.716	122.62

5.66	20.0	Flexure	kip-ft	304.65	38.40	84.06	2.349	77.51
5.66	20.0	Shear	kip	85.08	5.11	14.86	4.075	134.48
8.49	30.0	Flexure	kip-ft	304.65	50.23	104.05	1.788	59.01
8.49	30.0	Shear	kip	85.08	3.30	12.26	5.080	167.65
11.32	40.0	Flexure	kip-ft	304.65	57.22	116.56	1.538	50.77
11.32	40.0	Shear	kip	85.08	1.65	9.66	6.609	218.10
14.15	50.0	Flexure	kip-ft	304.65	59.54	118.00	1.501	49.53
14.15	50.0	Shear	kip	-85.08	-0.00	-7.38	8.869	292.67
16.98	60.0	Flexure	kip-ft	304.65	57.20	116.56	1.539	50.77
16.98	60.0	Shear	kip	-85.08	-1.65	-9.66	6.609	218.08
19.80	70.0	Flexure	kip-ft	304.65	50.19	104.05	1.788	59.02
19.80	70.0	Shear	kip	-85.08	-3.30	-12.26	5.080	167.63
22.63	80.0	Flexure	kip-ft	304.65	38.37	84.06	2.349	77.52
22.63	80.0	Shear	kip	-85.08	-5.12	-14.86	4.075	134.46
25.46	90.0	Flexure	kip-ft	291.74	21.57	49.37	4.125	136.14
25.46	90.0	Shear	kip	-89.88	-6.76	-17.45	3.589	118.44
26.81	94.8	Flexure	kip-ft	256.36	11.90	27.65	6.719	221.73
26.81	94.8	Shear	kip	-118.33	-7.55	-18.69	4.482	147.89
27.11	95.8	Shear	kip	-125.83	-7.72	-18.96	4.713	155.53
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	3267.00

Detailed Rating Results
17"x36" INT PSU - w/ Conc Repair + Post Tensioning
SU 4
Axle Load
Impact: With Impact
Lane: Single Lane

Span 1

							Legal	Legal
Location							Rating	Load Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj -LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	88.32	0.00	0.00	99.000	3465.00
1.17	4.1	Shear	kip	129.09	7.72	19.76	4.649	162.71
1.69	6.0	Flexure	kip-ft	243.32	13.52	32.50	5.359	187.56
1.69	6.0	Shear	kip	118.17	7.42	19.26	4.349	152.22
2.83	10.0	Flexure	kip-ft	284.36	21.61	51.35	3.855	134.94
2.83	10.0	Shear	kip	92.75	6.76	18.15	3.573	125.06
5.66	20.0	Flexure	kip-ft	304.65	38.40	87.11	2.266	79.32
5.66	20.0	Shear	kip	85.08	5.11	15.40	3.932	137.62
8.49	30.0	Flexure	kip-ft	304.65	50.23	111.07	1.675	58.63
8.49	30.0	Shear	kip	85.08	3.30	12.64	4.926	172.42

11.32	40.0	Flexure	kip-ft	304.65	57.22	127.15	1.410	49.36
11.32	40.0	Shear	kip	84.27	1.65	9.99	6.330	221.56
14.15	50.0	Flexure	kip-ft	304.65	59.54	127.65	1.387	48.56
14.15	50.0	Shear	kip	-85.08	-0.00	-7.78	8.408	294.29
16.98	60.0	Flexure	kip-ft	304.65	57.20	127.15	1.411	49.37
16.98	60.0	Shear	kip	-84.29	-1.65	-9.99	6.331	221.58
19.80	70.0	Flexure	kip-ft	304.65	50.19	111.07	1.675	58.64
19.80	70.0	Shear	kip	-85.08	-3.30	-12.64	4.926	172.40
22.63	80.0	Flexure	kip-ft	304.65	38.37	87.11	2.267	79.33
22.63	80.0	Shear	kip	-85.08	-5.12	-15.40	3.932	137.61
25.46	90.0	Flexure	kip-ft	291.74	21.57	51.35	3.967	138.84
25.46	90.0	Shear	kip	-89.88	-6.76	-18.15	3.451	120.79
26.81	94.8	Flexure	kip-ft	256.36	11.90	28.79	6.452	225.84
26.81	94.8	Shear	kip	-118.33	-7.55	-19.46	4.304	150.63
27.11	95.8	Shear	kip	-125.83	-7.72	-19.75	4.525	158.36
28.29	100.0	Flexure	kip-ft	86.22	0.00	0.00	99.000	3465.00

Note:

*Adj-LL is only applicable for Permit load rating.

Bridge Name: Matheson Hmck Bridge over Matheson Hammock Canal
NBI Structure ID: 874294D
Bridge ID: 874294D

Analyzed By: BrR
Analyze Date: Wednesday, October 06, 2021 10:33:34
Analysis Engine: AASHTO LRFR Engine Version 6.8.4.3002
Analysis Preference Setting: None

Report By: BrR
Report Date: Wednesday, October 06, 2021 10:41:31

Structure Definition Name: INT Span 2 - PS Conc PSU
Member Name: G10
Member Alternative Name: 17"x36" INT PSU - w/ Conc. Repair + Post Tensioning

Report by Action: ☒ Flexure ☒ Concrete Stresses ☒ Shear ☒ Critical

Detailed Rating Results
17"x36" INT PSU - w/ Conc. Repair + Post Tensioning
HL-93 (US)
Truck + Lane
Impact: With Impact
Lane: Single Lane

Span 2

							Inventory Rating	Inventory Load Rating	Operating Rating	Operating Load Rating
Location										
(ft)	Percent	Limit State	Units	Capacity	DL + Adj-LL*	LL	Factor	(Ton)	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	135.08	0.00	0.00	99.000	3564.00	99.000	3564.00
0.00	0.0	Concrete Stresses	ksi	0.86	-0.00	0.00	99.000	3564.00		
1.12	2.9	Shear	kip	94.16	10.73	20.86	2.212	79.64	2.868	103.23
1.12	2.9	Shear	kip	445.93	-5.24	67.36	6.698	241.12	9.343	336.35
1.48	3.8	Flexure	kip-ft	293.46	16.30	30.61	5.099	183.55	6.609	237.94
1.48	3.8	Shear	kip	89.01	10.52	20.57	2.107	75.84	2.731	98.32
1.48	3.8	Shear	kip	436.13	4.78	85.59	5.040	181.43	7.371	265.36
1.48	3.8	Concrete Stresses	ksi	1.77	0.12	0.23	9.193	330.96		
3.85	10.0	Flexure	kip-ft	344.64	39.61	73.09	2.307	83.06	2.991	107.68
3.85	10.0	Shear	kip	70.05	9.14	18.70	1.791	64.49	2.322	83.60
3.85	10.0	Shear	kip	424.83	54.28	180.89	2.049	73.75	2.753	99.11
3.85	10.0	Concrete Stresses	ksi	1.77	0.29	0.54	3.451	124.23		
7.70	20.0	Flexure	kip-ft	344.64	70.48	124.85	1.174	42.27	1.522	54.79
7.70	20.0	Shear	kip	44.94	6.90	15.71	1.321	47.56	2.897	104.28
7.70	20.0	Shear	kip	424.83	93.06	265.36	1.250	45.01	1.664	59.89
7.70	20.0	Concrete Stresses	ksi	1.77	0.52	0.92	1.711	61.60		
11.55	30.0	Flexure	kip-ft	344.64	92.34	156.13	0.839	30.20	1.087	39.15
11.55	30.0	Shear	kip	30.63	4.49	12.85	1.112	40.04	2.168	78.03
11.55	30.0	Shear	kip	424.83	120.65	313.56	0.970	34.92	1.283	46.19
11.55	30.0	Concrete Stresses	ksi	1.77	0.68	1.15	1.193	42.96		
15.40	40.0	Flexure		344.64	105.30	172.00	0.708	25.48	0.917	33.03

			kip-ft							
15.40	40.0	Shear	kip	26.59	2.24	10.26	1.325	47.69	2.415	86.93
15.40	40.0	Shear	kip	424.83	135.52	336.40	0.860	30.96	1.138	40.96
15.40	40.0	Concrete Stresses	ksi	1.77	0.77	1.26	0.989	35.61		
19.25	50.0	Flexure	kip-ft	344.64	109.62	171.21	0.693	24.95	0.898	32.34
19.25	50.0	Shear	kip	-26.93	0.00	-7.73	1.990	71.66	3.511	126.41
19.25	50.0	Shear	kip	424.83	137.84	329.53	0.871	31.35	1.120	40.33
19.25	50.0	Concrete Stresses	ksi	1.77	0.81	1.26	0.962	34.63		
23.10	60.0	Flexure	kip-ft	344.64	105.30	172.00	0.708	25.48	0.917	33.03
23.10	60.0	Shear	kip	-26.59	-2.24	-10.26	1.325	47.69	2.415	86.93
23.10	60.0	Shear	kip	424.83	135.52	336.40	0.860	30.96	1.138	40.96
23.10	60.0	Concrete Stresses	ksi	1.77	0.77	1.26	0.989	35.61		
26.95	70.0	Flexure	kip-ft	362.07	92.34	156.13	0.903	32.50	1.170	42.13
26.95	70.0	Shear	kip	-34.86	-4.49	-12.85	1.300	46.81	2.412	86.83
26.95	70.0	Shear	kip	441.60	118.83	312.68	1.032	37.16	1.367	49.23
26.95	70.0	Concrete Stresses	ksi	1.77	0.68	1.15	1.193	42.96		
30.80	80.0	Flexure	kip-ft	344.64	70.48	124.85	1.174	42.27	1.522	54.79
30.80	80.0	Shear	kip	-44.94	-6.90	-15.71	1.321	47.56	2.897	104.28
30.80	80.0	Shear	kip	424.83	93.06	265.36	1.250	45.01	1.664	59.89
30.80	80.0	Concrete Stresses	ksi	1.77	0.52	0.92	1.711	61.60		
34.65	90.0	Flexure	kip-ft	344.64	39.61	73.09	2.307	83.06	2.991	107.68
34.65	90.0	Shear	kip	-70.05	-9.14	-18.70	1.791	64.49	2.322	83.60
34.65	90.0	Shear	kip	424.83	54.28	180.89	2.049	73.75	2.753	99.11
34.65	90.0	Concrete Stresses	ksi	1.77	0.29	0.54	3.451	124.23		
37.02	96.2	Flexure	kip-ft	293.46	16.30	30.61	5.099	183.56	6.610	237.94
37.02	96.2	Shear	kip	-89.01	-10.52	-20.57	2.107	75.84	2.731	98.32
37.02	96.2	Shear	kip	436.13	4.78	85.59	5.040	181.43	7.371	265.36
37.02	96.2	Concrete Stresses	ksi	1.77	0.12	0.23	9.193	330.97		
37.38	97.1	Shear	kip	-94.28	-10.73	-20.86	2.215	79.73	2.871	103.36
37.38	97.1	Shear	kip	446.33	-5.46	66.97	6.747	242.88	9.399	338.38
38.50	100.0	Flexure	kip-ft	108.44	0.00	0.00	99.000	3564.00	99.000	3564.00
38.50	100.0	Concrete Stresses	ksi	0.86	0.00	0.00	99.000	3564.00		

Detailed Rating Results
17"x36" INT PSU - w/ Conc. Repair + Post Tensioning
HL-93 (US)
Tandem + Lane
Impact: With Impact
Lane: Single Lane

Span 2

							Inventory Rating	Inventory Load Rating	Operating Rating	Operating Load Rating
Location										
(ft)	Percent	Limit State	Units	Capacity	DL + Adj-LL*	LL	Factor	(Ton)	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	135.08	0.00	0.00	99.000	3564.00	99.000	3564.00
0.00	0.0	Concrete Stresses	ksi	0.86	-0.00	0.00	99.000	3564.00		
1.12	2.9	Shear	kip	94.16	10.73	18.64	2.475	89.11	3.209	115.51
1.12	2.9	Shear	kip	445.93	-3.06	57.34	7.831	281.92	10.728	386.19
1.48	3.8	Flexure	kip-ft	293.46	16.30	27.43	5.689	204.81	7.375	265.49
1.48	3.8	Shear	kip	89.01	10.52	18.43	2.352	84.68	3.049	109.77
1.48	3.8	Shear	kip	436.13	4.78	72.19	5.975	215.10	8.391	302.09
1.48	3.8	Concrete Stresses	ksi	1.77	0.12	0.20	10.258	369.29		
3.85	10.0	Flexure	kip-ft	344.64	39.61	66.60	2.532	91.16	3.282	118.17
3.85	10.0	Shear	kip	70.05	9.14	17.02	1.969	70.88	2.552	91.88
3.85	10.0	Shear	kip	424.83	54.28	162.82	2.276	81.93	3.071	110.55
3.85	10.0	Concrete Stresses	ksi	1.77	0.29	0.49	3.787	136.33		
7.70	20.0	Flexure	kip-ft	344.64	70.48	117.65	1.246	44.86	1.615	58.15
7.70	20.0	Shear	kip	49.78	6.90	14.77	1.592	57.31	3.080	110.88
7.70	20.0	Shear	kip	424.83	92.32	249.52	1.333	47.98	1.778	64.00
7.70	20.0	Concrete Stresses	ksi	1.77	0.52	0.86	1.816	65.37		
11.55	30.0	Flexure	kip-ft	344.64	92.34	153.13	0.855	30.79	1.109	39.92
11.55	30.0	Shear	kip	31.38	4.49	12.60	1.169	42.09	2.286	82.29
11.55	30.0	Shear	kip	424.83	120.44	307.44	0.990	35.64	1.311	47.21
11.55	30.0	Concrete Stresses	ksi	1.77	0.68	1.13	1.217	43.80		
15.40	40.0	Flexure	kip-ft	344.64	105.30	173.06	0.703	25.32	0.912	32.82
15.40	40.0	Shear	kip	26.38	2.24	10.48	1.285	46.27	2.342	84.31

15.40	40.0	Shear	kip	424.83	135.61	338.85	0.854	30.73	1.130	40.67
15.40	40.0	Concrete Stresses	ksi	1.77	0.77	1.27	0.983	35.39		
19.25	50.0	Flexure	kip-ft	344.64	109.62	177.43	0.669	24.07	0.867	31.20
19.25	50.0	Shear	kip	-25.78	0.00	-8.43	1.748	62.93	3.074	110.67
19.25	50.0	Shear	kip	424.83	138.07	342.40	0.838	30.15	1.082	38.96
19.25	50.0	Concrete Stresses	ksi	1.77	0.81	1.30	0.928	33.42		
23.10	60.0	Flexure	kip-ft	344.64	105.30	173.06	0.703	25.32	0.912	32.82
23.10	60.0	Shear	kip	-26.38	-2.24	-10.48	1.285	46.27	2.342	84.31
23.10	60.0	Shear	kip	424.83	135.61	338.85	0.854	30.73	1.130	40.67
23.10	60.0	Concrete Stresses	ksi	1.77	0.77	1.27	0.983	35.39		
26.95	70.0	Flexure	kip-ft	362.07	92.34	153.13	0.920	33.13	1.193	42.95
26.95	70.0	Shear	kip	-35.63	-4.49	-12.60	1.362	49.04	2.533	91.17
26.95	70.0	Shear	kip	441.60	118.62	306.50	1.054	37.94	1.398	50.31
26.95	70.0	Concrete Stresses	ksi	1.77	0.68	1.13	1.217	43.80		
30.80	80.0	Flexure	kip-ft	344.64	70.48	117.65	1.246	44.86	1.615	58.15
30.80	80.0	Shear	kip	-49.78	-6.90	-14.77	1.592	57.31	3.080	110.88
30.80	80.0	Shear	kip	424.83	92.32	249.52	1.333	47.98	1.778	64.00
30.80	80.0	Concrete Stresses	ksi	1.77	0.52	0.86	1.816	65.37		
34.65	90.0	Flexure	kip-ft	344.64	39.61	66.60	2.532	91.16	3.282	118.17
34.65	90.0	Shear	kip	-70.05	-9.14	-17.02	1.969	70.88	2.552	91.88
34.65	90.0	Shear	kip	424.83	54.28	162.82	2.276	81.93	3.071	110.55
34.65	90.0	Concrete Stresses	ksi	1.77	0.29	0.49	3.787	136.33		
37.02	96.2	Flexure	kip-ft	293.46	16.30	27.43	5.689	204.81	7.375	265.49
37.02	96.2	Shear	kip	-89.01	-10.52	-18.43	2.352	84.68	3.049	109.77
37.02	96.2	Shear	kip	436.13	4.78	72.19	5.975	215.10	8.391	302.09
37.02	96.2	Concrete Stresses	ksi	1.77	0.12	0.20	10.258	369.29		
37.38	97.1	Shear	kip	-94.28	-10.73	-18.65	2.478	89.22	3.212	115.65
37.38	97.1	Shear	kip	446.33	-3.18	57.07	7.877	283.57	10.795	388.61
38.50	100.0	Flexure	kip-ft	108.44	0.00	0.00	99.000	3564.00	99.000	3564.00
38.50	100.0	Concrete Stresses	ksi	0.86	0.00	0.00	99.000	3564.00		

Detailed Rating Results
17"x36" INT PSU - w/ Conc. Repair + Post Tensioning

C 3
Axle Load
Impact: With Impact
Lane: Single Lane

Span 2

							Legal	Legal
							Rating	Load
Location								Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj-LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	135.08	0.00	0.00	99.000	2772.00
1.12	2.9	Shear	kip	94.16	10.73	11.45	5.424	151.88
1.12	2.9	Shear	kip	445.93	14.71	18.70	23.057	645.59
1.48	3.8	Flexure	kip-ft	293.46	16.30	16.68	12.596	352.68
1.48	3.8	Shear	kip	89.01	10.52	11.27	5.175	144.91
1.48	3.8	Shear	kip	436.13	19.99	24.38	17.070	477.97
3.85	10.0	Flexure	kip-ft	344.64	39.61	38.88	5.839	163.49
3.85	10.0	Shear	kip	70.05	9.14	10.10	4.465	125.03
3.85	10.0	Shear	kip	424.83	54.28	58.80	6.302	176.46
7.70	20.0	Flexure	kip-ft	344.64	70.48	63.23	3.121	87.39
7.70	20.0	Shear	kip	70.05	6.90	8.21	5.755	161.13
7.70	20.0	Shear	kip	424.83	92.25	90.04	3.694	103.43
11.55	30.0	Flexure	kip-ft	344.64	92.34	81.45	2.165	60.61
11.55	30.0	Shear	kip	70.05	4.49	7.05	7.029	196.82
11.55	30.0	Shear	kip	424.83	119.98	116.90	2.608	73.02
15.40	40.0	Flexure	kip-ft	344.64	105.30	91.86	1.784	49.94
15.40	40.0	Shear	kip	70.05	2.24	5.89	8.778	245.79
15.40	40.0	Shear	kip	424.83	136.02	132.69	2.176	60.94
19.25	50.0	Flexure	kip-ft	344.64	109.62	91.12	1.753	49.08
19.25	50.0	Shear	kip	70.05	0.00	4.73	11.384	318.75
19.25	50.0	Shear	kip	424.83	140.50	132.96	2.139	59.88
23.10	60.0	Flexure	kip-ft	344.64	105.30	91.86	1.784	49.94
23.10	60.0	Shear	kip	-70.05	-2.24	-5.89	8.778	245.79
23.10	60.0	Shear	kip	424.83	136.02	132.69	2.177	60.94
26.95	70.0	Flexure	kip-ft	362.07	92.34	81.45	2.329	65.22
26.95	70.0	Shear	kip	-70.42	-4.49	-7.05	7.069	197.94
26.95	70.0	Shear	kip	441.60	119.34	116.31	2.771	77.58
30.80	80.0	Flexure	kip-ft	344.64	70.48	63.23	3.121	87.39
30.80	80.0	Shear	kip	-70.05	-6.90	-8.21	5.755	161.13
30.80	80.0	Shear	kip	424.83	92.25	90.04	3.694	103.43
34.65	90.0	Flexure	kip-ft	344.64	39.61	38.88	5.839	163.49
34.65	90.0	Shear	kip	-70.05	-9.14	-10.10	4.465	125.03
34.65	90.0	Shear	kip	424.83	54.28	58.80	6.302	176.46

37.02	96.2	Flexure	kip-ft	293.46	16.30	16.68	12.596	352.68
37.02	96.2	Shear	kip	-89.01	-10.52	-11.27	5.175	144.91
37.02	96.2	Shear	kip	436.13	19.99	24.38	17.071	477.98
37.38	97.1	Shear	kip	-94.28	-10.73	-11.45	5.430	152.05
37.38	97.1	Shear	kip	446.33	14.60	18.58	23.237	650.64
38.50	100.0	Flexure	kip-ft	108.44	0.00	0.00	99.000	2772.00

Detailed Rating Results
17"x36" INT PSU - w/ Conc. Repair + Post Tensioning
C 4
Axle Load
Impact: With Impact
Lane: Single Lane

Span 2

							Legal	Legal
							Rating	Load
Location								Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj-LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	135.08	0.00	0.00	99.000	3628.35
1.12	2.9	Shear	kip	94.16	10.73	16.06	3.868	141.77
1.12	2.9	Shear	kip	445.93	8.71	31.65	13.814	506.27
1.48	3.8	Flexure	kip-ft	293.46	16.30	23.41	8.973	328.87
1.48	3.8	Shear	kip	89.01	10.52	15.83	3.687	135.12
1.48	3.8	Shear	kip	436.13	14.06	39.54	10.674	391.20
3.85	10.0	Flexure	kip-ft	344.64	39.61	55.34	4.102	150.34
3.85	10.0	Shear	kip	70.05	9.14	14.37	3.137	114.97
3.85	10.0	Shear	kip	424.83	54.28	92.85	3.991	146.27
7.70	20.0	Flexure	kip-ft	344.64	70.48	93.36	2.114	77.47
7.70	20.0	Shear	kip	70.05	6.90	12.12	3.897	142.84
7.70	20.0	Shear	kip	424.83	89.96	139.88	2.394	87.74
11.55	30.0	Flexure	kip-ft	344.64	92.34	114.05	1.546	56.66
11.55	30.0	Shear	kip	70.05	4.49	9.87	5.020	183.98
11.55	30.0	Shear	kip	424.83	116.31	165.94	1.859	68.14
15.40	40.0	Flexure	kip-ft	344.64	105.30	126.11	1.299	47.62
15.40	40.0	Shear	kip	59.28	2.24	8.19	5.304	194.41
15.40	40.0	Shear	kip	424.83	133.38	182.99	1.593	58.37
19.25	50.0	Flexure	kip-ft	344.64	109.62	128.76	1.240	45.46
19.25	50.0	Shear	kip	-57.11	0.00	-6.69	6.568	240.71
19.25	50.0	Shear	kip	424.83	138.44	187.41	1.528	56.01
23.10	60.0	Flexure	kip-ft	344.64	105.30	126.11	1.299	47.62
23.10	60.0	Shear	kip	-59.28	-2.24	-8.19	5.304	194.41
23.10	60.0	Shear	kip	424.83	133.38	182.99	1.593	58.37

26.95	70.0	Flexure	kip-ft	362.07	92.34	114.05	1.664	60.97
26.95	70.0	Shear	kip	-70.42	-4.49	-9.87	5.049	185.03
26.95	70.0	Shear	kip	441.60	115.66	165.11	1.974	72.35
30.80	80.0	Flexure	kip-ft	344.64	70.48	93.36	2.114	77.47
30.80	80.0	Shear	kip	-70.05	-6.90	-12.12	3.897	142.84
30.80	80.0	Shear	kip	424.83	89.96	139.88	2.394	87.74
34.65	90.0	Flexure	kip-ft	344.64	39.61	55.34	4.102	150.34
34.65	90.0	Shear	kip	-70.05	-9.14	-14.37	3.137	114.97
34.65	90.0	Shear	kip	424.83	54.28	92.85	3.991	146.27
37.02	96.2	Flexure	kip-ft	293.46	16.30	23.41	8.973	328.87
37.02	96.2	Shear	kip	-89.01	-10.52	-15.83	3.687	135.12
37.02	96.2	Shear	kip	436.13	14.06	39.54	10.674	391.21
37.38	97.1	Shear	kip	-94.28	-10.73	-16.06	3.873	141.93
37.38	97.1	Shear	kip	446.33	8.60	31.48	13.905	509.61
38.50	100.0	Flexure	kip-ft	108.44	0.00	0.00	99.000	3628.35

Detailed Rating Results
17"x36" INT PSU - w/ Conc. Repair + Post Tensioning
C 5

Axle Load
Impact: With Impact
Lane: Single Lane

Span 2

							Legal	Legal
Location							Rating	Load Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj-LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	135.08	0.00	0.00	99.000	3960.00
1.12	2.9	Shear	kip	94.16	10.73	16.08	3.863	154.53
1.12	2.9	Shear	kip	445.93	8.69	31.72	13.785	551.38
1.48	3.8	Flexure	kip-ft	293.46	16.30	23.46	8.956	358.24
1.48	3.8	Shear	kip	89.01	10.52	15.86	3.680	147.19
1.48	3.8	Shear	kip	436.13	14.02	39.64	10.648	425.91
3.85	10.0	Flexure	kip-ft	344.64	39.61	55.39	4.099	163.94
3.85	10.0	Shear	kip	70.05	9.14	14.39	3.134	125.37
3.85	10.0	Shear	kip	424.83	54.28	92.95	3.987	159.47
7.70	20.0	Flexure	kip-ft	344.64	70.48	92.41	2.136	85.42
7.70	20.0	Shear	kip	70.05	6.90	12.00	3.938	157.50
7.70	20.0	Shear	kip	424.83	89.96	138.23	2.423	96.90
11.55	30.0	Flexure	kip-ft	344.64	92.34	114.81	1.536	61.43
11.55	30.0	Shear	kip	70.05	4.49	9.94	4.987	199.46
11.55	30.0	Shear	kip	424.83	116.22	167.09	1.847	73.88

15.40	40.0	Flexure	kip-ft	344.64	105.30	128.28	1.277	51.09
15.40	40.0	Shear	kip	57.66	2.24	8.24	5.123	204.94
15.40	40.0	Shear	kip	424.83	133.39	186.01	1.567	62.67
19.25	50.0	Flexure	kip-ft	344.64	109.62	132.83	1.202	48.09
19.25	50.0	Shear	kip	-54.70	0.00	-6.32	6.658	266.30
19.25	50.0	Shear	kip	424.83	139.00	192.50	1.485	59.39
23.10	60.0	Flexure	kip-ft	344.64	105.30	128.28	1.277	51.09
23.10	60.0	Shear	kip	-57.66	-2.24	-8.24	5.123	204.94
23.10	60.0	Shear	kip	424.83	133.39	186.01	1.567	62.67
26.95	70.0	Flexure	kip-ft	362.07	92.34	114.81	1.652	66.10
26.95	70.0	Shear	kip	-70.42	-4.49	-9.94	5.015	200.60
26.95	70.0	Shear	kip	441.60	115.57	166.25	1.961	78.44
30.80	80.0	Flexure	kip-ft	344.64	70.48	92.41	2.136	85.42
30.80	80.0	Shear	kip	-70.05	-6.90	-12.00	3.938	157.50
30.80	80.0	Shear	kip	424.83	89.96	138.23	2.423	96.90
34.65	90.0	Flexure	kip-ft	344.64	39.61	55.39	4.099	163.94
34.65	90.0	Shear	kip	-70.05	-9.14	-14.39	3.134	125.37
34.65	90.0	Shear	kip	424.83	54.28	92.95	3.987	159.47
37.02	96.2	Flexure	kip-ft	293.46	16.30	23.46	8.956	358.24
37.02	96.2	Shear	kip	-89.01	-10.52	-15.86	3.680	147.19
37.02	96.2	Shear	kip	436.13	14.02	39.64	10.648	425.91
37.38	97.1	Shear	kip	-94.28	-10.73	-16.08	3.868	154.72
37.38	97.1	Shear	kip	446.33	8.57	31.55	13.876	555.03
38.50	100.0	Flexure	kip-ft	108.44	0.00	0.00	99.000	3960.00

Detailed Rating Results
17"x36" INT PSU - w/ Conc. Repair + Post Tensioning
FL120 Span < 200ft
Axle Load
Impact: With Impact
Lane: Single Lane

Span 2

							Permit	Permit
Location							Rating	Load
(ft)	Percent	Limit	Units	Capacity	DL + Adj- LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	135.08	0.00	0.00	99.000	5940.00
1.12	2.9	Shear	kip	445.93	0.11	50.24	8.873	532.40
1.48	3.8	Flexure	kip-ft	293.46	16.30	35.85	6.347	380.83
1.48	3.8	Shear	kip	436.13	5.52	61.36	7.018	421.08
3.85	10.0	Flexure	kip-ft	344.64	39.61	85.33	2.882	172.94
3.85	10.0	Shear	kip	424.83	54.28	141.29	2.623	157.36

7.70	20.0	Flexure	kip-ft	344.64	70.48	144.69	1.478	88.65
7.70	20.0	Shear	kip	424.83	89.96	209.42	1.599	95.94
11.55	30.0	Flexure	kip-ft	344.64	92.34	179.27	1.065	63.93
11.55	30.0	Shear	kip	424.83	117.79	246.37	1.246	74.78
15.40	40.0	Flexure	kip-ft	344.64	105.30	196.07	0.905	54.32
15.40	40.0	Shear	kip	424.83	132.33	262.21	1.116	66.93
19.25	50.0	Flexure	kip-ft	344.64	109.62	193.35	0.895	53.69
19.25	50.0	Shear	kip	424.83	137.71	257.32	1.116	66.95
23.10	60.0	Flexure	kip-ft	344.64	105.30	196.07	0.905	54.32
23.10	60.0	Shear	kip	424.83	132.33	262.21	1.116	66.93
26.95	70.0	Flexure	kip-ft	362.07	92.34	179.27	1.146	68.79
26.95	70.0	Shear	kip	441.60	116.18	245.09	1.328	79.67
30.80	80.0	Flexure	kip-ft	344.64	70.48	144.69	1.478	88.65
30.80	80.0	Shear	kip	424.83	89.96	209.42	1.599	95.94
34.65	90.0	Flexure	kip-ft	344.64	39.61	85.33	2.882	172.94
34.65	90.0	Shear	kip	424.83	54.28	141.29	2.623	157.36
37.02	96.2	Flexure	kip-ft	293.46	16.30	35.85	6.347	380.83
37.02	96.2	Shear	kip	436.13	5.52	61.36	7.018	421.09
37.38	97.1	Shear	kip	446.33	-0.01	50.00	8.926	535.58
38.50	100.0	Flexure	kip-ft	108.44	0.00	0.00	99.000	5940.00

Detailed Rating Results
17"x36" INT PSU - w/ Conc. Repair + Post Tensioning
ST 5
Axle Load
Impact: With Impact
Lane: Single Lane

Span 2

							Legal	Legal
Location							Rating	Load Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj-LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	135.08	0.00	0.00	99.000	3960.00
1.12	2.9	Shear	kip	94.16	10.73	14.69	4.229	169.18
1.12	2.9	Shear	kip	445.93	10.50	27.85	15.637	625.49
1.48	3.8	Flexure	kip-ft	293.46	16.30	21.47	9.784	391.34
1.48	3.8	Shear	kip	89.01	10.52	14.52	4.020	160.79
1.48	3.8	Shear	kip	436.13	15.76	35.17	11.951	478.03
3.85	10.0	Flexure	kip-ft	344.64	39.61	51.52	4.406	176.26
3.85	10.0	Shear	kip	70.05	9.14	13.38	3.370	134.79
3.85	10.0	Shear	kip	424.83	54.28	84.94	4.363	174.50
7.70	20.0	Flexure	kip-ft	344.64	70.48	88.86	2.221	88.83

7.70	20.0	Shear	kip	70.05	6.90	11.54	4.094	163.78
7.70	20.0	Shear	kip	424.83	89.96	132.11	2.535	101.39
11.55	30.0	Flexure	kip-ft	344.64	92.34	112.03	1.574	62.95
11.55	30.0	Shear	kip	70.05	4.49	9.70	5.110	204.41
11.55	30.0	Shear	kip	424.83	116.53	162.91	1.893	75.70
15.40	40.0	Flexure	kip-ft	344.64	105.30	125.93	1.301	52.05
15.40	40.0	Shear	kip	59.67	2.24	7.86	5.566	222.66
15.40	40.0	Shear	kip	424.83	133.78	182.35	1.596	63.85
19.25	50.0	Flexure	kip-ft	344.64	109.62	128.11	1.247	49.86
19.25	50.0	Shear	kip	-58.06	0.00	-6.02	7.422	296.87
19.25	50.0	Shear	kip	424.83	139.22	185.71	1.538	61.52
23.10	60.0	Flexure	kip-ft	344.64	105.30	125.93	1.301	52.05
23.10	60.0	Shear	kip	-59.67	-2.24	-7.86	5.566	222.66
23.10	60.0	Shear	kip	424.83	133.78	182.35	1.596	63.85
26.95	70.0	Flexure	kip-ft	362.07	92.34	112.03	1.694	67.74
26.95	70.0	Shear	kip	-70.42	-4.49	-9.70	5.140	205.58
26.95	70.0	Shear	kip	441.60	115.89	162.09	2.009	80.38
30.80	80.0	Flexure	kip-ft	344.64	70.48	88.86	2.221	88.83
30.80	80.0	Shear	kip	-70.05	-6.90	-11.54	4.094	163.78
30.80	80.0	Shear	kip	424.83	89.96	132.11	2.535	101.39
34.65	90.0	Flexure	kip-ft	344.64	39.61	51.52	4.406	176.26
34.65	90.0	Shear	kip	-70.05	-9.14	-13.38	3.370	134.79
34.65	90.0	Shear	kip	424.83	54.28	84.94	4.363	174.50
37.02	96.2	Flexure	kip-ft	293.46	16.30	21.47	9.784	391.35
37.02	96.2	Shear	kip	-89.01	-10.52	-14.52	4.020	160.79
37.02	96.2	Shear	kip	436.13	15.76	35.17	11.951	478.03
37.38	97.1	Shear	kip	-94.28	-10.73	-14.69	4.235	169.38
37.38	97.1	Shear	kip	446.33	10.39	27.69	15.745	629.81
38.50	100.0	Flexure	kip-ft	108.44	0.00	0.00	99.000	3960.00

Detailed Rating Results
17"x36" INT PSU - w/ Conc. Repair + Post Tensioning
SU 2
Axle Load
Impact: With Impact
Lane: Single Lane

Span 2

							Legal	Legal
Location							Rating	Load Rating
(ft)	Percent	Limit State	Units	Capacity	DL + Adj-LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	135.08	0.00	0.00	99.000	1683.00

1.12	2.9	Shear	kip	94.16	10.73	9.87	6.291	106.96
1.12	2.9	Shear	kip	445.93	16.77	14.32	29.967	509.43
1.48	3.8	Flexure	kip-ft	293.46	16.30	14.44	14.543	247.23
1.48	3.8	Shear	kip	89.01	10.52	9.77	5.975	101.58
1.48	3.8	Shear	kip	436.13	21.95	19.35	21.406	363.90
3.85	10.0	Flexure	kip-ft	344.64	39.61	34.85	6.515	110.75
3.85	10.0	Shear	kip	70.05	9.14	9.05	4.982	84.70
3.85	10.0	Shear	kip	424.83	54.28	50.46	7.344	124.85
7.70	20.0	Flexure	kip-ft	344.64	70.48	60.77	3.247	55.20
7.70	20.0	Shear	kip	70.05	6.90	7.89	5.987	101.78
7.70	20.0	Shear	kip	424.83	92.66	86.20	3.853	65.51
11.55	30.0	Flexure	kip-ft	344.64	92.34	77.77	2.267	38.54
11.55	30.0	Shear	kip	70.05	4.49	6.73	7.362	125.15
11.55	30.0	Shear	kip	424.83	120.40	111.36	2.734	46.47
15.40	40.0	Flexure	kip-ft	344.64	105.30	85.84	1.909	32.45
15.40	40.0	Shear	kip	70.05	2.24	5.57	9.280	157.76
15.40	40.0	Shear	kip	424.83	136.44	123.89	2.328	39.57
19.25	50.0	Flexure	kip-ft	344.64	109.62	84.98	1.879	31.95
19.25	50.0	Shear	kip	70.05	0.00	4.41	12.206	207.50
19.25	50.0	Shear	kip	424.83	140.92	124.00	2.290	38.92
23.10	60.0	Flexure	kip-ft	344.64	105.30	85.84	1.909	32.45
23.10	60.0	Shear	kip	-70.05	-2.24	-5.57	9.280	157.76
23.10	60.0	Shear	kip	424.83	136.44	123.89	2.328	39.57
26.95	70.0	Flexure	kip-ft	362.07	92.34	77.77	2.440	41.47
26.95	70.0	Shear	kip	-70.42	-4.49	-6.73	7.404	125.87
26.95	70.0	Shear	kip	441.60	119.75	110.79	2.905	49.38
30.80	80.0	Flexure	kip-ft	344.64	70.48	60.77	3.247	55.20
30.80	80.0	Shear	kip	-70.05	-6.90	-7.89	5.987	101.78
30.80	80.0	Shear	kip	424.83	92.66	86.20	3.853	65.51
34.65	90.0	Flexure	kip-ft	344.64	39.61	34.85	6.515	110.75
34.65	90.0	Shear	kip	-70.05	-9.14	-9.05	4.982	84.69
34.65	90.0	Shear	kip	424.83	54.28	50.46	7.344	124.85
37.02	96.2	Flexure	kip-ft	293.46	16.30	14.44	14.543	247.23
37.02	96.2	Shear	kip	-89.01	-10.52	-9.77	5.975	101.58
37.02	96.2	Shear	kip	436.13	21.95	19.35	21.406	363.90
37.38	97.1	Shear	kip	-94.28	-10.73	-9.87	6.299	107.09
37.38	97.1	Shear	kip	446.33	16.66	14.21	30.232	513.94
38.50	100.0	Flexure	kip-ft	108.44	0.00	0.00	99.000	1683.00

Detailed Rating Results
17"x36" INT PSU - w/ Conc. Repair + Post Tensioning
SU 3
Axle Load
Impact: With Impact

Lane: Single Lane

Span 2

							Legal Rating	Legal Load Rating
Location								
(ft)	Percent	Limit State	Units	Capacity	DL + Adj- LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	135.08	0.00	0.00	99.000	3267.00
1.12	2.9	Shear	kip	94.16	10.73	18.08	3.436	113.37
1.12	2.9	Shear	kip	445.93	6.08	37.39	11.765	388.24
1.48	3.8	Flexure	kip-ft	293.46	16.30	26.43	7.947	262.24
1.48	3.8	Shear	kip	89.01	10.52	17.87	3.265	107.75
1.48	3.8	Shear	kip	436.13	11.39	46.35	9.163	302.38
3.85	10.0	Flexure	kip-ft	344.64	39.61	63.47	3.577	118.04
3.85	10.0	Shear	kip	70.05	9.14	16.49	2.735	90.27
3.85	10.0	Shear	kip	424.83	54.28	109.65	3.379	111.52
7.70	20.0	Flexure	kip-ft	344.64	70.48	109.61	1.800	59.41
7.70	20.0	Shear	kip	70.05	6.90	14.24	3.319	109.54
7.70	20.0	Shear	kip	424.83	89.96	168.00	1.993	65.78
11.55	30.0	Flexure	kip-ft	344.64	92.34	138.43	1.274	42.03
11.55	30.0	Shear	kip	55.12	4.49	11.98	3.177	104.85
11.55	30.0	Shear	kip	424.83	115.19	202.93	1.526	50.35
15.40	40.0	Flexure	kip-ft	344.64	105.30	156.17	1.049	34.63
15.40	40.0	Shear	kip	43.05	2.24	9.73	3.180	104.94
15.40	40.0	Shear	kip	424.83	132.50	225.69	1.295	42.74
19.25	50.0	Flexure	kip-ft	344.64	109.62	159.70	1.000	33.00
19.25	50.0	Shear	kip	-41.98	0.00	-7.48	4.315	142.38
19.25	50.0	Shear	kip	424.83	138.48	230.42	1.243	41.01
23.10	60.0	Flexure	kip-ft	344.64	105.30	156.17	1.049	34.63
23.10	60.0	Shear	kip	-43.05	-2.24	-9.73	3.180	104.94
23.10	60.0	Shear	kip	424.83	132.50	225.69	1.295	42.74
26.95	70.0	Flexure	kip-ft	362.07	92.34	138.43	1.371	45.23
26.95	70.0	Shear	kip	-58.59	-4.49	-11.98	3.401	112.22
26.95	70.0	Shear	kip	441.60	113.94	201.66	1.625	53.62
30.80	80.0	Flexure	kip-ft	344.64	70.48	109.61	1.800	59.41
30.80	80.0	Shear	kip	-70.05	-6.90	-14.24	3.319	109.54
30.80	80.0	Shear	kip	424.83	89.96	168.00	1.993	65.78
34.65	90.0	Flexure	kip-ft	344.64	39.61	63.47	3.577	118.04
34.65	90.0	Shear	kip	-70.05	-9.14	-16.49	2.735	90.27
34.65	90.0	Shear	kip	424.83	54.28	109.65	3.379	111.52
37.02	96.2	Flexure	kip-ft	293.46	16.30	26.43	7.947	262.24
37.02	96.2	Shear	kip	-89.01	-10.52	-17.87	3.265	107.75
37.02	96.2	Shear	kip	436.13	11.39	46.35	9.163	302.38

37.38	97.1	Shear	kip	-94.28	-10.73	-18.08	3.440	113.51
37.38	97.1	Shear	kip	446.33	5.96	37.19	11.840	390.72
38.50	100.0	Flexure	kip-ft	108.44	0.00	0.00	99.000	3267.00

Detailed Rating Results
17"x36" INT PSU - w/ Conc. Repair + Post Tensioning
SU 4
Axle Load
Impact: With Impact
Lane: Single Lane

Span 2

							Legal	Legal
							Rating	Load
Location								Rating
(ft)	Percent	Limit	Units	Capacity	DL + Adj- LL*	LL	Factor	(Ton)
0.00	0.0	Flexure	kip-ft	135.08	0.00	0.00	99.000	3465.00
1.12	2.9	Shear	kip	94.16	10.73	18.94	3.279	114.75
1.12	2.9	Shear	kip	445.93	4.95	39.82	11.074	387.60
1.48	3.8	Flexure	kip-ft	293.46	16.30	27.70	7.584	265.45
1.48	3.8	Shear	kip	89.01	10.52	18.72	3.116	109.07
1.48	3.8	Shear	kip	436.13	10.28	49.20	8.656	302.96
3.85	10.0	Flexure	kip-ft	344.64	39.61	66.43	3.417	119.61
3.85	10.0	Shear	kip	70.05	9.14	17.26	2.613	91.47
3.85	10.0	Shear	kip	424.83	54.28	115.78	3.200	112.02
7.70	20.0	Flexure	kip-ft	344.64	70.48	114.49	1.724	60.33
7.70	20.0	Shear	kip	70.05	6.90	14.87	3.178	111.23
7.70	20.0	Shear	kip	424.83	89.96	176.43	1.898	66.43
11.55	30.0	Flexure	kip-ft	344.64	92.34	147.43	1.196	41.86
11.55	30.0	Shear	kip	49.78	4.49	12.48	2.722	95.28
11.55	30.0	Shear	kip	424.83	116.12	216.90	1.423	49.81
15.40	40.0	Flexure	kip-ft	344.64	105.30	168.68	0.971	34.00
15.40	40.0	Shear	kip	38.99	2.24	10.10	2.757	96.49
15.40	40.0	Shear	kip	424.83	132.50	243.11	1.202	42.09
19.25	50.0	Flexure	kip-ft	344.64	109.62	171.55	0.931	32.58
19.25	50.0	Shear	kip	-38.35	0.00	-7.71	3.827	133.94
19.25	50.0	Shear	kip	424.83	138.59	246.79	1.160	40.60
23.10	60.0	Flexure	kip-ft	344.64	105.30	168.68	0.971	34.00
23.10	60.0	Shear	kip	-38.99	-2.24	-10.10	2.757	96.49
23.10	60.0	Shear	kip	424.83	132.50	243.11	1.202	42.09
26.95	70.0	Flexure	kip-ft	362.07	92.34	147.43	1.287	45.04
26.95	70.0	Shear	kip	-53.70	-4.49	-12.48	2.964	103.73
26.95	70.0	Shear	kip	441.60	114.73	215.57	1.516	53.07

30.80	80.0	Flexure	kip-ft	344.64	70.48	114.49	1.724	60.33
30.80	80.0	Shear	kip	-70.05	-6.90	-14.87	3.178	111.23
30.80	80.0	Shear	kip	424.83	89.96	176.43	1.898	66.43
34.65	90.0	Flexure	kip-ft	344.64	39.61	66.43	3.417	119.61
34.65	90.0	Shear	kip	-70.05	-9.14	-17.26	2.613	91.47
34.65	90.0	Shear	kip	424.83	54.28	115.78	3.200	112.02
37.02	96.2	Flexure	kip-ft	293.46	16.30	27.70	7.584	265.45
37.02	96.2	Shear	kip	-89.01	-10.52	-18.72	3.116	109.07
37.02	96.2	Shear	kip	436.13	10.28	49.20	8.656	302.96
37.38	97.1	Shear	kip	-94.28	-10.73	-18.95	3.283	114.89
37.38	97.1	Shear	kip	446.33	4.83	39.62	11.144	390.04
38.50	100.0	Flexure	kip-ft	108.44	0.00	0.00	99.000	3465.00

Note:

*Adj-LL is only applicable for Permit load rating.



Project #: D210107FL00.00
Designed By: YRA
Design Date: Nov-21
Checked By: MP
Check Date: Nov-21

Matheson Hmk Road over Matheson Hammock Canal
SUMMARY OF DEAD LOAD MOMENT & SHEAR REACTIONS (SPAN 2)

DEAD LOAD MOMENT REACTIONS FROM AASHTOWARE BrR (SPAN 2)								
	Self Weight (Slab Unit) (KIP-FT)	% of DC Slab Unit (KIP-FT)	Self Weight (Interior diagrams) (KIP-FT)	DC - Railing (KIP-FT)	DC - Curb/ Sidewalk (KIP-FT)	Total DC Selfweight of Slab Unit alone (per Slab Unit) (KIP-FT)	Total DC (Railing + Sidewalk) per Slab Unit (KIP-FT)	Total DC per Slab Unit (KIP-FT)
Location	0	0	0	0	0	0	0	0.00
1.48	12.5	0.1	0.3	0.7	2.6	12.9	3.3	16.20
3.85	30.5	0.3	0.7	1.8	6.3	31.5	8.1	39.60
7.7	54.2	0.5	1.4	3.2	11.2	56.1	14.4	70.50
11.55	71.1	0.7	1.6	4.2	14.7	73.4	18.9	92.30
15.4	81.3	0.8	1.6	4.8	16.8	83.7	21.6	105.30
19.25	84.7	0.8	1.6	5	17.5	87.1	22.5	109.60
23.1	81.3	0.8	1.6	4.8	16.8	83.7	21.6	105.30
26.95	71.1	0.7	1.6	4.2	14.7	73.4	18.9	92.30
30.8	54.2	0.5	1.4	3.2	11.2	56.1	14.4	70.50
34.65	30.5	0.3	0.7	1.8	6.3	31.5	8.1	39.60
37.02	12.5	0.1	0.3	0.7	2.6	12.9	3.3	16.20
38.5	0	0	0	0	0	0	0	0.00

** Existing condition assumes the removal of 7 strands, and 1 exterior stirrup leg to account for the controlling deterioration along the bottom face of the slab units.



Project #: D210107FL00.00
Designed By: YRA
Design Date: Nov-21
Checked By: MP
Check Date: Nov-21

Matheson Hmk Road over Matheson Hammock Canal
SUMMARY OF DEAD LOAD MOMENT & SHEAR REACTIONS (SPAN 2)

DEAD LOAD SHEAR REACTIONS FROM AASHTOWARE BrR (SPAN 2)								
	Self Weight (Slab Unit) (KIP)	% of DC Slab Unitx (KIP)	Self Weight (Interior diagrams) (KIP)	DC - Railing (KIP)	DC - Curb/ Sidewalk (KIP)	Total DC Selfweight of Slab Unit alone (per Slab Unit) (KIP)	Total DC (Railing + Sidewalk) per Slab Unit (KIP)	Total DC per Slab Unit (KIP)
Location								
0	8.8	0.09	0.49	0.52	1.82	9.38	2.34	11.72
1.48	8.12	0.08	0.16	0.48	1.68	8.36	2.16	10.52
3.85	7.04	0.07	0.16	0.41	1.45	7.27	1.86	9.13
7.7	5.28	0.05	0.16	0.31	1.09	5.49	1.4	6.89
11.55	3.52	0.04	0	0.21	0.73	3.56	0.94	4.50
15.4	1.76	0.02	0	0.1	0.36	1.78	0.46	2.24
19.25	0	0	0	0	0	0	0	0.00
23.1	-1.76	-0.02	0	-0.1	-0.36	-1.78	-0.46	-2.24
26.95	-3.52	-0.04	0	-0.21	-0.73	-3.56	-0.94	-4.50
30.8	-5.28	-0.05	-0.16	-0.31	-1.09	-5.49	-1.4	-6.89
34.65	-7.04	-0.07	-0.16	-0.41	-1.45	-7.27	-1.86	-9.13
37.02	-8.12	-0.08	-0.16	-0.48	-1.68	-8.36	-2.16	-10.52
38.5	-8.8	-0.09	-0.49	-0.52	-1.82	-9.38	-2.34	-11.72

** Existing condition assumes the removal of 7 strands, and 1 exterior stirrup leg to account for the controlling deterioration along the bottom face of the slab units.



Project #: D210107FL00.00
 Designed By: YRA
 Design Date: Nov-21
 Checked By: MP
 Check Date: Nov-21

Matheson Hmk Road over Matheson Hammock Canal
 SUMMARY OF DESIGN CAPACITY

LOAD RATING SUMMARY - CONTROLLING LEGAL LOAD (Assuming Post Tensioning)									
Span 2 - INTERIOR PSU-8 (LRFR) - SU4									
Location	Condition Factor	Unfactored DL (kip-ft)	Unfactored SU4 Truck LL (kip-ft)	Operating Rating Factor	Existing Flexural Capacity (kip-ft) **	Existing Shear Capacity (kip) **	Required Flexural Capacity (kip-ft) *	Required Shear Capacity (kip) *	
0.00	0.90	0	0	99	135.08	-	-	-	
1.12		-	-	-	-	94.16	-	-	
1.48		16.30	27.70	7.58	293.46	89.01	-	-	
3.85		39.61	66.43	3.42	344.64	70.05	-	-	
7.7		70.48	114.49	1.72	344.64	70.05	-	-	
11.55		92.34	147.43	1.20	344.64	49.78	-	-	
15.4		105.30	168.68	0.97	344.64	38.99	359.34	-	
19.25		109.62	171.55	0.93	344.64	-38.35	368.62	-	
23.1		105.30	168.68	0.97	344.64	-38.99	359.34	-	
26.95		92.34	147.43	1.29	344.64	-53.70	-	-	
30.8		70.48	114.49	1.72	344.64	-70.05	-	-	
34.65		39.61	66.43	3.42	344.64	-70.05	-	-	
37.02		16.30	27.70	7.58	293.46	-89.01	-	-	
37.39		-	-	-	-	-94.28	-	-	
38.5		0.00	0.00	99.00	108.44	-	-	-	

* Minimum Required capacity to meet a minimum Inventory Rating Factor of 1.1, conservatively.

** Existing condition assumes the removal of 7 strands, and 1 exterior stirrup leg to account for the controlling deterioration along the bottom face of the slab units.



Project #: D210107FL00.00
Designed By: YRA
Design Date: Nov-21
Checked By: MP
Check Date: Nov-21

Matheson Hmk Road over Matheson Hammock Canal
SUMMARY OF DESIGN CAPACITY

Notes:

- 1) Gross Section Properties from AASHTOWare Bridge Rating Software:

PS Box Beam - Circular Void

Name:	17"x36" PSU	
Description:	17"x36" Prestressed Slab Unit (Typ.)	
Sl Or Us Type:	US Customary	
Box Beam Type:	Circular Void	
Top Width:	35.0000	in
Number Circular Voids:	2	
Three Void Box Shape Indicator:	FALSE	
Ctc Distance Voids:	16.0000	in
Void Diameter:	10.0000	in
Interior Void Diameter:		in
Exterior Void Diameter:		in
Depth:	17.0000	in
Distance To Cg Void Bot:	9.0000	in
Bot Width:	36.0000	in
Shear Key Vertical Loc:	2.0000	in
Shear Key Height:	6.0000	in
Shear Key Depth:	1.5000	in
Area:	438.822	in^2
Nominal Weight Or Mass:	457.107	lb/ft
Ixx:	13330.101	in^4
Distance Y To Cg:	8.1667	in
Sxx Top:	1509.078	in^3
Sxx Bot:	1632.246	in^3
Nominal Depth:	17.0000	in
Volume Surface Ratio:	3.175	in
Half Depth Area Pos Flex:		in^2
Half Depth Area Neg Flex:		in^2
St Venant Torsional Constant:	14593.772	in^4



Project #: D210107FL00.00
Designed By: YRA
Design Date: Nov-21
Checked By: MP
Check Date: Nov-21

Matheson Hmk Road over Matheson Hammock Canal
SUMMARY OF DESIGN CAPACITY

Concrete Material

Name:	Class P (5000)
Description:	Class 5000 cement concrete
Si Or Us Type:	US Customary
28 Day Compressive Strength:	5.000 ksi
Initial Compressive Strength:	4.000 ksi
Density For DL:	0.150 kcf
Density For Modulus Of Elasticity:	0.145 kcf
Std Modulus Of Elasticity:	4074.28 ksi
Std Initial Modulus Of Elasticity:	3644.15 ksi
Coefficient Of Thermal Expansion:	0.0000060000 1/F
Poissons Ratio:	0.200
Composition Type:	Normal
Modulus Of Rupture:	0.537 ksi
Shear Factor:	1.000



Project #: D210107FL00.00
Designed By: YRA
Design Date: Nov-21
Checked By: MP
Check Date: Nov-21

Matheson Hmk Road over Matheson Hammock Canal
SUMMARY OF DESIGN CAPACITY

Reinforcing Steel Material

Name: Grade 40
Description: 40 ksi reinforcing steel
Si Or Us Type: US Customary
Yield Strength: 40.000 ksi
Modulus Of Elasticity: 29000.00 ksi
Ultimate Strength: 70.000 ksi
Reinforcing Bar Type: Plain

Prestress Strand Material

Name: 7/16" (7W-250) SR
Description: Stress relieved 7/16"/Seven Wire/fpu = 250
Si Or Us Type: US Customary
Strand Diameter: 0.4375 in
Strand Area: 0.108 in^2
Strand Type: Stress Relieved
Ultimate Tensile Strength: 250.000 ksi
Yield Strength: 212.500 ksi
Modulus Of Elasticity: 28500.00 ksi
Transfer Length Std: 21.8750 in
Transfer Length LRPD: 26.2500 in
Unit Load Per Length: 0.367 lb/ft
Epoxy Coated Indicator: FALSE

APPENDIX C – SONOVOID SLAB UNIT STRENGTHENING – CFRP EVALUATION

OBJECTIVE

Design of externally bonded Carbon FRP reinforcement in order to increase the Flexural Capacity of Sonovoid Slab Units 2-8 and 2-9, Bridge No.874294. Load rate CFRP strengthened slab units using LRFR Strength II for controlling FL-Legal Truck (SU4).

CODES AND SPECIFICATIONS

- "FDOT Bridge Load Rating Manual, "Florida Department of Transportation (FDOT) ", January 2021, FDOT BLRM , 2021 edition used for project consistency
- "FDOT Structures Design Guidelines (SDG). Structures Manual Vol.1", January 2021, FDOT
- "AASHTO LRFD Bridge Design Specifications, "American Association of State Highway and Transportation Officials (AASHTO), 9th Edition 2020
- "Fiber Reinforced Polymer Guidelines (FRPG). Structures Design Manual Vol.4", January 2021, FDOT
- "Guide for the Design and Construction of Externally Bonded FRP Systems for Strengthening Concrete Structures ", ACI 440.2R-08, ACI, 2008

Assumptions/Notes:

1. Assume all prestressing strands are bonded for flexural analysis
2. Calculations are an addendum to the AASHTOWare BrR Analysis
3. CFRP Strengthening will use the U-Wrap Method described in ([ACI 440.2R-08, Chapter 11](#)) and Flexural Strengthening analysis techniques in ([ACI 440.2R-08, Chapter 10](#))

Procedure:

1. Input Original Beam Geometry, Material Properties, Strength and Load Effects
2. AASHTOWARE BrR Refined Analysis Results Input
 - a. Moment
3. FRP Reinforcement Properties
4. Design of Externally Bonded FRP Reinforcement
 - a. Development Length of FRP
 - b. Flexural Capacity
 - c. Service Check
 - d. FRP Fatigue Check
5. Calculate HL93 Inventory, HL93 Operating, FL120 Permit, and the 7 Florida Legal Loads Ratings
6. Summary

Legend:

INPUT

<-----Data Input

OUTPUT

<-----Reference Checks and Design Results Output

INPUT DATA

Resistance factor for FRP (ACI 440.2R-08, Table 11.1)

$$\psi_f := 0.85$$

System Factor (FDOT BLRM Table 6A.4.2.4-1)

$$\phi_S := 1.0$$

Condition Factor (AASHTO MBE 6A.4.2.3)

$$\phi_C := 0.90$$

Load Factors per Table 6A.4.2.2-1 FDOT Load Rating Manual, January 2021

Load factor for Dead Load

$$\gamma_{DC} := 1.25$$

Load factor for Dead Load of Wearing Surface

$$\gamma_{DW} := 1.5$$

Load factor for Live Load - Inventory (1.75) and FL-120 (1.35)

$$\gamma_{INV} := 1.75$$

Load factor for Live Load - Operating

$$\gamma_{OPT} := 1.35$$

Load factor for Live Load - FL-120

$$\gamma_{FL120} := 1.35$$

Load factor for Live Load - Legal - Operating

$$\gamma_{FLSU_OPT} := 1.35$$

Material Properties

Concrete Information:

Correction factor for source of aggregate. (AASHTO 5.4.2.4-1. & FDOT SDG. 1.4.1-A)

$$K_1 := 1.0$$

Nominal compressive strength of concrete Slab Unit (non-composite).

$$f'_{c_bm} := 5.0 \cdot \text{ksi}$$

Slab Unit concrete strength at final (FDOT BLRM Table 6A.5.2.1-1)

$$f_c := 5.0 \cdot \text{ksi}$$

Deck Slab concrete strength at final (FDOT BLRM Table 6A.5.2.1-1)

$$f_{cslab} := 0 \cdot \text{ksi}$$

Weight of concrete and humidity (AASHTO Table 3.5.1-1 & FDOT SDG 1.4.1-A & 4.6.6)

$$w_c := 0.145 \frac{\text{kip}}{\text{ft}^3}$$

$$\text{Humidity} := 75$$

Modulus of elasticity for normalweight concrete Deck Slab. (AASHTO 5.4.2.4-2).

$$E_c := 120000 \cdot K_1 \cdot \left(w_c \cdot \frac{\text{ft}^3}{\text{kip}} \right)^{2.0} \cdot \left(f_{cslab} \cdot \frac{1}{\text{ksi}} \right)^{0.33} \cdot \text{ksi} = 0 \cdot \text{ksi}$$

Modulus of elasticity for normalweight concrete Slab Unit. (AASHTO 5.4.2.4-2).

$$E_{c_bm} := 120000 \cdot K_1 \cdot \left(w_c \cdot \frac{\text{ft}^3}{\text{kip}} \right)^{2.0} \cdot \left(f'_{c_bm} \cdot \frac{1}{\text{ksi}} \right)^{0.33} \cdot \text{ksi} = 4.291 \times 10^3 \cdot \text{ksi}$$

Modular Ratio
$$n_{trans} := \frac{E_c}{E_{c_bm}} = 0$$

Concrete cracking stress (AASHTO 5.4.2.6)
$$f_t := 0.24 \cdot \sqrt{\frac{f_c \cdot b_m}{ksi}} \cdot ksi = 0.537 \cdot ksi$$

Geometry Information:

Span length (CL bearing to CL bearing, Span 2)

$$L_{Span} := 38.50ft$$

(See Asbuilt Plans
PG. 8 of 13 of pdf)

Slab Section Properties - [Not Applicable to this Design]

Deck thickness (Assumed for Asphalt W.S.)

$$t_{slab} := 0in$$

Effective Deck Width

$$b_s := 0.0ft$$

Transformed Width

$$b_{transf} := n_{trans} \cdot b_s = 0 \cdot in$$

Height of the section (Slab Unit + Deck Slab)

$$h_c := 17in + t_{slab} = 17 \cdot in$$

Transformed Area

$$A_{ts} := t_{slab} \cdot b_{transf} = 0 \cdot in^2$$

Slab Unit Properties

Non-composite

(Tranformed) Composite

Slab Unit height

$$h_{nc} := 17in$$

$$h_c = 17 \cdot in$$

Size of Void

$$d_{void} := 10in$$

Bottom flange width

$$b_{f_bot} := 36in$$

Top flange width

$$b_{f_top} := 35in$$

Web width (assume effective web width)

$$b_w := b_{f_top} - 2 \cdot 1in - 2 \cdot \left(\frac{\pi \cdot d_{void}}{4} \right)$$

$$b_w = 17.292 \cdot in$$

Cross sectional area (From AASHTOWARE BrR)

$$A_{nc} := 438.822in^2$$

$$A_{ww} := A_{nc} + b_{transf} \cdot t_{slab}$$

$$A = 438.822 \cdot in^2$$

Moment of inertia

$$I_{nc} := 13330.101in^4$$

$$I := 13330.101in^4$$

C.G (from bottom)

$$y_{b_nc} := 8.1667in$$

$$y_b := 8.1667in$$

Top fiber to C.G.

$$y_{t_nc} := h_{nc} - y_{b_nc} = 8.833 \cdot in$$

$$y_t := h_c - y_b = 8.833 \cdot in$$

Section modulus at top fiber

$$S_{t_nc} := \frac{I_{nc}}{y_{t_nc}} = 1.509 \times 10^3 \cdot in^3$$

$$S_t := \frac{I}{y_t} = 1.509 \times 10^3 \cdot in^3$$

Section modulus at top of slab unit once section becomes composite

$$S_{top_girder_c} := \frac{I}{y_t - t_{slab}} = 1.509 \times 10^3 \cdot in^3$$

Section modulus at bottom fiber

$$S_{b_nc} := \frac{I_{nc}}{y_{b_nc}} = 1.632 \times 10^3 \cdot \text{in}^3 \quad S_b := \frac{I}{y_b} = 1.632 \times 10^3 \cdot \text{in}^3$$

Radius of gyration


$$r := \sqrt{\frac{I_{nc}}{A_{nc}}} = 5.512 \cdot \text{in}$$

▣ Slab Unit/Girder Dimensions (For Nominal Bending Strength)

Slab Unit Dimensions (Used for Flexural Design):

17"x36" Slab Unit:

<u>Base</u>	<u>Height</u>
$b_1 := 35\text{in}$	$h_1 := 2.0\text{in}$
$b_2 := 0.75\text{in}$	$h_2 := 0.75\text{in}$
$b_3 := 0.75\text{in}$	$h_3 := 0.75\text{in}$
$b_4 := 0.25\text{in}$	$h_4 := 0.25\text{in}$
$b_5 := 0.25\text{in}$	$h_5 := 0.25\text{in}$



▣ Slab Unit/Girder Dimensions (For Nominal Bending Strength)

Steel Information:

Strand Info: (7/16" seven-wire strand, Grade 250)

Strand diameter. (7/16")

$$d_s := 0.4375\text{in}$$

Strand area.

$$A_s := 0.108\text{in}^2$$

Specified tensile strength of prestressing steel (ksi).
(MBE Table 6A.5.2.3-1)

$$f_{pu} := 250\text{ksi}$$

Yield strength of prestressing steel (ksi).

$$f_{py} := 0.9 \cdot f_{pu} = 225 \cdot \text{ksi}$$

Modulus of elasticity for prestressing strands (ksi).
(MBE Table 6A.5.2.3-1)

$$E_p := 28500\text{ksi}$$

Total number of strands at critical section

$$N_{\text{Total_str}} := 15$$

Area of existing prestressing steel.

$$A_{ps} := N_{\text{Total_str}} \cdot A_s = 1.62 \cdot \text{in}^2$$

Total Losses to prestressing steel (Assumed).

$$\Delta f_{pT} := 0.75 \cdot f_{pu} \cdot 13.43\% = 25.181 \cdot \text{ksi}$$

Effective stress in prestressing steel after losses.

$$f_{pe} := 0.75f_{pu} - \Delta f_{pT} = 162.319 \cdot \text{ksi}$$

Effective force in prestressing steel after losses.


$$P_{pe} := A_{ps} \cdot f_{pe} = 262.956 \cdot \text{kip}$$

Effective prestress strain.

$$\epsilon_{pe} := \frac{f_{pe}}{E_p} = 0.0057$$

Strand Layout - Interior Units 2-8 & 2-9:

(Note: Assumed strand layout for Design, accounting for removal of severed/deteriorated strands per damages reported in the most current Inspection Reports, plus 50% of the adjacent strands)



Strand Locations (Measured inches From the Bottom)

"Location"	"From Bottom"	"No. Strands"
"Top Row"	14.5	4
"3rd Row"	6.5	0
"2nd Row"	4.5	5
"Bottom Row"	2.5	10

C.G. of PS to bottom fiber of slab unit at mid-span

$$y_{ps} := \frac{A_s \cdot (d_{strand_{3,2}} \cdot d_{strand_{3,1}} + d_{strand_{4,2}} \cdot d_{strand_{4,1}})}{(d_{strand_{3,2}} + d_{strand_{4,2}}) \cdot A_s} = 3.17 \cdot \text{in}$$

Prestressing strand eccentricity.

$$e_{nc} := y_{b_nc} - y_{ps} = 5.00 \cdot \text{in} \quad e_{ps} := y_b - y_{ps} = 5.00 \cdot \text{in}$$

Distance from the extreme compression fiber to the centroid of prestressing tendons.

$$d_{p_nc} := h_{nc} - y_{ps} = 13.83 \cdot \text{in} \quad d_p := h_c - y_{ps} = 13.83 \cdot \text{in}$$

Area of transverse reinforcement #4 stirrups
(Assume 3-legs of Transverse reinforcement)

$$A_v := 3(0.2) \text{ in}^2 = 0.6 \cdot \text{in}^2$$

Yield strength of stirrups (FDOT BLRM Table 6A.5.2.2-1)

$$f_y := 40 \text{ ksi}$$

▼ AASHTOWARE BrR-Inputs (Moment)

B. Moments (AASHTOWARE BrR Analysis Results):

(Note: Final Condition ensures that repaired structure satisfies a minimum Rating Factor of 1.0 for all Legal Loads)

Design Dead Load Moment Reactions:

$$M_g := (87.1 \text{ kip} \cdot \text{ft})$$

$$M_{\text{pre_DC}} := (0 \text{ kip} \cdot \text{ft})$$

$$M_{\text{pc}} := (0 \text{ kip} \cdot \text{ft})$$

$$M_c := (22.5 \text{ kip} \cdot \text{ft})$$

$$M_{\text{DC}} := M_g + M_{\text{pre_DC}} + M_{\text{pc}} + M_c = (109.6) \cdot \text{kip} \cdot \text{ft}$$

$$M_{\text{DW}} := (8.68 \text{ kip} \cdot \text{ft})$$

$$g := 0$$

Moment due to self weight of the slab unit (Midspan).
(Total DC Self weight moment from AASHTOWare BrR)

Moment due to additional precast components

Moment due dead load of deck slab
[Not Applicable]

Moment due to additional structural components
(Total DC Railing & Sidewalk/Curb moment from
AASHTOWare BrR)

Dead load moment from structural components and
non-structural attachments.

Moment due to existing wearing surface DL.

Design Live Load Distribution Factors:

$$LLDF_{M_HL93} := (0.256)$$

$$LLDF_{M_FL.Permit} := (0.256)$$

$$LLDF_{M_FL.Legal} := (0.256)$$

Live load distribution factor for HL93 moment from
AASHTOWare BrR Refined Analysis
(Note: Distribution Factor assuming post-tensioning is
repaired/restored)

Live load distribution factor for Permit moment from
AASHTOWare BrR Refined Analysis
(Note: Distribution Factor assuming post-tensioning is
repaired/restored)

Live load distribution factor for Legal moment from
AASHTOWare BrR Refined Analysis
(Note: Distribution Factor assuming post-tensioning is
repaired/restored)

Design Live Load Moment Reactions:

$$M_{LL_HL93} := (177.43 \text{ kip} \cdot \text{ft})$$

$$M_{LL_FL120} := (193.35 \text{ kip} \cdot \text{ft})$$

$$M_{LL_SU2} := (84.98 \text{ kip} \cdot \text{ft})$$

$$M_{LL_SU3} := (159.7 \text{ kip} \cdot \text{ft})$$

Live load moment from controlling HL-93 truck.

Live load moment from FL120 Permit truck.

Live load moment from SU2 FL-Legal truck.

Live load moment from SU3 FL-Legal truck.

$$M_{LL_SU4} := (171.55 \text{ kip}\cdot\text{ft})$$

Live load moment from controlling FL-Legal truck: SU4.

$$M_{LL_C3} := (91.12 \text{ kip}\cdot\text{ft})$$

Live load moment from C3 FL-Legal truck.

$$M_{LL_C4} := (128.76 \text{ kip}\cdot\text{ft})$$

Live load moment from C4 FL-Legal truck.

$$M_{LL_C5} := (132.83 \text{ kip}\cdot\text{ft})$$

Live load moment from C5 FL-Legal truck.

$$M_{LL_ST5} := (128.11 \text{ kip}\cdot\text{ft})$$

Live load moment from ST5 FL-Legal truck.

Controlling Live load moment FL-Legal truck: (SU4)

$$M_{LL_FL.Legal} := \left(\max(M_{LL_SU2}, M_{LL_SU3}, M_{LL_SU4}, M_{LL_C3}, M_{LL_C4}, M_{LL_C5}, M_{LL_ST5}) \right) = (171.55) \text{ kip}\cdot\text{ft}$$

Design Load Combinations:

(Note: Final Condition ensures that repaired structure satisfies a minimum Rating Factor of 1.0 for all Legal Loads)

Service:

$$M_{Ser_HL93} := 1.0 \cdot M_{DC} + 1.0 \cdot M_{DW} + 1.0 \cdot M_{LL_HL93} = (295.7) \cdot \text{kip}\cdot\text{ft}$$

Service moment (Service I) - Design.
[AASHTO LRFD Table 3.4.1-1.](#)

$$M_{Ser_FL120} := 1.0 \cdot M_{DC} + 1.0 \cdot M_{DW} + 1.0 \cdot M_{LL_FL120} = (311.6) \cdot \text{kip}\cdot\text{ft}$$

Service moment (Service I) - Permit.
[AASHTO LRFD Table 3.4.1-1.](#)

$$M_{Ser_FL.Legal} := 1.0 \cdot M_{DC} + 1.0 \cdot M_{DW} + 1.0 \cdot M_{LL_SU4} = (289.8) \cdot \text{kip}\cdot\text{ft}$$

Service moment (Service I) - Controlling FL-Legal.
[AASHTO LRFD Table 3.4.1-1.](#)

Strength:

$$M_{Str_HL93.inv} := 1.25 \cdot M_{DC} + 1.5 \cdot M_{DW} + \gamma_{INV} \cdot M_{LL_HL93} = (460.5) \cdot \text{kip}\cdot\text{ft}$$

Inv. Strength moment (Strength I) - Design.
[AASHTO LRFD Table 3.4.1-1.](#)

$$M_{Str_HL93.op} := 1.25 \cdot M_{DC} + 1.5 \cdot M_{DW} + \gamma_{OPT} \cdot M_{LL_HL93} = (389.6) \cdot \text{kip}\cdot\text{ft}$$

Op. Strength moment (Strength I) - Design.
[AASHTO LRFD Table 3.4.1-1.](#)

$$M_{Str_FL120} := 1.25 \cdot M_{DC} + 1.5 \cdot M_{DW} + 1.35 \cdot M_{LL_FL120} = (411) \cdot \text{kip}\cdot\text{ft}$$

Strength moment (Strength II) - Permit.
[AASHTO LRFD Table 3.4.1-1.](#)

$$M_{Str_SU2} := 1.25 \cdot M_{DC} + 1.5 \cdot M_{DW} + 1.35 \cdot M_{LL_SU2} = (264.7) \cdot \text{kip}\cdot\text{ft}$$

Strength moment (Strength I) - SU2 Legal.
[AASHTO LRFD Table 3.4.1-1.](#)

$$M_{Str_SU3} := 1.25 \cdot M_{DC} + 1.5 \cdot M_{DW} + 1.35 \cdot M_{LL_SU3} = (365.6) \cdot \text{kip}\cdot\text{ft}$$

Strength moment (Strength I) - SU3 Legal.
[AASHTO LRFD Table 3.4.1-1.](#)

$$M_{Str_SU4} := 1.25 \cdot M_{DC} + 1.5 \cdot M_{DW} + 1.35 \cdot M_{LL_SU4} = (381.6) \cdot \text{kip}\cdot\text{ft}$$

Strength moment (Strength I) - SU4 Legal.
[AASHTO LRFD Table 3.4.1-1.](#)

$$M_{Str_C3} := 1.25 \cdot M_{DC} + 1.5 \cdot M_{DW} + 1.35 \cdot M_{LL_C3} = (273) \cdot \text{kip}\cdot\text{ft}$$

Strength moment (Strength I) - C3 Legal.
[AASHTO LRFD Table 3.4.1-1.](#)

$$M_{Str_C4} := 1.25 \cdot M_{DC} + 1.5 \cdot M_{DW} + 1.35 \cdot M_{LL_C4} = (323.8) \cdot \text{kip} \cdot \text{ft}$$

Strength moment (Strength I) - C4 Legal.
AASHTO LRFD Table 3.4.1-1.

$$M_{Str_C5} := 1.25 \cdot M_{DC} + 1.5 \cdot M_{DW} + 1.35 \cdot M_{LL_C5} = (329.3) \cdot \text{kip} \cdot \text{ft}$$

Strength moment (Strength I) - C5 Legal.
AASHTO LRFD Table 3.4.1-1.

$$M_{Str_ST5} := 1.25 \cdot M_{DC} + 1.5 \cdot M_{DW} + 1.35 \cdot M_{LL_ST5} = (323) \cdot \text{kip} \cdot \text{ft}$$

Strength moment (Strength I) - ST5 Legal.
AASHTO LRFD Table 3.4.1-1.

$$M_{Str_FL.Legal} := \left(\max(M_{Str_SU2}, M_{Str_SU3}, M_{Str_SU4}, M_{Str_C3}, M_{Str_C4}, M_{Str_C5}, M_{Str_ST5}) \right) = (381.6) \text{ kip} \cdot \text{ft}$$

Strength moment (Strength I) - Controlling
Legal. AASHTO LRFD Table 3.4.1-1.

$$\phi M_{n_no_wrap} := (344.64 \text{ kip} \cdot \text{ft})$$

Capacity of member before FRP wrap is applied

▲ AASHTOWARE BrR-Inputs (Moment)

3. CFRP Reinforcement Properties

The amount of the CFRP reinforcement and its material properties are given as per net-fiber.

Thickness of the CFRP strip (*V-WrapTM - C200HM*)

$$t_f := 0.04 \text{ in}$$

Ultimate tensile strength of the CFRP

$$f_{fu_pre} := 155 \text{ ksi}$$

Rupture strain

$$\epsilon_{fu_pre} := 0.011$$

Modulus of elasticity of CFRP

$$E_f := 14 \cdot 10^6 \text{ psi} = 14000 \cdot \text{ksi}$$

Number of plies of CFRP sheets (Per preliminary recommendations)

$$n := 2$$

Width of the CFRP sheet (36" per preliminary recommendation from Structural Technologies)

$$w_f := 36 \text{ in}$$

CFRP orientation

$$\alpha_f := 90 \text{ deg}$$

Spacing of CFRP [Not Applicable]

$$s_{FRP} := 0 \text{ in}$$

Area of FRP for shear . (ACI 440.2R Eq. 11-4) [Not Applicable]

$$A_{fV} := 0 \text{ in}^2$$

Area of FRP for flexure (U-wrap)

$$A_{ff} := n \cdot t_f \cdot b_{f_bot} = 2.88 \cdot \text{in}^2$$

Environmental reduction factor for CFRP. (ACI 440.2R Table 9.1)

$$C_E := 0.85$$

Design ultimate tensile strength of CFRP. (ACI 440.2R Eq. 9-3)

$$f_{fu} := C_E \cdot f_{fu_pre} = 131.75 \cdot \text{ksi}$$

Ultimate rupture strain of CFRP reinforcement.
(ACI 440.2R Eq. 9-4)

$$\epsilon_{fu} := C_E \cdot \epsilon_{fu_pre} = 0.0093 \cdot \frac{\text{in}}{\text{in}}$$

4. DESIGN OF EXTERNALLY BONDED FRP REINFORCEMENT

(ACI 440.2R-08, Chapter 11)

The CFRP sheets will be applied along the bottom face of the deteriorated slab units, along the full length and across the entire width of the slab units.

▼ FRP Strength Criteria (Moment)

$$\text{Check_FRP_Strength_Criteria_Moment}_g := \begin{cases} \text{"OK"} & \text{if } \left(\left(\phi M_{n_no_wrap_g} \geq 1.1 M_{DC_g} + 1.0 M_{LL_HL93_g} \right) \right) \\ \text{"Not Good"} & \text{otherwise} \end{cases} \quad \text{[NOT APPLICABLE]}$$

FDOT FRPG Section 4.2.C
(For multiple girder Strengthening)

Check_FRP_Strength_Criteria_Moment = ("OK")

▲ FRP Strength Criteria (Moment)

▼ CFRP Development Length

FRP Reinforcement - Development Length

Determine length of CFRP needed to develop full bond capacity. Overlap length of CFRP sheets must be provided by manufacturer [ACI 440.2R-08 13.2](#)

$$l_{df} := 0.057 \cdot \sqrt{\frac{n \cdot E_f \cdot t_f}{\frac{f_{c_bm}}{\text{psi}} \cdot \text{psi} \cdot \text{in}}} \cdot \text{in} = 7.174 \cdot \text{in}$$

Development length needed to develop full bond strength of CFRP [ACI 440.2R-08 \(13-2\)](#)

▲ CFRP Development Length

▼ Ultimate Flexural Strength Pt.1

FRP Reinforcement - Flexural Capacity

Design material properties:

$$f_{fu} = 131.75 \cdot \text{ksi}$$

$$\epsilon_{fu} = 9.35 \times 10^{-3}$$

Area of the CFRP reinforcement

$$A_{fv} = 5.76 \cdot \text{in}^2$$

Effective depth of CFRP ([ACI 440.2R-08 Fig 11.2](#))

$$d_{vFRP} := (d_p - t_{slab} - 2\text{in}) = 11.833 \cdot \text{in}$$

Active bond length ([ACI 440.2R-08 11.4.1.2](#))

$$L_e := \frac{2500\text{in}}{\left(\frac{t_f}{\text{in}} \cdot \frac{E_f}{\text{psi}} \right)^{0.58}} = 0.775 \cdot \text{in}$$

Bond reduction coefficients (ACI 440.2R-08 11.4.1.2)

$$k_1 := \left(\frac{f_c}{\text{psi} \cdot 4000} \right)^{\frac{2}{3}} = 1.16 \quad k_2 := \frac{d_{\text{vFRP}} - L_e}{d_{\text{vFRP}}} = 0.934 \quad \text{for U-Wrap}$$

$$\kappa_v := \frac{k_1 \cdot k_2 \cdot \frac{L_e}{\text{in}}}{468 \cdot \epsilon_{fu}} = 0.192$$

$$\kappa_v := \min(0.75, \kappa_v) = 0.192$$

Effective strain of the CFRP reinforcement

$$\epsilon_{fe} := \min(\kappa_v \cdot \epsilon_{fu}, 0.004) = 0.0018$$

(ACI 440.2R-08 11.4.1.2)

Effective strength of the CFRP reinforcement

$$f_{fe} := \epsilon_{fe} \cdot E_f = 25.145 \cdot \text{ksi}$$

(ACI 440.2R Eq. 11-5)

Determine the existing state of strain

Determine strain at soffit during installation of CFRP. Tension is positive and compression is negative.

$$\epsilon_{bi} := \frac{-P_{pe}}{E_{c_bm} \cdot A_{nc}} + \frac{-P_{pe} \cdot e_{nc} + M_g + M_{pc}}{E_{c_bm} \cdot S_{b_nc}} + \frac{M_c}{E_{c_bm} \cdot S_b} = (-1.396 \times 10^{-4})$$

Determine the design strain of the FRP system

Determine strain at which debonding of CFRP may occur

$$\epsilon_{fd} := \min \left(0.083 \cdot \sqrt{\frac{f_{c_bm} \cdot \text{psi} \cdot \text{in}}{n \cdot E_f \cdot t_f \cdot \text{psi}}}, 0.9 \cdot \epsilon_{fu} \right) = 5.546 \times 10^{-3} \quad \text{ACI 440.2R-08 (10-2)}$$

Determine flexure capacity of section

The determination of flexural capacity for prestressed slab units repaired with CFRP wraps makes use of strain compatibility which is an iterative process. Each iteration involves the assumption of a neutral axis depth. Once an assumption is made, the strains in the compressive concrete face, CFRP wrap, and strands are determined based on a linear strain relationship. The calculated strains are then converted into compressive and tensile forces that are used to check if equilibrium within the cross section is obtained, iterations continue until equilibrium is reached. **It is assumed all strands are bonded at the section of interest.**

Guess neutral axis depth (reasonable guess is 0.1*depth of section):

$$c_n := (6.475 \text{ in})$$

Assumed depth from top of section to neutral axis

Determine the effective level of strain in the CFRP reinforcement:

$$d_f := h_c = 17 \cdot \text{in}$$

Depth from top of section to CFRP reinforcement

$$\varepsilon_{fe_i} := \text{for } i \in g$$

$$\varepsilon_{fe_i} \leftarrow \min \left[0.003 \cdot \left(\frac{d_f - c_i}{c_i} \right) - \varepsilon_{bi_i}, \varepsilon_{fd} \right]$$

Strain in CFRP reinforcement
ACI 440.2R-08 (10-16)

$$\varepsilon_{fe} = (5.016 \times 10^{-3})$$

$$\text{Controlling_Failure} := \text{for } i \in g$$

$$\left| \begin{array}{l} \text{Controlling_Failure}_i \leftarrow \text{"CFRP debonding/rupture controls"} \quad \text{if } \left| \varepsilon_{fe_i} \right| = \varepsilon_{fd} \\ \text{Controlling_Failure}_i \leftarrow \text{"Concrete crushing controls"} \quad \text{otherwise} \end{array} \right.$$

$$\text{Controlling_Failure} = (\text{"Concrete crushing controls"})$$

Determine strain at extreme compression fiber based on controlling failure type:

$$\varepsilon_c := \text{for } i \in g$$

$$\left| \begin{array}{l} \varepsilon_{c_i} \leftarrow \left(\varepsilon_{fe_i} + \varepsilon_{bi_i} \right) \cdot \frac{c_i}{d_f - c_i} \quad \text{if } \varepsilon_{fe_i} = \varepsilon_{fd} \\ \varepsilon_{c_i} \leftarrow 0.003 \quad \text{otherwise} \end{array} \right.$$

CFRP debonding/rupture

Concrete crushing

$$\varepsilon_c = (3 \times 10^{-3})$$

Strain at extreme compression fiber

Calculate the strain in the existing prestressing steel:

Net tensile strain in prestressing steel beyond decompression, at nominal strength

$$\epsilon_{pnet} := \text{for } i \in g \quad \left| \begin{array}{l} \epsilon_{pnet,i} \leftarrow \left(\epsilon_{fe,i} + \epsilon_{bi,i} \right) \cdot \left(\frac{d_p - c_i}{d_f - c_i} \right) \text{ if } \epsilon_{fe,i} = \epsilon_{fd} \\ \epsilon_{pnet,i} \leftarrow 0.003 \cdot \frac{d_p - c_g}{c_g} \text{ otherwise} \end{array} \right.$$

CFRP debonding/rupture
ACI 440.2R-08 (10-23b)

Concrete crushing
ACI 440.2R-08 (10-23a)

$$\epsilon_{pnet} = (3.409 \times 10^{-3})$$

$$\epsilon_{ps} := \text{for } i \in g \quad = (9.359 \times 10^{-3}) \quad \text{Strain in prestressing steel}$$

$$\epsilon_{ps,i} \leftarrow \min \left[\epsilon_{pe} + \frac{P_{pe}}{A_{nc} \cdot E_{c_bm}} \cdot \left(1 + \frac{e_{nc}^2}{r^2} \right) + \epsilon_{pnet,i}, 0.035 \right]$$

ACI 440.2R-08 (10-22)

$$\text{Check_steel_rupture}_g := \left| \begin{array}{l} \text{"Need to consider steel rupture"} \text{ if } \epsilon_{ps_g} \geq 0.035 \\ \text{"Steel rupture does not control OK"} \text{ otherwise} \end{array} \right.$$

Check if steel rupture controls
ACI 440.2R-08 (10-22)

Check_steel_rupture = ("Steel rupture does not control OK")

Calculate the stress level in prestressing steel and CFRP:

$$f_{ps_g} := \left(\left| \begin{array}{l} 28500 \cdot \epsilon_{ps} \text{ if } \epsilon_{ps_g} \leq 0.0076 \\ 250 - \frac{0.04}{\epsilon_{ps_g} - 0.0064} \text{ otherwise} \end{array} \right| \right) \cdot \text{ksi}$$

Stress in prestressing steel (applicable for Grade 250 ksi steel)
ACI 440.2R-08 (10-24b)

$$f_{ps_g} = 236.483 \cdot \text{ksi}$$

$$f_{fe} := E_f \cdot \epsilon_{fe} = (70.224) \cdot \text{ksi}$$

Stress in CFRP Reinforcement
ACI 440.2R-08 (10-21)

Calculate the internal force resultants and check equilibrium:

Use Whitney Stress Block to model stress if concrete crushing controls. If CFRP debonding/rupture controls use approximate stress block factors based on parabolic stress-strain relationship for concrete (see [ACI 440.2R-08 15.5 Step 9](#))

$$\beta_{1g} := \begin{cases} \text{if } \epsilon_{fe_g} = \epsilon_{fd} \\ \epsilon'_c \leftarrow \frac{1.7 \cdot f_{c_bm}}{E_{c_bm}} \\ \beta_1 \leftarrow \frac{4 \cdot \epsilon'_c - \epsilon_{c_g}}{6 \cdot \epsilon'_c - 2 \cdot \epsilon_{c_g}} \\ \text{if } \epsilon_{c_g} = 0.003 \\ \beta_1 \leftarrow \max \left(0.85 - \frac{f_{c_bm} - 4000 \text{ psi}}{1000 \cdot \text{psi}} \cdot 0.05, 0.65 \right) \text{ if } f_{c_bm} > 4000 \text{ psi} \\ \beta_1 \leftarrow 0.85 \text{ if } f_{c_bm} \leq 4000 \text{ psi} \end{cases}$$

Approximate stress block β factor based on parabolic stress-strain relationship [ACI 440.2R-08 15.5 Step 9](#)

Stress block β factor based on Whitney Stress Block

$$\beta_1 = (0.8)$$

$$\beta_{1g} = 0.8$$

$$\alpha_{1g} := \begin{cases} \alpha_1 \leftarrow 0.85 \text{ if } \epsilon_{c_g} = 0.003 \\ \text{otherwise} \\ \epsilon'_c \leftarrow \frac{1.7 \cdot f_{c_bm}}{E_{c_bm}} \\ \alpha_1 \leftarrow \frac{3 \cdot \epsilon'_c \cdot \epsilon_{c_g} - (\epsilon_{c_g})^2}{3 \cdot \beta_{1g} \cdot \epsilon'^2_c} \end{cases}$$

Stress block α factor based on Whitney Stress Block

Approximate stress block α factor based on parabolic stress-strain relationship [ACI 440.2R-08 15.5 Step 9](#)

$$\alpha_1 = (0.85)$$

$$\alpha_{1g} = 0.85$$

▲ Ultimate Flexural Strength Pt.1

▼ Strain Compatability Calcs

$$f_{w_{transf}} := \frac{b_1 \cdot (h_1 + h_2) - \left(2 \cdot \frac{1}{2} \cdot b_2 \cdot h_2\right)}{b_1 \cdot (h_1 + h_2)} \cdot b_1 = 34.795 \cdot \text{in}$$

Use transformed girder flange width
if stress block lies on or beyond
first tapered section of girder flange

```

Ten_Com := for i ∈ g
    if β1,i · ci ≤ tslab
        Comi ← α1,i · fc_bm · btransf · β1,i · ci
        Teni ← Aps · fpsi + Aff · ffei
        Stress block in deck
    if β1,i · ci > tslab ∧ β1,i · ci ≤ h1 + tslab
        Comi ← α1,i · fc_bm · btransf · tslab + α1,i · fc_bm · b1 · (β1,i · ci - tslab)
        Teni ← Aps · fpsi + Aff · ffei
        Stress block in top of flange
    if β1,i · ci > h1 + tslab ∧ β1,i · ci ≤ h1 + h2 + tslab
        Comi ← α1,i · fc_bm · btransf · tslab + α1,i · fc_bm · fwtransf · (β1,i · ci - tslab)
        Teni ← Aps · fpsi + Aff · ffei
        Stress block in first tapered section of flange
    if β1,i · ci > h1 + h2 + tslab ∧ β1,i · ci ≤ h1 + h2 + h4 + tslab
        Comi ← α1,i · fc_bm · btransf · tslab + α1,i · fc_bm · (h1 + h2) · fwtransf + α1,i · fc_bm · (β1,i · ci - tslab - h1 - h2) · (bw + b4)
        Teni ← Aps · fpsi + Aff · ffei
        Stress block in second tapered section of flange
    if β1,i · ci > h1 + h2 + h4 + tslab
        Comi ← α1,i · fc_bm · btransf · tslab + α1,i · fc_bm · (h1 + h2) · fwtransf + α1,i · fc_bm · (h4 · bw + h4 · b4) ...
        + α1,i · fc_bm · [β1,i · ci - tslab - (h1 + h2 + h4)] · bw
        Teni ← Aps · fpsi + Aff · ffei
        Stress block in web
    return augment(Ten, Com)

```

▲ Strain Compatability Calcs

▼ Ultimate Flexural Capacity Pt.2

$$T_{en_Com} = (585.349 \ 585.521) \cdot \text{kip}$$

Check if section is in equilibrium

	<u>Tension</u>	<u>Compression</u>
Equilibrium :=	for $i \in g$	
	$\text{Equilibrium}_i \leftarrow \text{"Equilibrium achieved"} \quad \text{if} \quad \left \frac{T_{en_Com_{i,0}} - T_{en_Com_{i,1}}}{T_{en_Com_{i,0}}} \right \leq 1\%$	
	$\text{Equilibrium}_i \leftarrow \text{"Equilibrium not achieved, adjust c value"} \quad \text{if} \quad \left \frac{T_{en_Com_{i,0}} - T_{en_Com_{i,1}}}{T_{en_Com_{i,0}}} \right > 1\%$	
	return Equilibrium	

Equilibrium = ("Equilibrium achieved")

Nominal flexural strength:

$$M_{np} := \left[A_{ps} \cdot f_{ps} \cdot \left(d_p - \frac{\beta_1 \cdot c}{2} \right) \right] = (358.946) \cdot \text{kip} \cdot \text{ft}$$

Prestressing steel contribution to flexural strength

Percent difference of calculated nominal strength of section without CFRP vs Conspan flexural capacity.
Use nominal section strength for check since AASHTO uses $\phi = 1.0$ and ACI use $\phi = 0.9$

$$\left| \frac{M_{np_g} - \phi M_{n_no_wrap_g}}{\phi M_{n_no_wrap_g}} \right| = 4.151\%$$

$$M_{nf} := \left[A_{ff} \cdot f_{fe} \cdot \left(d_f - \frac{\beta_1 \cdot c}{2} \right) \right] = (242.864) \cdot \text{kip} \cdot \text{ft}$$

CFRP contribution to flexural strength

Design flexural strength:

$$\phi_g := \begin{cases} \phi \leftarrow 0.9 & \text{if } \epsilon_{ps_g} \geq 0.013 \\ \phi \leftarrow 0.65 + \frac{0.25 \cdot (\epsilon_{ps_g} - 0.010)}{0.013 - 0.010} & \text{if } \epsilon_{ps_g} > 0.010 \wedge \epsilon_{ps_g} < 0.013 \\ \phi \leftarrow 0.65 & \text{if } \epsilon_{ps_g} \leq 0.01 \end{cases}$$

Strength reduction factor
[ACI 440.2R-08 \(10-19\)](#)

$$\phi = (0.65)$$

$$\phi M_n := \left[\phi \cdot (M_{np} + \psi_f \cdot M_{nf}) \right] = (367.497) \cdot \text{kip} \cdot \text{ft}$$

Design strength of composite section with CFRP wrap
[ACI 440.2R-08 \(10-26\)](#)

▲ Ultimate Flexural Capacity Pt.2

▼ Service I

FRP Reinforcement - Service Check

Check service stresses using Service I load combinations: SDG Vol 4. 4.2

Check if section will crack under service loads

$$f_D := \frac{-P_{pe}}{A_{nc}} + \frac{-P_{pe} \cdot e_{nc} + M_g + M_{pc}}{S_{b_nc}} + \frac{M_c}{S_b} = (-0.599) \cdot \text{ksi}$$

Stress at soffit due to dead load.
Tension is positive and compression
is negative

Check if section is cracked due to live load moment:

Is_section_cracked := for i ∈ g

$$\left| \begin{array}{l} \text{Is_section_cracked}_i \leftarrow \text{"Section is cracked; CFRP Strengthening Required"} \quad \text{if } f_{D_i} + \frac{M_{LL_FL_Legal}_i}{S_b} \geq f_r \\ \text{Is_section_cracked}_i \leftarrow \text{"Section is not cracked OK"} \quad \text{otherwise} \end{array} \right.$$

Is_section_cracked = ("Section is cracked; CFRP Strengthening Required")

Check stress in prestressing steel

Strain in prestressing steel. Tension is positive and compression is negative.

$$\epsilon_{ps_s} := \epsilon_{pe} - \frac{P_{pe}}{A_{nc} \cdot E_{c_bm}} \cdot \left(1 + \frac{e_{nc}^2}{r^2} \right) + \frac{(M_g + M_{pc}) \cdot e_{nc}}{I_{nc} \cdot E_{c_bm}} + \frac{(M_c + M_{LL_FL_Legal}) \cdot e}{I \cdot E_{c_bm}} = (5.736 \times 10^{-3})$$

f_{ps_s} := for i ∈ g

$$\left| \begin{array}{l} f_{ps_s_i} \leftarrow 28500 \cdot \epsilon_{ps_s_i} \cdot \text{ksi} \quad \text{if } \epsilon_{ps_s_i} \leq 0.0076 \\ f_{ps_s_i} \leftarrow \left(250 - \frac{0.04}{|\epsilon_{ps_s_i}| - 0.0064} \right) \cdot \text{ksi} \quad \text{if } \epsilon_{ps_s_i} > 0.0076 \end{array} \right.$$

Stress in prestressing steel
(applicable for 250 grade steel)
ACI 440.2R-08 (10-24b)

$$f_{ps_s} = (163.468) \cdot \text{ksi}$$

Check_steel_stress := for $i \in g$

$$\left| \begin{array}{l} \text{Check_steel_stress}_i \leftarrow \text{"OK"} \quad \text{if } \left| f_{ps_s_i} \right| \leq 0.82 \cdot f_{py} \wedge \left| f_{ps_s_i} \right| \leq 0.74 \cdot f_{pu} \\ \text{Check_steel_stress}_i \leftarrow \text{"NOT OK"} \quad \text{otherwise} \end{array} \right.$$

Check if stress in prestressing
steel satisfies
ACI 440.2R-08 (10-20a) & (10-20b)

Check_steel_stress = ("OK")

Check compressive stress in concrete

Tension is positive and compression is negative

Check top of precast slab unit:

$$f_{c_top_gir} := \frac{-P_{pe}}{A_{nc}} + \frac{P_{pe} \cdot e_{nc} - M_g - M_{pc}}{S_{t_nc}} - \frac{M_c}{S_{top_girder_c}} - \frac{M_{LL_FL.Legal}}{S_{top_girder_c}} = (-1.964) \cdot \text{ksi}$$

Stress at top of precast
girder

Check_top_girder_stress := for $i \in g$

$$\left| \begin{array}{l} \text{Check_top_girder_stress}_i \leftarrow \text{"OK"} \quad \text{if } \left| f_{c_top_gir_i} \right| \leq 0.45 \cdot f_{c_bm} \\ \text{Check_top_girder_stress}_i \leftarrow \text{"NOT OK"} \quad \text{otherwise} \end{array} \right.$$

Check_top_girder_stress = ("OK")

Check top of deck: - **[NO DECK PRESENT; CHECK NOT APPLICABLE]**

$$f_{c_top_deck} := \text{if} \left(t_{slab} = 0 \text{ in}, 0 \text{ ksi}, \frac{M_c}{S_t} \cdot n - \frac{M_{LL_FL.Legal}}{S_t} \cdot n \right) = 0 \cdot \text{ksi}$$

Stress at top of deck

Check_top_deck_stress := if $(t_{slab} = 0 \text{ in}, \text{"NOT APPLICABLE"}, \text{for } i \in g)$

$$\left| \begin{array}{l} \text{Check_top_deck_stress}_i \leftarrow \text{"OK"} \quad \text{if } \left| f_{c_top_deck_i} \right| \leq 0.45 \cdot f_{cslab} \\ \text{Check_top_deck_stress}_i \leftarrow \text{"NOT OK"} \quad \text{otherwise} \end{array} \right.$$

Check_top_deck_stress = "NOT APPLICABLE"

Check stress in CFRP

Tension is positive and compression is negative

$$f_{f_s} := \frac{E_f}{E_{c_bm}} \cdot \left(f_D + \frac{M_{LL_FL.Legal}}{S_b} \right) - \epsilon_{bi} \cdot E_f = (4.115) \cdot \text{ksi}$$

Stress in CFRP

Check_FRP_stress := for i ∈ g

$$\begin{cases} \text{Check_FRP_stress}_i \leftarrow \text{"OK"} & \text{if } |f_{f_s_i}| \leq 0.55 \cdot f_{fu} \\ \text{Check_FRP_stress}_i \leftarrow \text{"Not OK"} & \text{otherwise} \end{cases}$$

Check that stress in CFRP satisfies
[ACI 440.2R-08 Table 10.1](#)

Check_FRP_stress = ("OK")

▲ Service I

▼ FRP Fatigue Check

FRP Reinforcement - Fatigue

[SDG Vol. 4.2](#) states that the standard fatigue truck from LRFD should be used to check fatigue stresses in CFRP composite. By inspection, the standard fatigue truck will produce lower stresses within the section when compared to the truck used for the Service I stress check. If Service I is satisfied, no further analysis is required.
(Refer to [ACI 440.2R-08 10.2.9](#))

▲ FRP Fatigue Check

Summary:

The Flexural Loading Rating (LR) controlled by SU4 Legal Strength loading which produced a LR of 0.931 was increased by CFRP strengthening along the bottom face of the slab unit length. The CFRP strengthening design consisted of U-wrap method plies which are 36" wide (C200HM) along the controlling sections. The strengthened section resulted in a flexural load rating shown below:

Number of Plies
for U-Wrap Shear

n = 2

Width of Plies

w_f = 36·in

FRP Development Length

l_{df} = 7.174·in

FRP Stress Check

Check_FRP_stress = ("OK")

☒ Rating Factor (Moment)

RATING FACTOR FOR CONTROLLING TRUCK LOADING MOMENT

Design Rating Factors:

(Note: Final Condition ensures that repaired structure satisfies a minimum Rating Factor of 1.0 for all Legal Loads)

$$RF_{OPT.moment_HL93} := \frac{\phi M_n - (\gamma_{DC} \cdot M_{DC} + \gamma_{DW} \cdot M_{DW})}{\gamma_{OPT} \cdot M_{LL_HL93}}$$

$$RF_{INV.moment_HL93} := \frac{\phi M_n - (\gamma_{DC} \cdot M_{DC} + \gamma_{DW} \cdot M_{DW})}{\gamma_{INV} \cdot M_{LL_HL93}}$$

$$RF_{OPT.moment_FL120} := \frac{\phi M_n - (\gamma_{DC} \cdot M_{DC} + \gamma_{DW} \cdot M_{DW})}{\gamma_{OPT} \cdot M_{LL_FL120}}$$

$$RF_{OPT.moment_SU2} := \frac{\phi M_n - (\gamma_{DC} \cdot M_{DC} + \gamma_{DW} \cdot M_{DW})}{\gamma_{OPT} \cdot M_{LL_SU2}}$$

$$RF_{OPT.moment_SU3} := \frac{\phi M_n - (\gamma_{DC} \cdot M_{DC} + \gamma_{DW} \cdot M_{DW})}{\gamma_{OPT} \cdot M_{LL_SU3}}$$

$$RF_{OPT.moment_SU4} := \frac{\phi M_n - (\gamma_{DC} \cdot M_{DC} + \gamma_{DW} \cdot M_{DW})}{\gamma_{OPT} \cdot M_{LL_SU4}}$$

$$RF_{OPT.moment_C3} := \frac{\phi M_n - (\gamma_{DC} \cdot M_{DC} + \gamma_{DW} \cdot M_{DW})}{\gamma_{OPT} \cdot M_{LL_C3}}$$

$$RF_{OPT.moment_C4} := \frac{\phi M_n - (\gamma_{DC} \cdot M_{DC} + \gamma_{DW} \cdot M_{DW})}{\gamma_{OPT} \cdot M_{LL_C4}}$$

$$RF_{OPT.moment_C5} := \frac{\phi M_n - (\gamma_{DC} \cdot M_{DC} + \gamma_{DW} \cdot M_{DW})}{\gamma_{OPT} \cdot M_{LL_C5}}$$

$$RF_{OPT.moment_ST5} := \frac{\phi M_n - (\gamma_{DC} \cdot M_{DC} + \gamma_{DW} \cdot M_{DW})}{\gamma_{OPT} \cdot M_{LL_ST5}}$$

LRFR Load Rating Summary Table

Rating Type		Gross Axle Weight (tons)	Limit	Rating Factor	Rating Factor - Weight (tons)
Vehicle	Rating Level	Weight		RF *	Rating *
HL93	Inventory	36	Moment Strength	0.700	25.2
HL 93	Operating	36	Moment Strength	0.908	32.7
FL120	Permit	60	Moment Strength	0.833	50.0
FL120	Permit	60	Moment Strength	0.833	50.0
SU2	Legal	17	Moment Strength	1.896	32.2
SU3		33	Moment Strength	1.009	33.3
SU 4		35	Moment Strength	0.990	34.7
C3		28	Moment Strength	1.768	49.5
C4		36.7	Moment Strength	1.251	45.9
C5		40	Moment Strength	1.213	48.5
ST5		40	Moment Strength	1.257	50.3

* Per FDOT BLRM, Sectio 7.4 - Posting Avoidance, Rating results for SU4 Legal load computed based on the approximate AASHTO distribution equations may be rounded-up by up to 5%.

Rating Factor (Moment)



Project #: D210107FL00.00
Designed By: YRA
Design Date: Jan-22
Checked By: MAP
Check Date: Jan-22

Matheson Hmk Road over Matheson Hammock Canal
SUMMARY OF LOAD RATING RESULTS

Load Factors:

DL = 1.25 (Load Factor for Dead Load per FDOT BLRM Table 6A.4.2.2-1)
DW = 1.5 (Load Factor for Dead Load from Wearing Surface per FDOT BLRM Table 6A.4.2.2-1)
LL-INV = 1.75 (Load Factor for Design Inventory Live Load per FDOT BLRM Table 6A.4.2.2-1)
LL-OPE = 1.35 (Load Factor for Operating Live Load per FDOT BLRM Table 6A.4.2.2-1)
Factor_{PA} = 5% (Rounding up Factor for Posting Avoidance per FDOT BLRM Section 7.4)

SUMMARY OF LRFR RATINGS - SONOVOID SLAB UNITS (w/ Concrete Repairs and Post Tensioning Restored)														
Rating Type		Gross Axle Weight (tons)	Moment/Shear/ Service		Condition Factor	Live Load Distribution Factor	Design Flexural Strength (kip-ft) **	Unfactored DL Moment (kip-ft) [DC + Attachments]	Unfactored DW Moment (kip-ft) [DW]	Unfactored LL Moment (kip-ft) [LL + IM]	Rating Factor	Governing Location		Rating Factor - Weight (tons)
Vehicle	Rating Level	Weight	Member Type	Limit								Controlling Member [Span # - (Member #)]	Controlling Location (% Span)	
HL93	Inventory	36	Prestressed Concrete	Moment Strength	0.9	0.256	367.50	109.6	8.68	177.43	0.700	2 - 8	50.0	25.2
HL 93	Operating	36	Prestressed Concrete	Moment Strength		0.256					0.908	2 - 8	50.0	32.7
FL120	Permit	60	Prestressed Concrete	Moment Strength		0.256					0.833	2 - 8	50.0	50.0
FL120	Permit	60	Prestressed Concrete	Moment Strength		0.256					0.833	2 - 8	50.0	50.0
SU2	Legal	17	Prestressed Concrete	Moment Strength		0.256					1.896	2 - 8	50.0	32.2
SU3		33	Prestressed Concrete	Moment Strength		0.256					1.009	2 - 8	50.0	33.3
SU 4		35	Prestressed Concrete	Moment Strength		0.256					0.990	2 - 8	50.0	34.7
C3		28	Prestressed Concrete	Moment Strength		0.256					1.768	2 - 8	50.0	49.5
C4		36.7	Prestressed Concrete	Moment Strength		0.256					1.251	2 - 8	50.0	45.9
C5		40	Prestressed Concrete	Moment Strength		0.256					1.213	2 - 8	50.0	48.5
ST5		40	Prestressed Concrete	Moment Strength		0.256					1.258	2 - 8	50.0	50.3

* Per FDOT BLRM, Sectio 7.4 - Posting Avoidance, Rating results for SU4 Legal load computed based on the approximate AASHTO distribution equations may be rounded-up by up to 5%.

** Design Flexural Strength including strengthening repairs using the CFRP wraps (Refer to Appendix C).

APPENDIX D – LRFR BRIDGE RATING MATHCAD QUCIK CHECK

Mathcad Check for VIRTIS LRFD Moment Analysis

Bridge No: 874294

Description: Simply-supported, Prestressed Concrete Sonovoid Slab Units Bridge

Analysis Method: LRFD, HL93 Vehicle, 2 lane

ASSUMPTIONS

CONTROLLING MEMBER: Slab Unit 2-8

GOVERNING LIMIT STATE AND LOCATION: Strength I, Moment @ 0.5L

VIRTIS COMPUTED MOMENTS

$MU := 367.5 \text{ kip}\cdot\text{ft}$	Factored Ultimate Moment (Capacity)
$MDC_{\text{self}} := 87.1 \text{ kip}\cdot\text{ft}$	Dead Load Moment from Selfweight only
$MDW := 8.68 \text{ kip}\cdot\text{ft}$	Wearing Surface Moment
$MLT := 0 \text{ kip}\cdot\text{ft}$	Design Truck Load Moment
$MLL := 177.43 \text{ kip}\cdot\text{ft}$	Controlling Legal Load Moment
$MDC_{\text{attachment}} := 22.5 \text{ kip}\cdot\text{ft}$	Dead Load Moment from Attachments (Curb/Sidewalk + Railing)

FACTORS

$\phi_s := 1.0$	System Factor
$\phi_c := 0.90$	Condition Factor
$\gamma_{DC} := 1.25$	Dead Load Load Factor
$\gamma_{DW} := 1.5$	Wearing Surface Load Factor
$\gamma_{\text{Live}} := 1.75$	Inventory Live Load Factor
$\gamma_{\text{Lopt}} := 1.35$	Operating Live Load Factor
$\phi_{\text{moment}} := 0.90$	Nominal Moment Reduction Factor

DESIGN STRENGTH

$$M_n := \frac{MU}{(\phi_s \cdot \phi_c \cdot \phi_{\text{moment}})} \quad M_n = 453.7 \text{ kip}\cdot\text{ft}$$
$$\phi M_n := \phi_{\text{moment}} \cdot (M_n) \quad \phi M_n = 408.33 \text{ kip}\cdot\text{ft}$$

REQUIRED STRENGTH

$$M_u := \gamma_{DC} \cdot (MDC_{\text{self}} + MDC_{\text{attachment}}) + \gamma_{DW} \cdot MDW + \gamma_{\text{Live}} \cdot (MLL)$$
$$M_u = 460.52 \text{ kip}\cdot\text{ft}$$

RATINGS

$$R_{\text{inventory}} := \frac{\left[\phi_s \cdot \phi_c \cdot \phi_{Mn} - \left[\gamma_{DC} \cdot (MDC_{\text{self}} + MDC_{\text{attachment}}) + \gamma_{DW} \cdot MDW \right] \right]}{\gamma_{\text{Lin}} \cdot (MLL)}$$

$$R_{\text{operating}} := \frac{\left[\phi_s \cdot \phi_c \cdot \phi_{Mn} - \left[\gamma_{DC} \cdot (MDC_{\text{self}} + MDC_{\text{attachment}}) + \gamma_{DW} \cdot MDW \right] \right]}{\gamma_{\text{Lopt}} \cdot (MLL)}$$

$$R_{\text{inventory}} = 0.7$$

$$R_{\text{operating}} = 0.91$$

APPENDIX E – AS-BUILT BRIDGE PLANS

MATHESON HAMMOCK PARK

DADE COUNTY, FLORIDA

BRIDGE AND APPROACH ROAD

*As Built
Plans*



INDEX TO DRAWINGS

Sheet No.	Description
1	APPROACH ROAD PLAN
2	PROFILE
3	CROSS SECTIONS
4	"
5	BRIDGE PLAN & ELEVATION
6	END & INTERMEDIATE BENTS
7	SUPERSTRUCTURE
8	PRESTRESSED SLAB UNITS
9	APPROACH SLAB - PILING
10	MISCELLANEOUS DETAILS
11	BULKHEAD PLAN
12	"
	DETAILS

SITE NUMBER 274

HART-REYNOLDS & ASSOCIATES, INC.
CONSULTING ENGINEERS
CORAL GABLES, FLORIDA




PLAN

- ① *Doing nothing to remain*
- ② *Not existing really.*
- ③ *Remove existing two curves under polygonal paving. Emphasize new 2 x 4s going with rectangles, square surface, in accordance with typical Japanese garden, not existing old hole.*
- ④ *Remove existing retaining wall and embankment. In situation an important new element is introduced. The new element is program paving. Allow for road surface reduction.*
- ⑤ *Remove old topographical features of embankment and landscape. Profile is related to much existing cross-section of lands at river construction.*
- ⑥ *Spill driveway. To be covered under another project. All roads removed from roadway. Some old materials, existing road, existing trees, and some new materials. Embankment material shall be placed in these areas. See construction.*
- ⑦ *Complete existing bridge. See Specifications.*
- ⑧ *Design drainage channel.*
- ⑨ *Terrace to be graded to provide smooth transition between existing embankment and new road. Engineer will establish grades in field.*
- ⑩ *Existing 4" concrete sidewalk goes under main 16" Street 5'.*
- ⑪ *Set storm drain. Set storm 16" on Street 5'.*

DETAIL

WE / AIL






Date	Week	No.	Description
4-17-52	17	1	PA. BENT Lateral Movement



REVISIONS			
No.	Date	By	Description
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			
26			
27			
28			
29			
30			
31			
32			
33			
34			
35			
36			
37			
38			
39			
40			
41			
42			
43			
44			
45			
46			
47			
48			
49			
50			
51			
52			
53			
54			
55			
56			
57			
58			
59			
60			
61			
62			
63			
64			
65			
66			
67			
68			
69			
70			
71			
72			
73			
74			
75			
76			
77			
78			
79			
80			
81			
82			
83			
84			
85			
86			
87			
88			
89			
90			
91			
92			
93			
94			
95			
96			
97			
98			
99			
100			


HART-REYNOLDS & ASSOCIATES, INC.			
CONSULTING ENGINEERS			
CORAL GABLES, FLORIDA			
MATHESON HAMMOCK PARK			
DADE COUNTY, FLORIDA			
BRIDGE AND APPROACH ROAD			
Scale	Sheet	Project No.	Revision
1" = 40'	1	1001	1
1" = 40'	2	1001	2
1" = 40'	3	1001	3
1" = 40'	4	1001	4
1" = 40'	5	1001	5
1" = 40'	6	1001	6
1" = 40'	7	1001	7
1" = 40'	8	1001	8
1" = 40'	9	1001	9
1" = 40'	10	1001	10
1" = 40'	11	1001	11
1" = 40'	12	1001	12
1" = 40'	13	1001	13
1" = 40'	14	1001	14
1" = 40'	15	1001	15
1" = 40'	16	1001	16
1" = 40'	17	1001	17
1" = 40'	18	1001	18
1" = 40'	19	1001	19
1" = 40'	20	1001	20
1" = 40'	21	1001	21
1" = 40'	22	1001	22
1" = 40'	23	1001	23
1" = 40'	24	1001	24
1" = 40'	25	1001	25
1" = 40'	26	1001	26
1" = 40'	27	1001	27
1" = 40'	28	1001	28
1" = 40'	29	1001	29
1" = 40'	30	1001	30
1" = 40'	31	1001	31
1" = 40'	32	1001	32
1" = 40'	33	1001	33
1" = 40'	34	1001	34
1" = 40'	35	1001	35
1" = 40'	36	1001	36
1" = 40'	37	1001	37
1" = 40'	38	1001	38
1" = 40'	39	1001	39
1" = 40'	40	1001	40
1" = 40'	41	1001	41
1" = 40'	42	1001	42
1" = 40'	43	1001	43
1" = 40'	44	1001	44
1" = 40'	45	1001	45
1" = 40'	46	1001	46
1" = 40'	47	1001	47
1" = 40'	48	1001	48
1" = 40'	49	1001	49
1" = 40'	50	1001	50
1" = 40'	51	1001	51
1" = 40'	52	1001	52
1" = 40'	53	1001	53
1" = 40'	54	1001	54
1" = 40'	55	1001	55
1" = 40'	56	1001	56
1" = 40'	57	1001	57
1" = 40'	58	1001	58
1" = 40'	59	1001	59
1" = 40'	60	1001	60
1" = 40'	61	1001	61
1" = 40'	62	1001	62
1" = 40'	63	1001	63
1" = 40'	64	1001	64
1" = 40'	65	1001	65
1" = 40'	66	1001	66
1" = 40'	67	1001	67
1" = 40'	68	1001	68
1" = 40'	69	1001	69
1" = 40'	70	1001	70
1" = 40'	71	1001	71
1" = 40'	72	1001	72
1" = 40'	73	1001	73
1" = 40'	74	1001	74
1" = 40'	75	1001	75
1" = 40'	76	1001	76
1" = 40'	77	1001	77
1" = 40'	78	1001	78
1" = 40'	79	1001	79
1" = 40'	80	1001	80
1" = 40'	81	1001	81
1" = 40'	82	1001	82
1" = 40'	83	1001	83
1" = 40'	84	1001	84
1" = 40'	85	1001	85
1" = 40'	86	1001	86
1" = 40'	87	1001	87
1" = 40'	88	1001	88
1" = 40'	89	1001	89
1" = 40'	90	1001	90
1" = 40'	91	1001	91
1" = 40'	92	1001	92
1" = 40'	93	1001	93
1" = 40'	94	1001	94
1" = 40'	95	1001	95
1" = 40'	96	1001	96
1" = 40'	97	1001	97
1" = 40'	98	1001	98
1" = 40'	99	1001	99
1" = 40'	100	1001	100

1/2" = 10' 0"



STATIONS			
Station	Back	By	Project
11+70			
11+80			
11+90			
12+00			
12+10			
12+20			


HART-REYNOLDS & ASSOCIATES, INC.			
CONSULTING ENGINEERS			
CORAL GABLES, FLORIDA			
MATHESON HAMMOCK PARK			
DADE COUNTY, FLORIDA			
BRIDGE AND APPROACH ROAD			
Sheet No. 11-01	Scale	1" = 10'	3
Project No. 11-01	Scale	1" = 10'	3
Section No. 11-01	Scale	1" = 10'	3
CROSS SECTIONS			



1+00



1+20



1+40



1+60



1+80



2+00

ROAD TO
BEACH FACILITIES



18+40




18+60



18+80




19+00



19+20



19+40





19+60

Revised	By	No.	Revised	By	No.
1			2		
3			4		
5			6		
7			8		
9			10		
11			12		
13			14		
15			16		
17			18		
19			20		
21			22		
23			24		
25			26		
27			28		
29			30		
31			32		
33			34		
35			36		
37			38		
39			40		
41			42		
43			44		
45			46		
47			48		
49			50		
51			52		
53			54		
55			56		
57			58		
59			60		
61			62		
63			64		
65			66		
67			68		
69			70		
71			72		
73			74		
75			76		
77			78		
79			80		
81			82		
83			84		
85			86		
87			88		
89			90		
91			92		
93			94		
95			96		
97			98		
99			100		


HART-REYNOLDS & ASSOCIATES, INC.
CONSULTING ENGINEERS
CORAL GABLES, FLORIDA

MATHESON HAMMOCK PARK
DADE COUNTY, FLORIDA
BRIDGE AND APPROACH ROAD

Drawn: C. L. H.
Check: H. L. N.
Date: JUNE 1961
Project No.: 10-01
Sheet No.: 4
CROSS SECTIONS



**INTERMEDIATE BENT
COLUMN AND FOOTING DETAILS**




REVISIONS		REVISIONS	
No.	By	No.	By
1	10/1/41	2	10/1/41
3	10/1/41	4	10/1/41
5	10/1/41	6	10/1/41
7	10/1/41	8	10/1/41
9	10/1/41	10	10/1/41
11	10/1/41	12	10/1/41
13	10/1/41	14	10/1/41
15	10/1/41	16	10/1/41
17	10/1/41	18	10/1/41
19	10/1/41	20	10/1/41
21	10/1/41	22	10/1/41
23	10/1/41	24	10/1/41
25	10/1/41	26	10/1/41
27	10/1/41	28	10/1/41
29	10/1/41	30	10/1/41
31	10/1/41	32	10/1/41
33	10/1/41	34	10/1/41
35	10/1/41	36	10/1/41
37	10/1/41	38	10/1/41
39	10/1/41	40	10/1/41
41	10/1/41	42	10/1/41
43	10/1/41	44	10/1/41
45	10/1/41	46	10/1/41
47	10/1/41	48	10/1/41
49	10/1/41	50	10/1/41
51	10/1/41	52	10/1/41
53	10/1/41	54	10/1/41
55	10/1/41	56	10/1/41
57	10/1/41	58	10/1/41
59	10/1/41	60	10/1/41
61	10/1/41	62	10/1/41
63	10/1/41	64	10/1/41
65	10/1/41	66	10/1/41
67	10/1/41	68	10/1/41
69	10/1/41	70	10/1/41
71	10/1/41	72	10/1/41
73	10/1/41	74	10/1/41
75	10/1/41	76	10/1/41
77	10/1/41	78	10/1/41
79	10/1/41	80	10/1/41
81	10/1/41	82	10/1/41
83	10/1/41	84	10/1/41
85	10/1/41	86	10/1/41
87	10/1/41	88	10/1/41
89	10/1/41	90	10/1/41
91	10/1/41	92	10/1/41
93	10/1/41	94	10/1/41
95	10/1/41	96	10/1/41
97	10/1/41	98	10/1/41
99	10/1/41	100	10/1/41


HART-REYNOLDS & ASSOCIATES, INC.
CONSULTING ENGINEERS
CORPORATION
CORPORATION
CORPORATION

MATHESON HAMMOCK PARK
DADE COUNTY, FLORIDA
BRIDGE AND APPROACH ROAD

Sheet No. 6 of 12 Sheets




PROFILE OF BRIDGE DECK




SECTION A-A



SECTION B-B



SECTION C-C



PLAN

REVISIONS			
No.	Date	Description	By
1	JAN 1961	Initial design	J.R.
2	FEB 1961	Revised design	J.R.
3	MAR 1961	Final design	J.R.

HART-REYNOLDS & ASSOCIATES, INC.
CONSULTING ENGINEERS
CORAL GABLES, FLORIDA

MATHESON HAMMOCK PARK
DADE COUNTY, FLORIDA
BRIDGE AND APPROACH ROAD

Project No. 1-100

Sheet No. 7


Scale: 1" = 10'-0"

Superstructure




BRIDGE FRAMING PLAN


UNIT	NO.	DESCRIPTION
UNIT	1	UNIT 1
UNIT	2	UNIT 2
UNIT	3	UNIT 3
UNIT	4	UNIT 4
UNIT	5	UNIT 5
UNIT	6	UNIT 6
UNIT	7	UNIT 7
UNIT	8	UNIT 8
UNIT	9	UNIT 9
UNIT	10	UNIT 10



UNIT A, D, E, F



UNIT A, B, C, G, H



UNIT A, B, C, D, E, F, G, H



PLAN - PRESTRESSED UNITS

SECTION A-A


REVISIONS		Description	
No.	Date	No.	Date
1	10/1/54	1	10/1/54
2	10/1/54	2	10/1/54
3	10/1/54	3	10/1/54
4	10/1/54	4	10/1/54
5	10/1/54	5	10/1/54
6	10/1/54	6	10/1/54
7	10/1/54	7	10/1/54
8	10/1/54	8	10/1/54

HART-REYNOLDS & ASSOCIATES, INC.
CORAL GABLES, FLORIDA

MATHESON HAMMOCK PARK
DADE COUNTY, FLORIDA
BRIDGE AND APPROACH ROAD

PRESTRESSED SLAB UNIT


8



APPROACH SLAB SECTION A-A



APPROACH SLAB SECTION B-B



PILE POINT PICK-UP

NOTE: See note on sheet of these details for details of pile point pick-up.



SECTION

PILE POINT PICK-UP



SECTION

PILE POINT PICK-UP



ELEVATION

14'0" PRESTRESSED CONCRETE PILE

APPROACH SLAB PLAN

NOTE: See note on sheet of these details for details of pile point pick-up.


PLAN and approach slab details.

HART-REYNOLDS & ASSOCIATES, INC.
CONSULTING ENGINEERS
CORAL GABLES, FLORIDA

MATHESON HAMMOCK PARK
DADE COUNTY, FLORIDA
BRIDGE AND APPROACH ROAD

REV.	DATE	BY	DESCRIPTION
1	JUNE 1961		APPROACH SLAB - PILING
2			
3			
4			
5			
6			
7			
8			
9			


Sheet 9 of 12



SECTION 1-1




SECTION 2-2



SECTION 3-3

SECTION 4-4



SECTION 5-5




SECTION 6-6




SECTION 7-7


SECTION 8-8



SECTION 9-9



SECTION 10-10




SECTION 11-11


SECTION 12-12

REVISIONS		DATE		BY	
1	AS NOTED	10/1/50	10/1/50	10/1/50	10/1/50
<p>HART REYNOLDS & ASSOCIATES, INC. CONSULTING ENGINEERS 1000 BAYVIEW BLVD., SUITE 100 MIAMI BEACH, FLORIDA</p> <p>MATHESON HAMMOCK PARK DADE COUNTY, FLORIDA BRIDGE AND APPROACH ROAD</p> <p>Drawn by: J. H. R. H. L. B. Checked by: J. H. R. H. L. B. Date: JUNE 1951 Project No.: H-10 Sheet No.: 10 Miscellaneous Details</p>					

2




PART PLAN
Scale: 1/4" = 1'-0"



TYPICAL SECTION
Scale: 1/4" = 1'-0"

ALTERNATE TIE ROD DETAIL
Not To Scale



SECTION AND ELEVATION
Scale: 1/4" = 1'-0"



PRECAST RETAINING SLAB DETAIL
Scale: 1/4" = 1'-0"



CHANNEL MURDER DETAIL
Scale: 1/4" = 1'-0"

Revised	By	Date	Check	By	Date
REVISIONS HART-REYNOLDS & ASSOCIATES, INC. CONSULTING ENGINEERS CORAL GABLES, FLORIDA					
MATHESON HAMMOCK PARK DADE COUNTY, FLORIDA BRIDGE AND APPROACH ROAD					
Sheet	CLN	CLN	CLN	CLN	CLN
Project No.	10-10	10-10	10-10	10-10	10-10
Scale	1/4" = 1'-0"	1/4" = 1'-0"	1/4" = 1'-0"	1/4" = 1'-0"	1/4" = 1'-0"
Drawn	A.T. Green	Checked	A.T. Green	Designated	A.T. Green
BRIDGE DETAILS of 12 sheets					

**APPENDIX F – FDOT BRIDGE INSPECTION REPORT AND SUBSEQUENT INTERIM
REPORTS**



BRIDGE INSPECTION REPORT

PREPARED FOR: FDOT District 6
 BRIDGE OWNER: MIAMI-DADE COUNTY
 INSPECTION TYPE: Regular NBI
 CONTRACT No. CA611

Inspected by:
Marlin Engineering, Inc.

Bridge No. 874294

REPORT CONTAINS

Inspection Date: 4-06-2020


- | | | | |
|-----------------------------------------------------------|----------------------------------------------------------|---------------------------------------------------------------|---------------------------------------------------------|
| <input checked="" type="checkbox"/> BrM Inspection Report | <input checked="" type="checkbox"/> Bridge Profile | <input type="checkbox"/> Fracture Critical Data | <input type="checkbox"/> Addendum |
| <input checked="" type="checkbox"/> CIDR Information | <input checked="" type="checkbox"/> UW Inspection Report | <input checked="" type="checkbox"/> Load Rating Summary Sheet | <input type="checkbox"/> Mechanical and Electrical Data |



**Matheson Hammock Road over
 Matheson Hammock Canal**

Facility Carried & Location

Matheson Hammock Park



Location Map

Detour Length = N/A

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294**DISTRICT: D6 - Miami****INSPECTION DATE: 4/6/2020 GZJW**

BY:	Marlin Engineering, Inc.	STRUCTURE NAME:	Not recorded
OWNER:	2 County Hwy Agency	YEAR BUILT:	1967
MAINTAINED BY:	2 County Hwy Agency	SECTION NO.:	87 000 757
STRUCTURE TYPE:	5 Prestressed Concrete - 01 Slab	MP:	0.080
LOCATION:	Matheson Hammock Park	ROUTE:	00000
SERV. TYPE ON:	5 Highway-pedestrian	FACILITY CARRIED:	Matheson Hmk Road
SERV. TYPE UNDER:	5 Waterway	FEATURE INTERSECTED:	Matheson Hammock Canal

☐ FUNCTIONALLY OBSOLETE ☒ STRUCTURALLY DEFICIENT

TYPE OF INSPECTION: Regular NBI

DATE FIELD INSPECTION WAS PERFORMED: ABOVE WATER: 4/6/2020 UNDERWATER: 4/6/2020

SUFFICIENCY RATING: 15.5
HEALTH INDEX: 86.68

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection**

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW

BY: Marlin Engineering, Inc.	STRUCTURE NAME: Not recorded
OWNER: 2 County Hwy Agency	YEAR BUILT: 1967
MAINTAINED BY: 2 County Hwy Agency	SECTION NO.: 87 000 757
STRUCTURE TYPE: 5 Prestressed Concrete - 01 Slab	MP: 0.080
LOCATION: Matheson Hammock Park	ROUTE: 00000
SERV. TYPE ON: 5 Highway-pedestrian	FACILITY CARRIED: Matheson Hmk Road
SERV. TYPE UNDER: 5 Waterway	FEATURE INTERSECTED: Matheson Hammock Canal

- ☐ THIS BRIDGE CONTAINS FRACTURE CRITICAL COMPONENTS
- ☐ THIS BRIDGE IS SCOUR CRITICAL
- ☒ THIS REPORT IDENTIFIES DEFICIENCIES WHICH REQUIRE PROMPT CORRECTIVE ACTION
- ☐ FUNCTIONALLY OBSOLETE ☒ STRUCTURALLY DEFICIENT

TYPE OF INSPECTION: Regular NBI

DATE FIELD INSPECTION WAS PERFORMED: ABOVE WATER: 4/6/2020 UNDERWATER: 4/6/2020

OVERALL NBI RATINGS:

DECK: 3 Serious	CHANNEL: 6 Bank Slumping
SUPERSTRUCTURE: 3 Serious	CULVERT: N N/A (NBI)
SUBSTRUCTURE: 4 Poor	SUFF. RATING: 15.5
PERF. RATING: Poor	HEALTH INDEX: 86.68

FIELD PERSONNEL / TITLE / NUMBER:**INITIALS**

Porras, Omar - Senior Diver Bridge Inspector (CBI#0368) (lead)

Gomez, Hiram - Bridge Inspector Assistance

Jacob Popp - Bridge Inspector Assistance, Diver

Burgos, Daniel - Bridge Inspector Assistance, Diver

Campo, Luis - Bridge Inspector Assistant

REVIEWING BRIDGE INSPECTION SUPERVISOR:

Rego, Alexis - Bridge Inspector (CBI#00409)


CONFIRMING REGISTERED PROFESSIONAL ENGINEER:

Vers, Julie - Structural Design Manager (P.E. # 77896) Marlin Engineering
1700 NW 66 Avenue
Suite 106
Plantation Florida 33313

SIGNATURE: _____

DATE: _____

The official record of this package has been electronically signed and sealed by Julie A. Vers, P.E. on the date adjacent to the seal as required by Rule 61G15-23.004, F.A.C.. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.



This report contains information relating to the physical security of a structure and depictions of the structure. This information is confidential and exempt from public inspection pursuant to sections 119.071(3)(a) and 119.071(3)(b), Florida Statutes. Only the cover page of this report may be inspected and copied.

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW

All Elements

DECKS : Decks/Slabs

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8099 / 3	PS Conc Slab (Sonovoid)	3178	89.88	114	3.22	244	6.9	0	.	3536 (SF)
0	1080 / 3	Delamination/Spall/Patched Area	0	.	114	59.07	79	40.93	0	.	193 (SF)
0	1090 / 3	Exposed Rebar	0	.	0	.	1	100	0	.	1 (SF)
0	1100 / 3	Exposed Prestressing	0	.	0	.	20	100	0	.	20 (SF)
0	1110 / 3	Cracking (PSC)	0	.	0	.	144	100	0	.	144 (SF)
0	510 / 3	Wearing Surfaces	1929	73.23	0	.	705	26.77	0	.	2634 sq.ft
0	3220 / 3	Crack (Wearing Surface)	0	.	0	.	705	100	0	.	705 sq.ft

Element Inspection Notes:

8099/3 Notes: The top of the slab units is not visible due to an asphalt overlay. The width of the sonovoid slab units was field verified to be 3ft. wide.

SECONDARY:

_Object markers and centerline raised pavement markers are missing on the structure. Refer to Photo 01. NO CHANGE.
 _Sidewalk panels are loose and moves under pedestrian load. Refer to Photo 02. NO CHANGE.
 _The slab unit joints show evidence of water seepage. NO CHANGE. NCAR.

PREVIOUS RECOMMENDED CORRECTIVE ACTION:

_Replace the southern utility access panel of Span 1.
 _Shim all sidewalk panels throughout the structure.
 _Rehab/replace slab units 1-7, 1-8, 2-7, 2-8, 3-7 and 3-8.
 _Clean efflorescence on slab units 1-6 and 1-7 to monitor the cracks.
 _Repair cracks on slab units 1-6, 1-9, 2-6, 2-9, 3-6.
 _Repair spalled/delaminated areas on slab units 1-6, 1-9, 2-6, 2-9, and 3-6 as needed.

CORRECTIVE ACTION EVALUATION:

_The recommendation noted above was completed.
 _The recommendation noted above was not completed. Recommendation will be repeated.
 _The recommendation noted above was not completed. Recommendation will be repeated.
 _The recommendation noted above was not completed. Recommendation will be repeated.
 _The recommendation noted above was not completed. Recommendation will be repeated

Refer to Defects 1080, 1090, 1100, and 1110 for additional deficiencies.

1080/3

CS-3:

_Slab Unit 1-8 east edge has a spall/delamination 4ft. L x 15in. W x 2in. D and associated cracks with corrosion bleed-out near mid-span. Previously noted a delamination with associated cracks. (Total 8 SF) Refer to Photo 03. INCREASE.
 _Slab Unit 1-9, center line has a spall/delamination up to 36in. L x 24in. W x 2in. D over Abutment 1. (Total 6 SF) Refer to Photo 04. NO CHANGE.
 _Slab Unit 3-7 has an unsound repaired area 11ft. L x 2ft. W starting from Abutment 4 with hollow sounding throughout and associated cracks up to 1/16in. W with efflorescence and corrosion bleed-out. (Total 22 SF) Refer to Photo 05. NO CHANGE.
 _Slab Unit 3-8 has a spall/delamination up to 7ft. L x 3ft. W x 1in. D and associated cracks with corrosion bleed-out starting at Pier 3. (Total 21 SF) Refer to Photo 06. NO CHANGE.
 _Slab Unit 3-8 west edge has an unsound repaired area 11ft. L x 18in. W starting from Abutment 4 with hollow sounding throughout and associated cracks up to 1/16in. W with efflorescence. (Total 22 SF) NO CHANGE.

CS-2:

This report contains information relating to the physical security of a structure and depictions of the structure. This information is confidential and exempt from public inspection pursuant to sections 119.071(3)(a) and 119.071(3)(b), Florida Statutes. Only the cover page of this report may be inspected and copied.

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW

_Slab Unit 1-6, east edge has a delamination up to full length x 12in. W starting at Pier 2 cap. Previously noted as 3in. W. (Total 30 SF) INCREASE.

_Slab Unit 1-7, east edge has a delamination 7ft. L x 4in. W, starting at Pier 2 cap. (Total 7 SF) NEW.

_Slab Unit 1-9, west edge has a delamination up to 10ft. L x 14in. W, starting at Pier 2 cap. (Total 10 SF) NO CHANGE.

_Slab Unit 2-6, east edge has a delamination 30in. L x 4in. W starting at Pier 2 cap. (Total 3 SF). Refer to Photo 07. NO CHANGE.

_Slab Unit 2-7, west edge has a delamination up to 24in. L x 4in. W starting at Pier 2 cap. (Total 2 SF) Refer to Photo 07. NO CHANGE.

_Slab Unit 2-8 west half has two delaminated areas up to 15ft. L x 18in. W (average width) at south and north ends. (Total 60 SF). Refer to Photo 08. NO CHANGE.

_Slab Unit 3-6 has a delamination up to 24in. L x 6in. W on the east edge over Pier 3. (Total 2 SF) NO CHANGE.

1090/3

CS-3:

_Slab Unit 1-6 exhibits a spall with exposed rebar up to 15in. L x 6in. W x 1/2in. D with evidence of previous failed repair, at 9ft. from Abutment 1. (Total 1 SF) Refer to Photo 09. NO CHANGE.

1100/3

CS-3:

_Slab Unit 2-8 has a spall 10ft. L x 24in. W x up to 4in. D at mid-span with 6 exposed and corroded transverse rebars with up to 60% section remaining and 5 exposed and corroded prestressing strands with up to 0% section remaining (2 broken threads). (Total 20 SF) Refer to Photos 08 and 10. NO CHANGE.

1110/3

CS-3:

_Slab Unit 1-6 east edge has a delamination area full length x 12in. W with associated cracks up to 1/16in. W with efflorescence throughout. Previously noted as a delamination full length x 3in. W. (Total 30 SF) INCREASE.

_Slab Unit 1-7 east edge has a spall/delamination 24in. L x 12in. W with associated cracks up to 1/32in. W with efflorescence and corrosion bleed-out over Abutment 1. No corrosion bleed out was previously noted. (Total 2 SF) Refer to Photo 11. INCREASE.

_Slab Unit 1-8 west edge is intermittently delaminated up to 15ft. L x 15in. W with associated cracks up to 1/8in. W with efflorescence and corrosion bleed-out, starting at Abutment 1. (Total 15 SF) Refer to Photo 11. NO CHANGE.

_Slab Unit 1-8 has a delaminated area up to 7ft. L x 3ft. W and associated cracks up to 1/16in. W with efflorescence and corrosion bleed-out. (Total 21 SF) NO CHANGE.

_Slab Unit 1-9 west edge has a delaminated area 8ft. L x 10in. W and associated cracks up to 1/16in. W with efflorescence and corrosion bleed-out, starting near the 3/4 point and extending to Pier 2 cap. (Total 8 SF) NO CHANGE.

_Slab Unit 2-7 east edge is intermittently cracked/delaminated up to span length x 16in. W (average width). (Total 38 SF) NO CHANGE.

_Slab Unit 2-9 west edge has a delaminated area up to 5ft. L x 5in. W with associated cracking up to 1/4in. wide, starting at the Pier 2 cap. (Total 5 SF). NO CHANGE.

_Slabs Unit 3-7 has two delaminated areas, one starting at Pier 3 up to 8ft. L x 15in. W (average width) with associated cracks, and the second, near mid-span up to 3ft. L x 30in. W. (Total 25 SF) NO CHANGE.

510/3

PREVIOUS RECOMMENDED CORRECTIVE ACTION:

_Repair the asphalt overlay over the expansion joints and slab unit joints as needed.

CORRECTIVE ACTION EVALUATION:

_The corrective action noted above was not completed. Recommendation will be repeated.

Refer to Defect 3220 for deficiencies.

3220/3

CS-3:

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW

_The asphalt overlay has longitudinal cracks up to span length x 1/4in. W with associated rutting over the slab unit joints with upheaving up to 1in. H at the shoulders, possibly indicating independent slab units movement. (Total 600 SF) Refer to Photo 12. NO CHANGE.

_The asphalt overlay has transverse cracks up to roadway width x 1/4in. W with rutting and upheaving up to 3in. H and vegetation growth over the expansion joints. (Total 105 SF) Refer to Photo 13. NO CHANGE.

DECKS : Joints

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	301 / 3	Pourable Joint Seal	0	.	0	.	104	74.29	36	25.71	140 ft
0	2310 / 3	Leakage	0	.	0	.	104	100	0	.	104 ft
0	2330 / 3	Seal Damage	0	.	0	.	0	.	36	100	36 ft

Element Inspection Notes:

301/3 Note: The roadway joints are not visible due to an asphalt overlay.

PREVIOUS RECOMMENDED CORRECTIVE ACTION:

_Clean and seal the expansion joints.

CORRECTIVE ACTION EVALUATION:

_The corrective action noted above was not completed. Recommendation will be repeated.

Refer to Defects 2310 and 2330 for deficiencies.

2310/3 CS-3:
_There is evidence of moderate to heavy water seepage through the expansion joints on bents and abutment caps. (Total 104 LF) Refer to Photo 14. NO CHANGE. NCAR.

2330/3 CS-4:
_The sealant along the sidewalk expansion joints has deteriorated. (Total 36 LF) Refer to Photo 15. NO CHANGE.

MISCELLANEOUS : Channel

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8290 / 3	Channel	0	.	0	.	1	100	0	.	1 (EA)
0	9150 / 3	Bank Erosion	0	.	0	.	1	100	0	.	1 (EA)

Element Inspection Notes:

8290/3 FROM THE 2020 UNDERWATER INSPECTION:

Divers conducting the Underwater Inspection. Refer to Photo 16.

PREVIOUS RECOMMENDED CORRECTIVE ACTION:

_Repair undermining areas at the north seawall.

CORRECTIVE ACTION EVALUATION:

_The corrective action noted above was not completed. Recommendation will be repeated.

Refer to Defect 9150 for deficiencies.

9150/3 CS-3:
_There are two areas of undermining up to 22ft. L x 3in. H x 21in. of penetration with backfill migration under the north seawall, below Slab Units 2-2 and 2-5. Previously noted

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW

undermining up to 22ft. L x 9in. H x 21in. of penetration. (Total 1 ea.) Refer to Photo
 17. NO CHANGE.

MISCELLANEOUS : Other Elements

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	321 / 3	Re Conc Approach Slab	1410	100	0	.	0	.	0	.	1410 sq.ft
0	510 / 3	Wearing Surfaces	957	91.14	0	.	93	8.86	0	.	1050 sq.ft
0	3220 / 3	Crack (Wearing Surface)	0	.	0	.	93	100	0	.	93 sq.ft

Element Inspection Notes:

321/3 Note: The approach slabs are not visible due to an asphalt overlay.

SECONDARY:

_There are several approach roadway guardrails posts spalled/delaminated up to 14in. H x 3.5in. W x 1-1/4in D with exposed and corroded rebars at the following locations: NW guardrail, Posts 1, 2, 3, and 4, SW guardrail, Posts 2 and 4 from the bridge, SE guardrail, Post 1 from the bridge. Post 4 in NW guardrail was not previously noted. Refer to Photo 18. INCREASE.

_The approach guardrail panels exhibit moderate to heavy corrosion with numerous corrosion holes throughout. Refer to Photo 19. NO CHANGE.

PREVIOUS RECOMMENDED CORRECTIVE ACTION:

_Replace the approach guardrail panels and posts.

CORRECTIVE ACTION EVALUATION:

_The corrective action noted above was not completed. Recommendation will be repeated.

510/3 Refer to Defect 3220 for deficiencies.

3220/3 CS-3:

_The asphalt over the north approach slab has two longitudinal ravel cracks up to slab length x 1/8in. W in Lanes 1 and Lane 2. Previously noted cracks up to 1/16in. W (Total 40 SF) INCREASE. NCAR.

_The asphalt in both approach slab to approach roadway transitions has a transverse crack up to roadway width x 1/4in. W. (Total 53 SF) NO CHANGE. NCAR.

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	205 / 3	Re Conc Column	0	.	0	.	4	100	0	.	4 each
0	1090 / 3	Exposed Rebar	0	.	0	.	1	100	0	.	1 each
0	1130 / 3	Cracking (RC and Other)	0	.	0	.	3	100	0	.	3 each

Element Inspection Notes:

205/3 Note: At high tide, the seawater reaches the lower section of the columns.

PREVIOUS RECOMMENDED CORRECTIVE ACTION:

_Repair delaminated areas in columns.

CORRECTIVE ACTION EVALUATION:

_The corrective action noted above was not completed. Recommendation will be repeated.

Refer to Defects 1090 and 1130 for deficiencies.

1090/3 CS-3:

_Column 2-2, south face has a spall/delamination up to 7ft. H x 3ft. W x 3in. D with one

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW

exposed rebar and one stirrup, having areas of up to 80% section remaining. Additionally, there are areas of delamination around the column circumference covering the entire column height with associated cracks up to 1/4in. W. No exposed rebar was previously noted. (Total 1 ea.) Refer to Photo 20. INCREASE.

1130/3

CS-3:

_Columns 2-1, 3-1, and 3-2 have delaminated areas along their entire length with associated cracks up to full height x 1/16in. W, as a result of corrosion of the steel reinforcement. (Total 3 ea.) Refer to Photo 21. NO CHANGE.

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	215 / 3	Re Conc Abutment	65	92.86	0	.	5	7.14	0	.	70 ft
0	1080 / 3	Delamination/Spall/Patched Area	0	.	0	.	5	100	0	.	5 ft

Element Inspection Notes:

215/3

Refer to Defect 1080 for deficiencies.

1080/3

CS-3:

_Abutment 4 cap has a spall/delamination up to 5ft. L x full height x 2in. D with associated cracks up to 1/16in. W under Slab Units 3-10 and 3-11. (Total 5 LF) Refer to Photo 22. NEW.

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	234 / 3	Re Conc Pier Cap	49	72.06	12	17.65	7	10.29	0	.	68 ft
0	1080 / 3	Delamination/Spall/Patched Area	0	.	12	63.16	7	36.84	0	.	19 ft

Element Inspection Notes:

234/3

SECONDARY:

_Bents 2 and 3 caps have vegetation growth along the west end. Refer to Photo 23. NO CHANGE.

PREVIOUS RECOMMENDED CORRECTIVE ACTION:

_Remove vegetation from west end of caps.
 _Repair delaminations in Pier 2 and 3 caps.

CORRECTIVE ACTION EVALUATION:

_The corrective action noted above was not completed. Recommendation will be repeated.
 _The corrective action noted above was not completed. Recommendation will be repeated.

Refer to Defect 1080 for additional deficiencies.

1080/3

CS-3:

_Bent 2 cap has a spall/delamination up to 3ft. L x 16in. H x 1 in. D on the south face over Column 2-2, and on the same location, north face a delamination 20in. L x 12in. H. Previously noted only a delamination 3ft. L x 16in. H. (Total 3 LF) Refer to Photo 24. INCREASE.
 _Bent 3 cap, bottom and north faces has two unsound repaired areas with multidirectional cracks up to 1/64in. W. No unsound concrete with cracks was previously noted. (Total 4 LF) INCREASE.

CS-2:

_Pier 3 cap has intermittent delaminated areas up to 3ft. L x 16in. H between Columns 3-1 and 3-2, along the top and bottom north edges. Previously noted delaminations up to 3ft. L

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW

x 16in. H totaling 5 LF. (Total 12 LF) INCREASE.

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8393 / 3	Bulkhead Seawall Any Materia	0	.	0	.	354	100	0	.	354 ft
0	1130 / 3	Cracking (RC and Other)	0	.	0	.	314	100	0	.	314 ft
0	6000 / 3	Scour	0	.	0	.	40	100	0	.	40 ft

Element Inspection Notes:

8393/3 Note: This element represents the concrete seawall that lines both sides of the channel. The seawall is underwater during high tide. The seawalls have a total of 44 piles; 22 piles at each seawall.

SECONDARY:

_The brackets and fasteners attaching the clearance gauges to the seawalls exhibit heavy to severe corrosion. Refer to Photo 25.

FROM THE 2020 UNDERWATER INSPECTION:**SECONDARY:**

_SE and NW clearance gauges have moderate decay at bottom 3ft. Refer to Photo 26. NO CHANGE.

_The south seawall has two open joints up to 4in. W with backfill leakage behind Piles 15 and 18 from west. Refer to Photo 27. NO CHANGE.

PREVIOUS RECOMMENDED CORRECTIVE ACTION:

_Clean & seal cracks & repair delaminations/spalls in seawall caps.

_Seal open joints at the south seawall behind Piles 15 and 18.

CORRECTIVE ACTION EVALUATION:

_The corrective action noted above was not completed. Recommendation will be repeated.

_The corrective action noted above was not completed. Recommendation will be repeated.

Refer to Defects 1130 and 6000 for additional deficiencies.

1130/3

CS-3:

_The seawall caps on the north and south walls have up to 1/4in W cracks, with associated delaminations/spalls throughout their entire lengths. (Total 314 LF) Refer to Photo 28. NO CHANGE.

_The south seawall at Pile 13, SE corner has a spall 14in. H x 3-1/2in. W x 1in. D, 3ft. 9in. below cap. NO CHANGE. NCAR.

_South seawall piles have vertical cracks up to 31in. L x 1/8in. W, some with corrosion bleed out as follows: NO CHANGE. NCAR.

-Pile 3, NE corner has a crack, and west, north and east faces have cracks with corrosion bleed out.

-Pile 4, north face has a crack with corrosion bleed out.

-Pile 16, east face has a crack with corrosion bleed out.

-Pile 17, west, north and east faces have cracks with corrosion bleed out.

-Piles 19, 20 and 21, SW and SE corners have cracks.

_North seawall piles have vertical cracks intermittently throughout, up to 34in. L x 1/16in. W, some with corrosion bleed out as follows: NO CHANGE. NCAR.

-Piles 5 and 6, SW and SE corners have cracks with corrosion bleed out.

-Pile 3, SW corner has a crack.

-Pile 4, NW corner has a crack.

-Piles 7, 8, 10, 12, 13, 14, 15, 16, 17, 18, 19, 20, 23 have cracks in the SW and SE corners.

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW

-Pile 11, SE corner has a crack.

6000/3 From the 2020 Underwater Inspection:

CS-3:

_There are two areas of undermining up to 22ft. L x 9in. H x 21in. of penetration with backfill migration under the north seawall, below Slab Units 2 and 5. Refer to Element 8290 for related comments and recommended corrective actions. (Total 40 LF) NO CHANGE.

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8394 / 3	R/Conc Abut Slope Protection	3968	73.81	0	.	1408	26.19	0	.	5376 (SF)
0	1130 / 3	Cracking (RC and Other)	0	.	0	.	320	100	0	.	320 (SF)
0	4000 / 3	Settlement	0	.	0	.	1088	100	0	.	1088 (SF)

Element Inspection Notes:

8394/3 Note: At high tide, the seawater reaches the lower section of the concrete slope pavement.

SECONDARY:

_There is vegetation growth in the joints between the panels of slope protection in several locations. NO CHANGE. NCAR.

PREVIOUS RECOMMENDED CORRECTIVE ACTION:

_Repair settled & fractured sections of slope pavement.

CORRECTIVE ACTION EVALUATION:

_The corrective action noted above was not completed. Recommendation will be repeated.

Refer to Defects 1130 and 4000 for additional deficiencies.

1130/3 CS-3:
_The slope pavement has multidirectional cracks up to 5ft. L x 1/8in. W along the NE corner near the toe. (Total 320 SF) NO CHANGE. NCAR.

4000/3 CS-3:
_The top slope pavement section along the SW and NW corners has settled up to 4in. H. (Total 933 SF) NO CHANGE.
_The slope protection toe has a fractured and settled area of 15ft. x 7ft. x 2ft deep at the NW corner behind the seawall cap. Possibly due to water reaching this area at high tide, no undermining or backfill migration are noted in the channel adjacent area. (Total 105 SF) Refer to Photo 29. NO CHANGE.
_The SW slope protection toe has 5 fractured panels that have settled up to 3in. H. Possibly due to water reaching this area at high tide, no undermining or backfill migration are noted in the channel adjacent area. (Total 50 SF) Refer to Photo 30. NO CHANGE.

SUPERSTRUCTURE : Superstructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	333 / 3	Other Bridge Railing	167	83.5	33	16.5	0	.	0	.	200 ft
0	1000 / 3	Corrosion	0	.	30	100	0	.	0	.	30 ft
0	1020 / 3	Connection	0	.	3	100	0	.	0	.	3 ft

Element Inspection Notes:

333/3 Note: This element represents the concrete post and beam bridge rail with

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW

aluminum handrail on top across both sides of the structure.

CS-1:

_The concrete bridge rail beams have 1/64in W cracks at the junctures with the posts in several locations. NO CHANGE. NCAR.

PREVIOUS RECOMMENDED CORRECTIVE ACTION:

_Replace the approach guardrail panels and posts.

_Replace the missing railing nuts on left side of Bent 3.

_Clean & coat the corroded nuts of railing.

CORRECTIVE ACTION EVALUATION:

_The corrective action noted above was not completed. Recommendation will be repeated.

_The corrective action noted above was not completed. Recommendation will be repeated.

_The corrective action noted above was not completed. Recommendation will be repeated.

Refer to Defects 1000 and 1020 for additional deficiencies.

1000/3

CS-2:

_The rail anchor bolt nuts and washers have moderate corrosion at random locations: 25 nuts at west railing, and 5 nuts at east railing. (Total 30 LF) Refer to Photo 31. NO CHANGE.

1020/3

CS-2:

_There are several missing anchor bolt nuts at the aluminium rail posts at the following locations: (Total 3 ea.) Refer to Photo 32. INCREASE.

_West rail, Post 1-1 is missing 1 of 4 nuts. NEW.

_West rail, Post 2-6 is missing 2 of 4 nuts. NO CHANGE.

_East rail, Post 1-5 is missing 1 of 4 nuts. NEW.

Total Number of Elements*: 10

*excluding defects/protective systems

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW

Inspector Recommendations

UNIT: 0	DECKS		
ELEMENT/ENV: 301:2330 / 3 Seal Damage	ELEM CATEGORY: Joints		
CONDITION STATE			PRIORITY
4	MMS Quantity: 36 lf Element Estimated Quantity: 36 ft		3
WORK ORDER RECOMMENDATION: Install new sealant along the sidewalk expansion joints. Photo 15			
ELEMENT/ENV: 8099 / 3 PS Conc Slab (Sonovoid)	ELEM CATEGORY: Decks/Slabs		
CONDITION STATE			PRIORITY
1 , 2 , 3	MMS Quantity: 4 sf Element Estimated Quantity: 4 (SF)		3
WORK ORDER RECOMMENDATION: Replace missing object markers at the four corners of the bridge. Photo 01			
1 , 2 , 3	MMS Quantity: 300 sf Element Estimated Quantity: 300 (SF)		3
WORK ORDER RECOMMENDATION: Properly secure the sidewalk panels. Photo 02			
ELEMENT/ENV: 8099:510:3220 / 3 Crack (Wearing Surface)	ELEM CATEGORY: Decks/Slabs		
CONDITION STATE			PRIORITY
3	MMS Quantity: 600 sf Element Estimated Quantity: 600 sq.ft		0
WORK ORDER RECOMMENDATION: Monitor the slab units for independent movement. Photo 12			
3	MMS Quantity: 600 sf Element Estimated Quantity: 600 sq.ft		3
WORK ORDER RECOMMENDATION: Repair cracks on the asphalt along the slab unit joints. Photo 12			
3	MMS Quantity: 105 sf Element Estimated Quantity: 105 sq.ft		3
WORK ORDER RECOMMENDATION: Clean and repair cracks and rutting along the expansion joints. Photo 13			
ELEMENT/ENV: 8099:1080 / 3 Delamination/Spall/Patched Area	ELEM CATEGORY: Decks/Slabs		
CONDITION STATE			PRIORITY
2 , 3	MMS Quantity: 338 sf Element Estimated Quantity: 338 (SF)		3
WORK ORDER RECOMMENDATION: Repair spalls delaminations and cracks along the underside of the slabs units. Photos 03 to 11			

This report contains information relating to the physical security of a structure and depictions of the structure. This information is confidential and exempt from public inspection pursuant to sections 119.071(3)(a) and 119.071(3)(b), Florida Statutes. Only the cover page of this report may be inspected and copied.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection**

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW

Inspector Recommendations

UNIT: 0 DECKS**ELEMENT/ENV: 8099:1100 / 3 Exposed Prestressing****ELEM CATEGORY: Decks/Slabs**

CONDITION STATE			PRIORITY
3	MMS Quantity: 20 sf	Element Estimated Quantity: 20 (SF)	3
WORK ORDER RECOMMENDATION: Clean and coat exposed prestressing and reinforce Slab Unit 2-8. Photos 08 and 10			

UNIT: 0 MISCELLANEOUS**ELEMENT/ENV: 321 / 3 Re Conc Approach Slab****ELEM CATEGORY: Other Elements**

CONDITION STATE			PRIORITY
1	MMS Quantity: 80 sf	Element Estimated Quantity: 80 sq.ft	3
WORK ORDER RECOMMENDATION: Replace all the approach guardrail panels. Photo 19			
1	MMS Quantity: 7 sf	Element Estimated Quantity: 7 sq.ft	3
WORK ORDER RECOMMENDATION: Replace spalled and delaminated posts along the roadway approach guardrails. Photo 18			

ELEMENT/ENV: 8290:9150 / 3 Bank Erosion**ELEM CATEGORY: Channel**

CONDITION STATE			PRIORITY
3	MMS Quantity: 8 mh	Element Estimated Quantity: 1 (EA)	3
WORK ORDER RECOMMENDATION: Repair undermining areas at the north seawall. Photo 17			

UNIT: 0 SUBSTRUCTURE**ELEMENT/ENV: 205:1090 / 3 Exposed Rebar****ELEM CATEGORY: Substructure**

CONDITION STATE			PRIORITY
3	MMS Quantity: 16 mh	Element Estimated Quantity: 1 each	3
WORK ORDER RECOMMENDATION: Remove any loose concrete and repair delaminations and spalls along the Column 2-2. Photo 20			

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW

Inspector Recommendations

UNIT: 0 SUBSTRUCTURE**ELEMENT/ENV: 205:1130 / 3 Cracking (RC and Other)****ELEM CATEGORY: Substructure**

CONDITION STATE			PRIORITY
3	MMS Quantity: 8 mh	Element Estimated Quantity: 4 each	3
WORK ORDER RECOMMENDATION:			
Install cathodic protection to Bents 2 and 3 columns. Photos 20 and 21			
3	MMS Quantity: 80 mh	Element Estimated Quantity: 4 each	3
WORK ORDER RECOMMENDATION:			
Repair delaminations and seal cracks along Bents 2 and 3 columns. Photo 21			

ELEMENT/ENV: 215:1080 / 3 Delamination/Spall/Patched Area**ELEM CATEGORY: Substructure**

CONDITION STATE			PRIORITY
3	MMS Quantity: 8 mh	Element Estimated Quantity: 5 ft	3
WORK ORDER RECOMMENDATION:			
Repair spall/delamination on Abutment 4 cap under Slab Units 3-10 and 3-11. Photo 22			

ELEMENT/ENV: 234 / 3 Re Conc Pier Cap**ELEM CATEGORY: Substructure**

CONDITION STATE			PRIORITY
1 , 2 , 3	MMS Quantity: 2 mh	Element Estimated Quantity: 2 ft	3
WORK ORDER RECOMMENDATION:			
Remove vegetation growing on west end of Bents 2 and 3 caps. Photo 23			

ELEMENT/ENV: 234:1080 / 3 Delamination/Spall/Patched Area**ELEM CATEGORY: Substructure**

CONDITION STATE			PRIORITY
2 , 3	MMS Quantity: 16 mh	Element Estimated Quantity: 19 ft	3
WORK ORDER RECOMMENDATION:			
Repair spalls and delaminations along Bents 2 and 3 caps. Photo 24			

ELEMENT/ENV: 8393 / 3 Bulkhead Seawall Any Material**ELEM CATEGORY: Substructure**

CONDITION STATE			PRIORITY
3	MMS Quantity: 8 mh	Element Estimated Quantity: 4 ft	3
WORK ORDER RECOMMENDATION:			
Replace the clearance gauges and hardware on the seawall at both sides of the channel. Photos 25 and 26			

This report contains information relating to the physical security of a structure and depictions of the structure. This information is confidential and exempt from public inspection pursuant to sections 119.071(3)(a) and 119.071(3)(b), Florida Statutes. Only the cover page of this report may be inspected and copied.

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
 Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
 Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW

Inspector Recommendations

UNIT: 0 SUBSTRUCTURE
ELEMENT/ENV: 8393 / 3 Bulkhead Seawall Any Material**ELEM CATEGORY: Substructure**CONDITION
STATE

PRIORITY

3 MMS Quantity: 8 mh Element Estimated Quantity: 2 ft

3

WORK ORDER RECOMMENDATION:

Seal open joints at the south seawall behind Piles 15 and 18. Photo 27

ELEMENT/ENV: 8393:1130 / 3 Cracking (RC and Other)**ELEM CATEGORY: Substructure**CONDITION
STATE

PRIORITY

3 MMS Quantity: 40 mh Element Estimated Quantity: 314 ft

3

WORK ORDER RECOMMENDATION:

Repair delaminations and spalls along the seawall caps. Photo 28

ELEMENT/ENV: 8394:4000 / 3 Settlement**ELEM CATEGORY: Substructure**CONDITION
STATE

PRIORITY

3 MMS Quantity: 160 mh Element Estimated Quantity: 1088 (SF)

3

WORK ORDER RECOMMENDATION:

Repair settled and fractured areas along the slope protections. Photos 29 and 30

UNIT: 0 SUPERSTRUCTURE
ELEMENT/ENV: 333:1000 / 3 Corrosion**ELEM CATEGORY: Superstructure**CONDITION
STATE

PRIORITY

2 MMS Quantity: 30 lf Element Estimated Quantity: 30 ft

3

WORK ORDER RECOMMENDATION:

Clean and paint or replace corroded hardware along the bridge aluminium rail. Photo 31

ELEMENT/ENV: 333:1020 / 3 Connection**ELEM CATEGORY: Superstructure**CONDITION
STATE

PRIORITY

2 MMS Quantity: 3 lf Element Estimated Quantity: 3 ft

3

WORK ORDER RECOMMENDATION:

Replace missing nuts at the aluminium rail post connections. Photo 32

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection**

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW

Structure Notes

BRIDGE OWNER: MIAMI-DADE COUNTY

Bridge inventoried from south to north.

P/S Slab Units on R/Conc Caps and Abutments over P/Conc Columns. (3 spans)

Element 227/3 Re Conc Pile notes have been replaced by Element 205/3 Re Conc Column on 10/29/2019.

TRAFFIC RESTRICTIONS:

Based on the current load rating analysis dated 1/13/2020, it is recommended that this bridge be posted for the SU, C and ST5 type vehicles as follows: SU = 11 tons, C = 16 tons, ST5 = 18 tons. The bridge is currently posted for SU = 11 tons, C = 16 tons, ST5 = 18 tons. Refer to posting signs Photos 33 and 34.

REVIEWED BY:

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection**

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW

INSPECTION NOTES: **GZJW** **4/6/2020**

Sufficiency Rating Calculation Accepted by knmeira at 5/13/2020 9:36:35 AM

The Deck and Superstructure are coded 3 (Serious) due to spalls and delaminations along more than 25% of any of the slab units. Slabs Units 1-6, 2-7, and 2-8 meet this criteria. (04/06/2020)

The Substructure NBI Rating is coded 4 (Poor) due to the significant deterioration of Column 2-2. (04/06/2020)

The Channel NBI Rating was lowered from 7 to 6 due to areas of undermining on the channel below the North seawall. (04/06/2020)

LOAD CAPACITY EVALUATION:

Since the current load rating dated 1/13/2020, there is no indication that deterioration, geometric changes or additional dead load have occurred that would warrant a new load rating analysis. This only applies to this inspection dated 04/06/2020 per Julie A. Vers, P.E.

The structure is on a 6 months inspection frequency due to NBI Rating 3 for SIA Items 58 Deck and 59 Superstructure.

Element 8475 R/Conc Walls was replaced by 8393 Bulkhead Seawall Any Material during this inspection cycle. All previous notes were transferred accordingly. (04/06/2020)

The following elements were inspected underwater by the divers:

8290 Channel

8393 Bulkhead Seawall Any Material

LEGEND:

NCAR: NO CORRECTIVE ACTION RECOMMENDED.

RT: Right

LT: Left

NC: No Change

INC: Increase

CAT: Corrective Action Taken

L: Long

W: Wide

H: High

D: Deep

UW: Underwater

S.L.: Section Loss

in.: Inches

ft.: Feet

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 01 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Object markers and centerline raised pavement markers are missing on the structure.

WORK ORDER RECOMMENDATION:

Replace missing object markers at the four corners of the bridge.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 02 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Sidewalk panels are loose and moves under pedestrian load.

WORK ORDER RECOMMENDATION:
Properly secure the sidewalk panels.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 03 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Slab Unit 1-8 east edge has a spall/delamination 4ft. L x 15in. W x 2in. D and associated cracks with corrosion bleed-out near mid-span.

WORK ORDER RECOMMENDATION:

Repair spalls delaminations and cracks along the underside of the slabs units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection**

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 04 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Slab Unit 1-9, center line has a spall/delamination up to 36in. L x 24in. W x 2in. D over Abutment 1.

WORK ORDER RECOMMENDATION:

Repair spalls delaminations and cracks along the underside of the slabs units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 05 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Slab Unit 3-7 has an unsound repaired area 11ft. L x 2ft. W starting from Abutment 4 with hollow sounding throughout and associated cracks up to 1/16in. W with efflorescence and corrosion bleed-out.

WORK ORDER RECOMMENDATION:

Repair spalls delaminations and cracks along the underside of the slabs units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 06 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Slab Unit 3-8 has a spall/delamination up to 7ft. L x 3ft. W x 1in. D and associated cracks with corrosion bleed-out starting at Pier 3.

WORK ORDER RECOMMENDATION:

Repair spalls delaminations and cracks along the underside of the slabs units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 07 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Slab Units 2-6 and 2-7, east and west edges have delaminations up to 30in. L x 4in. W, starting at Pier 2 cap.

WORK ORDER RECOMMENDATION:

Repair spalls delaminations and cracks along the underside of the slabs units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection**

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 08 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Slab Unit 2-8 west half has two delaminated areas up to 15ft. L x 18in. W (average width) at south and north ends, and at midspan has a spall 10ft. L x 24in. W x up to 4in. D with exposed strands. Refer to Photo 10 for additional information.

WORK ORDER RECOMMENDATION:

Clean and coat exposed prestressing and reinforce Slab Unit 2-8.

Repair spalls delaminations and cracks along the underside of the slabs units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 09 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Slab Unit 1-6 exhibits a spall with exposed rebar up to 15in. L x 6in. W x 1/2in. D with evidence of previous failed repair, at 9ft. from Abutment 1.

WORK ORDER RECOMMENDATION:

Repair spalls delaminations and cracks along the underside of the slabs units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection**

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 10 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Slab Unit 2-8 has a spall 10ft. L x 24in. W x up to 4in. D at mid-span with 6 exposed and corroded transverse rebars with up to 60% section remaining and 5 exposed and corroded prestressing strands with up to 0% section remaining (2 broken threads).

WORK ORDER RECOMMENDATION:

Clean and coat exposed prestressing and reinforce Slab Unit 2-8.

Repair spalls delaminations and cracks along the underside of the slabs units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection**

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 11 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Slab Unit 1-7 east edge has a spall/delamination 24in. L x 12in. W with associated cracks up to 1/32in. W with efflorescence and corrosion bleed-out over Abutment 1. Slab Unit 1-8 west edge is intermittently delaminated up to 15ft. L x 15in. W with associated cracks up to 1/8in. W with efflorescence and corrosion bleed-out, starting at Abutment 1.

WORK ORDER RECOMMENDATION:

Repair spalls delaminations and cracks along the underside of the slabs units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection**

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 12 Element/Env 8099/ 510/3: PS Conc Slab (Sonovoid)/ Wearing Surfaces

The asphalt overlay has longitudinal cracks up to span length x 1/4in. W with associated rutting over the slab unit joints with upheaving up to 1in. H at the shoulders, possibly indicating independent slab units movement.

WORK ORDER RECOMMENDATION:

Repair cracks on the asphalt along the slab unit joints.
Monitor the slab units for independent movement.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection**

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 13 Element/Env 8099/ 510/3: PS Conc Slab (Sonovoid)/ Wearing Surfaces

The asphalt overlay has transverse cracks up to roadway width x 1/4in. W with rutting and upheaving up to 3in. H and vegetation growth over the expansion joints.

WORK ORDER RECOMMENDATION:

Clean and repair cracks and rutting along the expansion joints.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 14 Element/Env 301/3: Pourable Joint Seal

There is evidence of moderate to heavy water seepage through the expansion joints on bents and abutment caps.

WORK ORDER RECOMMENDATION:

None.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 15 Element/Env 301/3: Pourable Joint Seal

The sealant along the sidewalk expansion joints has deteriorated.

WORK ORDER RECOMMENDATION:

Install new sealant along the sidewalk expansion joints.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection**

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 16 Element/Env 8290/3: Channel

Divers conducting the Underwater Inspection.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW




Photo 17 Element/Env 8290/3: Channel

There are two areas of undermining up to 22ft. L x 3in. H x 21in. of penetration with backfill migration under the north seawall, below Slab Units 2-2 and 2-5.

WORK ORDER RECOMMENDATION:

Repair undermining areas at the north seawall.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection**

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 18 Element/Env 321/3: R/Conc Approach Slab

There are several approach roadway guardrails posts spalled/delaminated up to 14in. H x 3.5in. W x 1-1/4in D with exposed and corroded rebars. Shown Post 1 at NW approach guardrail.

WORK ORDER RECOMMENDATION:

Replace spalled and delaminated posts along the roadway approach guardrails.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 19 Element/Env 321/3: R/Conc Approach Slab

The approach guardrail panels exhibit moderate to heavy corrosion with numerous corrosion holes throughout.

WORK ORDER RECOMMENDATION:

Replace all the approach guardrail panels.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection**

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 20 Element/Env 205/3: Re Conc Column

Column 2-2, south face has a spall/delamination up to 7ft. H x 3ft. W x 3in. D with one exposed rebar and one stirrup, having areas of up to 80% section remaining. Additionally, there are areas of delamination around the column circumference covering the entire column height with associated cracks up to 1/4in. W.

WORK ORDER RECOMMENDATION:

Remove any loose concrete and repair delaminations and spalls along the Column 2-2.
Install cathodic protection to Bents 2 and 3 columns.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 21 Element/Env 205/3: Re Conc Column

Columns 2-1, 3-1, and 3-2 have delaminated areas along their entire length with associated cracks up to full height x 1/16in. W, as a result of corrosion of the steel reinforcement.

WORK ORDER RECOMMENDATION:

Install cathodic protection to Bents 2 and 3 columns.

Repair delaminations and seal cracks along Bents 2 and 3 columns.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 22 Element/Env 215/3: Re Conc Abutment

Abutment 4 cap has a spall/delamination up to 5ft. L x full height x 2in. D with associated cracks up to 1/16in. W under Slab Units 3-10 and 3-11.

WORK ORDER RECOMMENDATION:

Repair spall/delamination on Abutment 4 cap under Slab Units 3-10 and 3-11.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 23 Element/Env 234/3: Re. Concrete Pier Cap

Bents 2 and 3 caps have vegetation growth along the west end.

WORK ORDER RECOMMENDATION:

Remove vegetation growing on west end of Bents 2 and 3 caps.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection**

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 24 Element/Env 234/3: Re. Concrete Pier Cap

Bent 2 cap has a spall/delamination up to 3ft. L x 16in. H x 1 in. D on the south face over Column 2-2, and on the same location, north face a delamination 20in. L x 12in. H.

WORK ORDER RECOMMENDATION:

Repair spalls and delaminations along Bents 2 and 3 caps.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 25 Element/Env 8393/3: Bulkhead Seawall Any Material

The brackets and fasteners attaching the clearance gauges to the seawalls exhibit heavy to severe corrosion.

WORK ORDER RECOMMENDATION:

Replace the clearance gauges and hardware on the seawall at both sides of the channel.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 26 Element/Env 8393/3: Bulkhead Seawall Any Material

SE and NW clearance gauges have moderate decay at bottom 3ft.

WORK ORDER RECOMMENDATION:

Replace the clearance gauges and hardware on the seawall at both sides of the channel.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW




Photo 27 Element/Env 8393/3: Bulkhead Seawall Any Material

The south seawall has two open joints up to 4in. W with backfill leakage behind Piles 15 and 18 from west.

WORK ORDER RECOMMENDATION:

Seal open joints at the south seawall behind Piles 15 and 18.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 28 Element/Env 8393/3: Bulkhead Seawall Any Material

The seawall caps on the north and south walls have up to 1/4in W cracks, with associated delaminations/spalls throughout their entire lengths.

WORK ORDER RECOMMENDATION:

Repair delaminations and spalls along the seawall caps.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 29 Element/Env 8394/3: R/Conc Abut Slope Protection

The slope protection toe has a fractured and settled area of 15ft. x 7ft. x 2ft deep at the NW corner behind the seawall cap. The channel water reach this area at high tide.

WORK ORDER RECOMMENDATION:

Repair settled and fractured areas along the slope protections.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 30 Element/Env 8394/3: R/Conc Abut Slope Protection

The SW slope protection toe has 5 fractured panels that have settled up to 3in. H. The channel water reach this area at high tide.

WORK ORDER RECOMMENDATION:

Repair settled and fractured areas along the slope protections.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 31 Element/Env 333/3: Other Bridge Railing

The rail anchor bolt nuts and washers have moderate corrosion at random locations: 25 nuts at west railing, and 5 nuts at east railing.

WORK ORDER RECOMMENDATION:

Clean and paint or replace corroded hardware along the bridge aluminium rail.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 32 Element/Env 333/3: Other Bridge Railing

There are several missing anchor bolt nuts at the aluminium rail posts: west rail, Posts 1-1 and 2-6; and east rail, Post 1-5.

WORK ORDER RECOMMENDATION:

Replace missing nuts at the aluminium rail post connections.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 33 STRUCTURE NOTES: South Approach Posting Sign

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



Photo 34 STRUCTURE NOTES: North Approach Posting Sign

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



SCOUR EVALUATION

Channel looking West

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Inspection

Structure ID: 874294

DISTRICT: D6 - Miami

INSPECTION DATE: 4/6/2020 GZJW



SCOUR EVALUATION

Channel looking East

F. FIELD PREPARATION and CHECKLIST

Structure ID: 874294Inspection Date: 04/06/2020Underwater: 04/06/2020

A. Tools and Equipment

Full Size Cargo Van:	Yes:	X	No:		Pick-up Truck:	Yes:	X	No:	
Automobile:	Yes:		No:	X	Video:	Yes:	—	No:	<u>X</u>
Camera:	Yes:	X	No:						
NDT Equipment:	Yes:		No:	X					
NDT Type:		<u>N/A</u>							
Binoculars:	Yes:		No:	X					
Diving Performed:	Yes:	X	No:		Max Depth:	<u>10.6 ft.</u>		Current:	<u>Moderate</u>
Dive Mode:		<u>SCUBA</u>							

Hand Tools:

1. Standard Inspection Tools	2. Chipping Hammer
3. Inspection Hand Tools	4. Flashlight
5. Folding Rulers	

Other:

B. Services

Flag Crew: <u>N/A</u>	Snooper: <u>N/A</u>
Electrician: <u>N/A</u>	Other: _____

C. Scheduling (Brief Explanation)

Routine Inspection, no special scheduling needed.

Man Hours: 0 hrs. Dive Time: 2 hrs. Travel Time: 1 hr. Office Time: 1 hr.

D. Site Conditions


Boat Needed: NO Type of Boat: N/ALocation of Boat Ramp: N/ALengthy Travel Required: N/ADifficult Access: NOWater Obviously Polluted: NOWater quality is fair: YesStrong Water Current: YesOther: N/A

E. UNDERWATER ELEMENTS INSPECTED:

- 8290 Channel – 1ea.
- 8393 Bulkhead Seawall Any Material – 354 ft.

Bridge No.	874294	Analysis Method:	LRFR-LRFD	FDOT Bridge Load Rating Summary Form (Page 1 of 1)
Location	Matheson hammock Road over matheson Hammock Canal			
Description	3 Spans, 2-30'&1-40', Prestressed voided slab beams 36"x17"			

Rating Type	Rating Type	Gross Axle Weight (tons)	Moment/Shear/Service		Dead Load Factor	Live Load Factor	Live Load Distrib. Factor (axles)	Rating Factor	Span No. - Girder No., Interior/Exterior, %Span Length	RF-Weight (tons)
Level	Vehicle	Weight	Member Type	Limit	DC	LL	LLDF	RF	Governing Location	RATING
Inventory	HL93	36	Prestressed	Service	1.00	0.80	0.600	0.210	Central span, midspan	7.6
Operating	HL93	36	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.330	Central span, midspan	11.9
Permit	FL120	60	Prestressed	Strength, Shear	1.25/0.90	1.35	0.500	0.270	Central span, 1/4 point	16.2
Permit Max Span	FL120	60	Prestressed	Strength, Shear	1.25/0.90	1.35	0.500	0.270	Central span, 1/4 point	16.2
Legal	SU2	17	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.690	Central span, midspan	11.7
	SU3	33	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.370	Central span, midspan	12.2
	SU4	35	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.340	Central span, midspan	11.9
	C3	28	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.650	Central span, midspan	18.2
	C4	36.7	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.460	Central span, midspan	16.9
	C5	40	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.440	Central span, midspan	17.6
	ST5	40	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.460	Central span, midspan	18.4
Emergency Vehicle (EV)	EV2	28.75	Prestressed	NA	NA	NA	0.600			-1
	EV3	43	Prestressed	NA	NA	NA	0.600			-1

Original Design Load	HS20 or HS20-S16-44	Performed by:	Mengyuan Chen	Date:	01/13/20
Rating Type, Analysis	LRFR-LRFD	Checked by:	Juan A. Sobrino	Date:	01/13/20
Distribution Method	Others	Sealed By:	Juan A. Sobrino	Date:	01/13/20
Impact Factor	33.0% (axle loading)	FL P.E. No.:	73121		
FL120 Gov. Span Length	38.3 (feet)	Cert. Auth. No.:	27244		
Minimum Span Length	28.3 (feet)	Phone & email:	(+1) 305 648 00 10, miami@pedelta.om		
Recommended Posting	> 39.9% below (0.000-0.600) (Required)	Company:	Pedelta Inc.		
Recommended SU Posting*	11 (tons)	Address:	2000 Ponce de Leon Blvd., Suite 624, Coral Gables, Florida 33134, USA		
Recommended C Posting	16 (tons)	<div> <div>  <div> Juan A. Sobrino P.E. State of Florida, Professional Engineer </div> </div> <div> Digitally signed by Juan Sobrino Date: 2020.01.13 15:58:25 -05'00' </div> </div> <p>Juan A. Sobrino, State of Florida, Professional Engineer, License No 73121. This document has been electronically signed and sealed by Juan A. Sobrino on January 13th, 2020 using a SHA authentication code. Printed copies of this document are not considered signed and sealed and the SHA authentication code must be verified on any electronic copies.</p>			
Recommended ST5 Posting	18 (tons)				
Owner	02 County Highway Agency				
Location	Neither Interstate traffic nor within 1 mile reasonable access to an Interstate				
EV Posting	No. EV posting is not recommended. The FAST Act does not apply				
Floor Beam Present?	No				
Segmental Bridge?	No				
Project No. & Reason	432907-1-72-02 Deterioration				
Plans Status	Built				

This 10-11-2019 summary follows the FDOT Bridge Load Rating Manual (BLRM), and the FDOT BMS Coding Guide.

*Recommended SU Posting levels for Florida SU trucks adequately restricts AASHTO SU trucks; see BLRM Chapter 7.

fdot.gov/maintenance/LoadRating.shtm

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

Inspection/CIDR/Bridge Profile Report with PDF attachment(s)

Structure ID: 874294

CIDR

DATE PRINTED: 5/18/2020

Description

Structure Unit Identification

Bridge/Unit Key: 874294 0
 Structure Name:
 Description: SPANS 1 THRU 3
 Type: M - Main

Roadway Identification

NBI Structure No (8): 874294
 Position/Prefix (5): 1 - Route On Structure
 Kind Hwy (Rte Prefix): 4 County Hwy
 Design Level of Service: 8 Service Road
 Route Number/Suffix: 00000 / 0 N/A (NBI)
 Feature Intersect (6): Matheson Hammock Canal
 Critical Facility: Not Defense-crit
 Facility Carried (7): Matheson Hmk Road
 Mile Point (11): 0.08
 Latitude (16): 025d40'44.2" Long (17): 080d15'43.8"

Roadway Traffic and Accidents

Lanes (28): 2 Medians: 0 Speed: 15 mph
 ADT Class: 2 ADT Class 2
 Recent ADT (29): 736 Year (30): 2014
 Future ADT (114): 1168 Year (115): 2036
 Truck % ADT (109): 1
 Detour Length (19): 99 mi
 Detour Speed:
 Accident Count: -1 Rate:

Roadway Classification

Nat. Hwy Sys (104): 0 Not on NHS
 National base Net (12): 0 - Not on Base Network
 LRS Inventory Rte (13a): 87 000 757 Sub Rte (13b): 00
 Functional Class (26): 09 Rural Local
 Federal Aid System: OFF
 Defense Hwy (100): 0 Not a STRAHNET hwy
 Direction of Traffic (102): 2 2-way traffic
 Emergency: ☒

Roadway Clearances

Vertical (10): 99.99 ft Appr. Road (32): 26.25 ft
 Horiz. (47): 26.25 ft Roadway (51): 26.25 ft
 Truck Network (110): 0 Not part of natl netwo
 Toll Facility (20): 3 On free road
 Fed. Lands Hwy (105): 0 N/A (NBI)
 School Bus Route: ☐
 Transit Route: ☐

NBI Project Data

Proposed Work (075A): Not Applicable (P)
 Work To Be Done By (075B): Not Applicable (P)
 Improvement Length (076): 0 ft

Improvement Cost (094): \$ 0.00
 Roadway Improvement Cost (095): \$ 0.00
 Total Cost (096): \$ 0.00
 Year of Estimate (097):

NBI Rating

Channel (61): 6 Bank Slumping
 Deck (58): 3 Serious
 Superstructure (59): 3 Serious
 Substructure (60): 4 Poor

Culvert (62): N N/A (NBI)
 Waterway (71): 8 Equal Desirable
 Unrepaired Spalls: -1 sq.ft.
 Review Required: ☒

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

Inspection/CIDR/Bridge Profile Report with PDF attachment(s)

Structure ID: 874294

CIDR

DATE PRINTED: 5/18/2020

Structure Identification

Admin Area: Miami-Dade
 District (2): D6 - Miami
 County (3): (87)Miami-Dade
 Place Code (4): South Miami Heights
 Location (9): Matheson Hammock Park
 Border Br St/Reg (98): Not Applicable (P) Share: 0 %
 Border Struct No (99):
 FIPS State/Region (1): 12 Florida Region 4-Atlanta
 NBIS Bridge Len (112): Y - Meets NBI Length
 Parallel Structure (101): No || bridge exists
 Temp. Structure (103): Not Applicable (P)
 Maint. Resp. (21): 2 County Hwy Agency
 Owner (22): 2 County Hwy Agency
 Historic Signif. (37): 5 Not eligible for NRHP

Structure Type and Material

Curb/Sidewalk (50): Left: 1.5 ft Right: 5.5 ft
 Bridge Median (33): 0 No median
 Main Span Material (43A): 5 Prestressed Concrete
 Appr Span Material (44A): Not Applicable (P)
 Main Span Design (43B): 01 Slab
 Appr Span Design (44B): 00 Other (NBI)

Appraisal**Structure Appraisal**

Open/Posted/Closed (41): P Posted for load
 Deck Geometry (68): 5 Above Tolerable
 Underclearances (69): N Not applicable (NBI)
 Approach Alignment (72): 8-No Speed Red thru Curv
 Bridge Railings (36a): 0 Substandard
 Transitions (36b): 0 Substandard
 Approach Guardrail (36c): 0 Substandard
 Approach Guardrail Ends (36d): 0 Substandard
 Scour Critical (113): U Unknown Foundation

Minimum Vertical Clearance

Over Structure (53): 99.99 ft
 Under (reference) (54a): N Feature not hwy or RR
 Under (54b): 0 ft

Schedule**Current Inspection**

Inspection Date: 04/06/2020
 Inspector: KNMEIOP - Omar Porras
 Bridge Group: CA611
 Alt. Bridge Group:
 Primary Type: Regular NBI
 Review Required: ☒

Geometrics

Spans in Main Unit (45): 3
 Approach Spans (46): 0
 Length of Max Span (48): 38.3 ft
 Structure Length (49): 100.33 ft
 Total Length: 140.33 ft
 Deck Area: 3536 sqft
 Structure Flared (35): 0 No flare

Age and Service

Year Built (27): 1967
 Year Reconstructed (106): 0
 Type of Service On (42a): 5 Highway-pedestrian
 Under (42b): 5 Waterway
 Fracture Critical Details: Not Applicable

Deck Type and Material

Deck Width (52): 35.25 ft
 Skew (34): 0 deg
 Deck Type (107): 2 Concrete Precast Panel
 Surface (108): 6 Bituminous
 Membrane: 0 None
 Deck Protection: None

Navigation Data

Navigation Control (38): Permit Not Required
 Nav Vertical Clr (39): 0 ft
 Nav Horizontal Clr (40): 0 ft
 Min Vert Lift Clr (116): 0 ft
 Pier Protection (111): 1 Not Required

NBI Condition Rating

Sufficiency Rating: 15.5
 Health Index: 86.68
 Structural Eval (67): 3 Intolerable - Correct
 Deficiency: Structurally Deficient

Minimum Lateral Underclearance

Reference (55a): N Feature not hwy or RR
 Right Side (55b): 0 ft
 Left Side (56): 0 ft

Next Inspection Date Scheduled

NBI: 04/06/2022
 Element: 10/06/2020
 Fracture Critical:
 Underwater: 04/06/2022
 Other/Special: 10/06/2020
 Inventory Photo Update Due: 04/06/2024

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

Inspection/CIDR/Bridge Profile Report with PDF attachment(s)

Structure ID: 874294

CIDR

DATE PRINTED: 5/18/2020

Schedule Cont.

Inspection Types Performed

NBI ☒Element ☒Fracture Critical ☐Underwater ☒Other Special ☒

Inspection Intervals

Required (92)

Frequency (92)

Last Date (93)

Inspection Resources

Fracture Critical ☐

mos

Crew Hours: 4

Underwater ☒

24 mos

04/06/2020

Flagger Hours: 0

Other Special ☒

6 mos

04/06/2020

Helper Hours: 0

NBI

24 mos

(91) 04/06/2020 (90)

Snooper Hours: 0

Special Crew Hours: 3

Special Equip Hours: 0

Bridge Related

General Bridge Information

Parallel Bridge Seq:

Channel Depth: 10.6 ft

Radio Frequency: -1

Phone Number:

Exception Date:

Exception Type: Unknown

Accepted By Maint: 01/01/1967

Warranty Expiration: 00/00/0000

Performance Rating: Poor

Bridge Rail 1: Conc parapet-alum-rail

Bridge Rail 2: Not applicable-No rail

Electrical Devices: No electric service

Culvert Type: Not applicable

Maintenance Yard: Not FDOT Maintained

FIHS ON / OFF: No Routes on FIHS

Previous Structure:

2nd Previous Structure:

Replacement Structure:

Permitted Utilities: Power ☐Water ☒Gas ☐Fiber Optic ☐Sewage ☒Other ☐

Bridge Load Rating Information

Inventory Type (065): 3 LRFR Load & Res. Fact

Operating Type (063): 3 LRFR Load & Res. Fact

Original Design Load (031): HL 93

Date: 01/13/2020

Initials: JA

Load Rating Rev. Recom.: No

Load Rating Plans Status: Field Measurements

Inventory Rating (066): 7.6 tons

Operating Rating (064): 11.9 tons

FL120 Permit Rating: 16.2 tons

HS20/FL120 Max Span Rating: 16.2 tons

Dynamic Impact in Percent: 33 %

Governing Span Length: 38.3 ft

Minimum Span Length: 28.3 ft

Distribution Method: Others

Load Rating Notes:

LEGAL LOADS

SU2: 11.7 tons

SU3: 12.2 tons

SU4: 11.9 tons

C3: 18.2 tons

C4: 16.9 tons

C5: 17.6 tons

ST5: 18.4 tons

Posting (070): 2 20.0-29.9%below

Open/Posted/Closed (041): P Posted for load

FLOOR BEAM (FB)

FB Present: No

FB Span Length, Gov: 0.0 ft

FB Spacing, Gov: 0.0 ft

FB OPR Rating: 0.0 tons

FB SU4 OPR Rating: 0.0 tons

FB FL120 Rating: 0.0 tons

POSTING

Recom. SU Posting: 11 tons

Recom. C Posting: 16 tons

Recom. ST5 Posting: 18 tons

Actual SU Posting: 11 tons

Actual C Posting: 16 tons

Actual ST5 Posting: 18 tons

Actual Blanket Posting: 99 tons

Emergency Vehicle: 1 EV inapplicable

SEGMENTAL (SEG)

SEG Wing-Span: -1.0 ft

SEG Web-to-Web Span: -1.0 ft

SEG Transverse HL93 Operating: -1.00 RF

Bridge Scour and Storm Information

Pile Driving Record: No pile driving records

Foundation Type: Unknown

Mode of Flow: Tidal

Rating Scour Eval: Unknown

Highest Scour Eval: Unknown

Scour Evaluation Method:

Scour Recommended I: Unknown

Scour Recommended II: Unknown

Scour Recommended III: Unknown

Scour Elevation: -1 ft

Action Elevation: -1 ft

Storm Frequency: -1

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

Inspection/CIDR/Bridge Profile Report with PDF attachment(s)

Structure ID: 874294

CIDR

DATE PRINTED: 5/18/2020

Elements

Inspection Date: 04/06/2020 GZJW

DECKS : Decks/Slabs

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8099 / 3	PS Conc Slab (Sonovoid)	3178	89.88	114	3.22	244	6.9	0	.	3536 (SF)
0	1080 / 3	Delamination/Spall/Patched Area	0	.	114	59.07	79	40.93	0	.	193 (SF)
0	1090 / 3	Exposed Rebar	0	.	0	.	1	100	0	.	1 (SF)
0	1100 / 3	Exposed Prestressing	0	.	0	.	20	100	0	.	20 (SF)
0	1110 / 3	Cracking (PSC)	0	.	0	.	144	100	0	.	144 (SF)
0	510 / 3	Wearing Surfaces	1929	73.23	0	.	705	26.77	0	.	2634 sq.ft
0	3220 / 3	Crack (Wearing Surface)	0	.	0	.	705	100	0	.	705 sq.ft

DECKS : Joints

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	301 / 3	Pourable Joint Seal	0	.	0	.	104	74.29	36	25.71	140 ft
0	2310 / 3	Leakage	0	.	0	.	104	100	0	.	104 ft
0	2330 / 3	Seal Damage	0	.	0	.	0	.	36	100	36 ft

MISCELLANEOUS : Channel

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8290 / 3	Channel	0	.	0	.	1	100	0	.	1 (EA)
0	9150 / 3	Bank Erosion	0	.	0	.	1	100	0	.	1 (EA)

MISCELLANEOUS : Other Elements

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	321 / 3	Re Conc Approach Slab	1410	100	0	.	0	.	0	.	1410 sq.ft
0	510 / 3	Wearing Surfaces	957	91.14	0	.	93	8.86	0	.	1050 sq.ft
0	3220 / 3	Crack (Wearing Surface)	0	.	0	.	93	100	0	.	93 sq.ft

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	205 / 3	Re Conc Column	0	.	0	.	4	100	0	.	4 each
0	1090 / 3	Exposed Rebar	0	.	0	.	1	100	0	.	1 each
0	1130 / 3	Cracking (RC and Other)	0	.	0	.	3	100	0	.	3 each

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	215 / 3	Re Conc Abutment	65	92.86	0	.	5	7.14	0	.	70 ft
0	1080 / 3	Delamination/Spall/Patched Area	0	.	0	.	5	100	0	.	5 ft

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	234 / 3	Re Conc Pier Cap	49	72.06	12	17.65	7	10.29	0	.	68 ft
0	1080 / 3	Delamination/Spall/Patched Area	0	.	12	63.16	7	36.84	0	.	19 ft

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8393 / 3	Bulkhead Seawall Any Material	0	.	0	.	354	100	0	.	354 ft
0	1130 / 3	Cracking (RC and Other)	0	.	0	.	314	100	0	.	314 ft

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

Inspection/CIDR/Bridge Profile Report with PDF attachment(s)

Structure ID: 874294

CIDR

DATE PRINTED: 5/18/2020

0	6000 / 3	Scour	0	.	0	.	40	100	0	.	40 ft
---	----------	-------	---	---	---	---	----	-----	---	---	-------

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8394 / 3	R/Conc Abut Slope Protection	3968	73.81	0	.	1408	26.19	0	.	5376 (SF)
0	1130 / 3	Cracking (RC and Other)	0	.	0	.	320	100	0	.	320 (SF)
0	4000 / 3	Settlement	0	.	0	.	1088	100	0	.	1088 (SF)

SUPERSTRUCTURE : Superstructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	333 / 3	Other Bridge Railing	167	83.5	33	16.5	0	.	0	.	200 ft
0	1000 / 3	Corrosion	0	.	30	100	0	.	0	.	30 ft
0	1020 / 3	Connection	0	.	3	100	0	.	0	.	3 ft

Total Number of Elements*: 10

*excluding defects/protective systems

Inspection Information**Inspection Date:** 04/06/2020**Type:** Regular NBI**Inspector:** KNMEIOP - Omar Porras**Inspection Notes:** Sufficiency Rating Calculation Accepted by knmeira at 5/13/2020 9:36:35 AM

The Deck and Superstructure are coded 3 (Serious) due to spalls and delaminations along more than 25% of any of the slab units. Slabs Units 1-6, 2-7, and 2-8 meet this criteria. (04/06/2020)

The Substructure NBI Rating is coded 4 (Poor) due to the significant deterioration of Column 2-2. (04/06/2020)

The Channel NBI Rating was lowered from 7 to 6 due to areas of undermining on the channel below the North seawall. (04/06/2020)

LOAD CAPACITY EVALUATION:

Since the current load rating dated 1/13/2020, there is no indication that deterioration, geometric changes or additional dead load have occurred that would warrant a new load rating analysis. This only applies to this inspection dated 04/06/2020 per Julie A.Vers, P.E.

The structure is on a 6 months inspection frequency due to NBI Rating 3 for SIA Items 58 Deck and 59 Superstructure.

Element 8475 R/Conc Walls was replaced by 8393 Bulkhead Seawall Any Material during this inspection cycle. All previous notes were transferred accordingly. (04/06/2020)

The following elements were inspected underwater by the divers:

8290 Channel

8393 Bulkhead Seawall Any Material

LEGEND:

NCAR: NO CORRECTIVE ACTION RECOMMENDED.

RT: Right

LT: Left

NC: No Change

INC: Increase

CAT: Corrective Action Taken

L: Long

W: Wide

H: High

D: Deep

UW: Underwater

S.L.: Section Loss

in.: Inches

ft.: Feet

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**

REPORT ID: INSP005

Inspection/CIDR/Bridge Profile Report with PDF attachment(s)

Structure ID: 874294

CIDRDATE PRINTED: 5/18/2020

Structure Notes

BRIDGE OWNER: MIAMI-DADE COUNTY

Bridge inventoried from south to north.

P/S Slab Units on R/Conc Caps and Abutments over P/Conc Columns. (3 spans)

Element 227/3 Re Conc Pile notes have been replaced by Element 205/3 Re Conc Column on 10/29/2019.

TRAFFIC RESTRICTIONS:


Based on the current load rating analysis dated 1/13/2020, it is recommended that this bridge be posted for the SU, C and ST5 type vehicles as follows: SU = 11 tons, C = 16 tons, ST5 = 18 tons. The bridge is currently posted for SU = 11 tons, C = 16 tons, ST5 = 18 tons. Refer to posting signs Photos 33 and 34.

REVIEWED BY:


Schedule Notes

The structure is on a 6 months inspection frequency due to NBI Rating 3 for SIA Items 58 Deck and 59 Superstructure.

Left Profile by Inspection



Right Profile by Inspection



FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report with PDF attachment(s)
Bridge Profile

REPORT ID : INSP005
Structure ID : 874294

DATE PRINTED: 5/18/2020 12:12:35 PM

Profile Data - Numerical Summary

(All Heights are in Feet)

GZJW

Inspection Date and Key: 4/6/2020

Bent #

Left Height

Right Height

1

5.70

5.80

2

18.00

18.20

2.5

28.50

29.40

3

19.50

18.20

4

5.80

5.90

Air Temp: 82

Profile Notes:

Measurements were referenced from the top of the concrete barriers.
Waterline taken at mid channel: Left = 18.7 ft. and Right = 18.8 ft.
Maximum channel depth: 10.6 ft.

Inspection Date and Key: 4/19/2018

ODLG

1

5.60

5.80

2

18.00

18.10

2.5

29.00

29.00

3

18.80

18.20

4

5.70

5.90

Air Temp: 74

Profile Notes:

Measurements were referenced from the top of the concrete barriers.
Waterline taken at mid channel: Left = 18.3 ft. and Right = 18.4 ft.
Maximum channel depth: 10.7 ft.

Profile Data - Numerical Summary

Inspection Date and Key:	Bent #	Left Height	Right Height	(All Heights are in Feet)
4/29/2016 MOSY	1	6.50	6.40	
	2	18.00	18.00	
	2.5	29.60	30.40	
	3	19.30	18.10	
	4	6.70	6.50	

Air Temp: 1
Profile Notes:

Measurements referenced from the top of the concrete bridge rail.
Waterline at C/L of Channel = 19.2ft.
Water depth = 11.2ft.

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

Page 1 of 15

BRIDGE ID : 874294

Structure Inventory Photo Due Date : 04/06/2024



Bridge Number - 4/25/2014

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

Page 2 of 15

BRIDGE ID : 874294

Structure Inventory Photo Due Date : 04/06/2024



Typical Bridge Rail - 4/25/2014

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

Page 3 of 15

BRIDGE ID : 874294

Structure Inventory Photo Due Date : 04/06/2024



Southeast Oncoming Transition - 4/25/2014

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

Page 4 of 15

BRIDGE ID : 874294

Structure Inventory Photo Due Date : 04/06/2024



Northwest Oncoming Transition - 4/25/2014

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

Page 5 of 15

BRIDGE ID : 874294

Structure Inventory Photo Due Date : 04/06/2024



Southwest Off-Going Transition - 4/25/2014

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

Page 6 of 15

BRIDGE ID : 874294

Structure Inventory Photo Due Date : 04/06/2024



Northeast Off-Going Transition - 4/25/2014

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

Page 7 of 15

BRIDGE ID : 874294

Structure Inventory Photo Due Date : 04/06/2024



South Approach Looking North - 4/25/2014

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

Page 8 of 15

BRIDGE ID : 874294

Structure Inventory Photo Due Date : 04/06/2024



South Approach Looking South - 4/25/2014

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

Page 9 of 15

BRIDGE ID : 874294

Structure Inventory Photo Due Date : 04/06/2024



North Approach Looking South - 4/25/2014

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

Page 10 of 15

BRIDGE ID : 874294

Structure Inventory Photo Due Date : 04/06/2024



North Approach Looking North - 4/25/2014

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

Page 11 of 15

BRIDGE ID : 874294

Structure Inventory Photo Due Date : 04/06/2024



West Elevation - 4/25/2014

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

Page 12 of 15

BRIDGE ID : 874294

Structure Inventory Photo Due Date : 04/06/2024



East Elevation - 4/25/2014

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

Page 13 of 15

BRIDGE ID : 874294

Structure Inventory Photo Due Date : 04/06/2024



Typical Underside - 4/25/2014

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

Page 14 of 15

BRIDGE ID : 874294

Structure Inventory Photo Due Date : 04/06/2024



Channel Looking West - 4/25/2014

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

Page 15 of 15

BRIDGE ID : 874294

Structure Inventory Photo Due Date : 04/06/2024



Channel Looking East - 4/25/2014



BRIDGE INSPECTION REPORT

PREPARED FOR: FDOT District 6
 BRIDGE OWNER: Miami-Dade County
 INSPECTION TYPE: Interim CONTRACT No. CA611

Inspected by:
LARS Engineering, Inc.

Bridge No. 874294

REPORT CONTAINS

Inspection Date: 10-22-20


- | | | | |
|-----------------------------------------------------------|-----------------------------------------------|---------------------------------------------------------------|---------------------------------------------------------|
| <input checked="" type="checkbox"/> BrM Inspection Report | <input type="checkbox"/> Bridge Profile | <input type="checkbox"/> Fracture Critical Data | <input type="checkbox"/> Addendum |
| <input checked="" type="checkbox"/> CIDR Information | <input type="checkbox"/> UW Inspection Report | <input checked="" type="checkbox"/> Load Rating Summary Sheet | <input type="checkbox"/> Mechanical and Electrical Data |



**Matheson Hammock Road over
 Matheson Hammock Canal**

Facility Carried & Location

Matheson Hammock Park



Location Map

Detour Length = 3.13 mi.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM****Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)****Structure ID: 874294****Inspection****DISTRICT: D6 - Miami****INSPECTION DATE: 10/22/2020 MIGV**

BY:	LARS Engineering, Inc.	STRUCTURE NAME:	Not recorded
OWNER:	2 County Hwy Agency	YEAR BUILT:	1967
MAINTAINED BY:	2 County Hwy Agency	SECTION NO.:	87 000 757
STRUCTURE TYPE:	5 Prestressed Concrete - 01 Slab	MP:	0.080
LOCATION:	Matheson Hammock Park	ROUTE:	00000
SERV. TYPE ON:	5 Highway-pedestrian	FACILITY CARRIED:	Matheson Hmk Road
SERV. TYPE UNDER:	5 Waterway	FEATURE INTERSECTED:	Matheson Hammock Canal

☐ FUNCTIONALLY OBSOLETE☒ STRUCTURALLY DEFICIENT

TYPE OF INSPECTION: Interim

DATE FIELD INSPECTION WAS PERFORMED: ABOVE WATER: 10/22/2020 UNDERWATER: 4/6/2020

SUFFICIENCY RATING:	15.5
HEALTH INDEX:	85.67

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

Inspection/CIDR Report with PDF attachment(s) (INTERIM INSPECTION REPORT)

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV

BY: LARS Engineering, Inc.
 OWNER: 2 County Hwy Agency
 MAINTAINED BY: 2 County Hwy Agency
 STRUCTURE TYPE: 5 Prestressed Concrete - 01 Slab
 LOCATION: Matheson Hammock Park
 SERV. TYPE ON: 5 Highway-pedestrian
 SERV. TYPE UNDER: 5 Waterway

STRUCTURE NAME: Not recorded
 YEAR BUILT: 1967
 SECTION NO.: 87 000 757
 MP: 0.080
 ROUTE: 00000
 FACILITY CARRIED: Matheson Hmk Road
 FEATURE INTERSECTED: Matheson Hammock Canal

- ☐ THIS BRIDGE CONTAINS FRACTURE CRITICAL COMPONENTS
- ☐ THIS BRIDGE IS SCOUR CRITICAL
- ☒ THIS REPORT IDENTIFIES DEFICIENCIES WHICH REQUIRE PROMPT CORRECTIVE ACTION
- ☐ FUNCTIONALLY OBSOLETE ☒ STRUCTURALLY DEFICIENT

TYPE OF INSPECTION: Interim

DATE FIELD INSPECTION WAS PERFORMED: ABOVE WATER: 10/22/2020 UNDERWATER: 4/6/2020

OVERALL NBI RATINGS:

DECK: 3 Serious	CHANNEL: 6 Bank Slumping
SUPERSTRUCTURE: 3 Serious	CULVERT: N N/A (NBI)
SUBSTRUCTURE: 4 Poor	SUFF. RATING: 15.5
PERF. RATING: Poor	HEALTH INDEX: 85.67

FIELD PERSONNEL / TITLE / NUMBER:**INITIALS**

Marquez, Loren - Professional Engineer (P.E. # 85631) (lead)

Lledias, Jorge - Bridge Inspector Assistant

REVIEWING BRIDGE INSPECTION SUPERVISOR:

Leon, Adrian - Professional Engineer (P.E. #83827)


CONFIRMING REGISTERED PROFESSIONAL ENGINEER:

Marquez, Loren - Professional Engineer (P.E. # 85631) LARS Engineering, Inc.
 7225 NW 25th Street
 Suite 211
 Miami Florida 33122

SIGNATURE: _____

DATE: _____

The official record of this package has been electronically signed and sealed by Loren Marquez, P.E. on the date adjacent to the seal as required by Rule 61G15-23.004, F.A.C. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.



This report contains information relating to the physical security of a structure and depictions of the structure. This information is confidential and exempt from public inspection pursuant to sections 119.071(3)(a) and 119.071(3)(b), Florida Statutes. Only the cover page of this report may be inspected and copied.

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

Inspection/CIDR Report with PDF attachment(s) (INTERIM INSPECTION REPORT)

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV

All Elements

DECKS : Decks/Slabs

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8099 / 3	PS Conc Slab (Sonovoid)	3122	88.29	5	0.14	409	11.57	0	.	3536 (SF)
0	1080 / 3	Delamination/Spall/Patched Area	0	.	5	45.45	6	54.55	0	.	11 (SF)
0	1090 / 3	Exposed Rebar	0	.	0	.	1	100	0	.	1 (SF)
0	1100 / 3	Exposed Prestressing	0	.	0	.	20	100	0	.	20 (SF)
0	1110 / 3	Cracking (PSC)	0	.	0	.	292	100	0	.	292 (SF)
0	1900 / 3	Distortion	0	.	0	.	90	100	0	.	90 (SF)
0	510 / 3	Wearing Surfaces	1629	61.85	0	.	1005	38.15	0	.	2634 sq.ft
0	3220 / 3	Crack (Wearing Surface)	0	.	0	.	1005	100	0	.	1005 sq.ft

Element Inspection Notes:

8099/3 Notes: The top of the slab units is not visible due to an asphalt overlay. The width of the sonovoid slab units was field verified to be 3ft. wide.

SECONDARY:

_Object markers and centerline raised pavement markers are missing on the structure. (14 SF). - NO CHANGE. Refer to Photo 01.

_Sidewalk panels are loose and move under pedestrian load. (300 SF). - NO CHANGE.

_The slab unit joints show evidence of water seepage. - NO CHANGE. NCAR.

PREVIOUS RECOMMENDED CORRECTIVE ACTION:

- 1_Replace missing object markers at the four corners of the bridge.
- 2_Properly secure the sidewalk panels.
- 3_Repair spalls, delaminations, and cracks along the underside of the slab units.
- 4_Clean and coat exposed prestressing and reinforce Slab Unit 2-8.

CORRECTIVE ACTION EVALUATION:

- 1_Work not completed. Recommendation will be repeated.
- 2_Work not completed. Recommendation will be repeated.
- 3_Work not completed. Recommendation will be repeated.
- 4_Work not completed. Recommendation will be repeated.

For additional deficiencies refer to Defects 1080, 1090, 1100, 1110, and 1900.

1080/3

CS-3:

_Slab Unit 1-9, center line has a spall/delamination up to 36in. L x 24in. W x 2.5in. D over Abutment 1, with an exposed stirrup. (6 SF). - INCREASE. Refer to Photo 02.

CS-2:

_Slab Unit 2-6, east edge has a delamination 30in. L x 4in. W starting at Pier 2 cap. (3 SF). - NO CHANGE.

_Slab Unit 2-7, west edge has a delamination up to 24in. L x 4in. W starting at Pier 2 cap. (2 SF). - NO CHANGE.

1090/3

CS-3:

_Slab Unit 1-6 exhibits a spall with exposed rebar up to 11in. L x 5in. W x 1/8in. D with minor section loss and evidence of previous failed repair, at 9ft. from Abutment 1. (1

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

Inspection/CIDR Report with PDF attachment(s) (INTERIM INSPECTION REPORT)

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV

SF). - NO CHANGE. Refer to Photo 03.

1100/3

CS-3:

_Slab Unit 2-8 has a spall 10ft. L x 24in. W x up to 4in. D at mid-span with 6 exposed and corroded transverse rebars with up to 60% section remaining and 5 exposed and corroded prestressing strands with up to 0% section remaining (2 broken threads). (20 SF). - NO CHANGE. Refer to Photo 04.

1110/3

CS-3:

_Slab Unit 1-6 east edge has two delamination areas, one up to 5ft. L x 6in. W starting at Abutment 1 and the other starting at Pier Cap 2 up to 9ft. L x 12in. W with associated cracks up to 1/16in. W with efflorescence throughout. (Previously noted as a delamination full length x 12in. W.) (14 SF). - DECREASE. Refer to Photos 05 and 06.

_Slab Unit 1-7 east edge has a spall/delamination 24in. L x 12in. W with associated cracks up to 1/32in. W with efflorescence and corrosion bleed-out over Abutment 1. (2 SF). - NO CHANGE. Refer to Photo 07.

_Slab Unit 1-7, east edge has a delamination 7ft. L x 4in. W, with an associated crack of up to 1/16in. starting at Pier 2 cap. (7 SF). - INCREASE. Refer to Photo 08.

_Slab Unit 1-8 west edge is intermittently delaminated up to 15ft. L x 15in. W starting at Abutment 1 with associated cracks up to 1/4in. W with efflorescence and corrosion bleed-out and associated spalling up to 4ft. L x 6in. W x 2in. D approximately 10ft from Abutment 1. (Spalling was previously noted as spall/delamination on the east edge) (19 SF). - INCREASE. Refer to Photos 09 and 10.

_Slab Unit 1-8 east edge has a delamination 4ft. L x 15in. W and associated cracks up to 1/32in. W with efflorescence and corrosion bleed-out, 9ft. from Pier Cap 2. (Previously noted as spall/delamination near mid-span). (5 SF). - DECREASE. Refer to Photo 11.

_Slab Unit 1-8 has a delaminated area up to 8ft. L x 3ft. W and associated cracks up to 1/16in. W with efflorescence and corrosion bleed-out starting at Pier Cap 2. (24 SF). - INCREASE. Refer to Photo 12.

_Slab Unit 1-9 west edge has a delaminated area 9ft. L x 10in. W and associated cracks up to 1/16in. W with efflorescence and corrosion bleed-out, starting near the 3/4 point and extending to Pier 2 cap. (9 SF). - NO CHANGE. Refer to Photo 13.

_Slab Unit 2-7 east edge is intermittently cracked/delaminated up to span length x 16in. W (average width) with up to 1/4in. W cracks. (38 SF). - NO CHANGE. Refer to Photo 14.

_Slab Unit 2-8 west half has two delaminated areas up to 15ft. L x 18in. W (average width) at south and north ends, with associated cracks of up to 1/4in. W. (60 SF). - NO CHANGE. Refer to Photo 15.

_Slab Unit 2-9 west edge has a delaminated area up to 5ft. L x 5in. W with associated cracking up to 1/4in. wide, starting at the Pier 2 cap. (5 SF). - NO CHANGE.

_Slab Unit 3-6 has a delamination up to 24in. L x 6in. W on the east edge over Pier 3, with an associated crack of up to 1/16in. W. (2 SF). - INCREASE. Refer to Photo 16.

_Slab Unit 3-6 east edge has a delaminated area up to 42in. L x 8in. W with associated cracks up to 1/16in. W. (4 SF). - NEW. Refer to Photo 17.

_Slabs Unit 3-7 has two delaminated areas, one starting at Pier 3 up to 8ft. L x 15in. W (average width) with associated cracks, and the second, near mid-span up to 3ft. L x 30in. W. (25 SF). - NO CHANGE. Refer to Photos 18 and 19.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**

**Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV

_Slab Unit 3-7 has an unsound repaired area 12ft. L x up to slab width (3ft.) starting from Abutment 4 with hollow sounding throughout and associated cracks up to 1/16in. W with efflorescence and corrosion bleed-out. (30 SF). - INCREASE. Refer to Photo 20.

_Slab Unit 3-8 has a spall/delamination up to 8ft. L x 3ft. W x 1in. D and associated cracks with corrosion bleed-out starting at Pier 3. (24 SF). - INCREASE. Refer to Photo 21.

_Slab Unit 3-8 has an unsound repair/delamination up to 42in. L x 30in. W with associated cracks up to 1/16in. W with efflorescence starting at Abutment 4. (9 SF). - INCREASE. Refer to Photo 22.

_Slab Unit 3-8 has an unsound repair/delamination up to 74in. L x up to slab width (3ft.) with associated cracks up to 1/16in. W with efflorescence starting 5.5ft. from Abutment 4. (15 SF). - INCREASE. Refer to Photo 23.

1900/3

CS-3:

_Slab Unit 1-1 exhibits a slight outward rotation at Abutment 1 with up to 1/4in. height difference in reference to the top of the cap, potentially indicating shear key failure. (90 SF). - NO CHANGE. Refer to Photo 24.

510/3

PREVIOUS RECOMMENDED CORRECTIVE ACTION:

- 1_Monitor the slab units for independent movement.
- 2_Repair cracks on the asphalt along the slab unit joints.
- 3_Clean and repair cracks and rutting along the expansion joints.

CORRECTIVE ACTION EVALUATION:

- 1_Work not completed. Recommendation will be repeated.
- 2_Work not completed. Recommendation will be repeated.
- 3_Work not completed. Recommendation will be repeated.

For deficiencies refer to Defect 3220.

3220/3

CS-3:

_The asphalt overlay has longitudinal cracks up to span length x 1/4in. W with associated 1in. W rutting over the slab unit joints and upheaving up to 1in. H at the shoulders, possibly indicating independent slab unit movement. (600 SF). - NO CHANGE. Refer to Photos 25 and 26.

_The asphalt overlay at Spans 1 and 2 has multi-directional cracking up to 1/2in. W on Lane 2 (NB), worse condition is on Span 1 which has a 19.5ft L x 11ft. W area with hollow-sounding starting 1 ft. from the right sidewalk. (300 SF). - NEW. Refer to Photo 27.

_The asphalt overlay has transverse cracks up to roadway width x 1/4in. W with rutting and upheaving up to 3in. W and vegetation growth over the expansion joints. (105 SF). - NO CHANGE. Refer to Photo 28.

Total Number of Elements*: 1

*excluding defects/protective systems

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

Inspection/CIDR Report with PDF attachment(s) (INTERIM INSPECTION REPORT)

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV

Inspector Recommendations

UNIT: 0 DECKS
ELEMENT/ENV: 8099 / 3 PS Conc Slab (Sonovoid) ELEM CATEGORY: Decks/Slabs

CONDITION STATE		PRIORITY
1, 2, 3	MMS Quantity: 14 sf Element Estimated Quantity: 14 (SF)	3
WORK ORDER RECOMMENDATION:		
_Replace missing object markers at the four corners of the bridge and provide missing RPMs throughout the bridge. Refer to Photo 01.		
1, 2, 3	MMS Quantity: 300 sf Element Estimated Quantity: 300 (SF)	3
WORK ORDER RECOMMENDATION:		
_Properly secure the sidewalk panels.		

ELEMENT/ENV: 8099:510:3220 / 3 Crack (Wearing Surface) ELEM CATEGORY: Decks/Slabs

CONDITION STATE		PRIORITY
3	MMS Quantity: 900 sf Element Estimated Quantity: 900 sq.ft	3
WORK ORDER RECOMMENDATION:		
_Seal cracks on the asphalt along the slab unit joints and multi-directional cracks on Lane 2 (NB) in Spans 1 and 2. Refer to Photos 25, 26, and 27.		
3	MMS Quantity: 105 sf Element Estimated Quantity: 105 sq.ft	3
WORK ORDER RECOMMENDATION:		
_Clean and seal cracks and rutting along the expansion joints. Refer to Photo 28.		
3	MMS Quantity: 600 sf Element Estimated Quantity: 600 sq.ft	3
WORK ORDER RECOMMENDATION:		
_Monitor cracks along slab unit joints for independent movement of the slab units. Refer to Photos 25 and 26.		

ELEMENT/ENV: 8099:1080 / 3 Delamination/Spall/Patched Area ELEM CATEGORY: Decks/Slabs

CONDITION STATE		PRIORITY
2, 3	MMS Quantity: 303 sf Element Estimated Quantity: 303 (SF)	3
WORK ORDER RECOMMENDATION:		
_Repair spalls, delaminations, and cracks along the underside of the slab units. Refer to Photos 02 and 05 through 23.		

ELEMENT/ENV: 8099:1090 / 3 Exposed Rebar ELEM CATEGORY: Decks/Slabs

CONDITION STATE		PRIORITY
3	MMS Quantity: 1 sf Element Estimated Quantity: 1 (SF)	3
WORK ORDER RECOMMENDATION:		
_Clean and coat exposed rebar and repair spall along the underside of slab unit 1-6, 9ft. from Abutment 1. Refer to Photo 03.		

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**

**Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV

Inspector Recommendations

UNIT: 0 DECKS
ELEMENT/ENV: 8099:1100 / 3 Exposed Prestressing ELEM CATEGORY: Decks/Slabs

CONDITION STATE	PRIORITY
3 MMS Quantity: 20 sf Element Estimated Quantity: 20 (SF)	3
WORK ORDER RECOMMENDATION: _Clean and coat exposed prestressing and reinforce Slab Unit 2-8. Refer to Photo 04.	

ELEMENT/ENV: 8099:1900 / 3 Distortion ELEM CATEGORY: Decks/Slabs

CONDITION STATE	PRIORITY
3 MMS Quantity: 90 sf Element Estimated Quantity: 90 (SF)	3
WORK ORDER RECOMMENDATION: _Monitor slab unit 1-1 for possible independent movement on the slab unit. Refer to Photo 24.	

Structure Notes

BRIDGE OWNER: MIAMI-DADE COUNTY

Bridge inventoried from south to north. (Entrance on North end, boat ramp on South end).

P/S Slab Units on R/Conc Caps and Abutments over P/Conc Columns. (3 spans)

Element 227/3 Re Conc Pile notes have been replaced by Element 205/3 Re Conc Column on 10/29/2019.

Element 8475/3 R/Conc Walls notes have been replaced by Element 8393/3 Bulkhead Seawall Any Material on 04/06/2020.

The NBI Rating for Deck and Superstructure are coded 3 (Serious) due to spalls and delaminations along more than 25% of any of the slab units. Slabs Units 1-6, 2-7, and 2-8 meet this criteria. (04/06/2020).

The Substructure NBI Rating is coded 4 (Poor) due to the significant deterioration of Column 2-2. (04/06/2020).

The Channel NBI Rating was lowered from 7 to 6 due to areas of undermining on the channel below the North seawall. (04/06/2020).

TRAFFIC RESTRICTIONS:

Based on the current load rating analysis dated 1/13/2020, it is recommended that this bridge be posted for the SU, C and ST5 type vehicles as follows: SU = 11 tons, C = 16 tons, ST5 = 18 tons. The bridge is currently posted for SU = 11 tons, C = 16 tons, ST5 = 18 tons. Refer to posting signs Photos 29 and 30.

REVIEWED BY:

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**

**Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV

INSPECTION NOTES: **MIGV** **10/22/2020**

Sufficiency Rating Calculation Accepted by KNLREJP at 11/18/2020 2:56:35 PM

This Interim inspection (10/22/2020) was conducted to evaluate Element 8099 PS Conc Slab (Sonovoid), for the status of the entire structure refer to the last Regular NBI Inspection (04/06/2020).

LOAD CAPACITY EVALUATION:

Since the current load rating dated 1/13/2020, there is no indication that deterioration, geometric changes or additional dead load have occurred that would warrant a new load rating analysis. This only applies to this inspection dated 10/22/2020 per Loren Marquez, P.E.

The structure is on a 6 months inspection frequency due to NBI Rating 3 for SIA Items 58 Deck and 59 Superstructure.

The Deck and Superstructure are coded 3 (Serious) due to spalls and delaminations along more than 25% of any of the slab units. Slabs Units 1-6, 2-7, and 2-8 meet this criteria. (10/22/2020).

LEGEND:

NCAR: NO CORRECTIVE ACTION RECOMMENDED

RT: Right

LT: Left

L: Long

W: Wide

H: High

D: Deep

in.: Inches

ft.: Feet

LF: Linear Feet

SF: Square Feet

NE: Northeast

NW: Northwest

SE: Southeast

SW: Southwest

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM****Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)****Structure ID: 874294****Inspection****DISTRICT: D6 - Miami****INSPECTION DATE: 10/22/2020 MIGV**

PHOTO 01: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Object markers and centerline raised pavement markers are missing on the structure.

REPAIR RECOMMENDATION:

Replace missing object markers at the four corners of the bridge and provide missing RPMs throughout the bridge.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 02: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 1-9, center line has a spall/delamination up to 36in. L x 24in. W x 2.5in. D over Abutment 1, with an exposed stirrup.

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 03: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 1-6 exhibits a spall with exposed rebar up to 11in. L x 5in. W x 1/8in. D with minor section loss and evidence of previous failed repair, at 9ft. from Abutment 1.

REPAIR RECOMMENDATION:

Clean and coat exposed rebar and repair spall along the underside of slab unit 1-6, 9ft. from Abutment 1.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 04: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 2-8 has a spall 10ft. L x 24in. W x up to 4in. D at mid-span with 6 exposed and corroded transverse rebars with up to 60% section remaining and 5 exposed and corroded prestressing strands with up to 0% section remaining (2 broken threads).

REPAIR RECOMMENDATION:

Clean and coat exposed prestressing and reinforce Slab Unit 2-8.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 05: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 1-6 east edge has two delamination areas, one up to 5ft. L x 6in. W starting at Abutment 1 and the other starting at Pier Cap 2 up to 9ft. L x 12in. W with associated cracks up to 1/16in. W with efflorescence throughout. (Abutment 1 shown).

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 06: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 1-6 east edge has two delamination areas, one up to 5ft. L x 6in. W starting at Abutment 1 and the other starting at Pier Cap 2 up to 9ft. L x 12in. W with associated cracks up to 1/16in. W with efflorescence throughout. (Pier Cap 2 shown).

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 07: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 1-7 east edge has a spall/delamination 24in. L x 12in. W with associated cracks up to 1/32in. W with efflorescence and corrosion bleed-out over Abutment 1.

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 08: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 1-7, east edge has a delamination 7ft. L x 4in. W, with an associated crack of up to 1/16in. starting at Pier 2 cap.

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 09: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 1-8 west edge is intermittently delaminated up to 15ft. L x 15in. W starting at Abutment 1 with associated cracks up to 1/4in. W with efflorescence and corrosion bleed-out and associated spalling up to 4ft. L x 6in. W x 2in. D approximately 10ft from Abutment 1.

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 10: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 1-8 west edge is intermittently delaminated up to 15ft. L x 15in. W starting at Abutment 1 with associated cracks up to 1/4in. W with efflorescence and corrosion bleed-out and associated spalling up to 4ft. L x 6in. W x 2in. D approximately 10ft from Abutment 1.

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 11: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 1-8 east edge has a delamination 4ft. L x 15in. W and associated cracks up to 1/32in. W with efflorescence and corrosion bleed-out, 9ft. from Pier Cap 2.

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 12: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 1-8 has a delaminated area up to 8ft. L x 3ft. W and associated cracks up to 1/16in. W with efflorescence and corrosion bleed-out starting at Pier Cap 2.

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 13: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 1-9 west edge has a delaminated area 9ft. L x 10in. W and associated cracks up to 1/16in. W with efflorescence and corrosion bleed-out, starting near the 3/4 point and extending to Pier 2 cap.

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 14: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 2-7 east edge is intermittently cracked/delaminated up to span length x 16in. W (average width) with up to 1/4in. W cracks.

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 15: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 2-8 west half has two delaminated areas up to 15ft. L x 18in. W (average width) at south and north ends, with associated cracks of up to 1/4in. W.

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 16: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 3-6 has a delamination up to 24in. L x 6in. W on the east edge over Pier 3, with an associated crack of up to 1/16in. W.

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 17: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 3-6 east edge has a delaminated area up to 42in. L x 8in. W with associated cracks up to 1/16in. W.

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 18: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slabs Unit 3-7 has two delaminated areas, one starting at Pier 3 up to 8ft. L x 15in. W (average width) with associated cracks, and the second, near mid-span up to 3ft. L x 30in. W. (Pier 3 shown).

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 19: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slabs Unit 3-7 has two delaminated areas, one starting at Pier 3 up to 8ft. L x 15in. W (average width) with associated cracks, and the second, near mid-span up to 3ft. L x 30in. W. (Mid-span shown).

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 20: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 3-7 has an unsound repaired area 12ft. L x up to slab width (3ft.) starting from Abutment 4 with hollow-sounding throughout and associated cracks up to 1/16in. W with efflorescence and corrosion bleed-out.

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 21: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 3-8 has a spall/delamination up to 8ft. L x 3ft. W x 1in. D and associated cracks with corrosion bleed-out starting at Pier 3.

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 22: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 3-8 has an unsound repair/delamination up to 42in. L x 30in. W with associated cracks up to 1/16in. W with efflorescence starting at Abutment 4.

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 23: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 3-8 has an unsound repair/delamination up to 74in. L x up to slab width (3ft.) with associated cracks up to 1/16in. W with efflorescence starting 5.5ft. from Abutment 4.

REPAIR RECOMMENDATION:

Repair spalls, delaminations, and cracks along the underside of the slab units.

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 24: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

Slab Unit 1-1 exhibits a slight outward rotation at Abutment 1 with up to 1/4in. height difference in reference to the top of the cap, potentially indicating shear key failure.

REPAIR RECOMMENDATION:

Monitor slab unit 1-1 for possible independent movement of the slab unit.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 25: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

The asphalt overlay has longitudinal cracks up to span length x 1/4in. W with associated 1in. W rutting over the slab unit joints and upheaving up to 1in. H at the shoulders, possibly indicating independent slab unit movement.

REPAIR RECOMMENDATION:

- 1) Monitor cracks along slab unit joints for independent movement of the slab units.
- 2) Seal cracks on the asphalt along the slab unit joints and multi-directional cracks on Lane 2 (NB) in Spans 1 and 2.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 26: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

The asphalt overlay has longitudinal cracks up to span length x 1/4in. W with associated 1in. W rutting over the slab unit joints and upheaving up to 1in. H at the shoulders, possibly indicating independent slab unit movement.

REPAIR RECOMMENDATION:

- 1) Monitor cracks along slab unit joints for independent movement of the slab units.
- 2) Seal cracks on the asphalt along the slab unit joints and multi-directional cracks on Lane 2 (NB) in Spans 1 and 2.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 27: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

The asphalt overlay at Spans 1 and 2 has multi-directional cracking up to 1/2in. W on Lane 2 (NB), worse condition is on Span 1 which has a 19.5ft L x 11ft. W area with hollow-sounding starting 1 ft. from the right sidewalk.

REPAIR RECOMMENDATION:

Seal cracks on the asphalt along the slab unit joints and multi-directional cracks on Lane 2 (NB) in Spans 1 and 2.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 28: ELEMENT/ENV: 8099/3 PS Conc Slab (Sonovoid)

The asphalt overlay has transverse cracks up to roadway width x 1/4in. W with rutting and upheaving up to 3in. W and vegetation growth over the expansion joints.

REPAIR RECOMMENDATION:

Clean and seal cracks and rutting along the expansion joints.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV



PHOTO 29: STRUCTURE NOTES

South Approach Posting Sign.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 10/22/2020 MIGV




PHOTO 30: STRUCTURE NOTES

North Approach Posting Sign.

Bridge No.	874294	Analysis Method:	LRFR-LRFD	FDOT Bridge Load Rating Summary Form (Page 1 of 1)
Location	Matheson hammock Road over matheson Hammock Canal			
Description	3 Spans, 2-30'&1-40', Prestressed voided slab beams 36"x17"			

Rating Type	Rating Type	Gross Axle Weight (tons)	Moment/Shear/Service		Dead Load Factor	Live Load Factor	Live Load Distrib. Factor (axles)	Rating Factor	Span No. - Girder No., Interior/Exterior, %Span Length	RF-Weight (tons)
Level	Vehicle	Weight	Member Type	Limit	DC	LL	LLDF	RF	Governing Location	RATING
Inventory	HL93	36	Prestressed	Service	1.00	0.80	0.600	0.210	Central span, midspan	7.6
Operating	HL93	36	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.330	Central span, midspan	11.9
Permit	FL120	60	Prestressed	Strength, Shear	1.25/0.90	1.35	0.500	0.270	Central span, 1/4 point	16.2
Permit Max Span	FL120	60	Prestressed	Strength, Shear	1.25/0.90	1.35	0.500	0.270	Central span, 1/4 point	16.2
Legal	SU2	17	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.690	Central span, midspan	11.7
	SU3	33	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.370	Central span, midspan	12.2
	SU4	35	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.340	Central span, midspan	11.9
	C3	28	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.650	Central span, midspan	18.2
	C4	36.7	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.460	Central span, midspan	16.9
	C5	40	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.440	Central span, midspan	17.6
	ST5	40	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.460	Central span, midspan	18.4
Emergency Vehicle (EV)	EV2	28.75	Prestressed	NA	NA	NA	0.600			-1
	EV3	43	Prestressed	NA	NA	NA	0.600			-1

Original Design Load	HS20 or HS20-S16-44	Performed by:	Mengyuan Chen	Date:	01/13/20
Rating Type, Analysis	LRFR-LRFD	Checked by:	Juan A. Sobrino	Date:	01/13/20
Distribution Method	Others	Sealed By:	Juan A. Sobrino	Date:	01/13/20
Impact Factor	33.0% (axle loading)	FL P.E. No.:	73121		
FL120 Gov. Span Length	38.3 (feet)	Cert. Auth. No.:	27244		
Minimum Span Length	28.3 (feet)	Phone & email:	(+1) 305 648 00 10, miami@pedelta.om		
Recommended Posting	> 39.9% below (0.000-0.600) (Required)	Company:	Pedelta Inc.		
Recommended SU Posting*	11 (tons)	Address:	2000 Ponce de Leon Blvd., Suite 624, Coral Gables, Florida 33134, USA		
Recommended C Posting	16 (tons)	<div> <div>  <div> Juan A. Sobrino P.E., State of Florida, Professional Engineer </div> </div> <div> Digitally signed by Juan Sobrino Date: 2020.01.13 15:58:25 -05'00' </div> </div> <p>Juan A. Sobrino, State of Florida, Professional Engineer, License No 73121.</p> <p>This document has been electronically signed and sealed by Juan A. Sobrino on January 13th, 2020 using a SHA authentication code. Printed copies of this document are not considered signed and sealed and the SHA authentication code must be verified on any electronic copies.</p>			
Recommended ST5 Posting	18 (tons)				
Owner	02 County Highway Agency				
Location	Neither Interstate traffic nor within 1 mile reasonable access to an Interstate				
EV Posting	No. EV posting is not recommended. The FAST Act does not apply				
Floor Beam Present?	No				
Segmental Bridge?	No				
Project No. & Reason	432907-1-72-02 Deterioration				
Plans Status	Built				

This 10-11-2019 summary follows the FDOT Bridge Load Rating Manual (BLRM), and the FDOT BMS Coding Guide.

*Recommended SU Posting levels for Florida SU trucks adequately restricts AASHTO SU trucks; see BLRM Chapter 7.

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

Inspection/CIDR Report with PDF attachment(s)

Structure ID: 874294

CIDR

DATE PRINTED: 11/24/2020

Description

Structure Unit Identification

Bridge/Unit Key: 874294 0
 Structure Name:
 Description: SPANS 1 THRU 3
 Type: M - Main

Roadway Identification

NBI Structure No (8): 874294
 Position/Prefix (5): 1 - Route On Structure
 Kind Hwy (Rte Prefix): 4 County Hwy
 Design Level of Service: 8 Service Road
 Route Number/Suffix: 00000 / 0 N/A (NBI)
 Feature Intersect (6): Matheson Hammock Canal
 Critical Facility: Not Defense-crit
 Facility Carried (7): Matheson Hmk Road
 Mile Point (11): 0.08
 Latitude (16): 025d40'44.2" Long (17): 080d15'43.8"

Roadway Traffic and Accidents

Lanes (28): 2 Medians: 0 Speed: 15 mph
 ADT Class: 2 ADT Class 2
 Recent ADT (29): 736 Year (30): 2014
 Future ADT (114): 1168 Year (115): 2041
 Truck % ADT (109): 1
 Detour Length (19): 99 mi
 Detour Speed:
 Accident Count: -1 Rate:

Roadway Classification

Nat. Hwy Sys (104): 0 Not on NHS
 National base Net (12): 0 - Not on Base Network
 LRS Inventory Rte (13a): 87 000 757 Sub Rte (13b): 00
 Functional Class (26): 09 Rural Local
 Federal Aid System: OFF
 Defense Hwy (100): 0 Not a STRAHNET hwy
 Direction of Traffic (102): 2 2-way traffic
 Emergency: ☒

Roadway Clearances

Vertical (10): 99.99 ft Appr. Road (32): 26.25 ft
 Horiz. (47): 26.25 ft Roadway (51): 26.25 ft
 Truck Network (110): 0 Not part of natl netwo
 Toll Facility (20): 3 On free road
 Fed. Lands Hwy (105): 0 N/A (NBI)
 School Bus Route: ☐
 Transit Route: ☐

NBI Project Data

Proposed Work (075A): Not Applicable (P)
 Work To Be Done By (075B): Not Applicable (P)
 Improvement Length (076): 0 ft

Improvement Cost (094): \$ 0.00
 Roadway Improvement Cost (095): \$ 0.00
 Total Cost (096): \$ 0.00
 Year of Estimate (097):

NBI Rating

Channel (61): 6 Bank Slumping
 Deck (58): 3 Serious
 Superstructure (59): 3 Serious
 Substructure (60): 4 Poor

Culvert (62): N N/A (NBI)
 Waterway (71): 8 Equal Desirable
 Unrepaired Spalls: -1 sq.ft.
 Review Required: ☒

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

Inspection/CIDR Report with PDF attachment(s)

Structure ID: 874294

CIDR

DATE PRINTED: 11/24/2020

Structure Identification

Admin Area: Miami-Dade
 District (2): D6 - Miami
 County (3): (87)Miami-Dade
 Place Code (4): South Miami Heights
 Location (9): Matheson Hammock Park
 Border Br St/Reg (98): Not Applicable (P) Share: 0 %
 Border Struct No (99):
 FIPS State/Region (1): 12 Florida Region 4-Atlanta
 NBIS Bridge Len (112): Y - Meets NBI Length
 Parallel Structure (101): No || bridge exists
 Temp. Structure (103): Not Applicable (P)
 Maint. Resp. (21): 2 County Hwy Agency
 Owner (22): 2 County Hwy Agency
 Historic Signif. (37): 5 Not eligible for NRHP

Structure Type and Material

Curb/Sidewalk (50): Left: 1.5 ft Right: 5.5 ft
 Bridge Median (33): 0 No median
 Main Span Material (43A): 5 Prestressed Concrete
 Appr Span Material (44A): Not Applicable (P)
 Main Span Design (43B): 01 Slab
 Appr Span Design (44B): 00 Other (NBI)

Appraisal**Structure Appraisal**

Open/Posted/Closed (41): P Posted for load
 Deck Geometry (68): 5 Above Tolerable
 Underclearances (69): N Not applicable (NBI)
 Approach Alignment (72): 8-No Speed Red thru Curv
 Bridge Railings (36a): 0 Substandard
 Transitions (36b): 0 Substandard
 Approach Guardrail (36c): 0 Substandard
 Approach Guardrail Ends (36d): 0 Substandard
 Scour Critical (113): U Unknown Foundation

Minimum Vertical Clearance

Over Structure (53): 99.99 ft
 Under (reference) (54a): N Feature not hwy or RR
 Under (54b): 0 ft

Schedule**Current Inspection**

Inspection Date: 10/22/2020
 Inspector: KNLRELM - Loren Marquez
 Bridge Group: CA611
 Alt. Bridge Group:
 Primary Type: Interim
 Review Required: ☒

Geometrics

Spans in Main Unit (45): 3
 Approach Spans (46): 0
 Length of Max Span (48): 38.3 ft
 Structure Length (49): 100.33 ft
 Total Length: 140.33 ft
 Deck Area: 3536 sqft
 Structure Flared (35): 0 No flare

Age and Service

Year Built (27): 1967
 Year Reconstructed (106): 0
 Type of Service On (42a): 5 Highway-pedestrian
 Under (42b): 5 Waterway
 Fracture Critical Details: Not Applicable

Deck Type and Material

Deck Width (52): 35.25 ft
 Skew (34): 0 deg
 Deck Type (107): 2 Concrete Precast Panel
 Surface (108): 6 Bituminous
 Membrane: 0 None
 Deck Protection: None

Navigation Data

Navigation Control (38): Permit Not Required
 Nav Vertical Clr (39): 0 ft
 Nav Horizontal Clr (40): 0 ft
 Min Vert Lift Clr (116): 0 ft
 Pier Protection (111): 1 Not Required

NBI Condition Rating

Sufficiency Rating: 15.5
 Health Index: 85.67
 Structural Eval (67): 3 Intolerable - Correct
 Deficiency: Structurally Deficient

Minimum Lateral Underclearance

Reference (55a): N Feature not hwy or RR
 Right Side (55b): 0 ft
 Left Side (56): 0 ft

Next Inspection Date Scheduled

NBI: 04/06/2022
 Element: 04/06/2021
 Fracture Critical:
 Underwater: 04/06/2022
 Other/Special: 04/06/2021
 Inventory Photo Update Due: 04/06/2024

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

Inspection/CIDR Report with PDF attachment(s)

Structure ID: 874294

CIDR

DATE PRINTED: 11/24/2020

Schedule Cont.**Inspection Types
Performed**NBI ☐Element ☒Fracture Critical ☐Underwater ☐Other Special ☒**Inspection Intervals****Required (92)****Frequency (92)****Last Date (93)****Inspection Resources**Fracture Critical ☐

mos

Crew Hours: 4

Underwater ☒

24 mos

04/06/2020

Flagger Hours: 0

Other Special ☒

6 mos

10/22/2020

Helper Hours: 0

NBI

24 mos

(91) 04/06/2020 (90)

Snooper Hours: 0

Special Crew Hours: 3

Special Equip Hours: 0

Bridge Related**General Bridge Information**

Parallel Bridge Seq:

Channel Depth: 10.6 ft

Radio Frequency: -1

Phone Number:

Exception Date:

Exception Type: Unknown

Accepted By Maint: 01/01/1967

Warranty Expiration: 00/00/0000

Performance Rating: Poor

Bridge Rail 1: Conc parapet-alum-rail

Bridge Rail 2: Not applicable-No rail

Electrical Devices: No electric service

Culvert Type: Not applicable

Maintenance Yard: Not FDOT Maintained

FIHS ON / OFF: No Routes on FIHS

Previous Structure:

2nd Previous Structure:

Replacement Structure:

Permitted Utilities: Power ☐Water ☒Gas ☐Fiber Optic ☐Sewage ☒Other ☐**Bridge Load Rating Information**

Inventory Type (065): 3 LRFR Load & Res. Fact

Operating Type (063): 3 LRFR Load & Res. Fact

Original Design Load (031): HL 93

Date: 01/13/2020

Initials: JS

Load Rating Rev. Recom.: No

Load Rating Plans Status: Field Measurements

Inventory Rating (066): 7.6 tons

Operating Rating (064): 11.9 tons

FL120 Permit Rating: 16.2 tons

HS20/FL120 Max Span Rating: 16.2 tons

Dynamic Impact in Percent: 33 %

Governing Span Length: 38.3 ft

Minimum Span Length: 28.3 ft

Distribution Method: Others

Load Rating Notes:

LEGAL LOADS

SU2: 11.7 tons

SU3: 12.2 tons

SU4: 11.9 tons

C3: 18.2 tons

C4: 16.9 tons

C5: 17.6 tons

ST5: 18.4 tons

Posting (070): 2 20.0-29.9%below

Open/Posted/Closed (041): P Posted for load

POSTING

Recom. SU Posting: 11 tons

Recom. C Posting: 16 tons

Recom. ST5 Posting: 18 tons

Actual SU Posting: 11 tons

Actual C Posting: 16 tons

Actual ST5 Posting: 18 tons

Actual Blanket Posting: 99 tons

Emergency Vehicle: 1 EV inapplicable

FLOOR BEAM (FB)

FB Present: No

FB Span Length, Gov: 0.0 ft

FB Spacing, Gov: 0.0 ft

FB OPR Rating: 0.0 tons

FB SU4 OPR Rating: 0.0 tons

FB FL120 Rating: 0.0 tons

SEGMENTAL (SEG)

SEG Wing-Span: -1.0 ft

SEG Web-to-Web Span: -1.0 ft

SEG Transverse HL93 Operating: -1.00 RF

Bridge Scour and Storm Information

Pile Driving Record: No pile driving records

Foundation Type: Unknown

Mode of Flow: Tidal

Rating Scour Eval: Minimal Risk

Highest Scour Eval: Unknown

Scour Evaluation Method:

Scour Recommended I: Unknown

Scour Recommended II: Unknown

Scour Recommended III: Unknown

Scour Elevation: -1 ft

Action Elevation: -1 ft

Storm Frequency: -1

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

Inspection/CIDR Report with PDF attachment(s)

Structure ID: 874294

CIDR

DATE PRINTED: 11/24/2020

Elements

Inspection Date: 10/22/2020 MIGV

DECKS : Decks/Slabs

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8099 / 3	PS Conc Slab (Sonovoid)	3122	88.29	5	0.14	409	11.57	0	.	3536 (SF)
0	1080 / 3	Delamination/Spall/Patched Area	0	.	5	45.45	6	54.55	0	.	11 (SF)
0	1090 / 3	Exposed Rebar	0	.	0	.	1	100	0	.	1 (SF)
0	1100 / 3	Exposed Prestressing	0	.	0	.	20	100	0	.	20 (SF)
0	1110 / 3	Cracking (PSC)	0	.	0	.	292	100	0	.	292 (SF)
0	1900 / 3	Distortion	0	.	0	.	90	100	0	.	90 (SF)
0	510 / 3	Wearing Surfaces	1629	61.85	0	.	1005	38.15	0	.	2634 sq.ft
0	3220 / 3	Crack (Wearing Surface)	0	.	0	.	1005	100	0	.	1005 sq.ft

DECKS : Joints

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	301 / 3	Pourable Joint Seal	0	.	0	.	104	74.29	36	25.71	140 ft
0	2310 / 3	Leakage	0	.	0	.	104	100	0	.	104 ft
0	2330 / 3	Seal Damage	0	.	0	.	0	.	36	100	36 ft

MISCELLANEOUS : Channel

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8290 / 3	Channel	0	.	0	.	1	100	0	.	1 (EA)
0	9150 / 3	Bank Erosion	0	.	0	.	1	100	0	.	1 (EA)

MISCELLANEOUS : Other Elements

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	321 / 3	Re Conc Approach Slab	1410	100	0	.	0	.	0	.	1410 sq.ft
0	510 / 3	Wearing Surfaces	957	91.14	0	.	93	8.86	0	.	1050 sq.ft
0	3220 / 3	Crack (Wearing Surface)	0	.	0	.	93	100	0	.	93 sq.ft

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	205 / 3	Re Conc Column	0	.	0	.	4	100	0	.	4 each
0	1090 / 3	Exposed Rebar	0	.	0	.	1	100	0	.	1 each
0	1130 / 3	Cracking (RC and Other)	0	.	0	.	3	100	0	.	3 each

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	215 / 3	Re Conc Abutment	65	92.86	0	.	5	7.14	0	.	70 ft
0	1080 / 3	Delamination/Spall/Patched Area	0	.	0	.	5	100	0	.	5 ft

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	234 / 3	Re Conc Pier Cap	49	72.06	12	17.65	7	10.29	0	.	68 ft
0	1080 / 3	Delamination/Spall/Patched Area	0	.	12	63.16	7	36.84	0	.	19 ft

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

Inspection/CIDR Report with PDF attachment(s)

Structure ID: 874294

CIDR

DATE PRINTED: 11/24/2020

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8393 / 3	Bulkhead Seawall Any Material	0	.	0	.	354	100	0	.	354 ft
0	1130 / 3	Cracking (RC and Other)	0	.	0	.	314	100	0	.	314 ft
0	6000 / 3	Scour	0	.	0	.	40	100	0	.	40 ft

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8394 / 3	R/Conc Abut Slope Protection	3968	73.81	0	.	1408	26.19	0	.	5376 (SF)
0	1130 / 3	Cracking (RC and Other)	0	.	0	.	320	100	0	.	320 (SF)
0	4000 / 3	Settlement	0	.	0	.	1088	100	0	.	1088 (SF)

SUPERSTRUCTURE : Superstructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	333 / 3	Other Bridge Railing	167	83.5	33	16.5	0	.	0	.	200 ft
0	1000 / 3	Corrosion	0	.	30	100	0	.	0	.	30 ft
0	1020 / 3	Connection	0	.	3	100	0	.	0	.	3 ft

Total Number of Elements*: 10

*excluding defects/protective systems

Inspection Information**Inspection Date:** 10/22/2020**Type:** Interim**Inspector:** KNLRELM - Loren Marquez**Inspection Notes:** Sufficiency Rating Calculation Accepted by KNLREJP at 11/18/2020 2:56:35 PM

This Interim inspection (10/22/2020) was conducted to evaluate Element 8099 PS Conc Slab (Sonovoid), for the status of the entire structure refer to the last Regular NBI Inspection (04/06/2020).

LOAD CAPACITY EVALUATION:

Since the current load rating dated 1/13/2020, there is no indication that deterioration, geometric changes or additional dead load have occurred that would warrant a new load rating analysis. This only applies to this inspection dated 10/22/2020 per Loren Marquez, P.E.

The structure is on a 6 months inspection frequency due to NBI Rating 3 for SIA Items 58 Deck and 59 Superstructure.

The Deck and Superstructure are coded 3 (Serious) due to spalls and delaminations along more than 25% of any of the slab units. Slabs Units 1-6, 2-7, and 2-8 meet this criteria. (10/22/2020).

LEGEND:

NCAR: NO CORRECTIVE ACTION RECOMMENDED

RT: Right

LT: Left

L: Long

W: Wide

H: High

D: Deep

in.: Inches

ft.: Feet

LF: Linear Feet

SF: Square Feet

NE: Northeast

NW: Northwest

SE: Southeast

SW: Southwest

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**

REPORT ID: INSP005

Inspection/CIDR Report with PDF attachment(s)

Structure ID: 874294

CIDRDATE PRINTED: 11/24/2020

Structure Notes

BRIDGE OWNER: MIAMI-DADE COUNTY

Bridge inventoried from south to north. (Entrance on North end, boat ramp on South end).

P/S Slab Units on R/Conc Caps and Abutments over P/Conc Columns. (3 spans)

Element 227/3 Re Conc Pile notes have been replaced by Element 205/3 Re Conc Column on 10/29/2019.

Element 8475/3 R/Conc Walls notes have been replaced by Element 8393/3 Bulkhead Seawall Any Material on 04/06/2020.

The NBI Rating for Deck and Superstructure are coded 3 (Serious) due to spalls and delaminations along more than 25% of any of the slab units. Slabs Units 1-6, 2-7, and 2-8 meet this criteria. (04/06/2020).

The Substructure NBI Rating is coded 4 (Poor) due to the significant deterioration of Column 2-2. (04/06/2020).

The Channel NBI Rating was lowered from 7 to 6 due to areas of undermining on the channel below the North seawall. (04/06/2020).

TRAFFIC RESTRICTIONS:

Based on the current load rating analysis dated 1/13/2020, it is recommended that this bridge be posted for the SU, C and ST5 type vehicles as follows: SU = 11 tons, C = 16 tons, ST5 = 18 tons. The bridge is currently posted for SU = 11 tons, C = 16 tons, ST5 = 18 tons. Refer to posting signs Photos 29 and 30.

REVIEWED BY:

Schedule Notes



**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM****Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)****Structure ID: 874294****Inspection****DISTRICT: D6 - Miami****INSPECTION DATE: 4/26/2021 HIXS**

BY: Marlin Engineering, Inc.	STRUCTURE NAME: Not recorded
OWNER: 2 County Hwy Agency	YEAR BUILT: 1967
MAINTAINED BY: 2 County Hwy Agency	SECTION NO.: 87 000 757
STRUCTURE TYPE: 5 Prestressed Concrete - 01 Slab	MP: 0.080
LOCATION: Matheson Hammock Park	ROUTE: 00000
SERV. TYPE ON: 5 Highway-pedestrian	FACILITY CARRIED: Matheson Hmk Road
SERV. TYPE UNDER: 5 Waterway	FEATURE INTERSECTED: Matheson Hammock Canal

☐ FUNCTIONALLY OBSOLETE☒ STRUCTURALLY DEFICIENT

TYPE OF INSPECTION: Interim

DATE FIELD INSPECTION WAS PERFORMED: ABOVE WATER: 4/26/2021 UNDERWATER: 4/6/2020

SUFFICIENCY RATING:	15.5
HEALTH INDEX:	85.48

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

Inspection/CIDR Report with PDF attachment(s) (INTERIM INSPECTION REPORT)

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS

BY: Marlin Engineering, Inc.
 OWNER: 2 County Hwy Agency
 MAINTAINED BY: 2 County Hwy Agency
 STRUCTURE TYPE: 5 Prestressed Concrete - 01 Slab
 LOCATION: Matheson Hammock Park
 SERV. TYPE ON: 5 Highway-pedestrian
 SERV. TYPE UNDER: 5 Waterway

STRUCTURE NAME: Not recorded
 YEAR BUILT: 1967
 SECTION NO.: 87 000 757
 MP: 0.080
 ROUTE: 00000
 FACILITY CARRIED: Matheson Hmk Road
 FEATURE INTERSECTED: Matheson Hammock Canal

- ☐ THIS BRIDGE CONTAINS FRACTURE CRITICAL COMPONENTS
- ☐ THIS BRIDGE IS SCOUR CRITICAL
- ☒ THIS REPORT IDENTIFIES DEFICIENCIES WHICH REQUIRE PROMPT CORRECTIVE ACTION
- ☐ FUNCTIONALLY OBSOLETE ☒ STRUCTURALLY DEFICIENT

TYPE OF INSPECTION: Interim

DATE FIELD INSPECTION WAS PERFORMED: ABOVE WATER: 4/26/2021 UNDERWATER: 4/6/2020

OVERALL NBI RATINGS:

DECK: 3 Serious	CHANNEL: 6 Bank Slumping
SUPERSTRUCTURE: 3 Serious	CULVERT: N N/A (NBI)
SUBSTRUCTURE: 4 Poor	SUFF. RATING: 15.5
PERF. RATING: Poor	HEALTH INDEX: 85.48

FIELD PERSONNEL / TITLE / NUMBER:**INITIALS**

Guzman, Armando - Bridge Inspector (CBI#00407) (lead)

Monterail, Jonathan - Assistant Bridge Inspector

Rego, Alexis - Bridge Inspector (CBI#00409)

Campo, Luis - Bridge Inspector (CBI #00619)

Alfonso, Rene - Bridge Inspector Assistance

REVIEWING BRIDGE INSPECTION SUPERVISOR:

Rego, Alexis - Bridge Inspector (CBI#00409)

CONFIRMING REGISTERED PROFESSIONAL ENGINEER:

Vers, Julie - Structural Design Manager (P.E. # 77896) Marlin Engineering
 1700 NW 66 Avenue
 Suite 106
 Plantation Florida 33313

SIGNATURE: _____

DATE: _____

The official record of this package has been electronically signed and sealed by Julie A. Vers, P.E. on the date adjacent to the seal as required by Rule 61G15-23.004, F.A.C.. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.



This report contains information relating to the physical security of a structure and depictions of the structure. This information is confidential and exempt from public inspection pursuant to sections 119.071(3)(a) and 119.071(3)(b), Florida Statutes. Only the cover page of this report may be inspected and copied.

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

Inspection/CIDR Report with PDF attachment(s) (INTERIM INSPECTION REPORT)

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS

All Elements

DECKS : Decks/Slabs

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8099 / 3	PS Conc Slab (Sonovoid)	3099	87.64	14	0.4	423	11.96	0	.	3536 (SF)
0	1080 / 3	Delamination/Spall/Patched Area	0	.	14	70	6	30	0	.	20 (SF)
0	1100 / 3	Exposed Prestressing	0	.	0	.	35	100	0	.	35 (SF)
0	1110 / 3	Cracking (PSC)	0	.	0	.	292	100	0	.	292 (SF)
0	1900 / 3	Distortion	0	.	0	.	90	100	0	.	90 (SF)
0	510 / 3	Wearing Surfaces	1734	65.83	0	.	900	34.17	0	.	2634 sq.ft
0	3220 / 3	Crack (Wearing Surface)	0	.	0	.	900	100	0	.	900 sq.ft

Element Inspection Notes:

8099/3 Notes: The top of the slab units is not visible due to an asphalt overlay. The width of the sonovoid slab units was field verified to be 3ft. wide.

SECONDARY:

_Centerline raised pavement markers are missing along the structure. Previously missing object markers were installed. Refer to Photo 01. NO CHANGE.

_Sidewalk concrete panels are loose and move under pedestrian load. (Total 300 SF). Refer to Photo 02. NO CHANGE.

_The underside of the slab unit joints and bent caps show evidence of water seepage. NO CHANGE. NCAR.

_There is one exposed piece of corroded scrap metal on Slab Unit 1-6 underside at 9ft. from Abutment 1. Previously documented under Defect 1090 as a spall with exposed rebar having minor section loss. Refer to Photo 03. NO CHANGE.

Refer to Defects 1080, 1100, 1110, and 1900 for additional deficiencies

PREVIOUS RECOMMENDED CORRECTIVE ACTION:

_Replace missing object markers at the four corners of the bridge and provide missing RPMs throughout the bridge.

_Properly secure the sidewalk panels.

_Monitor slab unit 1-1 for possible independent movement on the slab unit.

_Clean and coat exposed prestressing and reinforce Slab Unit 2-8.

_Repair spalls, delaminations, and cracks along the underside of the slab units

_Clean and coat exposed rebar and repair spall along the underside of slab unit 1-6, 9ft. from Abutment 1.

CORRECTIVE ACTION EVALUATION:

_The corrective action noted above was partially completed. Recommendation will be issued to provide missing RPMs.

_The corrective action noted above was not completed. Recommendation will be repeated.

_The corrective action noted above was not completed. Recommendation will be repeated.

_The corrective action noted above was not completed. Recommendation will be repeated.

_The corrective action noted above was not completed. Recommendation will be repeated.

_The corrective action noted above was not completed. Recommendation will be repeated.

1080/3 CS-3:

_Slab Unit 1-9 exhibits a spall/delamination up to 36in. L x 24in. W x 2.5in. D over Abutment 1, with an exposed stirrup, no measurable section loss. (Total 6 SF). Refer to Photo 04. NO CHANGE.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**

**Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS

CS-2:

_Slab Unit 2-6, east edge exhibits a delamination 30in. L x 4in. W starting at Pier 2 cap. (Total 3 SF). NO CHANGE.

_Slab Unit 2-7, west edge exhibits a delamination up to 24in. L x 4in. W starting at Pier 2 cap. (Total 2 SF). NO CHANGE.

_Slab Unit 2-8 underside exhibits a delamination up to full width x 36in. L with associated cracks and rust staining, starting at Bent 2 cap. (Total 9 SF). Refer to Photo 05. NEW.

1100/3

CS-3:

_Slab Unit 2-8, midspan has a spall 15ft. L x 24in. W x up to 4in. D with 7 exposed and corroded transverse rebars with up to 60% section remaining and 5 exposed and corroded prestressing strands with up to 0% section remaining (3 broken strands). Previously noted a spall 10ft. L x 24in. W x up to 4in. D with 5 exposed strands, 2 broken threads, and 6 exposed transverse rebars. (Total 20 SF). Refer to Photo 06. INCREASE.

_Slab Unit 2-9, midspan has a spall/delamination up to 15ft. L x 12in. W x 2in. D with 2 prestressing strands and 7 transverse rebars having up to 90% section remaining. (Total 15 SF). Refer to Photo 06. NEW.

1110/3

CS-3:

_Slab Unit 1-6 east edge has two delamination areas, one up to 5ft. L x 6in. W starting at Abutment 1 and the other starting at Pier Cap 2 up to 9ft. L x 12in. W with associated cracks up to 1/16in. W with efflorescence throughout. (Total 14 SF). NO CHANGE.

_Slab Unit 1-7 east edge has a spall/delamination 24in. L x 12in. W with associated cracks up to 1/32in. W with efflorescence and corrosion bleed-out over Abutment 1. (Total 2 SF). NO CHANGE.

_Slab Unit 1-7, east edge has a delamination 7ft. L x 4in. W, with an associated crack of up to 1/16in. starting at Pier 2 cap. (Total 7 SF). NO CHANGE.

_Slab Unit 1-8 west edge is intermittently delaminated up to 15ft. L x 15in. W starting at Abutment 1 with associated cracks up to 1/4in. W with efflorescence and corrosion bleed-out and associated spalling up to 4ft. L x 6in. W x 2in. D approximately 10ft from Abutment 1. (Total 19 SF). Refer to Photo 07. NO CHANGE.

_Slab Unit 1-8 east edge has a delamination 4ft. L x 15in. W and associated cracks up to 1/32in. W with efflorescence and corrosion bleed-out, 9ft. from Pier Cap 2. (Total 5 SF). NO CHANGE.

_Slab Unit 1-8 has a delaminated area up to 8ft. L x 3ft. W and associated cracks up to 1/16in. W with efflorescence and corrosion bleed-out starting at Pier Cap 2. (Total 24 SF). NO CHANGE.

_Slab Unit 1-9 west edge has a delaminated area 9ft. L x 10in. W and associated cracks up to 1/16in. W with efflorescence and corrosion bleed-out, starting near the 3/4 point and extending to Pier 2 cap. (Total 9 SF). NO CHANGE.

_Slab Unit 2-7 east edge is intermittently cracked/delaminated up to span length x 16in. W (average width) with up to 1/4in. W cracks. (Total 38 SF). NO CHANGE.

_Slab Unit 2-8 west half has two delaminated areas up to 15ft. L x 18in. W (average width) at south and north ends, with associated cracks of up to 1/4in. W. (Total 60 SF). NO CHANGE.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**

**Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS

_Slab Unit 2-9 west edge has a delaminated area up to 5ft. L x 5in. W with associated cracking up to 1/4in. wide, starting at the Pier 2 cap. (Total 5 SF). NO CHANGE.

_Slab Unit 3-6 has a delamination up to 24in. L x 6in. W on the east edge over Pier 3, with an associated crack of up to 1/16in. W. (Total 2 SF). NO CHANGE.

_Slab Unit 3-6 east edge has a delaminated area up to 42in. L x 8in. W with associated cracks up to 1/16in. W. (Total 4 SF). NO CHANGE.

_Slabs Unit 3-7 has two delaminated areas, one starting at Pier 3 up to 8ft. L x 15in. W (average width) with associated cracks, and the second, near mid-span up to 3ft. L x 30in. W. (Total 25 SF). NO CHANGE.

_Slab Unit 3-7 has an unsound repaired area 12ft. L x up to slab width (3ft.) starting from Abutment 4 with hollow sounding throughout and associated cracks up to 1/16in. W with efflorescence and corrosion bleed-out. (Total 30 SF). Refer to Photo 08. NO CHANGE.

_Slab Unit 3-8 has a spall/delamination up to 8ft. L x 3ft. W x 1in. D and associated cracks with corrosion bleed-out starting at Pier 3. (Total 24 SF). Refer to Photo 09. NO CHANGE.

_Slab Unit 3-8 has an unsound repair/delamination up to 42in. L x 30in. W with associated cracks up to 1/16in. W with efflorescence starting at Abutment 4. (Total 9 SF). NO CHANGE.

_Slab Unit 3-8 has an unsound repair/delamination up to 74in. L x up to slab width (3ft.) with associated cracks up to 1/16in. W with efflorescence starting 5.5ft. from Abutment 4. (Total 15 SF). NO CHANGE.

1900/3

CS-3:

_Slab Unit 1-1 exhibits a slight outward rotation at Abutment 1 with up to 1/4in. height difference in reference to the top of the cap, potentially indicating shear key failure. (Total 90 SF). Refer to Photo 10. NO CHANGE. NCAR.

510/3

For deficiencies refer to Defect 3220.

PREVIOUS RECOMMENDED CORRECTIVE ACTION:

_Clean and seal cracks and rutting along the expansion joints.

_Seal cracks on the asphalt along the slab unit joints and multi-directional cracks on Lane 2 (NB) in Spans 1 and 2.

_Monitor cracks along slab unit joints for independent movement of the slab units.

CORRECTIVE ACTION EVALUATION:

_The corrective action noted above was completed.

_The corrective action noted above was not completed. Recommendation will be repeated.

_The corrective action noted above was not completed. Recommendation will be repeated.

3220/3

CS-3:

_The asphalt overlay has longitudinal cracks up to span length x 1/4in. W with associated 1in. W rutting over the slab unit joints and upheaving up to 1in. H at the shoulders, possibly indicating independent slab unit movement. (Total 600 SF). Refer to Photo 11. NO CHANGE.

_The asphalt overlay at Spans 1 and 2 has multi-directional cracking up to 1/2in. W on Lane 2 (NB), worse condition is on Span 1 which has a hollow-sounding area 19.5ft L x 11ft. W, starting 1 ft. from the right sidewalk. (Total 300 SF). Refer to Photo 12. NO CHANGE.

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

Inspection/CIDR Report with PDF attachment(s) (INTERIM INSPECTION REPORT)

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	205 / 3	Re Conc Column	0	.	0	.	4	100	0	.	4 each
0	1090 / 3	Exposed Rebar	0	.	0	.	1	100	0	.	1 each
0	1130 / 3	Cracking (RC and Other)	0	.	0	.	3	100	0	.	3 each

Element Inspection Notes:

205/3 Note: At high tide, the seawater reaches the lower section of the columns.

Refer to Defects 1090 and 1130 for deficiencies.

PREVIOUS RECOMMENDED CORRECTIVE ACTION:

- _Remove any loose concrete and repair delaminations and spalls along the Column 2-2.
- _Repair delaminations and seal cracks along Bents 2 and 3 columns.
- _Install cathodic protection to Bents 2 and 3 columns.

CORRECTIVE ACTION EVALUATION:

- _The corrective action noted above was not completed. Recommendation will be repeated.
- _The corrective action noted above was not completed. Recommendation will be repeated.
- _The corrective action noted above was not completed. Recommendation will be repeated.

1090/3

CS-3:

_Column 2-2, south face has a spall/delamination up to 55in. H x 32in. W x 4in. D with two exposed longitudinal rebars and five stirrups, having areas of up to 80% section remaining. Additionally, there are areas of delamination around the column circumference covering the entire column height with associated cracks up to 1/4in. W as a consequence of corrosion of the steel reinforcement. Previously noted as a spall/delamination 7ft. H x 3ft. W x 3in. D with one exposed rebar and one stirrup. (Total 1 ea.) Refer to Photos 13, 14, and 15. INCREASE.

1130/3

CS-3:

_Columns 2-1, 3-1, and 3-2 have delaminated areas along their entire length with associated cracks up to full height x 1/16in. W, as a result of corrosion of the steel reinforcement. (Total 3 ea.) NO CHANGE.

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	234 / 3	Re Conc Pier Cap	48	70.59	12	17.65	8	11.76	0	.	68 ft
0	1080 / 3	Delamination/Spall/Patched Area	0	.	12	60	8	40	0	.	20 ft

Element Inspection Notes:

234/3 Refer to Defect 1080 for additional deficiencies.

PREVIOUS RECOMMENDED CORRECTIVE ACTION:

- _Remove vegetation growing on west end of Bents 2 and 3 caps.
- _Repair spalls and delaminations along Bents 2 and 3 caps.

CORRECTIVE ACTION EVALUATION:

- _The corrective action noted above was completed.
- _The corrective action noted above was not completed. Recommendation will be repeated.

1080/3

CS-3:

_Bent 2 cap, south face has a spall/delamination up to 48in. L x 17in. H x 3/4 in. D over Column 2-2, and on the same location, north face a delamination 20in. L x 12in. H. Previously noted in the south face as a spall/delamination up to 3ft. L x 16in. H x 1 in.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM****Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)****Structure ID: 874294****Inspection****DISTRICT: D6 - Miami****INSPECTION DATE: 4/26/2021 HIXS**

D. (Total 4 LF) Refer to Photos 16 and 17. INCREASE.

_Bent 3 cap, bottom and north faces has two unsound repaired areas up to 30in. L x 24in. W with multidirectional cracks up to 1/64in. W between Columns 3-1 and 3-2. (Total 4 LF) Refer to Photo 18. NO CHANGE.

CS-2:

_Pier 3 cap has intermittent delaminated areas up to 3ft. L x 16in. H between Columns 3-1 and 3-2, along the top and bottom north edges. (Total 12 LF) Refer to Photo 18. NO CHANGE.

Total Number of Elements*: 3

*excluding defects/protective systems

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**

**Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS

Inspector Recommendations

UNIT: 0	DECKS		
ELEMENT/ENV:	8099 / 3 PS Conc Slab (Sonovoid)	ELEM CATEGORY:	Decks/Slabs
CONDITION STATE			PRIORITY
1 , 2 , 3	MMS Quantity: 300 sf Element Estimated Quantity: 300 (SF)		3
WORK ORDER RECOMMENDATION:			
Properly secure the sidewalk concrete panels. Photo 02			
1 , 2 , 3	MMS Quantity: 10 sf Element Estimated Quantity: 10 (SF)		3
WORK ORDER RECOMMENDATION:			
Replace missing raised pavement markers along the centerline of the structure. Photo 01			
ELEMENT/ENV:	8099:510:3220 / 3 Crack (Wearing Surface)	ELEM CATEGORY:	Decks/Slabs
CONDITION STATE			PRIORITY
3	MMS Quantity: 600 sf Element Estimated Quantity: 600 sq.ft		3
WORK ORDER RECOMMENDATION:			
Monitor the slab units for independent movement. Photo 11			
3	MMS Quantity: 900 sf Element Estimated Quantity: 900 sq.ft		3
WORK ORDER RECOMMENDATION:			
Seal cracks on the asphalt along the slab unit joints and multi-directional cracks on Lane 2 (NB) in Spans 1 and 2. Photos 11 and 12			
ELEMENT/ENV:	8099:1080 / 3 Delamination/Spall/Patched Area	ELEM CATEGORY:	Decks/Slabs
CONDITION STATE			PRIORITY
2 , 3	MMS Quantity: 298 sf Element Estimated Quantity: 298 (SF)		3
WORK ORDER RECOMMENDATION:			
Clean and coat exposed steel and repair spalls and delaminations along the underside of sonovoid slabs. Photos 03 to 05 and 07 to 09			
ELEMENT/ENV:	8099:1100 / 3 Exposed Prestressing	ELEM CATEGORY:	Decks/Slabs
CONDITION STATE			PRIORITY
3	MMS Quantity: 35 sf Element Estimated Quantity: 35 (SF)		2
WORK ORDER RECOMMENDATION:			
Clean and coat exposed prestressing strands and rebars, repair spalls and reinforce the Slab units 2-8 and 2-9. Photo 06			

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**

**Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS

Inspector Recommendations

UNIT: 0 SUBSTRUCTURE
ELEMENT/ENV: 205:1090 / 3 Exposed Rebar ELEM CATEGORY: Substructure

CONDITION STATE			PRIORITY
3	MMS Quantity: 40 mh	Element Estimated Quantity: 1 each	2
WORK ORDER RECOMMENDATION: Clean and coat exposed rebars, repair spalls/delaminations and reinforce Column 2-2. Photos 13 to 15			

ELEMENT/ENV: 205:1130 / 3 Cracking (RC and Other) ELEM CATEGORY: Substructure

CONDITION STATE			PRIORITY
3	MMS Quantity: 40 mh	Element Estimated Quantity: 4 each	3
WORK ORDER RECOMMENDATION: Repair delaminations and seal cracks along Bents 2 and 3 columns. Photos 13 to 15			
3	MMS Quantity: 80 mh	Element Estimated Quantity: 4 each	3
WORK ORDER RECOMMENDATION: Install jackets with cathodic protection to Bents 2 and 3 columns. Photos 13 to 15			

ELEMENT/ENV: 234:1080 / 3 Delamination/Spall/Patched Area ELEM CATEGORY: Substructure

CONDITION STATE			PRIORITY
2 , 3	MMS Quantity: 40 mh	Element Estimated Quantity: 20 ft	2
WORK ORDER RECOMMENDATION: Repair spalls and delaminations along Bents 2 and 3 caps. Photos 16 to 18			

Structure Notes

BRIDGE OWNER: MIAMI-DADE COUNTY

Bridge inventoried from south to north. (Entrance on North end, boat ramp on South end).

P/S Slab Units on R/Conc Caps and Abutments over P/Conc Columns. (3 spans)

TRAFFIC RESTRICTIONS:

Based on the current load rating analysis dated 1/13/2020, the bridge is posted for the SU, C and ST5 type vehicles as follows:
 SU = 11 tons, C = 16 tons, ST5 = 18 tons. Refer to posting signs Photos 19 and 20.

REVIEWED BY:

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**

**Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS

INSPECTION NOTES: **HIXS** **4/26/2021**

Sufficiency Rating Calculation Accepted by knmeira at 5/5/2021 3:15 PM.

The structure is on a 6 months inspection frequency due to NBI Rating 3 for SIA Items 58 Deck and 59 Superstructure. (04/26/2021).

This Interim inspection (04/26/2021) was conducted to evaluate Element 8099 PS Conc Slab (Sonovoid), Element 234 Re Conc Pier Cap and Element 205 Re Conc Column, for the status of the entire structure refer to the last Regular NBI Inspection (04/06/2020).

The Deck and Superstructure are coded 3 (Serious) due to spalls and delaminations along more than 25% of any of the slab units. Slabs Units 1-6, 2-7, and 2-8 meet this criteria. (04/26/2021).

The Substructure NBI Rating is coded 4 (Poor) due to extensive spalls with exposed rebars along Column 2-2, and delaminations and cracks along the columns and pier caps throughout the structure. (04/26/2021).

LOAD CAPACITY EVALUATION:

Since the current load rating dated 1/13/2020, there is no indication that deterioration, geometric changes or additional dead load have occurred that would warrant a new load rating analysis. This only applies to this inspection dated 04/26/2021 per Julie A. Vers, P.E.

LEGEND:

NCAR: NO CORRECTIVE ACTION RECOMMENDED

RT: Right

LT: Left

L: Long

W: Wide

H: High

D: Deep

in.: Inches

ft.: Feet

LF: Linear Feet

SF: Square Feet

NE: Northeast

NW: Northwest

SE: Southeast

SW: Southwest

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294
DISTRICT: D6 - Miami

Inspection

INSPECTION DATE: 4/26/2021 HIXS



Photo 01 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Centerline raised pavement markers are missing along the structure. Previously missing object markers were installed.

WORK ORDER RECOMMENDATION:

Replace missing raised pavement markers along the centerline of the structure.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS



Photo 02 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Sidewalk concrete panels are loose and move under pedestrian load.

WORK ORDER RECOMMENDATION:

Properly secure the sidewalk concrete panels.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS



Photo 03 Element/Env 8099/3: PS Conc Slab (Sonovoid)

There is one exposed piece of corroded scrap metal on Slab Unit 1-6 underside at 9ft. from Abutment 1.

WORK ORDER RECOMMENDATION:

Clean and coat exposed steel and repair spalls and delaminations along the underside of sonovoid slabs.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS



Photo 04 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Slab Unit 1-9 exhibits a spall/delamination up to 36in. L x 24in. W x 2.5in. D over Abutment 1, with an exposed stirrup, no measurable section loss.

WORK ORDER RECOMMENDATION:

Clean and coat exposed steel and repair spalls and delaminations along the underside of sonovoid slabs.

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS



Photo 05 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Slab Unit 2-8 underside exhibits a delamination up to full width x 36in. L with associated cracks and rust staining, starting at Bent 2 cap.

WORK ORDER RECOMMENDATION:

Clean and coat exposed steel and repair spalls and delaminations along the underside of sonovoid slabs.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS



Photo 06 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Slab Unit 2-8, midspan has a spall 15ft. L x 24in. W x up to 4in. D with 7 exposed and corroded transverse rebars with up to 60% section remaining and 5 exposed and corroded prestressing strands with up to 0% section remaining (3 broken strands).

Slab Unit 2-9, midspan has a spall/delamination up to 15ft. L x 12in. W x 2in. D with 2 prestressing strands and 7 transverse rebars having up to 90% section remaining.

WORK ORDER RECOMMENDATION:

Clean and coat exposed prestressing strands and rebars, repair spalls and reinforce the Slab units 2-8 and 2-9.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS



Photo 07 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Slab Unit 1-8 west edge is intermittently delaminated up to 15ft. L x 15in. W starting at Abutment 1 with associated cracks up to 1/4in. W with efflorescence and corrosion bleed-out and associated spalling up to 4ft. L x 6in. W x 2in. D approximately 10ft from Abutment 1.

WORK ORDER RECOMMENDATION:

Clean and coat exposed steel and repair spalls and delaminations along the underside of sonovoid slabs.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS



Photo 08 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Slab Unit 3-7 has an unsound repaired area 12ft. L x up to slab width (3ft.) starting from Abutment 4 with hollow sounding throughout and associated cracks up to 1/16in. W with efflorescence and corrosion bleed-out.

WORK ORDER RECOMMENDATION:

Clean and coat exposed steel and repair spalls and delaminations along the underside of sonovoid slabs.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS



Photo 09 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Slab Unit 3-8 has a spall/delamination up to 8ft. L x 3ft. W x 1in. D and associated cracks with corrosion bleed-out starting at Pier 3.

WORK ORDER RECOMMENDATION:

Clean and coat exposed steel and repair spalls and delaminations along the underside of sonovoid slabs.

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS



Photo 10 Element/Env 8099/3: PS Conc Slab (Sonovoid)

Slab Unit 1-1 exhibits a slight outward rotation at Abutment 1 with up to 1/4in. height difference in reference to the top of the cap, potentially indicating shear key failure. No anti-rotation block is in place.

WORK ORDER RECOMMENDATION:
None.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS



Photo 11 Element/Env 8099/ 510/3: PS Conc Slab (Sonovoid)/ Wearing Surfaces

The asphalt overlay has longitudinal cracks up to span length x 1/4in. W with associated 1in. W rutting over the slab unit joints and upheaving up to 1in. H at the shoulders, possibly indicating independent slab unit movement.

WORK ORDER RECOMMENDATION:

- _ Seal cracks on the asphalt along the slab unit joints and multi-directional cracks on Lane 2 (NB) in Spans 1 and 2.
- _ Monitor the slab units for independent movement.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS



Photo 12 Element/Env 8099/ 510/3: PS Conc Slab (Sonovoid)/ Wearing Surfaces

The asphalt overlay at Spans 1 and 2 has multi-directional cracking up to 1/2in. W on Lane 2 (NB), worse condition is on Span 1 which has a hollow-sounding area 19.5ft L x 11ft. W, starting 1 ft. from the right sidewalk.

WORK ORDER RECOMMENDATION:

Seal cracks on the asphalt along the slab unit joints and multi-directional cracks on Lane 2 (NB) in Spans 1 and 2.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS



Photo 13 Element/Env 205/3: Re Conc Column

Column 2-2, south face has a spall/delamination up to 55in. H x 32in. W x 4-3/4in. D with two exposed longitudinal rebars and five stirrups, having areas of up to 80% section remaining.

WORK ORDER RECOMMENDATION:

- _ Clean and coat exposed rebars, repair spalls/delaminations and reinforce Column 2-2.
- _ Repair delaminations and seal cracks along Bents 2 and 3 columns.
- _ Install jackets with cathodic protection to Bents 2 and 3 columns.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS



Photo 14 Element/Env 205/3: Re Conc Column

Spall/delamination with exposed reinforcement having up to 80% remaining in south face of Column 2-2. (close up view)

WORK ORDER RECOMMENDATION:

- _Clean and coat exposed rebars, repair spalls/delaminations and reinforce Column 2-2.
- _Repair delaminations and seal cracks along Bents 2 and 3 columns.
- _Install jackets with cathodic protection to Bents 2 and 3 columns.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294
DISTRICT: D6 - Miami

Inspection

INSPECTION DATE: 4/26/2021 HIXS



Photo 15 Element/Env 205/3: Re Conc Column

Areas of delamination around the column circumference covering the entire column height with associated cracks up to 1/4in. W as a consequence of corrosion of the steel reinforcement.

WORK ORDER RECOMMENDATION:

- _ Clean and coat exposed rebars, repair spalls/delaminations and reinforce Column 2-2.
- _ Repair delaminations and seal cracks along Bents 2 and 3 columns.
- _ Install jackets with cathodic protection to Bents 2 and 3 columns.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS



Photo 16 Element/Env 234/3: Re. Concrete Pier Cap

Bent 2 cap, south face has a spall/delamination up to 48in. L x 17in. H x 3/4 in. D over Column 2-2, and on the same location, north face a delamination 20in. L x 12in. H. (south view)

WORK ORDER RECOMMENDATION:

Repair spalls and delaminations along Bents 2 and 3 caps.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS



Photo 17 Element/Env 234/3: Re. Concrete Pier Cap

Bent 2 cap, south face has a spall/delamination up to 48in. L x 17in. H x 3/4 in. D over Column 2-2, and on the same location, north face a delamination 20in. L x 12in. H. (bottom view)

WORK ORDER RECOMMENDATION:

Repair spalls and delaminations along Bents 2 and 3 caps.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS



Photo 18 Element/Env 234/3: Re. Concrete Pier Cap

Areas of unsound repairs on the bottom face of Pier 3 cap, intermittent delaminated areas up to 3ft. L x 16in. H between Columns 3-1 and 3-2, along the top and bottom north edges.

WORK ORDER RECOMMENDATION:

Repair spalls and delaminations along Bents 2 and 3 caps.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS



Photo 19: STRUCTURE NOTES

North Approach Posting Sign

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR Report with PDF attachment(s)
(INTERIM INSPECTION REPORT)**

Structure ID: 874294

Inspection

DISTRICT: D6 - Miami

INSPECTION DATE: 4/26/2021 HIXS




Photo 20: STRUCTURE NOTES

South Approach Posting Sign

Bridge No.	874294	Analysis Method:	LRFR-LRFD	FDOT Bridge Load Rating Summary Form (Page 1 of 1)
Location	Matheson hammock Road over matheson Hammock Canal			
Description	3 Spans, 2-30'&1-40', Prestressed voided slab beams 36"x17"			

Rating Type	Rating Type	Gross Axle Weight (tons)	Moment/Shear/Service		Dead Load Factor	Live Load Factor	Live Load Distrib. Factor (axles)	Rating Factor	Span No. - Girder No., Interior/Exterior, %Span Length	RF-Weight (tons)
Level	Vehicle	Weight	Member Type	Limit	DC	LL	LLDF	RF	Governing Location	RATING
Inventory	HL93	36	Prestressed	Service	1.00	0.80	0.600	0.210	Central span, midspan	7.6
Operating	HL93	36	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.330	Central span, midspan	11.9
Permit	FL120	60	Prestressed	Strength, Shear	1.25/0.90	1.35	0.500	0.270	Central span, 1/4 point	16.2
Permit Max Span	FL120	60	Prestressed	Strength, Shear	1.25/0.90	1.35	0.500	0.270	Central span, 1/4 point	16.2
Legal	SU2	17	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.690	Central span, midspan	11.7
	SU3	33	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.370	Central span, midspan	12.2
	SU4	35	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.340	Central span, midspan	11.9
	C3	28	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.650	Central span, midspan	18.2
	C4	36.7	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.460	Central span, midspan	16.9
	C5	40	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.440	Central span, midspan	17.6
	ST5	40	Prestressed	Strength, Moment	1.25/0.90	1.35	0.600	0.460	Central span, midspan	18.4
Emergency Vehicle (EV)	EV2	28.75	Prestressed	NA	NA	NA	0.600			-1
	EV3	43	Prestressed	NA	NA	NA	0.600			-1

Original Design Load	HS20 or HS20-S16-44	Performed by:	Mengyuan Chen	Date:	01/13/20
Rating Type, Analysis	LRFR-LRFD	Checked by:	Juan A. Sobrino	Date:	01/13/20
Distribution Method	Others	Sealed By:	Juan A. Sobrino	Date:	01/13/20
Impact Factor	33.0% (axle loading)	FL P.E. No.:	73121		
FL120 Gov. Span Length	38.3 (feet)	Cert. Auth. No.:	27244		
Minimum Span Length	28.3 (feet)	Phone & email:	(+1) 305 648 00 10, miami@pedelta.om		
Recommended Posting	> 39.9% below (0.000-0.600) (Required)	Company:	Pedelta Inc.		
Recommended SU Posting*	11 (tons)	Address:	2000 Ponce de Leon Blvd., Suite 624, Coral Gables, Florida 33134, USA		
Recommended C Posting	16 (tons)	<div>  <p>Digitally signed by Juan Sobrino Date: 2020.01.13 15:58:25 -05'00'</p> </div>			
Recommended ST5 Posting	18 (tons)				
Owner	02 County Highway Agency				
Location	Neither interstate traffic nor within 1 mile reasonable access to an interstate				
EV Posting	No. EV posting is not recommended. The FAST Act does not apply				
Floor Beam Present?	No	<p>Juan A. Sobrino, State of Florida, Professional Engineer, License No 73121.</p> <p>This document has been electronically signed and sealed by Juan A. Sobrino on January 13th, 2020 using a SHA authentication code. Printed copies of this document are not considered signed and sealed and the SHA authentication code must be verified on any electronic copies.</p>			
Segmental Bridge?	No				
Project No. & Reason	432907-1-72-02 Deterioration				
Plans Status	Built				

This 10-11-2019 summary follows the FDOT Bridge Load Rating Manual (BLRM), and the FDOT BMS Coding Guide.

*Recommended SU Posting levels for Florida SU trucks adequately restricts AASHTO SU trucks; see BLRM Chapter 7.

fdot.gov/maintenance/LoadRating.shtm

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

Inspection/CIDR Report with PDF attachment(s)

Structure ID: 874294

CIDR

DATE PRINTED: 6/25/2021

Description

Structure Unit Identification

Bridge/Unit Key: 874294 0
 Structure Name:
 Description: SPANS 1 THRU 3
 Type: M - Main

Roadway Identification

NBI Structure No (8): 874294
 Position/Prefix (5): 1 - Route On Structure
 Kind Hwy (Rte Prefix): 4 County Hwy
 Design Level of Service: 8 Service Road
 Route Number/Suffix: 00000 / 0 N/A (NBI)
 Feature Intersect (6): Matheson Hammock Canal
 Critical Facility: Not Defense-crit
 Facility Carried (7): Matheson Hmk Road
 Mile Point (11): 0.08
 Latitude (16): 025d40'44.2" Long (17): 080d15'43.8"

Roadway Traffic and Accidents

Lanes (28): 2 Medians: 0 Speed: 15 mph
 ADT Class: 2 ADT Class 2
 Recent ADT (29): 736 Year (30): 2020
 Future ADT (114): 1168 Year (115): 2042
 Truck % ADT (109): 1
 Detour Length (19): 99 mi
 Detour Speed:
 Accident Count: -1 Rate:

Roadway Classification

Nat. Hwy Sys (104): 0 Not on NHS
 National base Net (12): 0 - Not on Base Network
 LRS Inventory Rte (13a): 87 000 757 Sub Rte (13b): 00
 Functional Class (26): 09 Rural Local
 Federal Aid System: OFF
 Defense Hwy (100): 0 Not a STRAHNET hwy
 Direction of Traffic (102): 2 2-way traffic
 Emergency: ☒

Roadway Clearances

Vertical (10): 99.99 ft Appr. Road (32): 26.25 ft
 Horiz. (47): 26.25 ft Roadway (51): 26.25 ft
 Truck Network (110): 0 Not part of natl netwo
 Toll Facility (20): 3 On free road
 Fed. Lands Hwy (105): 0 N/A (NBI)
 School Bus Route: ☐
 Transit Route: ☐

NBI Project Data

Proposed Work (075A): Not Applicable (P)
 Work To Be Done By (075B): Not Applicable (P)
 Improvement Length (076): 0 ft

Improvement Cost (094): \$ 0.00
 Roadway Improvement Cost (095): \$ 0.00
 Total Cost (096): \$ 0.00
 Year of Estimate (097):

NBI Rating

Channel (61): 6 Bank Slumping
 Deck (58): 3 Serious
 Superstructure (59): 3 Serious
 Substructure (60): 4 Poor

Culvert (62): N N/A (NBI)
 Waterway (71): 8 Equal Desirable
 Unrepaired Spalls: -1 sq.ft.
 Review Required: ☒

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

Inspection/CIDR Report with PDF attachment(s)

Structure ID: 874294

CIDR

DATE PRINTED: 6/25/2021

Structure Identification

Admin Area: Miami-Dade
 District (2): D6 - Miami
 County (3): (87)Miami-Dade
 Place Code (4): South Miami Heights
 Location (9): Matheson Hammock Park
 Border Br St/Reg (98): Not Applicable (P) Share: 0 %
 Border Struct No (99):
 FIPS State/Region (1): 12 Florida Region 4-Atlanta
 NBIS Bridge Len (112): Y - Meets NBI Length
 Parallel Structure (101): No || bridge exists
 Temp. Structure (103): Not Applicable (P)
 Maint. Resp. (21): 2 County Hwy Agency
 Owner (22): 2 County Hwy Agency
 Historic Signif. (37): 5 Not eligible for NRHP

Structure Type and Material

Curb/Sidewalk (50): Left: 1.5 ft Right: 5.5 ft
 Bridge Median (33): 0 No median
 Main Span Material (43A): 5 Prestressed Concrete
 Appr Span Material (44A): Not Applicable (P)
 Main Span Design (43B): 01 Slab
 Appr Span Design (44B): 00 Other (NBI)

Appraisal

Structure Appraisal

Open/Posted/Closed (41): P Posted for load
 Deck Geometry (68): 5 Above Tolerable
 Underclearances (69): N Not applicable (NBI)
 Approach Alignment (72): 8-No Speed Red thru Curv
 Bridge Railings (36a): 0 Substandard
 Transitions (36b): 0 Substandard
 Approach Guardrail (36c): 0 Substandard
 Approach Guardrail Ends (36d): 0 Substandard
 Scour Critical (113): U Unknown Foundation

Minimum Vertical Clearance

Over Structure (53): 99.99 ft
 Under (reference) (54a): N Feature not hwy or RR
 Under (54b): 0 ft

Schedule

Current Inspection

Inspection Date: 04/26/2021
 Inspector: KNMEIAG - Armando Guzman
 Bridge Group: CA611
 Alt. Bridge Group:
 Primary Type: Interim
 Review Required: ☒

Geometrics

Spans in Main Unit (45): 3
 Approach Spans (46): 0
 Length of Max Span (48): 38.3 ft
 Structure Length (49): 100.33 ft
 Total Length: 140.33 ft
 Deck Area: 3536 sqft
 Structure Flared (35): 0 No flare

Age and Service

Year Built (27): 1967
 Year Reconstructed (106): 0
 Type of Service On (42a): 5 Highway-pedestrian
 Under (42b): 5 Waterway
 Fracture Critical Details: Not Applicable

Deck Type and Material

Deck Width (52): 35.25 ft
 Skew (34): 0 deg
 Deck Type (107): 2 Concrete Precast Panel
 Surface (108): 6 Bituminous
 Membrane: 0 None
 Deck Protection: None

Navigation Data

Navigation Control (38): Permit Not Required
 Nav Vertical Clr (39): 0 ft
 Nav Horizontal Clr (40): 0 ft
 Min Vert Lift Clr (116): 0 ft
 Pier Protection (111): 1 Not Required

NBI Condition Rating

Sufficiency Rating: 15.5
 Health Index: 85.48
 Structural Eval (67): 3 Intolerable - Correct
 Deficiency: Structurally Deficient

Minimum Lateral Underclearance

Reference (55a): N Feature not hwy or RR
 Right Side (55b): 0 ft
 Left Side (56): 0 ft

Next Inspection Date Scheduled

NBI: 04/26/2022
 Element: 10/26/2021
 Fracture Critical:
 Underwater: 04/26/2022
 Other/Special: 10/26/2021
 Inventory Photo Update Due: 04/26/2024

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

Inspection/CIDR Report with PDF attachment(s)

Structure ID: 874294

CIDR

DATE PRINTED: 6/25/2021

Schedule Cont.

Inspection Types Performed

NBI ☐Element ☒Fracture Critical ☐Underwater ☐Other Special ☒

Inspection Intervals

Required (92)

Frequency (92)

Last Date (93)

Inspection Resources

Fracture Critical ☐

mos

Crew Hours: 2

Underwater ☒

24 mos

04/06/2020

Flagger Hours: 0

Other Special ☒

6 mos

04/26/2021

Helper Hours: 0

NBI

24 mos

(91) 04/06/2020 (90)

Snooper Hours: 0

Special Crew Hours: 3

Special Equip Hours: 0

Bridge Related

General Bridge Information

Parallel Bridge Seq:

Channel Depth: 10.6 ft

Radio Frequency: -1

Phone Number:

Exception Date:

Exception Type: Unknown

Accepted By Maint: 01/01/1967

Warranty Expiration: 00/00/0000

Performance Rating: Poor

Bridge Rail 1: Conc parapet-alum-rail

Bridge Rail 2: Not applicable-No rail

Electrical Devices: No electric service

Culvert Type: Not applicable

Maintenance Yard: Not FDOT Maintained

FIHS ON / OFF: No Routes on FIHS

Previous Structure:

2nd Previous Structure:

Replacement Structure:

Permitted Utilities: Power ☐Water ☒Gas ☐Fiber Optic ☐Sewage ☒Other ☐

Bridge Load Rating Information

Inventory Type (065): 3 LRFR Load & Res. Fact

Operating Type (063): 3 LRFR Load & Res. Fact

Original Design Load (031): HL 93

Date: 01/13/2020

Initials: JS

Load Rating Rev. Recom.: No

Load Rating Plans Status: Field Measurements

Inventory Rating (066): 7.6 tons

Operating Rating (064): 11.9 tons

FL120 Permit Rating: 16.2 tons

HS20/FL120 Max Span Rating: 16.2 tons

Dynamic Impact in Percent: 33 %

Governing Span Length: 38.3 ft

Minimum Span Length: 28.3 ft

Distribution Method: Others

Load Rating Notes:

LEGAL LOADS

SU2: 11.7 tons

SU3: 12.2 tons

SU4: 11.9 tons

C3: 18.2 tons

C4: 16.9 tons

C5: 17.6 tons

ST5: 18.4 tons

Posting (070): 2 20.0-29.9%below

Open/Posted/Closed (041): P Posted for load

FLOOR BEAM (FB)

FB Present: No

FB Span Length, Gov: 0.0 ft

FB Spacing, Gov: 0.0 ft

FB OPR Rating: 0.0 tons

FB SU4 OPR Rating: 0.0 tons

FB FL120 Rating: 0.0 tons

POSTING

Recom. SU Posting: 11 tons

Recom. C Posting: 16 tons

Recom. ST5 Posting: 18 tons

Actual SU Posting: 11 tons

Actual C Posting: 16 tons

Actual ST5 Posting: 18 tons

Actual Blanket Posting: 99 tons

Emergency Vehicle: 1 EV inapplicable

SEGMENTAL (SEG)

SEG Wing-Span: -1.0 ft

SEG Web-to-Web Span: -1.0 ft

SEG Transverse HL93 Operating: -1.00 RF

Bridge Scour and Storm Information

Pile Driving Record: No pile driving records

Foundation Type: Unknown

Mode of Flow: Tidal

Rating Scour Eval: Minimal Risk

Highest Scour Eval: Unknown

Scour Evaluation Method:

Scour Recommended I: Unknown

Scour Recommended II: Unknown

Scour Recommended III: Unknown

Scour Elevation: -1 ft

Action Elevation: -1 ft

Storm Frequency: -1

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

Inspection/CIDR Report with PDF attachment(s)

Structure ID: 874294

CIDR

DATE PRINTED: 6/25/2021

Elements

Inspection Date: 04/26/2021 HIXS

DECKS : Decks/Slabs

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8099 / 3	PS Conc Slab (Sonovoid)	3099	87.64	14	0.4	423	11.96	0	.	3536 (SF)
0	1080 / 3	Delamination/Spall/Patched Area	0	.	14	70	6	30	0	.	20 (SF)
0	1100 / 3	Exposed Prestressing	0	.	0	.	35	100	0	.	35 (SF)
0	1110 / 3	Cracking (PSC)	0	.	0	.	292	100	0	.	292 (SF)
0	1900 / 3	Distortion	0	.	0	.	90	100	0	.	90 (SF)
0	510 / 3	Wearing Surfaces	1734	65.83	0	.	900	34.17	0	.	2634 sq.ft
0	3220 / 3	Crack (Wearing Surface)	0	.	0	.	900	100	0	.	900 sq.ft

DECKS : Joints

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	301 / 3	Pourable Joint Seal	0	.	0	.	104	74.29	36	25.71	140 ft
0	2310 / 3	Leakage	0	.	0	.	104	100	0	.	104 ft
0	2330 / 3	Seal Damage	0	.	0	.	0	.	36	100	36 ft

MISCELLANEOUS : Channel

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8290 / 3	Channel	0	.	0	.	1	100	0	.	1 (EA)
0	9150 / 3	Bank Erosion	0	.	0	.	1	100	0	.	1 (EA)

MISCELLANEOUS : Other Elements

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	321 / 3	Re Conc Approach Slab	1410	100	0	.	0	.	0	.	1410 sq.ft
0	510 / 3	Wearing Surfaces	957	91.14	0	.	93	8.86	0	.	1050 sq.ft
0	3220 / 3	Crack (Wearing Surface)	0	.	0	.	93	100	0	.	93 sq.ft

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	205 / 3	Re Conc Column	0	.	0	.	4	100	0	.	4 each
0	1090 / 3	Exposed Rebar	0	.	0	.	1	100	0	.	1 each
0	1130 / 3	Cracking (RC and Other)	0	.	0	.	3	100	0	.	3 each

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	215 / 3	Re Conc Abutment	65	92.86	0	.	5	7.14	0	.	70 ft
0	1080 / 3	Delamination/Spall/Patched Area	0	.	0	.	5	100	0	.	5 ft

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	234 / 3	Re Conc Pier Cap	48	70.59	12	17.65	8	11.76	0	.	68 ft
0	1080 / 3	Delamination/Spall/Patched Area	0	.	12	60	8	40	0	.	20 ft

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8393 / 3	Bulkhead Seawall Any Material	0	.	0	.	354	100	0	.	354 ft
0	1130 / 3	Cracking (RC and Other)	0	.	0	.	314	100	0	.	314 ft

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

Inspection/CIDR Report with PDF attachment(s)

Structure ID: 874294

CIDR

DATE PRINTED: 6/25/2021

0	6000 / 3	Scour	0	.	0	.	40	100	0	.	40 ft
---	----------	-------	---	---	---	---	----	-----	---	---	-------

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8394 / 3	R/Conc Abut Slope Protection	3968	73.81	0	.	1408	26.19	0	.	5376 (SF)
0	1130 / 3	Cracking (RC and Other)	0	.	0	.	320	100	0	.	320 (SF)
0	4000 / 3	Settlement	0	.	0	.	1088	100	0	.	1088 (SF)

SUPERSTRUCTURE : Superstructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	333 / 3	Other Bridge Railing	167	83.5	33	16.5	0	.	0	.	200 ft
0	1000 / 3	Corrosion	0	.	30	100	0	.	0	.	30 ft
0	1020 / 3	Connection	0	.	3	100	0	.	0	.	3 ft

Total Number of Elements*: 10

*excluding defects/protective systems

Inspection Information

Inspection Date: 04/26/2021

Type: Interim

Inspector: KNMEIAG - Armando Guzman

Inspection Notes: Sufficiency Rating Calculation Accepted by knmeira at 5/5/2021 3:15 PM.

The structure is on a 6 months inspection frequency due to NBI Rating 3 for SIA Items 58 Deck and 59 Superstructure. (04/26/2021).

This Interim inspection (04/26/2021) was conducted to evaluate Element 8099 PS Conc Slab (Sonovoid), Element 234 Re Conc Pier Cap and Element 205 Re Conc Column, for the status of the entire structure refer to the last Regular NBI Inspection (04/06/2020).

The Deck and Superstructure are coded 3 (Serious) due to spalls and delaminations along more than 25% of any of the slab units. Slabs Units 1-6, 2-7, and 2-8 meet this criteria. (04/26/2021).

The Substructure NBI Rating is coded 4 (Poor) due to extensive spalls with exposed rebars along Column 2-2, and delaminations and cracks along the columns and pier caps throughout the structure. (04/26/2021).

LOAD CAPACITY EVALUATION:

Since the current load rating dated 1/13/2020, there is no indication that deterioration, geometric changes or additional dead load have occurred that would warrant a new load rating analysis. This only applies to this inspection dated 04/26/2021 per Julie A. Vers, P.E.

LEGEND:

NCAR: NO CORRECTIVE ACTION RECOMMENDED

RT: Right

LT: Left

L: Long

W: Wide

H: High

D: Deep

in.: Inches

ft.: Feet

LF: Linear Feet

SF: Square Feet

NE: Northeast

NW: Northwest

SE: Southeast

SW: Southwest

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**

REPORT ID: INSP005

Structure ID: 874294

**Inspection/CIDR Report with PDF attachment(s)
CIDR**DATE PRINTED: 6/25/2021

Structure Notes

BRIDGE OWNER: MIAMI-DADE COUNTY

Bridge inventoried from south to north. (Entrance on North end, boat ramp on South end).

P/S Slab Units on R/Conc Caps and Abutments over P/Conc Columns. (3 spans)

TRAFFIC RESTRICTIONS:

Based on the current load rating analysis dated 1/13/2020, the bridge is posted for the SU, C and ST5 type vehicles as follows: SU = 11 tons, C = 16 tons, ST5 = 18 tons. Refer to posting signs Photos 19 and 20.

REVIEWED BY:

Schedule Notes

**APPENDIX G – STRUCTURAL TECHNOLOGIES, LLC., PRELIMINARY BRIDGE REPAIR
RECOMMENDATIONS**

SECTION A-A


SECTION 5-B

Date	Mach	Rz	Description


HART-REYNOLDS & ASSOCIATES, INC.
CONSULTING ENGINEERS
CORAL GABLES, FLORIDA

MATHESON HAMMOCK PARK
DADE COUNTY, FLORIDA
BRIDGE AND APPROACH ROAD

Project C.B. H.M.	Drawn D.F.C.	Checked C.L.B. H.M.	No. 7	of 12 Sheets
Approved	Date JUNE 1961	Project No. Q-101		
SUPERSTRUCTURE				
Notes As Shown				



PARTIALLY FILL CORES WITH CONCRETE TO CONNECT THE NEW CIP CONCRETE



LONGITUDINAL FRP 2 PILES 36" WIDE VWRAP C200HM FULL LENGTH OF PLANK - 40 FT

INSTALL #4 CONCRETE 18" DIA. CORES WITH RE-500 V2 EPOXY 6" INTO THE EXISTING CONCRETE

31#2 (PER PLANK) 24" WITH GOOD PT STRANDS

PLANK UNIT 2-8 (VERIFY)

PLANK UNIT 2-9 (VERIFY)

2021-10-01 MATHESON HAMMOCK ROAD OVER MH CANAL

PROPOSED REPAIR/STRENGTHENING

1. (2) PLANKS - UNIT 2-8 AND UNIT 2-9 AT SECOND SPAN.
2. REMOVE ALL DELAMINATED/SPALLED CONCRETE DOWN TO SOUND CONCRETE. THE EXTENT/LENGTH OF REPAIR WILL BE DEPENDENT ON THE DAMAGE/CORROSION IN THE STRANDS (REFER TO ITEM 4).
3. CUT AND REMOVE SIGNIFICANTLY CORRODED STEEL. EXPOSE AT A MIN. 3 FT OF SOUND PRESTRESSING STRANDS ON BOTH ENDS OF THE REPAIR AREA. NOTE THERE ARE UP TO (7) PT STRANDS AFFECTED BY DAMAGED/REPAIR WHICH NEEDS TO BE EXPOSED.
4. APPLY CORROSION INHIBITORS TO ALL EXPOSED STEEL TO PREVENT FUTURE CORROSION.
5. INSTALL NEW LONGITUDINAL STEEL AND L-DOWELS, AS SHOWN. SPLICE LONGITUDINAL STEEL WITH THE PT STRANDS 30".
6. PARTIALLY FILL THE CORES WITH FOAM MATERIAL AS SHOWN TO CREATE A BACKING FOR THE REPAIR CONCRETE.
7. FORM AND PUMP HIGH EARLY STRENGTH CONCRETE REPAIR MATERIAL WITH MIN. F'C-6000 PSI.
8. INSTALL V-WRAP FRP REINFORCEMENT AS SHOWN.
9. APPLY 2 COATS OF TSTRATA TC TO BOTTOM OF THE TWO UNITS (CONCRETE AND FRP).

BRIDGE FRAMING PLAN

BRIDGE SLAB SCHEDULE			
UNIT NO.	UNIT LENGTH	SPACING	REMARKS
1	24'-0"	24'-0"	Interior with main strands
2	24'-0"	24'-0"	Interior with main strands
3	24'-0"	24'-0"	Interior with main strands
4	24'-0"	24'-0"	Interior with main strands
5	24'-0"	24'-0"	Interior with main strands
6	24'-0"	24'-0"	Interior with main strands
7	24'-0"	24'-0"	Interior with main strands
8	24'-0"	24'-0"	Interior with main strands
9	24'-0"	24'-0"	Interior with main strands
10	24'-0"	24'-0"	Interior with main strands
11	24'-0"	24'-0"	Interior with main strands
12	24'-0"	24'-0"	Interior with main strands
13	24'-0"	24'-0"	Interior with main strands
14	24'-0"	24'-0"	Interior with main strands
15	24'-0"	24'-0"	Interior with main strands
16	24'-0"	24'-0"	Interior with main strands
17	24'-0"	24'-0"	Interior with main strands
18	24'-0"	24'-0"	Interior with main strands
19	24'-0"	24'-0"	Interior with main strands
20	24'-0"	24'-0"	Interior with main strands
21	24'-0"	24'-0"	Interior with main strands
22	24'-0"	24'-0"	Interior with main strands
23	24'-0"	24'-0"	Interior with main strands
24	24'-0"	24'-0"	Interior with main strands
25	24'-0"	24'-0"	Interior with main strands
26	24'-0"	24'-0"	Interior with main strands
27	24'-0"	24'-0"	Interior with main strands
28	24'-0"	24'-0"	Interior with main strands
29	24'-0"	24'-0"	Interior with main strands
30	24'-0"	24'-0"	Interior with main strands
31	24'-0"	24'-0"	Interior with main strands
32	24'-0"	24'-0"	Interior with main strands
33	24'-0"	24'-0"	Interior with main strands
34	24'-0"	24'-0"	Interior with main strands
35	24'-0"	24'-0"	Interior with main strands
36	24'-0"	24'-0"	Interior with main strands
37	24'-0"	24'-0"	Interior with main strands
38	24'-0"	24'-0"	Interior with main strands
39	24'-0"	24'-0"	Interior with main strands
40	24'-0"	24'-0"	Interior with main strands
41	24'-0"	24'-0"	Interior with main strands
42	24'-0"	24'-0"	Interior with main strands
43	24'-0"	24'-0"	Interior with main strands
44	24'-0"	24'-0"	Interior with main strands
45	24'-0"	24'-0"	Interior with main strands
46	24'-0"	24'-0"	Interior with main strands
47	24'-0"	24'-0"	Interior with main strands
48	24'-0"	24'-0"	Interior with main strands
49	24'-0"	24'-0"	Interior with main strands
50	24'-0"	24'-0"	Interior with main strands
51	24'-0"	24'-0"	Interior with main strands
52	24'-0"	24'-0"	Interior with main strands
53	24'-0"	24'-0"	Interior with main strands
54	24'-0"	24'-0"	Interior with main strands
55	24'-0"	24'-0"	Interior with main strands
56	24'-0"	24'-0"	Interior with main strands
57	24'-0"	24'-0"	Interior with main strands
58	24'-0"	24'-0"	Interior with main strands
59	24'-0"	24'-0"	Interior with main strands
60	24'-0"	24'-0"	Interior with main strands
61	24'-0"	24'-0"	Interior with main strands
62	24'-0"	24'-0"	Interior with main strands
63	24'-0"	24'-0"	Interior with main strands
64	24'-0"	24'-0"	Interior with main strands
65	24'-0"	24'-0"	Interior with main strands
66	24'-0"	24'-0"	Interior with main strands
67	24'-0"	24'-0"	Interior with main strands
68	24'-0"	24'-0"	Interior with main strands
69	24'-0"	24'-0"	Interior with main strands
70	24'-0"	24'-0"	Interior with main strands
71	24'-0"	24'-0"	Interior with main strands
72	24'-0"	24'-0"	Interior with main strands
73	24'-0"	24'-0"	Interior with main strands
74	24'-0"	24'-0"	Interior with main strands
75	24'-0"	24'-0"	Interior with main strands
76	24'-0"	24'-0"	Interior with main strands
77	24'-0"	24'-0"	Interior with main strands
78	24'-0"	24'-0"	Interior with main strands
79	24'-0"	24'-0"	Interior with main strands
80	24'-0"	24'-0"	Interior with main strands
81	24'-0"	24'-0"	Interior with main strands
82	24'-0"	24'-0"	Interior with main strands
83	24'-0"	24'-0"	Interior with main strands
84	24'-0"	24'-0"	Interior with main strands
85	24'-0"	24'-0"	Interior with main strands
86	24'-0"	24'-0"	Interior with main strands
87	24'-0"	24'-0"	Interior with main strands
88	24'-0"	24'-0"	Interior with main strands
89	24'-0"	24'-0"	Interior with main strands
90	24'-0"	24'-0"	Interior with main strands
91	24'-0"	24'-0"	Interior with main strands
92	24'-0"	24'-0"	Interior with main strands
93	24'-0"	24'-0"	Interior with main strands
94	24'-0"	24'-0"	Interior with main strands
95	24'-0"	24'-0"	Interior with main strands
96	24'-0"	24'-0"	Interior with main strands
97	24'-0"	24'-0"	Interior with main strands
98	24'-0"	24'-0"	Interior with main strands
99	24'-0"	24'-0"	Interior with main strands
100	24'-0"	24'-0"	Interior with main strands

NOTE: Small spans may be indicated here at all exterior abutments.

PLAN - PRESTRESSED UNITS



ELEVATION - PRESTRESSED UNITS



HART-REYNOLDS & ASSOCIATES, INC.		CORAL GABLES, FLORIDA	
MATHESON HAMMOCK PARK		DADE COUNTY, FLORIDA	
BRIDGE AND APPROACH ROAD		CORAL GABLES, FLORIDA	
Drawn By: J.C.	Checked By: J.C.	Scale: 1"=10'-0"	Sheet: 8
Date: JUNE 1961	Project No.	Project No.	Project No.
Author: J.C.	Appr'd: J.C.	Appr'd: J.C.	Appr'd: J.C.
PRESTRESSED SLAB UNITS		of 12. Sheet	