

MIAMI-DADE COUNTY
DEPARTMENT OF TRANSPORTATION AND PUBLIC WORKS (DTPW)

ADDENDUM NO. 1
October 13, 2023

PROJECT: Roadway Resurfacing -Multiple Sites
Project No. 20230159

BID DUE DATE: December 6, 2023; 02:00 P.M.

FROM: Miami-Dade County DTPW
Capital Improvements Division
111 NW First Street, 14th Floor
Miami, FL 33128
305.375.2930

TO: Prospective Bidders and Interested Parties

This Addendum forms part of the project solicitation documents and will be incorporated into the Contract Documents, as applicable. Insofar as the Original Contract Documents, Drawings and Specifications are inconsistent, this Addendum shall govern. Please acknowledge receipt of this Addendum, at the time of bid submittal to Miami-Dade County, in the space provided on the "Acknowledgement of Addenda Form" provided with the project solicitation documents. Failure to acknowledge receipt of all addenda may be cause for disqualification.

CHANGES TO THE INVITATION TO BID:

1. Bid Due date has been postponed to Wednesday, December 6, 2023.

CHANGES TO THE BID FORM:

1. Delete Bid Form dated 9/25/2023 and replace it with attached Revised Bid Form dated 10/13/2023 for Addendum No. 1. Changes to the Bid Form are as follows.

The following bid items quantities has been changed:

327-70	MILLING EXISTING PAVEMENT (1")
334-2-13-1	HOT MIX ASPHALT TRAFFIC C, SP-9.5
337-8-42	HOT MIX ASPHALT FRICTION COURSE TRAFFIC C, FC-9.5, PG 76-22

END OF ADDENDUM NO. 1



Alfredo E. Muñoz, P.E.

Chief, Capital Improvements Division

Department of Transportation and Public Works (DTPW)

AM: aa

c: Alicia Arce, DTPW
Caesar Suarez, SBD
Project File

Katherine Fernandez, DTPW
Laurie Johnson, SBD
Clerk of the Board

Joaquín Rabassa, P.E. DTPW
Marcia Martin, SBD
Jacqueline Fussell, SBD

Bid Form

PROJECT TITLE: Roadway Resurfacing – Multiple Sites

PROJECT NO: 20230159

IF THIS PROPOSAL IS ACCEPTED, THE UNDERSIGNED AGREES TO COMPLETE ALL WORK UNDER THIS CONTRACT WITHIN SEVEN HUNDRED TWENTY (720) CALENDAR DAYS AFTER THE EFFECTIVE DATE ESTABLISHED IN THE *NOTICE TO PROCEED WITH CONTRACT WORK*.

Item No	Quantity	Unit	Description	Written Unit Amount	Unit Price	Total
1WSR	800.0	S.F.	Saw cut and remove an average of two (2) inches of temporary cold asphalt patch on trench in order to expose and evaluate the condition of the base. If base is found suitable, clean loose material and replace the amount of cold patch removed with hot type S asphaltic concrete up to the level of the surrounding surface.			
2WSR	1,500.0	S.F.	Saw cut and remove an average of two (2) inches of existing temporary cold asphalt patch on trench in order to expose and evaluate the condition of the base. If base is found unsuitable by the Engineer, remove base material and replace with a minimum of eight (8) inches of compacted limerock or six (6) inches of hot S asphaltic concrete. In either case, replace the cold patch removed with hot type S asphaltic concrete up to the level of the surrounding surface.			
5WS1-A	3.0	P.N.	Night Differential for Milling			
6WS1-A	3.0	P.N.	Night Differential for Resurfacing			
101-1-B	15.0	W.O.	Mobilization			
102-74-2	30,000.0	EA/DAY	BARRICADES (Temporary, Type III, 6')			
102-76	500.0	EA/DAY	FLASHING ARROW BOARD (Temporary, Multimode)			
102-8A	80.0	S.Y.	RE-GRADE EXISTING SWALE (Without sod) (When required by the Engineer.)			
102-99	600.0	EA/DAY	VARIABLE MESSAGE SIGN (Temporary)			
102-60A	1,200.0	EA/DAY	WORK ZONE SIGNS			
110-4	60.0	S.Y.	REMOVAL OF EXISTING PAVEMENT			

Bid Form

PROJECT TITLE: Roadway Resurfacing – Multiple Sites

PROJECT NO: 20230159

IF THIS PROPOSAL IS ACCEPTED, THE UNDERSIGNED AGREES TO COMPLETE ALL WORK UNDER THIS CONTRACT WITHIN SEVEN HUNDRED TWENTY (720) CALENDAR DAYS AFTER THE EFFECTIVE DATE ESTABLISHED IN THE *NOTICE TO PROCEED WITH CONTRACT WORK*.

Item No	Quantity	Unit	Description	Written Unit Amount	Unit Price	Total
110-4-1-1	1,200.0	L.F.	REMOVAL AND DISPOSAL OF EXISTING CURB AND GUTTER			
110-4-2A	1,200.0	S.Y.	REMOVAL OF EXISTING CONCRETE SIDEWALK (up to 8" thick, including base preparation)			
120-1	30.0	C.Y.	REGULAR EXCAVATION			
120-2-3	30.0	C.Y.	EMBANKMENT FOR ROAD BUILD-UP (Borrow material from Contractor's own source)			
120-2-4	20.0	C.Y.	EMBANKMENT MATERIAL FOR SHOULDER - Borrow material, from contractor's own source, see Special Provisions for description of material.			
160-4	20.0	S.Y.	TYPE "B" STABILIZATION (12" Thick) (Min. C.B.R. 30)			
200-2	60.0	S.Y.	BASE PREPARATION FOR NEW SIDEWALK CONSTRUCTION (Where needed at the discretion of the Engineer)			
210-1-2	60.0	S.Y.	LIMEROCK BASE (8" double course) (Primed)			
327-70	105,000.0	S.Y.	MILLING EXISTING PAVEMENT [(1")(Payment for greater cuts will be paid proportionally)]			
334-2-13-1	5,100.0	TON	Hot Mix Asphalt, Traffic C, SP-9.5			
337-8-42	10,050.0	TON	Hot Mix Asphalt Friction Course, Traffic C, FC-9.5, PG 76-22			
425-4(2)	20.0	EA.	ADJUSTING INLETS			

Bid Form

PROJECT TITLE: Roadway Resurfacing – Multiple Sites

PROJECT NO: 20230159

IF THIS PROPOSAL IS ACCEPTED, THE UNDERSIGNED AGREES TO COMPLETE ALL WORK UNDER THIS CONTRACT WITHIN SEVEN HUNDRED TWENTY (720) CALENDAR DAYS AFTER THE EFFECTIVE DATE ESTABLISHED IN THE *NOTICE TO PROCEED WITH CONTRACT WORK*.

Item No	Quantity	Unit	Description	Written Unit Amount	Unit Price	Total
425-5	80.0	EA.	ADJUST MANHOLE (This item is contingent upon field conditions and may be increased, decreased or eliminated by the Engineer)			
425-6	100.0	EA.	ADJUST EXISTING VALVE BOXES (MIAMI-DADE COUNTY ONLY) (This item is contingent upon field conditions and may be increased, decreased or eliminated by the Engineer)			
425-721E	30.0	EA.	REMOVAL AND DISPOSAL of existing damaged frames and pick up new frames at Miami-Dade Water and Sewer, including adjustment and installation of Manholes.			
425-721F	30.0	EA.	REMOVAL AND DISPOSAL of existing damaged frames and pick up new frames at Miami-Dade Water and Sewer, including adjustment and installation of Water Valves.			
425-944B	20.0	EA.	RECONSTRUCT MANHOLE			
520-2A	2,500.0	L.F.	CONCRETE CURB AND/OR GUTTER (Any type, Including base preparation)			
522-1(1)	1,800.0	S.Y.	CONCRETE SIDEWALK [4" THICK, 3,000 P.S.I. CONCRETE AT 28 DAYS (Includes the cost of pedestrian ramps and sidewalk curbs)			
522-2	700.0	S.Y.	CONCRETE SIDEWALK (6" Thick, 3000 P.S.I. concrete at 28 days) (including pedestrian ramps and sidewalk curbs)			
527-2	800.0	S.F.	DETECTABLE WARNING ON WALKING SURFACE			
575-1-1	100.0	S.Y.	SODDING (Pensacola Bahia or match existing) (includes watering)			
635-1-11	30.0	AS.	PULL BOX, METER TYPE (Polymer)			
700-40-01	40.0	AS.	ROADSIDE SIGNS {(SINGLE POST) (LESS THAN 12 S.F.)}			

Bid Form

PROJECT TITLE: Roadway Resurfacing – Multiple Sites

PROJECT NO: 20230159

IF THIS PROPOSAL IS ACCEPTED, THE UNDERSIGNED AGREES TO COMPLETE ALL WORK UNDER THIS CONTRACT WITHIN SEVEN HUNDRED TWENTY (720) CALENDAR DAYS AFTER THE EFFECTIVE DATE ESTABLISHED IN THE *NOTICE TO PROCEED WITH CONTRACT WORK*.

Item No	Quantity	Unit	Description	Written Unit Amount	Unit Price	Total
700-46-22	10.0	EA.	RESET EXISTING POST AND SIGN			
701-16-111	4.0	N.M.	AUDIBLE & VIBRATORY PAVEMENT MARKING, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"			
705-71-361	60.0	EA.	36" TUBULAR DELINEATOR			
706-1-12	6,000.0	EA.	REFLECTIVE PAVEMENT MARKERS (class B, mono or bi-directional, all colors)			
710-11-121	88,000.0	L.F.	PAINTED PAVEMENT MARKINGS (Standard, White, solid, 6")			
710-11-122	800.0	L.F.	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 8"			
710-11-123	12,000.0	L.F.	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 12"			
710-11-124	1,000.0	L.F.	PAINTED PAVEMENT MARKINGS (Standard, White, solid, 18")			
710-11-125	7,400.0	L.F.	PAINTED PAVEMENT MARKINGS (Standard, White, solid, 24")			
710-11-141	32,000.0	L.F.	PAINTED PAVEMENT MARKINGS (Standard) (White) (Skip) (6")			
710-11-160	60.0	EA.	PAINTED PAVEMENT MARKINGS (Standard)(White)(Message)			
710-11-170	260.0	EA	PAINTED PAVEMENT MARKING (Standard) (White) (Arrows)			

Bid Form

PROJECT TITLE: Roadway Resurfacing – Multiple Sites

PROJECT NO: 20230159

IF THIS PROPOSAL IS ACCEPTED, THE UNDERSIGNED AGREES TO COMPLETE ALL WORK UNDER THIS CONTRACT WITHIN SEVEN HUNDRED TWENTY (720) CALENDAR DAYS AFTER THE EFFECTIVE DATE ESTABLISHED IN THE *NOTICE TO PROCEED WITH CONTRACT WORK*.

Item No	Quantity	Unit	Description	Written Unit Amount	Unit Price	Total
710-11-221	38,000.0	L.F.	PAINTED PAVEMENT MARKINGS (Standard, Yellow, solid, 6")			
710-11-224	3,200.0	L.F.	PAINTED PAVEMENT MARKINGS,STANDARD,YELLOW,SOLID, 18"			
710-11-241	20,000.0	L.F.	PAINTED PAVEMENT MARKINGS (Standard) (Yellow) (Skip) (6")			
711-2	70.0	L.F.	SKIP TRAFFIC STRIPE (6' STRIPE, 10' SPACE) (WHITE THERMOPLASTIC) (6" WIDE)			
711-5	1,260.0	L.F.	GUIDELINES [(6" DOTTED) (2'-4' White) (Thermoplastic)]			
711-11-121	76,000.0	L.F.	THERMOPLASTIC (White) (Solid) (6")			
711-11-122	1,200.0	L.F.	THERMOPLASTIC (White) (Solid) (8")			
711-11-123	14,000.0	L.F.	THERMOPLASTIC (White) (Solid) (12")			
711-11-124	1,200.0	L.F.	THERMOPLASTIC (White) (Solid) (18")			
711-11-125	6,000.0	L.F.	THERMOPLASTIC (White) (Solid) (24")			
711-11-141	17,000.0	L.F.	THERMOPLASTIC (White) (Skip) (6")			
711-11-160	60.0	EA.	THERMOPLASTIC (White) (Message)			

Bid Form

PROJECT TITLE: Roadway Resurfacing – Multiple Sites

PROJECT NO: 20230159

IF THIS PROPOSAL IS ACCEPTED, THE UNDERSIGNED AGREES TO COMPLETE ALL WORK UNDER THIS CONTRACT WITHIN SEVEN HUNDRED TWENTY (720) CALENDAR DAYS AFTER THE EFFECTIVE DATE ESTABLISHED IN THE *NOTICE TO PROCEED WITH CONTRACT WORK*.

Item No	Quantity	Unit	Description	Written Unit Amount	Unit Price	Total
711-11-170	260.0	EA	THERMOPLASTIC (White) (Arrows)			
711-11-221	66,000.0	L.F.	THERMOPLASTIC (Yellow) (Solid) (6")			
711-11-224	1,400.0	L.F.	THERMOPLASTIC (Yellow) (Solid) (18")			
711-11-241	5,000.0	L.F.	THERMOPLASTIC (Yellow) (Skip) (6")			
711-14-160	200.0	EA.	Thermoplastic, Preformed, White, Message			
711-14-160-Bike	80.0	EA	Thermoplastic, Preformed, White, Bicycle Message and Arrow			
711-14-670	130.0	S.Y.	Thermoplastic, Preformed, Green Bike Lane			
711-72	300.0	S.F.	REMOVAL OF EXISTING PAVEMENT MARKINGS (Thermoplastic & Paint)			

Total: _____

The bidder understands and agrees that the above total is inclusive of all work necessary to complete the job as described in the plans and specifications.

Quantities are established and are included only for the purpose of facilitating the uniform comparison of bids submitted. The County shall not be held responsible if the quantities are not accurate and all computations for compensation shall be based upon the actual work performed, whether greater or less than estimated quantities.

Tax Identification Number: _____

D.C. Certificate of competency No: _____

Bidder's Name: _____

Bidder's telephone Number: _____

Bidder's address: _____

Bid Form

PROJECT TITLE: Roadway Resurfacing – Multiple Sites

PROJECT NO: 20230159

IF THIS PROPOSAL IS ACCEPTED, THE UNDERSIGNED AGREES TO COMPLETE ALL WORK UNDER THIS CONTRACT WITHIN SEVEN HUNDRED TWENTY (720) CALENDAR DAYS AFTER THE EFFECTIVE DATE ESTABLISHED IN THE *NOTICE TO PROCEED WITH CONTRACT WORK*.

BIDDER ACKNOWLEDGES THAT INCLUDED IN THE VARIOUS ITEMS OF THE PROPOSAL AND IN THE TOTAL BID PRICE ARE COSTS FOR COMPLYING WITH THE FLORIDA TRENCH SAFETY ACT (90-96), LAWS OF FLA. EFFECTIVE OCTOBER 1st, 1990. THE BIDDER FURTHER IDENTIFIES THE COSTS TO BE SUMMARIZED BELOW:

	Trench Safety Measure (Description)	Units of Measure (LF, SY)	Unit (Quantity)	Unit Cost	Extended Cost
A.	_____	_____	_____	_____	_____
B.	_____	_____	_____	_____	_____
C.	_____	_____	_____	_____	_____
D.	_____	_____	_____	_____	_____

FAILURE TO COMPLETE THE ABOVE MAY RESULT IN THE BID BEING DECLARED NON-RESPONSIVE