



February 28, 2025

## RESPONSE LETTER NO. 3 TO REQUEST FOR INFORMATION

**Project Title:** Snowden Pedestrian Bridge No. 879043  
**Project No.:** 20240235

**A. Email from Mrs. Thelma E. Garcia, from GLF Construction Corporation; on February 20, 2025, at 12:25 PM (Email Attached).**

**Question No. 1:** This question is Electrical/Structural related to the recessed Alphabet Lighting Installed in the 1.5-inch pedestrian handrail as show in Detail A Sheet 23 of 39.

a) Pay Item Notes 715-1-11 Lighting Conductors, Insulated, No. 10 or less. Item includes conductors in the railings. The Pay Items do not include provisions for a raceway (conduit) or approved raceway to be installed.

**Answer No.1:** No raceway (conduit) required, conductors to be installed inside handrailing.

**Question No. 2:** b) Is the Pedestrian Handrail to be UL?

**Answer No. 2:** Yes, it is.

**Question No. 3:** c) Sheet 25 of 29 Notes 1. All wires external to Control Cabinet to be terminated to a terminal in the handrail.  
Can the County please provide details on termination in the handrail.

**Answer No. 3:** The note as stated above is incorrect, actual note is "All wires external to Control Cabinet to be terminated to a terminal." No terminals are needed in railing. The conductors from the Control Cabinet shall be routed to the LED driver as shown in the plans. The conductors for the lighting in the handrailing shall be routed as show in the plans and through the handrailing to each light as specified by the manufacture terminating at the last light in each handrailing.

**Question No. 4:** d) Sheet B-1 of 39 Ped Bridge Structure Plans General Notes:  
Item W. The contractor's EOR is responsible for the design and detailing of the Steel Truss Bridge Superstructure Including Trusses, Concrete Deck, Bridge Railing, Floor Beams, Bridge Joints, Bearing Assemblies and Anchor Bolts.  
Sheet B-4 of 39 Notes 3. The Contractor shall submit shop drawings signed and sealed by a Florida Registered Engineer for the proposed Railing.  
The question being back to the raceway, conductors and terminations to the recessed lighting.

- Answer No. 4:** No raceway (conduit) required, conductors to be installed inside handrailing.
- Question No. 5:** Does the County's User Access Program (UAP) and/or Inspector General fee apply to this project?
- Answer No. 5:** No. Please, refer to Solicitation Documents, Volume II, Supplementary Conditions, section 1.09 Miami-Dade County's User Access Program (UAP).
- Question No. 6:** Will the County consider bid postponement in order to properly submit a bid?
- Answer No. 6:** Please, *refer to Addendum no. 1.*, Section A. Changes to the Invitation to Bid.

**END OF REQUEST FOR INFORMATION No. 3**

Sincerely,



Tiondra Wright  
Chief, Capital Improvement Division.  
Department of Transportation and Public Works (DTPW)

TW: tw

cc:

Marco Movilla, DTPW  
Gabriel Delgado, P.E., DTPW  
Laurie Johnson, SBD  
Caesar Suarez, SBD  
Project File

Katherine Fernandez, DTPW  
Ryan Fisher, P.E., DTPW  
Maylin Torres, SBD  
Eric Perez, SBD  
Clerk of the Board

**Snowden Pedestrian Bridge No. 879043**

**RPQ No. 20240235**

**Request for Information No.3  
(RFI)**

**E-mails Attached**

**From:** [Thelma E. Garcia](#)  
**To:** [Movilla, Marco \(DTPW\)](#)  
**Cc:** [Clerk of the Board \(COC\)](#)  
**Subject:** MDC "Snowden Pedestrian Bridge No. 879043" project - Bid date:: 2/26/25 - GLF RFI # 01  
**Date:** Thursday, February 20, 2025 12:25:36 PM

---

EMAIL RECEIVED FROM EXTERNAL  
SOURCE

Good afternoon:

We hereby kindly request answers to the following questions:

1. This question is Electrical/Structural related to the recessed Alphabet Lighting Installed in the 1.5 inch pedestrian handrail as show in Detail A Sheet 23 of 39.
  - a. Pay Item Notes 715-1-11 Lighting Conductors, Insulated, No. 10 or less.

Item includes conductors in the railings. The Pay Items do not include provisions for a raceway (conduit) or approved raceway to be installed.
  - b. Is the Pedestrian Handrail to be UL?
  - c. Sheet 25 of 29 Notes 1. All wires external to Control Cabinet to be terminated to a terminal in the handrail.

Can the County please provide details on termination in the handrail.
  - d. Sheet B-1 of 39 Ped Bridge Structure Plans General Notes:

Item W. The contractor's EOR is responsible for the design and detailing of the Steel Truss Bridge Superstructure Including Trusses, Concrete Deck, Bridge Railing, Floor Beams, Bridge Joints, Bearing Assemblies and Anchor Bolts.

Sheet B-4 of 39 Notes 3. The Contractor shall submit shop drawings signed and sealed by a Florida Registered Engineer for the proposed Railing.

The question being back to the raceway, conductors and terminations to the recessed lighting.
2. Does the County's User Access Program (UAP) and/or Inspector General fee apply to this project?
3. Will the County consider bid postponement in order to properly submit a bid?

Thank you for your prompt response.

Sincerely,



Thelma E. Garcia

Assistant Vice-President

1 SE 3rd Avenue, Suite 1600

Miami, Florida 33131

Direct: (786) 843-3401

Tel: (305) 371-5228 Ext. 3401

Fax: (305) 371-9201

[www.glfusa.com](http://www.glfusa.com)

[tegarcia@glfusa.com](mailto:tegarcia@glfusa.com)