

Water and Sewer
 3071 SW 38 Avenue
 Douglas Building
 Miami Fl 33146



MIAMI-DADE COUNTY, FLORIDA
REQUEST FOR PRICE QUOTATION (RPQ)
 Contract No: MCC 7360 Plan
 RPQ No: P16283

INVITATION TO BID

A RPQ has been issued for the work identified below. If you are interested in submitting a bid for this project, please submit your bid via Electronic Bidding, attention to William Diaz at no later than 4/3/2026 at 10:00 AM. If you have any questions, contact Johnny A. Ceballos at 786-268-5293.

This RPQ is issued under the terms and conditions of the Miscellaneous Construction Contracts (MCC) Program MCC 7360 Plan.

RPQ DETAILED BREAKDOWN

Bid Due Date:	4/3/2026	Time Due:	10:00 AM	Submitted Via:	Electronic Bidding
Estimated Value:	\$1,221,324 (excluding Contingencies and Dedicated Allowances)				
Project Name:	Sewage Pump Station 304 Upgrade				
Project Location:	15701 NW 37 Ave Miami Gardens, Fl 33054				
License Requirements:	Primary:	General Building Contractor; General Engineering; Underground Utility / Excavation			
	Sub:	Electrical Contractor; Landscape Contractor			
Scope of Work:	<p>(Contractor must obtain and submit all permits prior to performing any work).</p> <p>A. The project consists of furnishing all materials, labor, and equipment necessary to upgrade Sewage Pump Station No. 304, including, but not limited to, excavation, demolition, and modification work. Furnish and install a temporary construction chain-link fence with a privacy screen. Coordinate with the school administration adjacent to the property for the location.</p> <p>B. Furnish, install, operate, and remove temporary sewage effluent by-pass pumps, equipment, and accessories. Contractor shall submit plans, calculations, and specifications for Department's approval before installation.</p> <p>C. Furnish and install appropriate barriers to ensure safety around the Construction zone. The Contractor shall install a temporary 6-foot chain link fence with privacy windscreen mesh within the construction zone.</p> <p>D. Furnish and install Tree protection barriers around existing trees to remain.</p> <p>E. Remove from Dry Well existing pumps, piping, valves, fittings, dehumidifier, electrical components, emergency discharge connection, existing sewer clean out plug, existing concrete slabs, existing steel grating, and ladders.</p> <p>F. The Contractor shall demolish and remove existing dry well from ground elevation to 6-feet below existing ground elevation, including concrete dry well access, and steel beams; Contractor shall seal all existing holes left by the removal of pipes, equipment and ladders before backfilling. Existing dry well portion to remain shall be filled with flowable fill.</p> <p>G. Partially remove upper portion of existing wet well from Top of Hatch at EL (+) 8.83' down to EL (+) 6.00'. Remove existing wet well top slab, all piping and fillets in wet well; clean inside of wet well structure, sandblast to remove coating, patch and repair all joints and cracks, and prepare surface to apply new coating. Apply new coating.</p> <p>H. Demolish and remove existing Electrical Control Panel, SCADA Antenna, Concrete slab and buried conduits; Remove Unistrut frame for support of panels. Remove the existing Standby Generator Set and concrete Pad; Remove all electrical services.</p> <p>I. Remove backflow preventer, water meter, and portion of water service indicated; Remove approximately +/- 20 LF of 4-inch Force Main, fittings, and valves, to point of connection; Remove approximately +/- 15 LF existing Emergency Pump Discharge piping, fittings, and valves.</p> <p>J. Remove approximately +/- 110 LF existing chain link fence, 10-foot and 12-foot swing gates; furnish and install new 6-foot fence, new 10-foot-wide swing gate, and a 12-foot-wide access swing gate as indicated on drawings and as specified.</p> <p>K. Existing Electrical Equipment shall be assumed and managed as Asbestos Containing Material (ACM), unless determined otherwise by an accredited laboratory. Contractor shall comply with EPA and OSHA Regulations. (Refer to Asbestos and Lead Survey performed by ATC Group Services on April 26, 2022; found in Appendix.</p> <p>L. The Contractor shall remove all unsuitable soil material from the site and replace it with clean soil and backfill per specifications. Raise site to Elevation shown in plans and adjust influent manhole Rim Elevation to match proposed ground elevation per WASD STD SS-8.0. All new backfill over excavated areas, demolished areas, and areas required to raise the ground elevation to elevation indicated Fill placed shall pass compaction tests to comply with specifications. New clean soil shall be approved by the Department.</p> <p>M. Contractor shall perform exploratory excavation to field verify the horizontal and vertical locations of buried utilities prior to construction.</p> <p>N. Prior to digging the Contractor shall call Sunshine 811 and request utility locations. .</p> <p>O. All salvaged equipment shall be cleaned and delivered to Pumping Station Maintenance Division as requested.</p> <p>P. The Contractor is responsible for applying and obtaining a Temporary Access Permit from South Florida Water Management District (SFWMD) before any construction/mobilization activity within the SFWMD Right-of-Way.</p> <p>Q. Contractor is responsible for providing MOT Plans and obtaining Public Works approvals/Permit, as required for activities performed on Public Roads.</p> <p>R. Furnish and install a new 50kw generator with enclosure and sub-base tank.</p> <p>S. Remove and Relocate as required: palm trees, bush, existing water meter and connect line to existing service; Remove existing RTU antenna, existing electric box, existing concrete slab for electrical service.</p> <p>T. Construct concrete slab for wet well, generator, and electrical equipment, Top El (+)9.5'. Cast top portion of the concrete wall for wet well.</p> <p>U. Furnish and install new back flow preventer unit, hose-bibb, and tie-in to new proposed water meter.</p> <p>V. Furnish and install concrete valve box with pipe sleeves for electrical conduits, and a 1-1/2" opening for sump pump discharge to wet well; provide (4) four 8- inch core openings for 4-inch</p>				

piping and seal with non-shrink epoxy grout. Furnish and install 4-inch flanged coupling and dustcap with petcock; mount on 3-inch diameter steel pipe support.
 W. Furnish and install wet well and valve box concrete top slab. Provide base for valves and concrete base for submersible pumps and fillets. Furnish and install supports for valve in valve box assembly.
 X. Furnish and install aluminum access hatches for wet well and valve box.
 Y. Sandblast interior of wetwell. Furnish and install material to rehabilitate existing Wet Well with a concrete protective coating; furnish and install two (2) 15 HP submersible pumps, piping, valves and related equipment and accessories; furnish and install bubbler control system and related equipment; Construct emergency connection. Provide (2) two 8-inch core openings for 4-inch piping and seal with non-shrink epoxy grout. Provide 1-1/2-inch PVC schedule 80 from sump pump to wet well and from ARV drainpipe to Wet Well (Typ. of 2). Provide a 4-inch Ductile Iron vent pipe.
 Z. Furnish and construct Unistrut and steel structure framework and attach electrical work panels, meter, telemetry system and related equipment, electrical conduits and junction boxes, R.T.U. panel and new S.C.A.D.A. equipment. Furnish and install electrical conduits and junction boxes. Provide grounding for steel frame structure. Provide a minimum of 3-feet in front of the panels. R.T.U. panel and S.C.A.D.A. equipment furnished by the Department; provide electrical work.

 AA. Furnish and install new meter and main disconnect.
 BB. Furnish and install 12' x 24' asphalt pavement driveway as indicated on drawings. Provide a Type I, 1-1/2-inch-thick asphalt pavement on 8-inch compacted limerock base course and 12-inch stabilized subbase per section for Typical Asphalt Pavement provided on Sheet C-4 of drawings.
 CC. Provide mechanical work; furnish all materials, equipment and supplies necessary for pump station startup and testing; furnish and install sewage force main pipe and fittings; connection to existing sewage force main; replace any sod, sidewalk, pavement damaged during construction; all disturbed landscaping, sidewalk and pavement disturbed during construction shall be restored to equal or better condition and as approved by the Engineer; and other appurtenant and miscellaneous items for a complete, satisfactory and functional installation at Pumping Station No. 304, located at 15701 NW 37th Avenue, Miami Gardens, Florida 33054; in Section 52, Township 16, Range 41, Miami-Dade County, Florida.
 DD. Contractor shall perform exploratory excavation to field verify the horizontal and vertical locations of buried utilities prior to construction.
 EE. Prior to digging, the Contractor shall call Sunshine 811 and request utility locations.
 FF. All salvaged equipment shall be cleaned and delivered to Pumping Station Maintenance Division as requested.
 GG. If sheet piling is required, the Contractor shall submit shop drawings and calculations signed and sealed by a Registered State of Florida Professional Engineer.
 HH. It is the intent of the Department to obtain a complete and working installation under this Project and any items of labor, equipment or materials which may reasonably be assumed as necessary to accomplish this end shall be supplied, whether they are specifically shown on the Plans or stated herein

Document Pickup:	Contact:	William Diaz	Phone No:	3053892970	Date:	2/2/2026	
	Location:	3071 SW 38 Ave, Miami FI 33146					
Pre-Bid Meeting::	YES	Mandatory:	YES	Date:	3/5/2026	Time:	10:00 AM
	Location:	15701 NW 37 Ave Miami Gardens, FI 33054					
Site Meeting:	YES	Mandatory:	YES	Date:	3/5/2026	Time:	10:00 AM
	Location:	15701 NW 37 Ave Miami Gardens, FI 33054					
Bid shall be submitted to:	Contact:	William Diaz					
	Address:	3071 SW 38th Ave,					
	Email:	william.diaz@miamidade.gov	FAX # :	786-552-8613			
Type of Contract:	Multiple Trade		Method of Award:	Lowest Responsible Bidder			
Method of Payment:	Scheduled Monthly Payments		Insurance Required:	YES			
Additional Insurance Required:	NO		If Yes - Minimum Coverage:				
Performance & Payment Bond Required:	YES		Bid Bond Required:	YES			
Davis Bacon:	NO	Maintenance Wages:	NO	AIPP:	NO	Amount:	
DBE Participation:	NO	Percentage:	0.00%	DBE Subcontractor Forms Required:	NO		
SBE-S Requirements	YES	Percentage:	1.00%				
SBE-Services Commodity Set-Aside	NO	If Yes, Service =					
SBE-G Requirements	NO	Percentage:	0.00%				
SBE-Goods Commodity Set-Aside	NO	If Yes, Goods =					
Liquidated Damages:	YES	\$\$ Per Day:	\$1,000.00				
For RPQ's less than \$10,000, if no LD rate is specified, the County reserves the right to assess actual damages in lieu of LDs.							
Design Drawing Included:	YES	Shop Drawing Included:	YES	Specifications Included:	YES		
Anticipated Start Date:	4/20/2026		Calendar Days for Project Completion:	360			
Comments:	Pursuant to Section 2-8.10 of the Code of Miami-Dade County, this Contract is subject to a user access fee under the County's User Access Program (UAP) in the amount of two percent (2%). All construction services provided under this contract are subject to the 2% UAP. This fee applies to all Contract usage whether by County Departments or by any other governmental, quasi-governmental or not-for-profit entity. From every payment made to the Contractor under this contract (including the payment of retainage), the County will deduct the two percent (2%) UAP fee provided in the ordinance and the Contractor will accept such reduced amount as full compensation for any and all deliverables under the contract. The County shall retain the 2%						

UAP for use by the County to help defray the cost of its procurement program. Contractor participation in this pay request reduction portion of the UAP is mandatory.

Provided, however, UAP shall not be applicable for total contract values, inclusive of contingency and allowance accounts, of less than five hundred thousand dollars (\$500,000.00).

Bid submission must be electronic, through the eBuilder Bid Portal, with a hard copy sent to WASD postmarked within one (1) business day of the bid submittal date, mailed to WASD [3071 SW 38th Avenue, Suite 107, Miami, FL 33146]

The original Bid bond Security (in the form of a bid bond or cashier's check) MUST be delivered to WASD, at the address above, BEFORE the bids are opened. Failure to deliver the original will result in the bid submission being rejected as non-responsive.

Invited bidders should have received an Invitation to Bid with an Invitation Key linked to the Invitee's email address. Upon request, an invitation can be sent to multiple email addresses within the same company. However, if multiple bids are submitted by the same company, ALL submitted bids will be rejected.

The bid set includes electronic bid instructions. Training on electronic bid submission is available every Monday from 9 – 10 and every Wednesday from 1 – 2. Email the Contracting Officer or paul.adams@miamidade.gov for further information or to schedule training on alternative dates.

The RFI cut-off date is five (5) business days prior to the bid due date.

Liquidated Damages - \$1,000.00 per day.

The contractor must include in their bid package the following documents:

1. Appendix 5A,
2. Quotation Forms Pages,
3. Addendums,
4. Bid Bond - Note: A Bid Bond will be required only if the bid meets or exceeds \$200K.

In addition, a Performance and Payment Bond with additional insurance will be required once bid is Awarded and bid meets or exceeds \$200K.

////////////////////////////////////
PRA section recommends a 1.0 % SBE-G&S goal in the following recommended services/commodities:

- NIGP 98852 Landscaping
- NIGP 90974: Site Clean-up

DISCLOSURE:

- Contractor shall indemnify and hold harmless the County and its officers, employees, agents and instrumentalities from any and all liability, losses or damages, including attorneys' fees and costs of defense, which the County or its officers, employees, agents or instrumentalities may incur as a result of claims, demands, suits, causes of actions or proceedings of any kind or nature arising out of, relating to or resulting from the performance of this Agreement by the Contractor or its employees, agents, servants, partners principals or subcontractors. Contractor shall pay all claims and losses in connection therewith and shall investigate and defend all claims, suits or actions of any kind or nature in the name of the County, where applicable, including appellate proceedings, and shall pay all costs, judgments, and attorney's fees which may issue thereon. Contractor expressly understands and agrees that any insurance protection required by this Agreement or otherwise provided by the Contractor shall in no way limit the responsibility to indemnify, keep and save harmless and defend the County or its officers, employees, agents and instrumentalities as herein provided.

The Contractor shall furnish to **Water and Sewer, 3071 SW 38 Avenue, Douglas Building, Miami FI 33146**, Certificate(s) of Insurance which indicate that insurance coverage has been obtained which meets the requirements as outlined below:

- A.** Worker's Compensation Insurance for all employees of the Contractor as required by Florida Statute 440.
 - a. If applicable should include coverage required under the U.S. Longshoremen and Harbor Workers' Act (USL&H) and/or Jones Act for any activities on or about navigable water.
- B.** Commercial General Liability in an amount not less than \$1,000,000 per occurrence, and \$2,000,000 in the aggregate. Miami-Dade County must be shown as an additional insured with respect to this coverage.
- C.** Automobile Liability Insurance covering all owned, non-owned and hired vehicles used in connection with the work, in an amount not less than \$1,000,000 combined single limit per occurrence for bodily injury and property damage.

*Under no circumstances are Contractors permitted on the Aviation Department, Aircraft Operating Airside (A.O.A) at Miami International Airport without increasing automobile coverage to \$5 million. Only vehicles owned or leased by a company will be authorized. \$1 million limit applies at all other airports.

VERIFICATION OF EMPLOYMENT ELIGIBILITY (E-VERIFY):

By entering the Contract, the Awarded Bidder becomes obligated to comply with the provisions of Section 448.095, Florida Statute, titled "Verification of Employment Eligibility." This includes but is not limited to utilization of the U.S. Department of Homeland Security's E-Verify System to verify the employment eligibility of all newly hired employees by the Awarded Bidder effective, January 1, 2021, and requiring all Subcontractors to provide an affidavit attesting that the Subcontractor does not employ, contract with, or subcontract with, an unauthorized alien. Failure to comply may lead to termination of this Awarded Bidder, or if a Subcontractor knowingly violates the statute, the subcontract must be terminated immediately. Any challenge to termination under this provision must be filed in the Circuit Court no later than twenty (20) calendar days after the date of termination. If this Contract is terminated for a violation of the statute by the Awarded Bidder, the Awarded Bidder may not be awarded a public contract for a period of one year after the date of termination, and the Awarded Bidder may be liable for any additional costs incurred by the County resulting from the termination of the Contract. Public and private employers must enroll in the E-Verify System (<http://www.uscis.gov/e-verify>) and retain the I-9 Forms for inspection.