



RPQ ADDENDUM

Addendum No.:	10	Date:	5/18/2026
Project No.:	DA159A	Project Title:	MIA Bldg 3151 40-Year Recertification
RPQ No.:	DA159A	RPQ Due Date:	5/27/2026
Project Location:	MIA Bldg 3151	Project Manager:	G. De Castro Borges

This Addendum serves to respond to the Request for Information (RFI) submitted by the following Contractors:

Sayed Gabriel Antar of AARYA Construction & Design, Inc., received on 5/15/2026, 12:41PM.

Q.1 Please, let me know the quantity of Bollards that need replacing. The plans mentioned some need to be removed but doesn't give a clear quantity.

A.1 There are two bollards that require changing.

Q.2 Also, if we are to paint the others that won't be replaced. Is there any painting scope included?

A.2 Contractor is not responsible for painting the bollards not being replaced.

Ismael Santana of Epic Consultants, Inc., received on 5/15/2026, 1:03PM.

Q.3 Sheet S-302 indicates an existing CMU wall to be cut and filled with solid concrete. However, based on our recent site visit and as referenced in the S-901 photographs, this CMU wall does not appear to exist in the field.

Please verify the intent of this detail and advise if:

- The CMU wall was removed under a previous phase or scope, or
- The detail is no longer applicable and should be disregarded, or
- An alternative condition/detail should be followed.

A.3 Detail 3 on sheet S-302 is for the specific condition that only occurs at Column line 13 in the north bay. The reference picture is 9/S-902.

All else remains the same. This document must be signed and returned as part of your RPQ response. Failure to return this document signed may result in your RPQ response being rejected as non-responsive.

Name of Contractor: _____

Name of Individual Authorized to Sign: _____

Title: _____

Signature: _____