



RPQ ADDENDUM

Addendum No.:	8	Date:	5/12/2026
Project No.:	DA159A	Project Title:	MIA Bldg 3151 40-Year Recertification
RPQ No.:	DA159A	RPQ Due Date:	5/20/2026
Project Location:	MIA Bldg 3151	Project Manager:	G. De Castro Borges

This Addendum serves to respond to the Request for Information (RFI) submitted by the following Contractors:

Sri Challagali of Sleiman Construction, LLC, received on 5/11/2026, 5:12PM.

Q.1 Should the transformers be specified as copper or aluminum?

A.1 Transformers should be specified as copper.

Q.2 Plan E-101, keyed notes E4 and E5, indicate replacement of existing light fixtures in the second-floor bathrooms and the ground-floor shop. However, the drawings and addenda do not provide sufficient information regarding the quantity of these fixtures. Please confirm the required fixture counts or advise if this is an omission.

A.2 There is one light fixture in the bathroom. For Keynote 5 on E-101, contractor to assume 5 fixtures for shop lights.

Q.3 Please confirm the manufacturer and model of the existing ceiling tiles, as well as the type and manufacturer/model of the existing grid system (e.g., 9/16" or 15/16").

A.3 Manufacturer and model of ceiling grid and tiles is unknown. Assume 9/16" for bid purposes. Contractor to verify in field once contract is awarded.

All else remains the same. This document must be signed and returned as part of your RPQ response. Failure to return this document signed may result in your RPQ response being rejected as non-responsive.

Name of Contractor: _____

Name of Individual Authorized to Sign: _____

Title: _____

Signature: _____