

# DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER) BOARD AND CODE ADMINISTRATION DIVISION

#### **NOTICE OF ACCEPTANCE (NOA)** Regency Plus, Inc.

2000 Locust Gap Highway Mount Carmel, PA 17851

#### Scope:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER - Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami-Dade County) and/ or the AHJ (in areas other than Miami-Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

#### **DESCRIPTION:** Series "Tech 5108" White PVC Fixed Window – L.M.I.

**APPROVAL DOCUMENT:** Drawing No. **RPLS0060**, titled "Series Tech 5108 Vinyl Fixed Window (LMI)", sheets 1 through 5 of 5, dated 09/16/08, with revision **J** dated 10/20/2020, prepared by PTC Product Design Group, LLC, signed and sealed by Robert J. Amoruso, P.E., bearing the Miami–Dade County Product Control Revision stamp with the Notice of Acceptance number and expiration date by the Miami–Dade County Product Control Section.

#### MISSILE IMPACT RATING: Large and Small Missile Impact Resistant

**LABELING:** Each unit shall bear a permanent label with the manufacturer's name or logo, city, state, series, and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/ or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA **revises NOA No. 20-0109.04** and consists of this page 1, evidence pages E-1 and E-2, as well as approval document mentioned above.

The submitted documentation was reviewed by Sifang Zhao, P.E.





01/21/2021

NOA No. 20-1103.06 Expiration Date: January 28, 2025 Approval Date: January 21, 2021 Page 1

# **NOTICE OF ACCEPTANCE:** EVIDENCE SUBMITTED

#### 1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA's

#### A. DRAWINGS

- 1. Manufacturer's die drawings and sections. (Submitted under NOA No. 08–1021.04)
- 2. Drawing No. **RPLS0060**, titled "Series Tech 5108 Vinyl Fixed Window (LMI)", sheets 1 through 5 of 5, dated 09/16/08, with revision **H** dated 12/24/19, prepared by PTC Product Design Group, LLC, signed and sealed by Robert J. Amoruso, P.E.

#### B. TESTS

- 1. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94
  - 2) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94
  - 3) Water Resistance Test, per FBC, TAS 202-94
  - 4) Large Missile Impact Test per FBC, TAS 201-94
  - 5) Cyclic Wind Pressure Loading per FBC, TAS 203-94
  - 6) Forced Entry Test, per FBC 2411.3.2.1, and TAS 202-94

along with marked-up drawings and installation diagram of a series 5108 white PVC fixed window, prepared by National Certified Testing Laboratories, Inc., Test Report No. **NCTL-110-11363-1**, dated 05/15/08, signed and sealed by Harold E. Rupp, P.E. (*Submitted under NOA No. 08-1021.04*)

- 2. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94
  - 2) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94
  - 3) Water Resistance Test, per FBC, TAS 202-94
  - 4) Large Missile Impact Test per FBC, TAS 201-94
  - 5) Cyclic Wind Pressure Loading per FBC, TAS 203-94
  - 6) Forced Entry Test, per FBC 2411.3.2.1, and TAS 202-94

along with marked-up drawings and installation diagram of a series 5108 white PVC fixed window, prepared by National Certified Testing Laboratories, Inc., Test Report No. **NCTL-110-22857-1**, dated 12/17/19, signed and sealed by Joseph A. Reed, P.E. (*Submitted under NOA No. 20-0109.04*)

# C. CALCULATIONS

- Anchor verification calculations and structural analysis, complying with FBC 5<sup>th</sup> Edition (2014), dated 06/11/15 with revision dated 09/01/15, prepared by PTC Product Design Group, LLC, signed and sealed by Robert J. Amoruso, P.E. (*Submitted under NOA No. 15-0618.01*)
- 2. Glazing complies with **ASTM E1300-04**

# CI. QUALITY ASSURANCE

**1.** Miami-Dade Department of Regulatory and Economic Resources (RER)

# CII. MATERIAL CERTIFICATIONS

1. Notice of Acceptance No. 19-0305.02 issued to Kuraray America, Inc. for their "Trosifol® Ultraclear, Clear and Color PVB Glass Interlayers" dated 05/09/19, expiring on 07/08/24.

> Sifang Zhao, P.E. Product Control Examiner NOA No. 20-1103.06 Expiration Date: January 28, 2025 Approval Date: January 21, 2021

# **NOTICE OF ACCEPTANCE:** EVIDENCE SUBMITTED

#### E. MATERIAL CERTIFICATIONS (CONTINUED)

1. Notice of Acceptance No. **18-0122.02**, issued to **ENERGI Fenestration Solutions USA**, **Inc.**, for their **White Rigid PVC Exterior Extrusions for Windows and Doors**, approved on 03/08/18, expiring on 02/28/23.

#### F. STATEMENTS

Statement letter of conformance, complying with FBC 6<sup>th</sup> Edition (2017), dated January 8, 2018, prepared by PTC Product Design Group, LLC, signed and sealed by Robert J. Amoruso, P.E. (Submitted under NOA No. 18-0122.10)

#### G. OTHERS

 Notice of Acceptance No. 18-0918.03, issued to Regency Plus, Inc. for their Series "5108" White PVC Fixed Window – L.M.I., approved on 10/11/18 and expiring on 01/28/20.

#### 2. NEW EVIDENCE SUBMITTED

#### A. DRAWINGS

1. Drawing No. **RPLS0060**, titled "Series Tech 5108 Vinyl Fixed Window (LMI)", sheets 1 through 5 of 5, dated 09/16/08, with revision **H** dated 12/24/19, prepared by PTC Product Design Group, LLC, signed and sealed by Robert J. Amoruso, P.E.

#### B. TESTS

1. None.

- C. CALCULATIONS
  - 1. None.

#### D. QUALITY ASSURANCE

**1.** Miami-Dade Department of Regulatory and Economic Resources (RER)

# E. MATERIAL CERTIFICATIONS

1. None.

# F. STATEMENTS

1. Statement letter of conformance, complying with **FBC** 7<sup>th</sup> **Edition** (2020), and of no financial interest, dated 10/20/2020, prepared by PTC Product Design Group, LLC, signed and sealed by Robert J. Amoruso, P.E.

# G. OTHERS

1. Notice of Acceptance No. 20-0109.04, issued to Regency Plus, Inc. for their Series "5108" White PVC Fixed Window – L.M.I., approved on 01/30/20 and expiring on 01/28/25.

Sifang Zhao, P.E. Product Control Examiner NOA No. 20-1103.06 Expiration Date: January 28, 2025 Approval Date: January 21, 2021

# **REGENCY PLUS, INC. SERIES TECH 5108 VINYL FIXED WINDOW (LARGE MISSII** INSTALLATION ANCHORAGE DETAILS

#### NOTES:

- 1. THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH REQUIREMENTS OF THE 7th EDITION (2020) FLORIDA BUILDING CODE INCLUDING THE HIGH VELOCITY HURRICANE ZO
- 2. 2X WOOD FRAMING, 1X OR 2X WOOD BUCK, METAL FRAMING AND CONCRETE/MASONRY OPENING TO BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO STRUCTURE. FRAMING AND THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD.
- 3. 1X BUCK OVER CONCRETE/MASONRY IS OPTIONAL. WHEN 1X BUCK IS USED, INSTALLATION ANCHORS WILL PASS THROUGH WINDOW FRAME AND 1X BUCK INTO CONCRETE/MASONRY SUBSTRATE. WHEI DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO STRUCTURE AND IS THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD. DISSIMILAR MATERIALS MUST BE SEPARAT MEMBRANE. SELECTION OF COATING OR MEMBRANE IS THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD.
- 4. THE PRODUCT SHOWN HEREIN HAS BEEN TESTED TO TAS 201, TAS 202 AND TAS 203. SEE TEST REPORT NO. NCTL-110-22857-1, DATED 12/17/19 BY NATIONAL CERTIFIED TESTING LABORATORIES, YORK, F JOSEPH A.REED, FLORIDA P.E. NO. 58920
- 5. MATERIAL:
- 5.1. FRAME: EXTRUDED RIGID PVC BY ENERGI FENESTRATION SOLUTIONS USA, INC. PER CURRENT MD NOA.
- 5.2. LAMINATE GLASS INTERLAYER: TROSIFOL INTERLAYER BY KURARAY AMERICA, INC. PER CURRENT MD NOA.
- 6. GLAZING:
- 6.1. GLAZING DETAIL AS TESTED:
- 6.1.1. OVERALL: 7/8" NOMINAL INSULATING LAMINATED GLASS.
- 6.1.2. GLASS THICKNESS: (1) LITE OF 3/16" NOMINAL TEMPERED GLASS TO THE INTERIOR AND (1) LITE OF LAMINATED GLASS TO THE EXTERIOR.
- 6.1.3. LAMINATED LITE: (2) LITES OF 1/8" NOMINAL ANNEALED GLASS SEPARATED BY A 0.090" TROSIFOL INTERLAYER BY KURARAY AMERICA, INC
- 6.1.4. SPACER TYPE/SIZE: 3/8" NOMINAL CARDINAL ENDUR IG EDGE SPACER (A1-D) ALUMINUM
- 6.1.5. GLAZING SYSTEM: INTERIOR GLAZED WITH (2)-LEAF DUAL DUROMETER AND SIKAFLEX 552 BACKBEDDING WITH A SNAP-IN (2)-LEAF DUAL DUROMETER RIGID VINYL GLAZING BEAD.
- 6.2. ALL SETTING BLOCKS AND GASKET MATERIALS SHALL BE IN COMPLIANCE WITH THE CURRENT EDITION OF THE FLORIDA BUILDING CODE. SETTING BLOCKS SHALL BE NEOPRENE WITH A 70 TO 90 SH MATERIALS SHALL BE EDPM WITH A MINIMUM 60 SHORE A DUROMETER.
- 6.3. AS TESTED GLAZING MEETS ASTM E1300-09a FOR THE DESIGN CONDITIONS SHOWN IN THIS PRODUCT APPROVAL DOCUMENT.
- 7. APPROVED IMPACT PROTECTIVE SYSTEM IS NOT REQUIRED FOR THIS PRODUCT IN WIND BORNE DEBRIS REGIONS INCLUDING THE HVHZ.
- 8. SHIM AS REQUIRED AT EACH INSTALLATION ANCHOR WITH LOAD BEARING SHIM. SHIM WHERE SPACE OF 1/16" OR GREATER OCCURS. MAXIMUM ALLOWABLE SHIM STACK TO BE 1/4".
- 9. FOR ANCHORING INTO CONCRETE/MASONRY USE 1/4" HEX HEAD TAPCONS WITH SUFFICIENT LENGTH TO ACHIEVE A 1 1/2" MINIMUM EMBEDMENT INTO CONCRETE WITH 1 1/2" MINIMUM EDGE DISTANCE . MASONRY WITH 2" MINIMUM EDGE DISTANCE. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS. 4" MINIMUM SPACING BETWEEN ADJACENT ANCHORS REQUIRED. ANCHOR LOCATE
- 10. FOR ANCHORING INTO WOOD FRAMING OR 2X BUCK USE ONE OF THE FOLLOWING:
- 10.1. SHOWN IN SECTION VIEWS: #12 PAN HEAD WOOD SCREWS (WS) WITH SUFFICIENT LENGTH TO ACHIEVE A 1 3/8" MINIMUM EMBEDMENT INTO SUBSTRATE WITH 7/8" MINIMUM EDGE DISTANCE AND MIN SPACING OF 2" ON CENTER. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS. ANCHOR LOCATIONS HAVE +/- 1" TOLERANCE.
- 10.2. NOT SHOWN IN SECTION VIEWS: #14 PAN HEAD WOOD SCREWS (WS) WITH SUFFICIENT LENGTH TO ACHIEVE A 1 1/2" MINIMUM EMBEDMENT INTO SUBSTRATE WITH 1" MINIMUM EDGE DISTANCE AND SPACING OF 2" ON CENTER. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS. ANCHOR LOCATIONS HAVE +/- 1" TOLERANCE.
- 11. FOR ANCHORING INTO METAL STRUCTURE USE #14 PAN OR HEX HEAD SHEET METAL OR SELF DRILLING SCREWS WITH SUFFICIENT LENGTH TO ACHIEVE 3 THREADS MINIMUM BEYOND STRUCTURE INTE EDGE DISTANCE AND MINIMUM ANCHOR-TO-ANCHOR SPACING OF 2" ON CENTER. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS. ANCHOR LOCATIONS HAVE +/- 1" TOLERANC
- 12. ALL FASTENERS TO BE CORROSION RESISTANT OR HAVE A CORROSION RESISTANT COATING
- 13. INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BELOW:
- 13.1. WOOD MINIMUM SPECIFIC GRAVITY OF (G) 0.42 (NON-HVHZ) AND 0.55 (HVHZ)
- 13.2. CONCRETE MINIMUM COMPRESSIVE STRENGTH OF 2500 PSI
- 13.3. MASONRY STRENGTH CONFORMANCE TO ASTM C-90, MEDIUM WEIGHT WITH DENSITY > 117 PCF
- 13.4. METAL SUBSTRATE: STEEL 18GA (0.0428"), Fy = 33KSI / Fu = 45 KSI OR ALUMINUM 6063-T5 0.048" THICK MINIMUM.
- 13.4.1. METAL SUBSTRATE TO MEET MINIMUM FBC HVHZ CODE REQUIREMENTS.

DESIGN PRESSURE RATING (PSF)	IMPACT RATING
±55.0 PSF	LARGE MISSILE IMPACT

			RJA	RJA	RJA	BΥ
S, INC.			20/20	24/19	8/18	ATE
OW	(LARGE MISSILE IMPACT)	810	10/2	12/;	1,1	
GE DE	TAILS	CT #420-0	TO 7TH 0) FBC	OR NEW ING	TO 6TH 7) FBC	PTION
IDA BUILDING	CODE INCLUDING THE HIGH VELOCITY HURRICANE ZONE (HVHZ).	ROJE	ОАТЕ . (202	ATE F TEST	DATE . (201	DESCRI
O PROPERLY	TRANSFER ALL LOADS TO STRUCTURE. FRAMING AND CONCRETE/MASONRY OPENING IS		UPI	UPD		
FRAME AND 1X ENGINEER OF	( BUCK INTO CONCRETE/MASONRY SUBSTRATE. WHEN USED, 1X BUCKS SHALL BE F RECORD. DISSIMILAR MATERIALS MUST BE SEPARATED WITH APPROVED COATING OR	┝	~	Ŧ	U	REV
12/17/19 BY N	ATIONAL CERTIFIED TESTING LABORATORIES, YORK, PA, SIGNED AND SEALED BY	WAY	51 VINDOW (LMI)		DRAWING NO: RPLS0060	SHEET: 1 OF 5
E EXTERIOR. MERICA, INC.		CY PLUS, INC ST GAP HIGH	<u>MEL, PA 178</u> INYL FIXED V	DRAWN BY:	SCALE: N.T.S.	REV: J
LEAF DUAL DUROMETER RIGID VINYL GLAZING BEAD. 3 CODE. SETTING BLOCKS SHALL BE NEOPRENE WITH A 70 TO 90 SHORE A DUROMETER. GASKET		REGENC 000 LOCUS	MT. CARN CH 5108 V	ES AND DES	Broup, LLC FI 32752-0775	tc-corp.com Vo. 25935
(HZ.		2	ES TE	NOTE	esign G	nfo@pi Auth. h
	OWABLE SHIM STACK TO BE 1/4".		ERIE		duct D	1788 i Cert. of
MBEDMENT IN SPACING BETV	TO CONCRETE WITH 1 1/2" MINIMUM EDGE DISTANCE AND 1" MINIMUM EMBEDMENT INTO VEEN ADJACENT ANCHORS REQUIRED. ANCHOR LOCATIONS HAVE +/- 1" TOLERANCE.		S		PTC Pro	321-690- FBPE 0
IENT INTO SUE E +/- 1" TOLER BEDMENT INTO	BSTRATE WITH 7/8" MINIMUM EDGE DISTANCE AND MINIMUM ANCHOR-TO-ANCHOR ANCE. ) SUBSTRATE WITH 1" MINIMUM EDGE DISTANCE AND MINIMUM ANCHOR-TO-ANCHOR	┝	Robert , Florida	J. Amoru P.E. No	Ca Iso, P.E. . 49752	) -
I 47 T TOLLK	IIEVE 3 THREADS MINIMUM BEYOND STRUCTURE INTERIOR WALL WITH 3/4" MINIMUM DETAILS. ANCHOR LOCATIONS HAVE +/- 1" TOLERANCE.	MOU * PROM	No.	AMES	A COLORIZATION	Wither * Outre
	TABLE OF CONTENTS			1000		
SHEET	DESCRIPTION					
1	NOTES AND DESIGN PRESSURE CHART					
2	ELEVATION & ANCHOR LOCATION					
3	HORIZONTAL & VERTICAL SECTIONS - WOOD AND CONCRETE/MASONRY SUBSTRATE INSTALLATION	PRO as co Build	DUC1 mplyin	<b>REV</b> g with	ISED the Flo	orida
4	HORIZONTAL & VERTICAL SECTIONS - METAL SUBSTRATE INSTALLATION, GLAZING DETAIL	NOA- Expira	No.	20-1 ate <u>01</u>	103.0 /28/20	6 025
5	COMPONENTS, FRAME CORNER CONSTRUCTION AND BILL OF MATERIALS	By Miam	i-Dade	Produe	ct Conf	rol





		RJA	-	RJA	RJA	ВΥ
	10	10/20/20		12/24/19	1/8/18	DATE
)	PROJECT #420-081	UPDATE TO 7TH ED. (2020) FBC	UPDATE FOR NEW TESTING		UPDATE TO 6TH ED. (2017) FBC	DESCRIPTION
SEE GLAZING DETAIL 1 ON SHEET 4		7	:	Г	Ċ	REV
6 R CAULK S E WIDTH N N MIN. EMBEDMENT - CONCRETE I. EMBEDMENT - MASONRY -CONCRETE/MASONRY BY OTHERS (SEE NOTE 2, SHEET 1)	REGENCY PLUS, INC. 2000 LOCUST GAP HIGHWAY	MT. CARMEL, PA 17851 TITLE: SERIES TECH 5108 VINYL FIXED WINDOW (LMI)	HOR & VERT SECTIONS - WOOD & CONCRETE/MASONRY SUBSTRATE	DRAWN BY: DATE: BR DD/16/08	PC Product Design Group, LLC SCALE: DRAWING NO: PTC Product Design Group, LLC N.T.S. RPLS0060	721-690-1788 info@ptic-corp.com REV: J SHEET: 3.0F 5 FBPE Cert. of Auth. No. 25935
-1/4" ITW TAPCON INSTALLATION ANCHOR MIN. EDGE DISTANCE - CONCRETE IN. EDGE DISTANCE - MASONRY OPERLY SECURED 1X WOOD BUCK OTHERS (SEE NOTE 3, SHEET 1) ICK PROTECTION BY SEE NOTE 3, SHEET 1)	PRO as c Build NOA Expi	Complying Contraction I		moru ES 1975 E 2011 REVI AL	ISED the Flor 103.06 /28/20	rida 6
JBSTRATE	By Mian	ni-Dade	2 e Pr	oduc	t Contr	<u>ol</u>



		RJA	2			RJA	BY
	10	10/20/20		10/20/20		1/8/18	DATE
IM.	CT #420-08	ro 7th )) FBC		JR NEW NG		ro 6th 7) FBC	TION
ED AND ANCHORED TO PROPERLY F THE ARCHITECT OR ENGINEER OF	PROJE	UPDATE -	ED. (202(	JPDATE F(	TESTI	UPDATE <sup>-</sup> ED. (2017	DESCRIF
THROUGH WINDOW FRAME AND 1X BUCK ERLY TRANSFER ALL LOADS TO MUST BE SEPARATED WITH APPROVED R ENGINEER OF RECORD.		-	,	-	5	ს	REV
R GREATER OCCURS. MAXIMUM				DETAIL	0	09	ю
/E A 1 1/2" MINIMUM EMBEDMENT INTO / EDGE DISTANCE. LOCATE ANCHORS AS JIRED. ANCHOR LOCATIONS HAVE +/- 1"				E, GLAZING L	DATE: 09/16/C	DRAWING NO: RPLS00	SHEET: 4 OF
3/8" MINIMUM EMBEDMENT INTO ITER. LOCATE ANCHORS AS SHOWN IN	, <b>INC.</b> HIGHWAY	17851		BSTRAT	.× BR	T.S.	- -
A 1 1/2" MINIMUM EMBEDMENT INTO ER. LOCATE ANCHORS AS SHOWN IN	<b>Y PLUS</b> T GAP ⊢	1EL, PA	NYL FIX	I AL SU	DRAWN B	SCALE: N.	REV:
S WITH SUFFICIENT LENGTH TO ACHIEVE 3 CHOR-TO-ANCHOR SPACING OF 2" ON +/- 1" TOLERANCE.	2000 LOCUS	MT. CARM	SERIES TECH 5108 VID	ORL & VERT SECTIONS - ME		PTC Product Design Group, LLC	321-690-1788 info@ptc-corp.com FBPF Cert. of Auth. No. 25935
7 6 INTERIOR	1000 * PROMIN	Robe	ert J ida	ATTE A		so, P.E 49752	This ER + Unit
DETAIL 1	PRO as co Build NOA- Expir By Miam	DU mpl ing 0 No. ation	CT ying Cod n D:	Rig w le 2( ate	<b>EVI</b> vith ( <u>0-1</u> 01/ oduc	SED the Flo 103.0 28/20 t Cont	rida 6 )25 rol



					RJA	RJA	RJA <sup>BY</sup>
L THICKNESS	SASH STOP FRAME COVER 0.070" TYPICAL WALL THICKNESS				310 10/20/20	12/24/19	1/8/18 DATE
→ 1.400"					PROJECI #420-08 UPDATE TO 7TH ED. (2020) FBC	UPDATE FOR NEW TESTING	ED. (2017) FBC
	0.84/	1 1		L	~	т	REv G
▶ 1				Г		2	
L THICKNESS	) GLAZING BEAD 0.070" TYPICAL WALL THICKNESS				A DOW (LMI)	UCTION AND BO	DRAWING NO: RPLS0060 SHEET: 5 OF 5
0.825"	0.720" 0.750"			'Y PLUS, INC.	T GAP HIGHWA IEL, PA 17851 NYL FIXED WIN	DRAWN BY: DRAWN BY: BB	scale: N.T.S. REV: J
33"		CORNER	CONSTRUCTION	REGENC	2000 LOCUS MT. CARN MT. CARN SERIES TECH 5108 VI	COMPONENTS, FRAME CC	PTC Product Design Group, LLC (Box 520775, Longwood, FL 32752-0775 321-690-1788 info@ptc-oorp.com FBPE Cert. of Auth. No. 25935
Part Numbers	Desc	cription	Supplier	- F	Robert J	I. Amoruso	o, P.E.
		ilpuoi.			Florida I	P.E. No. 4	.9752
hite 1060 / / / 80 / AG	Master Frame		Energi Fenestration		INCAL JA	CENSE	Optim
hite 10/0///30	Sash Stop Frame Cover		Energi Fenestration**	in the second	O. NO	49752	50
hito 1103 / 7726	DW Glazing Boad		Energi Fenestration**	100	* 14	Joly	20/20
Sikafley Black	Wet Glaze (Fixed Center Section)		SikallS		D. ST	ATE OF	EE
icane Laminate Impact	Operating Sash E366 2 7mm / 0.90 PVB (K	Auraray America Inc. Trosifil) Interlayer IG	Cardinal		SSI SSI	ORIO	NOTIN
-VG-1208B	Black Glazing Tape 1/8 x 3/8 x 85' (Fixed (	Center Section)	Industrial Sales		in in	MAL	111.
-8K-0.0062-028-064	70 to 90 Shore A Durometer)	Frank Lowe					
		Cardinal					
8WHZ	Weep Hole Cover White		Product Design	- F			
11022	30PP12-18P50-9/16 X1 3/8 X 3 Foam Bloc'	k	Lindenmeyr				
*** ENERGI FENES	STRATION SOLUTIONS USA, INC., PER CURF	RENT MD NOTICE OF ACCEPTANCE (NOA)		PI as Bu N( Ex By	RODUCT ; complying uilding Cod DA-No. (piration D;	REVIS g with th 20-11( ate 01/2	<b>ED</b> e Florida )3.06 :8/2025
	L THICKNESS  L THICKNESS  L THICKNESS  L THICKNESS  A  D  C  C  C  C  C  C  C  C  C  C  C  C	L THICKNESS       (2)       SASH STOP FRAME COVER 0.070" TYPICAL WALL THICKNESS         Image: state of the stat	L THICKNESS	L THICKNESS	L THICKNESS	L THICKNESS L THI	L THICKNESS L THICKNESS A CALL THICKNESS A CA