



MIAMI-DADE COUNTY  
PRODUCT CONTROL SECTION

11805 SW 26 Street, Room 208  
Miami, Florida 33175-2474  
T (786) 315-2590 F (786) 315-2599

DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)  
BOARD AND CODE ADMINISTRATION DIVISION

**NOTICE OF ACCEPTANCE (NOA)**

[www.miamidade.gov/economy](http://www.miamidade.gov/economy)

**Reynaers, Inc.**

**21430 N. 15<sup>th</sup> Lane, Suite 100**

**Phoenix, AZ 85027**

**SCOPE:**

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER - Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami-Dade County) and/ or the AHJ (in areas other than Miami-Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

**DESCRIPTION: Series "CS77" Outswing Aluminum Casement Window - L.M.I.**

**APPROVAL DOCUMENT:** Drawing No. **CS77CASELMI**, titled "CS77 Series Casement Window", sheets 1 through 7 of 7, dated 07/30/18, prepared by manufacturer, signed and sealed by Scott Wolters, P.E., bearing the Miami-Dade County Product Control Revision stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Section.

**MISSILE IMPACT RATING: Large Missile Impact Resistant**

**LABELING:** Each unit shall bear a permanent label with the manufacturer's name or logo, city, state, series, and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/ or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA **revises NOA#18-1226.02** consists of this page 1 and evidence pages E-1, E-2 and E-3, as well as approval document mentioned above.

The submitted documentation was reviewed by **Sifang Zhao, P.E.**



*S. Z.*  
09/23/2021

NOA No. 21-0615.12  
Expiration Date: April 25, 2024  
Approval Date: September 23, 2021  
Page 1



**NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED**

**1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA's**

**A. DRAWINGS**

1. Manufacturer's die drawings and sections.
2. Drawing No **CS77CASELMI**, titled "CS77 Series Fixed Window", sheets 1 through 7 of 7, dated 07/30/18, prepared by manufacturer, signed and sealed by Scott Wolters, P.E.

**B. TESTS**

1. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94  
2) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94  
3) Water Resistance Test, per FBC, TAS 202-94  
4) Large Missile Impact Test per FBC, TAS 201-94  
5) Cyclic Wind Pressure Loading per FBC, TAS 203-94  
6) Forced Entry Test, per ASTM F588, and TAS 202-94  
along with marked-up drawings and installation diagram of aluminum fixed and outswing casement window mulled units, prepared by Intertek, Inc. Test Report No. **G4624.01-450-18 R0**, dated 11/02/18, signed and sealed by Vinu J. Abraham, P.E.

**C. CALCULATIONS**

1. Anchor verification calculations and structural analysis, complying with **FBC-6<sup>th</sup> Edition (2017)**, dated 11/16/18 and 03/28/19, prepared by Wolters Engineering, Inc., signed and sealed by Scott Wolters, P.E.
2. Glazing complies with **ASTM E1300-09**

**D. QUALITY ASSURANCE**

1. Miami-Dade Department of Regulatory and Economic Resources (RER).



---

Sifang Zhao, P.E.  
Product Control Examiner  
NOA No. 21-0615.12  
Expiration Date: April 25, 2024  
Approval Date: September 23, 2021



**NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED**

**E. MATERIAL CERTIFICATIONS**

1. Notice of Acceptance No. **17-0808.02** issued to **Kuraray America, Inc.** for their “**SentryGlas® (Clear and White) Glass Interlayers**” dated 12/28/17, expiring on 07/04/23.
2. Project No. **TFB-001-02-01**, prepared by PRI Construction Materials Technologies LLC, dated 02/08/18 to 08/16/18, issued to **Technoform Bautech**, for their **I-Strut Insulating Strip** comprised of Polyamide with 25% glass fibers, per **ASTM D1929-16** “*Standard Test Method for Ignition Properties of Plastics*”, per **ASTM D635-14** “*Standard Test Method for Rate of Burning and/or Extent and Time of Burning of Plastics in a Horizontal Position*”, per **ASTM D638-14** “*Standard Test Methods for Tensile Properties of Plastics*”, per **ASTM G155-04** “*Standard Practice for Operating Xenon Arc Light Apparatus for Exposure of Non-Metallic Materials*” and **ASTM D2843-16** “*Standard Test Method for the Density of Smoke from the Burning Decomposition of Plastics*”, signed and sealed by Zachary Priest, P.E.
3. Material Data Sheet for “insulating profiles made of PA 66 GF25 – dry impact resistant, to fit into Technoform I-Strut™ Aluminum Standard Reglet.
4. Test report No. **ATI-60520.02-106-18**, prepared by Architectural Testing, Inc., dated 11/09/06, with revision date 11/29/06, issued to **Ensinger, Inc.**, for their **Tecatherm® 66GF insulbar material** comprised of Polyamide with 25% glass fibers, per **ASTM G 155-00ae1**, “*Standard Practice for Operating Xenon Arc Light Apparatus for Exposure of /Non-Metallic Materials*”, per **ASTM D638-03** “*Standard Test Methods for Tensile Properties of Plastics*”, for exposed & unexposed sample per Xenon Arc after 4500 Hours, **ASTM D635-98** “*Standard Test Method for Rate of Burning and/or Extent and Time of Burning of Plastics in a Horizontal Position*”, **ASTM D1929-96** (2000)e01 “*Standard Test Method for Determining Ignition Properties of Plastics*” and **ASTM D2843-99** “*Standard Test Method for Density of Smoke from the Burning or Decomposition of Plastics*”, signed and sealed by Joseph A. Reed, P.E.

**F. STATEMENTS**

1. Statement letter of conformance, complying with the **FBC 6<sup>th</sup> Edition (2017)**, dated November 16, 2018, issued by Wolters Engineering, Inc., signed and sealed by Scott Wolters, P.E.
2. Statement letter of no financial interest, dated November 16, 2018, issued by Wolters Engineering, Inc., signed and sealed by Scott Wolters, P.E.
3. Laboratory compliance letters for Test Report No. **G4624.01-450-18**, issued by Intertek, Inc., dated November 26, 2018, signed and sealed by Vinu J. Abraham, P.E.

**G. OTHERS**

1. None.



---

Sifang Zhao, P.E.  
Product Control Examiner  
NOA No. 21-0615.12  
Expiration Date: April 25, 2024  
Approval Date: September 23, 2021



**NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED**

**2. NEW EVIDENCE SUBMITTED**

**A. DRAWINGS**

1. None.

**B. TESTS**

1. None

**C. CALCULATIONS**

1. None.

**D. QUALITY ASSURANCE**

1. Miami-Dade Department of Regulatory and Economic Resources (RER)

**E. MATERIAL CERTIFICATIONS**

1. Notice of Acceptance No. **20-0915.19** issued to **Kuraray America, Inc.** for their “**SentryGlas® (Clear and White) Glass Interlayers**” dated 11/19/20, expiring on 07/04/23.

**F. STATEMENTS**

1. Statement letter of conformance, complying with **FBC 7<sup>th</sup> Edition (2020)** and of no financial interest, dated April 12, 2021, issued by Wolters Engineering, Inc., signed and sealed by Scott Wolters, P.E.

**G. OTHERS**

1. Notice of Acceptance No. **18-1226.02**, issued to Reynaers, Inc., for their **Series Series “CS77” Outswing Aluminum Casement Window - L.M.I.**, approved on 04/25/19 and expiring on 04/25/24.



---

Sifang Zhao, P.E.  
Product Control Examiner  
NOA No. 21-0615.12  
Expiration Date: April 25, 2024  
Approval Date: September 23, 2021




## GENERAL NOTES:


1. ALLOWABLE DESIGN PRESSURE:  $\pm 65$  PSF
2. THIS PRODUCT HAS BEEN DESIGNED AND TESTED TO TAS 201, 202, & 203 PROTOCOLS IN ACCORDANCE WITH THE REQUIREMENTS OF THE CURRENT EDITION OF THE FLORIDA BUILDING CODE (FBC), INCLUDING THE HVHZ PROVISIONS.
3. THIS PRODUCT AS SHOWN HEREIN IS LARGE AND SMALL MISSILE IMPACT RESISTANT FOR INSTALLATIONS UP TO 30 FT ABOVE GRADE. (SHUTTERS ARE REQUIRED FOR INSTALLATIONS  $> 30$  FT ABOVE GRADE).
4. WOOD OR MASONRY OPENINGS, BUCKS, AND BUCK FASTENERS, BY OTHERS, SHALL BE PROPERLY DESIGNED AND INSTALLED TO TRANSFER LOADS TO THE STRUCTURE.
5. ANCHOR TYPE, SIZE, SPACING, AND EMBEDMENT SHALL BE AS INDICATED IN THIS APPROVAL. ANCHOR EMBEDMENT TO SUBSTRATE SHALL BE BEYOND WALL DRESSING OR STUCCO.
6. ALL FASTENERS PENETRATING INTO PRESSURE TREATED WOOD SHALL BE CAPABLE OF PREVENTING CORROSION DUE TO REACTION WITH PRESSURE TREATMENT CHEMICALS.
7. DISSIMILAR MATERIALS THAT COME INTO CONTACT SHALL BE PROTECTED TO PREVENT GALVANIC REACTIONS.
8. NO STRESS INCREASES WERE USED IN THE DESIGN OR ANALYSIS OF THIS PRODUCT. A WIND LOAD DURATION FACTOR  $C_d = 1.6$  WAS USED FOR THE ANALYSIS OF WOOD SCREWS ONLY.

## CORNER CONSTRUCTION:

9. WINDOW FRAME CORNERS ARE MITERED AND CRIMPED OVER 0687853.00 AND 0687952.00 CORNER KEYS, AND SECURED WITH REYNASEAL DUO.
10. WINDOW SASH CORNERS ARE MITERED AND CRIMPED OVER (2) 0687771.00 CORNER KEYS, SECURED WITH REYNASEAL DUO, AND SEALED WITH REYNAPROTECTOR.




DOUBLE CASEMENT WINDOW  
(EXTERIOR VIEW)




CASEMENT WINDOW  
(EXTERIOR VIEW)

DESIGN PRESSURE  
 $\pm 65$  PSF



OPTIONAL CS77 FIXED WINDOWS  
PER SEPARATE PRODUCT APPROVAL.




DOUBLE CASEMENT WINDOW  
WITH OPTIONAL FIXED SIDELITES  
(EXTERIOR VIEW)

OPTIONAL CS77 FIXED WINDOWS  
PER SEPARATE PRODUCT APPROVAL.

FOR FASTENER AND HARDWARE  
LOCATIONS SEE SHEET 2/7.

**PRODUCT REVISED**  
as complying with the Florida  
Building Code  
NOA-No. 21-0615.12  
Expiration Date 04/25/2024  
By   
Miami-Dade Product Control



DATE	7/30/18
DATE	
REVISION DESCRIPTION	
NO.	


CS77 SERIES CASEMENT WINDOW

**REYNAERS, INC.**  
21430 NORTH 15TH LANE, SUITE 111  
PHOENIX, AZ 85027  
Ph: (480) 272-9688  
www.reynaers.com








DRAWING NO. CS77CASELMI  
SHEET NO. 1 OF 7




## FASTENER AND HARDWARE LOCATIONS



SYMBOL LEGEND:

-  STRAP ANCHOR 0566016 WITH (2) FASTENERS PER FRAME ANCHOR CHART ON SHEET 6/7.
-  SOBINCO LOCKING HARDWARE, (10) PER VENT (FOR MORE INFO SEE BILL OF MATERIALS ON SHEET 7/7).
-  SOBINCO HINGES 060.9012 (LEFT) OR 060.9013 (RIGHT), (2) PER VENT.
-  SOBINCO LOCK HANDLE 060.6543.
-  WEEP SLOT AND COVER 069.6831.04, (3) PER VENT.
-  VENT DECOMPRESSION (3/16" DIA.)
-  GLASS SETTING BLOCK OR CORNER BLOCK.

**PRODUCT REVISED**  
as complying with the Florida  
Building Code  
NOA-No. 21-0615.12  
Expiration Date 04/25/2024  
By   
Miami-Dade Product Control


[illegible]




1  
3

2  
3

EXTERIOR



3/4" GLASS  
BITE




GLAZING DETAIL

1 7/16" INSULATED LAMINATED


1/4" HEAT STRENGTHENED  
5/8" AIR SPACE WITH ALUM.  
SPACER (BUTYL/SILICONE  
SEAL)  
1/4" HEAT STRENGTHENED  
0.090" SENTRYGLAS INTERLAYER  
1/4" HEAT STRENGTHENED

**PRODUCT REVISED**  
as complying with the Florida  
Building Code  
NOA-No. 21-0615.12  
Expiration Date 04/25/2024  
By   
Miami-Dade Product Control




DATE	7/30/18
DATE	
REVISION DESCRIPTION	
NO.	
CS77 SERIES CASEMENT WINDOW	
<b>REYNAERS, INC.</b>	
21430 NORTH 15TH LANE, SUITE 111 PHOENIX, AZ 85027	
Ph: (480) 272-9688 www.reynaers.com	
DRAWING NO.	CS77CASELMI
SHEET NO.	3 OF 7







EXTERIOR

3  
4



4  
4

**PRODUCT REVISED**  
as complying with the Florida  
Building Code  
NOA-No. 21-0615.12  
Expiration Date 04/25/2024  
By   
Miami-Dade Product Control



NO.	REVISION DESCRIPTION	DATE	DATE
			7/30/18

CS77 SERIES CASEMENT WINDOW

**REYNAERS, INC.**


21430 NORTH 15TH LANE, SUITE 111  
PHOENIX, AZ 85027

Ph: (480) 272-9688  
www.reynaers.com

DRAWING NO.  
CS77CASELMI

SHEET NO.  
4 OF 7






FIXED WINDOW PER  
SEPARATE PRODUCT  
APPROVAL


SEE GLAZING DETAIL  
ON SHEET 3.

5  
5



13/16"

6  
5

**PRODUCT REVISED**  
as complying with the Florida  
Building Code  
NOA-No. 21-0615.12  
Expiration Date 04/25/2024  
By   
Miami-Dade Product Control

NO.	REVISION DESCRIPTION	DATE	DATE
			7/30/18

CS77 SERIES CASEMENT WINDOW



# REYNAERS, INC.

21430 NORTH 15TH LANE, SUITE 111  
PHOENIX, AZ 85027  
Ph: (480) 272-9688  
www.reynaers.com


SCOTT WOLTERS  
FL PE# 62354  
MAR 28 2019  
STATE OF FLORIDA  
PROFESSIONAL ENGINEER

DRAWING NO.  
CS77CASELMI  
SHEET NO. 5 OF 7





TYPICAL ANCHOR CONDITIONS  
(HEAD SHOWN. SILL AND JAMBS ARE SIMILAR)



TYPICAL ANCHOR CONDITIONS  
WITH OPTIONAL WOOD BUCKS (1x MAX)

FRAME ANCHOR CHART:

SUBSTRATE	ANCHOR	MIN. EMBEDMENT	MIN. EDGE DISTANCE	SPACING
WOOD (2x, S.G.= 0.55 MIN)	#14 WOOD SCREW (Gr. 5 MIN)	1 7/8"	1"	1 1/4"
STEEL STUD (16 Ga, 33 KSI MIN)	1/4"-14 ITW TEKS SCREW, ELCO DRIL-FLEX, or ELCO SS BI-FLEX	FULL*	3/4"	1 1/4"
ALUM. ( 1/8" 6063-T5 MIN) OR STEEL (1/8", 33 KSI MIN)	1/4"-14 ITW TEKS SCREW, ELCO DRIL-FLEX, or ELCO SS BI-FLEX	FULL*	3/4"	1 1/4"
CONCRETE (3000 PSI MIN)	1/4" DIA. ITW TAPCON, ELCO ULTRACON, or ELCO SS AGGRE-GATOR	1 3/4"	1 3/4"	1 3/4"
GROUT-FILLED CMU (ASTM C90 MIN)	1/4" DIA. ITW TAPCON, ELCO ULTRACON, or ELCO SS AGGRE-GATOR	1 3/4"	1 3/4"	1 3/4"

\* FULLY PENETRATES METAL WITH 3 THREADS BEYOND

**PRODUCT REVISED**  
as complying with the Florida  
Building Code  
NOA-No. 21-0615.12


Expiration Date 04/25/2024

By   
Miami-Dade Product Control

DATE	7/30/18
DATE	
REVISION DESCRIPTION	
NO.	

CS77 SERIES CASEMENT WINDOW

**REYNAERS, INC.**  
21430 NORTH 15TH LANE, SUITE 111  
PHOENIX, AZ 85027  
Ph: (480) 272-9688  
www.reynaers.com



DRAWING NO.	CS77CASELM1
SHEET NO.	6 OF 7




Bill of Materials					
Profiles					
ID Mark	Part Number	Description	Material	Manufacturer	Notes
1	0060371.51	Connection Profile	AW 6060 T66	Reynaers	
2	0083052.51	Window Vent Outward Opening	AW 6060 T66	Reynaers	
3	0083183.51	Outer Frame 64mm	AW 6060 T66	Reynaers	
4	0300019.51	Drip cap	AW 6060 T66	Reynaers	
5	0303649.51	Glazing Bead	AW 6060 T66	Reynaers	
6	0303647.51	Glazing Bead	AW 6060 T66	Reynaers	
Accessories and Hardware					
ID Mark	Part Number	Description	Material	Manufacturer	Notes
7	0215169.-	Screw Self-Drilling M5x11	stainless steel	Reynaers	
8	0525310.-	st-Screw din 7981 Inox 4.2x16	stainless steel	Nestinox	
9	0525327.-	Screw DIN 7982 Inox 4.2x25	stainless steel	Fabory	
10	0606007.-	Adjustment rod 400mm	PA6	Sobinco	
11	0606010.-	Adjustment rod 250mm	PA6	Sobinco	
12	0606013.-	Adjustment rod 400mm	PA6	Sobinco	
13	0606014.-	Connecting rod 365mm	PA6	Sobinco	
14	0606016.-	Connecting rod 160mm	PA6	Sobinco	
15	0606042.-	Lock Plate	zinc, stainless steel	Sobinco	
16	0606107.-	Adjustment rod 60mm	aluminum	Sobinco	
17	0606150.-	Connecting rod 110mm	PA6	Sobinco	
18	0606543	Handle		Sobinco	
19	0607161.-	Drive plate set outward opening		Sobinco	
20	0607162.-	Restrictor set outward opening		Sobinco	
21	0608746.00	Rebate Support 16.4x3.5	Zamac 5	Pedeo	
22	0609012.-	Hinge Side Tuti Left 671<fb<1300		Sobinco	
23	0609013.-	Hinge Side Tuti Right 671<fb<1300		Sobinco	
24	0609016.-	Reinforcement set Invision fg >130kg	Aluminum, stainless steel	Sobinco	
25	0609204.-	Central closure safe	zamac 5, stainless steel	Sobinco	
26	0609205.-	Central closure safe	zamac 5, stainless steel	Sobinco	
27	0609710.-	Handle side TUTI burglar protection		Sobinco	
28	0687771.00	Crimp Corner Cleats 10.3x43.8	die cast alu	Monticelli	
29	0687853.00	Crimp Corner Cleat 17.85x10.45	die cast alu	Monticelli or Fratelli	
30	0687952.00	Corner Cleat 26.05x17.4	die cast alu	Fratelli Comunello	
31	0696660.04	end Piece 030.0019.xx	PA	Stockplastics	
32	0696831.04	Weep hole cover	ASA	Custers kunststoffen or	
33	0698704.01	Glass Support	POM	Custers kunststoffen	
34	0698748.01	Glass Support	POM	Custers kunststoffen	
35		Glass Setting Block/Corner Block	Neoprene		(2)/Sill, (1)/ea. Jamb, (1)/Head
36	0849108.-	Reynafix	synthetic rubber	Novatio	
37	0869208.SY	Reynaprotector	silicone	Weiss Chemie + Technik	
38	0849080.-	Reynaseal duo	Cosmoten duo	Weiss Chemie + Technik	
39		1/4" x 4" Steel Reinforcing	Steel (Galv. or Primer finish)		
Gaskets					
ID Mark	Part Number	Description	Material	Manufacturer	Notes
40	0808442.04	Acoustic Gasket	EPDM + cellular EPDM	Polecex	
41	8809114.04	Outer Glazing Gasket	EPDM	Polecex	
42	8809126.04	Inner Glazing Gasket	EPDM	Polecex	
43	0809381.04	Gasket 4.3mm	EPDM foam	Polecex	Install with Sealant
44	8809657.04	Central Gasket	EPDM	Polecex	
Building Connection					
ID Mark	Part Number	Description	Material	Manufacturer	Notes
45		Silicone DC 790	silicone	Dow Corning	
46		Illmod 600 15/5-10mm	PU foam	Tremco Illbruck	
47	0566016.-	Fixing lug	low carbon galvanized steel	MS Decoupe	
Thermal Breaks					
ID Mark	Part Number	Description	Material	Manufacturer	Notes
48	000.0865.04	Frame Thermal Brake	Tecatherm 66 GF	Ensinger	
49	000.0866.04	Frame Thermal Break	Tecatherm 66 GF	Ensinger	
50	000.0867.04	Sash Thermal Break	Tecatherm 66 GF	Ensinger	
51	000.0891.04	Sash Thermal Break	Tecatherm 66 GF	Ensinger	
52	000.0840.04	Mullion Thermal Break	Tecatherm 66 GF	Ensinger	

**PRODUCT REVISED**  
as complying with the Florida  
Building Code

NOA-No. 21-0615.12

Expiration Date 04/25/2024

By   
Miami-Dade Product Control



DATE 7/30/18

DATE	REVISION DESCRIPTION	NO.

**REYNAERS, INC.**  
21430 NORTH 15TH LANE, SUITE 111  
PHOENIX, AZ 85027  
Ph: (480) 272-9688  
www.reynaers.com

CS77 SERIES CASEMENT WINDOW  
DRAWING NO. CS77CASELMI  
SHEET NO. 7 OF 7