

MIAMI-DADE COUNTY PRODUCT CONTROL SECTION

11805 SW 26 Street, Room 208 Miami, Florida 33175-2474 T (786) 315-2590 F (786) 315-2599

www.miamidade.gov/building

DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER) BOARD AND CODE ADMINISTRATION DIVISION

NOTICE OF ACCEPTANCE (NOA)

Amarr Garage Doors dba Entrematic 165 Carriage Court Winston Salem, NC 27105

SCOPE: This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER-Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Model "1200 Amarr Heritage 3000 (Dp: +42.0, -46.0 psf)" Insulated Steel Sectional Garage Door up to 18'-0" Wide with Optional Impact Resistant Window – L.M.I.

APPROVAL DOCUMENT: Drawing No. **IRC-1218-165-26-I**, titled "Model #1200 Amarr Heritage 3000", sheets 1 through 4 of 4, dated 03/07/22, prepared by manufacturer, signed and sealed by Thomas L. Shelmerdine, P.E., bearing the Miami-Dade County Product Control Revision stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Section.

MISSILE IMPACT RATING: Large and Small Missile Impact Resistant

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, manufacturing address, model number, the positive and negative design pressure rating, indicate impact rated if applicable, installation instruction drawing reference number, approval number (NOA), the applicable test standards, and the statement reading 'Miami-Dade County Product Control Approved' is to be located on the door's side track, bottom angle, or inner surface of a panel.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA revises and renews NOA No. 20-1015.24 and consists of this page 1 and evidence pages E-1, E-2 and E-3, as well as approval document mentioned above.

The submitted documentation was reviewed by Manuel Perez, P.E.

MIAMI-DADE COUNTY
APPROVED

5/17/22

NOA No. 22-0414.04 Expiration Date: October 04, 2027 Approval Date: May 26, 2022 Page 1

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA'S

A. **DRAWINGS**

- Manufacturer's die drawings and sections. 1. (Submitted under NOA No. 07-0820.05)
- 2. Drawing No. IRC-1218-165-26-I, titled "Model #1200 Heritage & Oak Summit 3000 Short, Long, Flush and Oak Summit Panels", sheets 1 through 4 of 4, dated 06/07/07, with revision B dated 11/11/13, prepared by manufacturer, signed and sealed by Thomas L. Shelmerdine, P.E.

(Submitted under NOA No. 14-0414.11)

В. **TESTS**

- 1. Test reports on: 1) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
 - 2) Large Missile Impact Test per FBC, TAS 201-94
 - 3) Cyclic Wind Pressure Loading per FBC, TAS 203-94
 - 4) Tensile Test per ASTM E8
 - 5) Forced Entry Resistance Test per FBC, TAS 202-94

along with marked-up drawings and installation diagram of 18'x 7' 24 ga steel garage door, prepared by American Test Lab, Inc., Test Report No. ATLNC 1111.01-13, dated 12/17/13 and addendum letter, signed and sealed by David W. Johnson, P.E.

(Submitted under NOA No. 14-0414.11)

2. Test report on Evaluation of Painted or Coated Specimens Subjected to Corrosive Environments per ASTM D1654 & ASTM B117, prepared by Architectural Testing, Inc., Test Report No. A7420.01-106-18, dated 04/12/11, signed and sealed by Joseph A. Reed, P.E.

(Submitted under NOA No. 12-0228.09)

Test report on Forced Entry Test per FBC, TAS 202-94, prepared by American Test 3. Lab, Inc., Test Report # ATLNC-0912.01-11, dated 10/13/11, signed and sealed by David W. Johnson, P.E.

(Submitted under NOA No. 12-0228.09)

- 4. Test reports on: 1) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
 - 2) Large Missile Impact Test per FBC, TAS 201-94
 - 3) Cyclic Wind Pressure Loading per FBC, TAS 203-94

along with marked-up drawings and installation diagram of a 9' x 7' Sectional Steel Garage Door, prepared by American Test Lab, Inc., Report No. ATLNC-0604.01-07, dated 06/30/07, signed and sealed by David W. Johnson, P.E.

(Submitted under NOA No. 07-0820.05)

5. Test report on Tensile Test for 3 Samples per ASTM E 8, prepared by Hurricane Engineering & Testing Inc., Test Report No. HETI-07-T734, dated 06/26/07, signed and sealed by Candido F. Font, P.E.

(Submitted under NOA No. 07-0820.05)

Manuel Perez, P.E **Product Control Examiner** NOA No. 22-0414.04

Expiration Date: October 04, 2027 Approval Date: May 26, 2022

Amarr Garage Doors dba Entrematic

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA'S (CONTINUED)

C. CALCULATIONS

1. Anchor calculations prepared by Structural Solutions, P.A., dated 01/24/12, signed and sealed by Thomas L. Shelmerdine, P.E. (Submitted under NOA No. 14-0414.11)

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER)

E. MATERIAL CERTIFICATIONS

- 1. Test report on Surface Burning Characteristics on the expanded polystyrene UL file # R11812.
- 2. Notice of Acceptance No. 17-1219.02 issued to Covestro, LLC for their "Makrolon Polycarbonate Sheets" dated 03/22/18, expiring on 08/27/22.
- 3. Notice of Acceptance No. 20-0622.01 issued to Eastman Chemical Company (MA) for their "Saflex PVB Clear and Color Glass Interlayers" dated 08/06/20, expiring on 05/21/21.

D. STATEMENTS

1. Statement letter of conformance, complying with **FBC** 7th **Edition (2020)** and of no financial interest, dated August 27, 2020, issued by Structural Solutions, P.A., signed and sealed by Thomas L. Shelmerdine, P.E. (Submitted under NOA No. 17-1010.30)

G. OTHERS

1. Notice of Acceptance No. **17-1010.30**, issued to Amarr Garage Doors for their Model 1200 Heritage & Oak Summit 3000 Insulated Steel Sectional Garage Door up to 18'-0" Wide with Impact Resistant Windows (DP +42.0, -46.0 PSF), approved on 12/28/17 and expiring on 10/04/22.

Manuel Perez, P.E.
Product Control Examiner
NOA No. 22-0414.04
Expiration Date: October 04, 2027

Approval Date: May 26, 2022

Amarr Garage Doors dba Entrematic

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

2. NEW EVIDENCE SUBMITTED

A. DRAWINGS

1. Drawing No. **IRC-1218-165-26-I**, titled "Model #1200 Amarr Heritage 3000", sheets 1 through 4 of 4, dated 03/07/22, prepared by manufacturer, signed and sealed by Thomas L. Shelmerdine, P.E.

B. TESTS

- 1. Test reports on: 1) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94,
 - 2) Forced Entry Resistance Test per FBC, TAS 202-94
 - 3) Large Missile Impact Test per FBC, TAS 201-94
 - 4) Cyclic Wind Pressure Loading per FBC, TAS 203-94
 - 5) Tensile Test per ASTM E8

along with marked-up drawings and installation diagram of a Model 1200 Heritage 3000, 18' x 7', 24 ga. steel Sectional Steel Garage Door, prepared by American Test Lab, Inc., Report No. **ATLNC 1206.01-21**, dated 03/30/22, signed and sealed by David W. Johnson, P.E.

C. CALCULATIONS

1. Anchor calculations prepared by Structural Solutions, P.A., dated 04/04/22, signed and sealed by Thomas L. Shelmerdine, P.E.

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER)

E. MATERIAL CERTIFICATIONS

- 1. Notice of Acceptance No. **22-0317.02** issued to **Plaskolite**, **LLC** for their "**TUFFAK Polycarbonate Sheets**" dated 04/21/22 expiring on 08/27/27.
- 2. Notice of Acceptance No. 21-0216.01 issued to Eastman Chemical Company (MA) for their "Saflex PVB Interlayers Clear and Colored for Glass" dated 04/29/21, expiring on 05/21/26.

F. STATEMENTS


1. Statement letter of conformance, complying with FBC 7th Edition (2020) and of no financial interest, dated 04/04/22, issued by Structural Solutions, P.A., signed and sealed by Thomas L. Shelmerdine, P.E.

G. OTHERS

1. Notice of Acceptance No. **20-1015.24**, issued to Amarr Garage Doors dba Entrematic for their Model 1200 Heritage & Oak Summit 3000 Insulated Steel Sectional Garage Door up to 18'-0" Wide with Impact Resistant Windows – L.M.I., approved on 01/21/21 and expiring on 10/04/22.

Manuel Pérez, P.E. Product Control Examiner NOA No. 22-0414.04


Expiration Date: October 04, 2027 Approval Date: May 26, 2022



SPECIFICATIONS AND NOTES

- 1. ALL THE LOAD FROM THE DOOR IS TRANSFERRED TO THE VERTICAL TRACK, FROM THE TRACK THE LOAD IS TRANSFERRED TO THE VERTICAL JAMBS. THE HORIZONTAL JAMB OR HEADER RECEIVES NO PORTION OF THE LOAD TRANSFERRED FROM THE DOOR.
- 2. EACH VERTICAL JAMBS RECEIVES MAXIMUM DESIGN LOADS OF: +378.0 LBS/FT & -414.0 LBS/FT
- 3. DOOR AND HARDWARE WILL BE DESIGNED, MANUFACTURED AND INSTALLED WITH STANDARDS AS SET FORTH BY DASMA.
- 4. DOOR SECTIONS SHALL BE 24 GA. (.0216) MIN. EXTERIOR SKIN ROLLED FORMED, W/ BAKED ON POLYESTER FINISH
- 5. SUPPORTING STRUCTURAL ELEMENTS SHALL BE DESIGNED BY A REGISTRED PROFESSIONAL ENGINEER FOR WIND LOADS INDICATED ON THIS DRAWING IN ADDITION TO OTHER LOADINGS.
- 6. DOORS OVER (4) SECTIONS REFER TABLES ON PAGE 4
- 7. THIS APPROVAL REQUIRES THE MANUFACTURER TO DO TESTING OF ALL COILS USED TO FABRICATE DOOR PANELS UNDER THIS NOTICE OF ACCEPTANCE. A MINIMUM OF 2 SPECIMENS SHALL BE CUT FROM EACH COIL AND TENSILE TESTED ACCORDING TO ASTM E-8 BY A DADE COUNTY APPROVED LAB SELECTED AND PAID BY THE MANUFACTURER. EVERY 3 MONTHS, 4 TIMES A YEAR, THE MANUFACTURER SHALL MAIL TO THIS OFFICE: A COPY OF THE TEST REPORTS WITH CONFIRMATION THAT THE SPECIMENS WERE SELECTED FROM COILS AT THE MANUFACTURER PRODUCTION FACILITIES. AND A NOTARIZED STATEMENT FROM THE MANUFACTURER THAT ONLY COILS WITH YIELD STRENGTH OF 41,000 PSI OR MORE SHALL BE USED TO MAKE DOOR PANELS FOR DADE COUNTY UNDER THIS NOTICE OF ACCEPTANCE.

INTERIOR OF GARAGE MAX. WIDTH 18'0" JAMB DESIGN LOADS +378.0 LBS/FT -414.0 LBS/FT SEE NOTES 1 & 2 PAGE 2



2 X 6 VERTICAL JAMB ATTACHMENT TO 2,000 PSI CONCRETE HILTI KWIK BOLT 3/8' X 4' STARTING 6' FROM ENDS THEN 10' O.C. (2 1/2' EMBEDMENT) HILTI SLEEVE ANCHOR 3/8' X 2-3/4' STARTING 6' FROM ENDS THEN 10' O.C. (1 1/4' EMBEDMENT) HILTI SLEEVE ANCHOR 3/8' X 2-3/4' STARTING 6' FROM ENDS THEN 10' O.C. (1 1/4' EMBEDMENT) HILTI SLEEVE ANCHOR 3/8' X 2-3/4' STARTING 6' FROM ENDS THEN 10' O.C. (2 1/2' EMBEDMENT) 2 X 6 VERTICAL JAMB ATTACHMENT TO HOLLOW C-90 BLOCK SIMPSON 1/4' X 3' TITEN SCREWS STARTING 6' FROM ENDS, USE PAIRS OF FASTENERS (3" APART) AT 8" D.C. (1 1/2" EMBEDMENT) HILTI 1/4" X 2-3/4" KWIK-CON II+ SCREWS STARTING 6" FROM ENDS, USE PAIRS OF FASTENERS (3" APART) AT 8" D.C. (1 1/4" EMBEDMENT) 2 X 6 VERTICAL JAMB ATTACHMENT TO GROUTED C-90 BLOCK (2000 PSI GROUT) HILTI SLEEVE ANCHOR 3/8" X 2-3/4" STARTING 6" FROM ENDS THEN 12" D.C. (1 1/4" EMBEDMENT) (OR, USE FASTENERS FOR HOLLOW C-90 BLOCK) *LAGS AND BOLTS CAN BE COUNTERSUNK TO PROVIDE A FLUSH MOUNTING SURFACE. *PREPARATION OF WOOD JAMBS BY OTHERS HOLLOW BLOCK CONCRETE VIIII GROUTED BLOCK STRUCTURE STRUCTURE STRUCTURE STRUCTURE 1-1/2" MIN

3" MIN

WOOD JAMB ATTACHMENT TO STRUCTURE

2 X 6 VERTICAL JAMB ATTACHMENT TO WOOD FRAME STRUCTURE 5/16' X 3' LAG SCREWS STARTING 6' FROM ENDS THEN 12' D.C. (1 1/2' EMBEDMENT)

PRODUCT REVISED as complying with the Florida **Building Code** 22-0414.04 NOA-No. **Expiration Date: 10/04/2027** By: Manuel Peres

Miami-Dade Product Control

DATE BY DESCRIPTION OF REVISIONS MAX SIZE 18' x 14'


+42.0 PSF -46.0 PSF ARGE MISSILE IMPACT RESISTANCE

DESIGN LOADS PORIDA

ENTRE/MATIC


MODEL #1200 AMARR HERITAGE 3000


SIZE	DRAWN BY	DRC	DATE	03/07/22		DRAWING NUMBER
В	CHECKED BY	RLR				IRC-1218-165-26-I
165 C	ARRIAGE COUR	SHEET 2 OF 4				




STANDARD TRACK CONFIGURATION FOR 6'6" UP TO 14' TALL DOORS N.T.S.

AVAILABLE TRACK CONFIGURATIONS N.T.S.







INTERMEDIATE SECTION



OPTIONAL SHORT PANEL GLAZED SECTION R-TRUSS AND STILE LAYOUT N.T.S.



SHORT PANEL IMPACT GLAZING FASTENER DETAIL N.T.S.



(14) #8 X 1" (LONG PANEL WINDOW) (10) #8 X 1" (SHORT PANEL WINDOW)


SECTION B-B IMPACT WINDOW DETAIL


PRODUCT REVISED
as complying with the Florida
Building Code
NOA-No. 22-0414.04

Expiration Date: 10/04/2027

By: Manuel Prez

Miami-Dade Product Control





10-5/8*****

MAX. DLO

-38-1/16" MAX, DLO-

MODEL #1200 AMARR HERITAGE 3000

SIZE	DRAWN BY	DRC	DATE	03/07/22		DRAWING NUMBER
В	CHECKED BY	RLR				IRC-1218-165-26-I
165 C	ARRIAGE COUR	SHEET 3 OF 4				

TABLE 1

DOOR		SECTION HEIGHTS								
HEIGHT	Btm	#2	#3	#4	#5	#6	#7	#8		
14' 0"	21"	21"	21"	21"	21"	21"	21"	21"		
13' 6"	21"	21"	21"	21"	21"	18"	18"	21"		
13' 0"	21"	21"	21"	18"	18"	18"	18"	21"		
12' 6"	21"	18"	18"	18"	18"	18"	18"	21"		
12' 0"	21"	21"	21"	21"	21"	18"	21"			
11' 6"	21"	21"	21"	18"	18"	18"	21"			
11' 0"	21"	18"	18"	18"	18"	18"	21"			
10' 6"	21"	21"	21"	21"	21"	21"				
10' 0"	21"	21"	21"	18"	18"	21"				
9'6"	21"	18"	18"	18"	18"	21"				
9' 0"	18"	18"	18"	18"	18"	18"				
8' 6"	21"	21"	21"	18"	21"					
8' 0"	21"	18"	18"	18"	21"					
7' 6"	18"	18"	18"	18"	18"					
7' 0"	21"	21"	21"	21"						
6' 6"	21"	18"	18"	21"						

TABLE 2

DOOR	TRACK ATTACHMENT										SPLICE				
HEIGHT	Α	В	С	D	E	F	G	Н	I	J	K	L	M	N	S
6' 6"	3"	14"	27"	38"	46"	56"	64"							18.	70"
7'	3"	14"	27"	38"	46"	56"	68"								76"
7' 6"	3"	14"	27"	38"	46"	56"	68"	78"							82"
8'	3"	14"	27"	38"	46"	56"	68"	78"							88"
8' 6"	3"	14"	27"	38"	46"	56"	68"	78"	88"						94"
9'	3"	14"	27"	38"	46"	56"	68"	78"	88"						100"
9' 6"	3"	14"	27"	38"	46"	56"	68"	78"	88"	98"					106"
10'	3"	14"	27"	38"	46"	56"	68"	78"	88"	100"					112"
10' 6"	3"	14"	27"	38"	46"	56"	68"	78"	88"	100"	110"				118"
11'	3"	14"	27"	38"	46"	56"	68"	78"	88"	100"	110"				124"
11' 6"	3"	14"	27"	38"	46"	56"	68"	78"	88"	100"	110"	120"			130"
12'	3"	14"	27"	38"	46"	56"	68"	78"	88"	100"	110"	122"			136"
12'6"	3"	14"	27"	38"	46"	56"	68"	78"	88"	100"	109"	122"	132"		142"
13'	3"	14"	27"	38"	46"	56"	68"	78"	88"	100"	114"	122"	134"		148"
13' 6"	3"	14"	27"	38"	46"	56"	68"	78"	88"	100"	109"	122"	134"	144"	154"
14'	3"	14"	27"	38"	46"	56"	68"	78"	88"	100"	114"	122"	134"	146"	160"

ALL TRACK ATTACHMENT SPACING +/-2" ALLOWED WITH SYP NO. 2 OR BETTER ONLY

TABLE 3

IADLL							
SECTION	STRUT SIZE						
TOP	5.5"						
- 	5.5"						
7TH 							
CTII	5.5"						
6TH							
	5.5"						
5TH							
	5.5"						
4TH							
200	5.5"						
3RD							
2010	5.5"						
2ND							
DOTTON 4	5.5"						
воттом	3"						

PRODUCT REVISED
as complying with the Florida
Building Code
NOA-No. 22-0414.04
Expiration Date: 10/04/2027
By: Manual Pres

Miami-Dade Product Control

REV DESCRIPTION OF	FREVISIONS	DATE	BY						
MAX SIZE 18' x 14' DESIGN LOADS +42.0 PSF -46.0 PSF	Structural Solutions, PE (FL PE #0048579) Structural Solutions, PA (FL Firm #29412) A PA (FL Firm #29412) A PA (FL Firm #29412)	HELM NSE 8579	dba Structural Solutions of North Carolina, Inc. 5921-G W. Friendly Ave., Greensboro, NC 27410						
LARGE MISSILE IMPACT RESISTANCE	Thomas L. Shelmerdine, PE Structural Solutions, PA (F)	AL EN	dba Structural Solutio						
Amarr									
	ENTRE/MATIC	-							

MODEL #1200 AMARR HERITAGE 3000

075	DRAWN RY	DRC	DATE	03/07/22		U	DAWA	NC :	NUMBER	
SIZE	DRAMY DI	DNG	DAIL	03/01/22						ו מנ
В	CHECKED BY	RLR				IKC-1	210	5-	165-2	<u> </u>
165 C	ARRIAGE COUR	SHEET	4	0F	4					