



DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)
BOARD AND CODE ADMINISTRATION DIVISION
NOTICE OF ACCEPTANCE (NOA)

MIAMI-DADE COUNTY
PRODUCT CONTROL SECTION
11805 SW 26 Street, Room 208
Miami, Florida 33175-2474
T (786) 315-2590 F (786) 315-2599
www.miamidade.gov/building

Amarr Garage Doors dba Entrematic
165 Carriage Court
Winston Salem, NC 27105

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER-Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Model 1200 Heritage 3000 (Dp: +37.0, -45.0 psf) Insulated Steel Sectional Garage Door up to 16'-0" Wide with Optional Impact Resistant Windows

APPROVAL DOCUMENT: Drawing No. **IRC-1216-155-26-I**, titled "Model #1200 Amarr Heritage 3000", sheets 1 through 3 of 3, dated 03/14/2022, prepared by manufacturer, signed and sealed by Thomas L. Shelmerdine, P.E. on 04/07/2022, bearing the Miami-Dade County Product Control approval stamp with the Notice of Acceptance number and approval date by the Miami-Dade County Product Control Section.

MISSILE IMPACT RATING: Large and Small Missile Impact Resistant

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, manufacturing address, model number, the positive and negative design pressure rating, indicate impact rated if applicable, installation instruction drawing reference number, approval number (NOA), the applicable test standards, and the statement reading 'Miami-Dade County Product Control Approved' is to be located on the door's side track, bottom angle, or inner surface of a panel.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA consists of this page 1 and evidence page E-1, as well as approval document mentioned above. The submitted documentation was reviewed by **Carlos M. Utrera, P.E.**



NOA No. 22-0414.15
Expiration Date: May 26, 2027
Approval Date: May 26, 2022
Page 1

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

A. DRAWINGS

1. Drawing No. **IRC-1216-155-26-I**, titled "Model #1200 Amarr Heritage 3000", sheets 1 through 3 of 3, dated 03/14/2022, prepared by manufacturer, signed and sealed by Thomas L. Shelmerdine, P.E. on 04/07/2022.

B. TESTS

1. Test reports on: 1) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
2) Large Missile Impact Test per FBC, TAS 201-94
3) Cyclic Wind Pressure Loading per FBC, TAS 203-94
4) Forced Entry Test per FBC, TAS 202-94
5) Tensile Test per ASTM E 8
along with marked-up drawings and installation diagram of a 16' x 7' 24 ga. Steel Sectional Garage Door Model # 1200, prepared by American Test Lab, Inc., Report No. **ATLNC-1129.01-21**, dated 04/06/2022, signed and sealed by David W. Johnson, P.E.
2. Test report on Evaluation of Painted or Coated Specimens Subjected to Corrosive Environments per ASTM D1654-08 & ASTM B117-11, prepared by Intertek/Architectural Testing, Inc., Test Report No. **C5463.01-106-18**, dated 04/03/2013, signed and sealed by Joseph A. Reed, P.E.

C. CALCULATIONS

1. Anchor calculations prepared by Structural Solutions, P.A., dated 04/07/2022, signed and sealed by Thomas L. Shelmerdine, P.E.

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER).

E. MATERIAL CERTIFICATIONS


1. Notice of Acceptance No. **22-0317.02** issued to **Plaskolite, LLC** for their "**TUFFAK Polycarbonate Sheets**", approved on 04/21/2022 and expiring on 08/27/2027.
2. Test report on Atlas EPS Self-Ignition Temperature per ASTM D1929-16, prepared by Intertek, Test Report No. **102609488MID-002**, dated 06/13/2016, signed and sealed by Frederick D. Curkeet, P.E.
3. UL listing on Atlas EPS Flame Spread and Smoke Developed per UL 723 (ASTM E84), **UL # BRYX.R16529**, dated 02/11/2021.

F. STATEMENTS

1. Statement letter of code conformance with **7th Edition (2020)** of the **FBC**, and of no financial interest, dated 04/07/2022, issued by Structural Solutions, PA., signed and sealed by Tomas L. Shelmerdine, P.E.



Carlos M. Utrera, P.E.
Product Control Examiner
NOA No. 22-0414.15
Expiration Date: May 26, 2027
Approval Date May 26, 2022



TYPICAL TOP FIXTURES
N.T.S.

TYPICAL CENTER HINGE
N.T.S.

14GA. ADJUSTABLE SLIDE BRACKET ATTACHED W/(2) 1/4"-20 X 5/8" CARRIAGE BOLTS AND NUTS

2" 10 BALL STEEL 9" STEM ROLLER W/ BOLT RETAINER USED FOR NON-THREADED SHAFT


5 1/2"H X 18 GA. R-TRUSS ATTACHED W/(2) 1/4" X 1" HEX HEAD SCREWS AT EACH END STILE

14 GA. (MIN.) END HINGE ROLLER CARRIERS ATTACHED W/ (5) TOTAL 1/4" X 1" HEX HEAD SCREWS (2) SCREWS UPPER LEAF (3) SCREWS LOWER LEAF


11GA. ADJUSTABLE ROLLER CARRIER BRACKET ATTACHED TO R-TRUSS W/ (3) 1/4" X 1" HEX HEAD SCREWS

TYPICAL END HINGE
N.T.S.

TOP FIXTURE REINFORCEMENT ILLUSTRATION




TOP FIXTURE ADDER PIECE




TOP VIEW

ISOMETRIC VIEW



SIDE VIEW



INSIDE ELEVATION
N.T.S.

3" X 5-11/16" BOTTOM BRACKET 13 GA. THICK ATTACHED W/(3) 1/4" X 1" HEX HEAD SCREWS

2" 10 BALL STEEL 9" STEM ROLLER W/ 7/16" RETAINER FOR NON-THREADED SHAFTS

TYPICAL BOTTOM BRACKET
N.T.S.

CFC-FREE EXPANDED POLYSTYRENE INSULATION DENSITY: 0.80 LBS/FT³ (MIN.)

12 GA. GALV. COMMERCIAL TOP ROLLER BRACKET ATTACHED WITH (3) 1/4" X 1" HEX HEAD UNIV. SCREWS PER BRACKET ADJUSTABLE SLIDE BRACKET IS ASSEMBLED WITH (2) 5/16" X 3/4" BOLT & NUT PER BRACKET

TOP SECTION 5 1/2"H X 18 GA. R-TRUSS (33KSD) STACKED ON BOTTOM OF TOP ROLLER BRACKET W/ (2) 1/4" X 1" HEX HEAD SCREWS AT EACH END STILE AND W/ (2) 1/4" X 1" SCREWS AT EACH CENTER HINGE LOCATION

14GA. END HINGE

11 GA. ADJUSTABLE ROLLER CARRIER BRACKET

5 1/2"H X 18 GA. R-TRUSS (33KSD) ON INTERMEDIATE AND BOTTOM SECTIONS ATTACHED W/ (2) 1/4" X 1" HEX HEAD SCREWS AT EACH END STILE AND AT EACH CENTER STILE

INTERIOR SKIN 27 GA. MIN

BOTTOM BRACKET ATTACHED W/ (3) 1/4" X 1" HEX HEAD SCREWS

EXTRUDED VINYL BOTTOM SEAL ATTACHED WITH SCREWS

SECTION A-A (SIDE VIEW)
N.T.S.


REV	DESCRIPTION OF REVISIONS	DATE	BY
-----	--------------------------	------	----

MAX SIZE 16" WIDTH 14" HEIGHT (DOOR HEIGHT SUBJECT TO WEIGHT LIMITATIONS)

DESIGN LOADS +37.0 PSF -45.0 PSF

TEST LOADS +55.5 PSF -67.5 PSF

Thomas L. Shelmerdine, PE (FL PE #0048579) Structural Solutions, PA (FL Firm #29412)



dba Structural Solutions of North Carolina, Inc. 5921-G W. Friendly Ave., Greensboro, NC 27410

Amarr
ENTREMATIC


MODEL #1200 AMARR HERITAGE 3000

SIZE	DRAWN BY	DRC	DATE	03/09/22	DRAWING NUMBER
B	CHECKED BY	RLR	DATE	03/14/22	IRC-1216-155-26-1
ENTREMATIC 165 CARRIAGE COURT WINSTON-SALEM, N.C. 27105					SHEET 1 OF 3

PRODUCT APPROVED
as complying with the Florida Building Code
NOA-No. 22-0414.15

Approval Date 05/26/2022

By *[Signature]*
Miami-Dade Product Control



TRACK MOUNTING DETAIL
N.T.S.

LARGE MISSILE IMPACT RESISTANT

TABLE 1

DOOR HEIGHT	TRACK ATTACHMENT									SPLICE
	A	B	C	D	E	F	G	H	I	
6' 6"	3.5"	10"	21"	42"	63"					70"
7'	3.5"	10"	21"	42"	63"					76"
7' 6"	3.5"	10"	21"	42"	63"					82"
8'	3.5"	10"	21"	42"	63"					88"
8' 6"	3.5"	10"	21"	42"	63"	84"				94"
9'	3.5"	10"	21"	42"	63"	84"				100"
9' 6"	3.5"	10"	21"	42"	63"	84"				106"
10'	3.5"	10"	21"	42"	63"	84"	105"			112"
10' 6"	3.5"	10"	21"	42"	63"	84"	105"			118"
11'	3.5"	10"	21"	42"	63"	84"	105"			124"
11' 6"	3.5"	10"	21"	42"	63"	84"	105"			130"
12'	3.5"	10"	21"	42"	63"	84"	105"	126"		136"
12' 6"	3.5"	10"	21"	42"	63"	84"	105"	126"		142"
13'	3.5"	10"	21"	42"	63"	84"	105"	126"		148"
13' 6"	3.5"	10"	21"	42"	63"	84"	105"	126"	147"	154"
14'	3.5"	10"	21"	42"	63"	84"	105"	126"	147"	160"

ALL TRACK ATTACHMENT SPACING +/- 2" ALLOWED WITH SYP NO. 2 OR BETTER ONLY


TABLE 2

DOOR HEIGHT	SECTION HEIGHTS							
	Btm	#2	#3	#4	#5	#6	#7	#8
14' 0"	21"	21"	21"	21"	21"	21"	21"	21"
13' 6"	21"	21"	21"	21"	21"	18"	18"	21"
13' 0"	21"	21"	21"	18"	18"	18"	18"	21"
12' 6"	21"	18"	18"	18"	18"	18"	18"	21"
12' 0"	21"	21"	21"	21"	21"	18"	21"	
11' 6"	21"	21"	21"	18"	18"	18"	21"	
11' 0"	21"	18"	18"	18"	18"	18"	21"	
10' 6"	21"	21"	21"	21"	21"	21"		
10' 0"	21"	21"	21"	18"	18"	21"		
9' 6"	21"	18"	18"	18"	18"	21"		
9' 0"	18"	18"	18"	18"	18"	18"		
8' 6"	21"	21"	21"	18"	21"			
8' 0"	21"	18"	18"	18"	21"			
7' 6"	18"	18"	18"	18"	18"			
7' 0"	21"	21"	21"	21"				
6' 6"	21"	18"	18"	21"				

WOOD JAMB ATTACHMENT TO STRUCTURE

2 X 6 VERTICAL JAMB ATTACHMENT TO WOOD FRAME STRUCTURE
5/16" X 3" LAG SCREWS STARTING 6" FROM ENDS THEN 16" O.C. (1 1/2" EMBEDMENT)
2 X 6 VERTICAL JAMB ATTACHMENT TO 2,000 PSI CONCRETE
HILTI KWIK BOLT 3/8" X 4" STARTING 6" FROM ENDS THEN 24" O.C. (2 1/2" EMBEDMENT)
HILTI SLEEVE ANCHOR 3/8" X 2-3/4" STARTING 6" FROM ENDS THEN 14" O.C. (1 1/4" EMBEDMENT)
ITW/RAMSET REDHEAD (TRU-BOLT) 3/8" X 4" STARTING 6" FROM ENDS THEN 24" O.C. (2 1/2" EMBEDMENT)
2 X 6 VERTICAL JAMB ATTACHMENT TO HOLLOW C-90 BLOCK
SIMPSON 1/4" X 3" TITEN SCREWS STARTING 6" FROM ENDS, USE PAIRS OF FASTENERS
(3" APART) AT 8" O.C. (1 1/2" EMBEDMENT)
HILTI 1/4" X 2-3/4" KWIK-CON II+ SCREWS STARTING 6" FROM ENDS, USE PAIRS OF
FASTENERS (3" APART) AT 8" O.C. (1 1/4" EMBEDMENT)
2 X 6 VERTICAL JAMB ATTACHMENT TO GROUTED C-90 BLOCK (2000 PSI GROUT)
HILTI SLEEVE ANCHOR 3/8" X 2-3/4" STARTING 6" FROM ENDS THEN 16" O.C. (1 1/4"
EMBEDMENT) (OR, USE FASTENERS FOR HOLLOW C-90 BLOCK)

*LAGS AND BOLTS CAN BE COUNTERSUNK TO PROVIDE A FLUSH MOUNTING SURFACE.
*PREPARATION OF WOOD JAMBS BY OTHERS



PRODUCT APPROVED
as complying with the Florida
Building Code
NOA-No. 22-0414.15
Approval Date 05/26/2022
By *[Signature]*
Miami-Dade Product Control

REV	DESCRIPTION OF REVISIONS	DATE	BY

MAX SIZE
16" WIDTH
14" HEIGHT
(DOOR HEIGHT
SUBJECT TO
WEIGHT LIMITATIONS)

DESIGN LOADS
+37.0 PSF
-45.0 PSF

TEST LOADS
+55.5 PSF
-67.5 PSF

Thomas L. Shelmerdine, PE (FL PE #0048579)
Structural Solutions, PA (FL Firm #29412)

THOMAS L. SHELMERDINE
LICENSE
No. 48579
STATE OF
FLORIDA
PROFESSIONAL ENGINEER
FL

dba Structural Solutions of North Carolina, Inc.
5921-G W. Friendly Ave., Greensboro, NC 27410



Amarr
ENTREMATIC

MODEL #1200 AMARR HERITAGE 3000


SIZE	DRAWN BY	DRC	DATE	03/09/22	DRAWING NUMBER
B	CHECKED BY	RLR	DATE	03/14/22	IRC-1216-155-26-I

ENTREMATIC
165 CARRIAGE COURT WINSTON-SALEM, N.C. 27105


SHEET 2 OF 3



AVAILABLE TRACK CONFIGURATIONS
N.T.S.





OPTIONAL LONG PANEL GLAZED SECTION STRUT AND STILE LAYOUT
N.T.S.




OPTIONAL SHORT PANEL GLAZED SECTION STRUT AND STILE LAYOUT
N.T.S.

SPECIFICATIONS AND NOTES


1. ALL THE LOAD FROM THE DOOR IS TRANSFERRED TO THE VERTICAL TRACK, FROM THE TRACK THE LOAD IS TRANSFERRED TO THE VERTICAL JAMBS. THE HORIZONTAL JAMB OR HEADER RECEIVES NO PORTION OF THE LOAD TRANSFERRED FROM THE DOOR.
2. EACH VERTICAL JAMBS RECEIVES MAXIMUM DESIGN LOADS OF: +296.0 LBS/FT & -360.0 LBS/FT
3. DOOR AND HARDWARE WILL BE DESIGNED, MANUFACTURED AND INSTALLED WITH STANDARDS AS SET FORTH BY DASMA.
4. DOOR SECTIONS SHALL BE 24 GA. (.0216) MIN. EXTERIOR SKIN ROLLED FORMED, W/ BAKED ON POLYESTER FINISH
5. SUPPORTING STRUCTURAL ELEMENTS SHALL BE DESIGNED BY A REGISTERED PROFESSIONAL ENGINEER FOR WIND LOADS INDICATED ON THIS DRAWING IN ADDITION TO OTHER LOADINGS.
6. THIS APPROVAL REQUIRES THE MANUFACTURER TO DO TESTING OF ALL COILS USED TO FABRICATE DOOR PANELS UNDER THIS NOTICE OF ACCEPTANCE. A MINIMUM OF 2 SPECIMENS SHALL BE CUT FROM EACH COIL AND TENSILE TESTED ACCORDING TO ASTM E-8 BY A DADE COUNTY APPROVED LAB SELECTED AND PAID BY THE MANUFACTURER. EVERY 3 MONTHS, 4 TIMES A YEAR, THE MANUFACTURER SHALL MAIL TO THIS OFFICE: A COPY OF THE TEST REPORTS WITH CONFIRMATION THAT THE SPECIMENS WERE SELECTED FROM COILS AT THE MANUFACTURER PRODUCTION FACILITIES. AND A NOTARIZED STATEMENT FROM THE MANUFACTURER THAT ONLY COILS WITH YIELD STRENGTH OF 40,000 PSI OR MORE SHALL BE USED TO MAKE DOOR PANELS FOR DADE COUNTY UNDER THIS NOTICE OF ACCEPTANCE.



SHORT PANEL IMPACT GLAZING FASTENER DETAIL
N.T.S.



LONG PANEL IMPACT GLAZING FASTENER DETAIL
N.T.S.



SECTION B-B IMPACT WINDOW DETAIL
N.T.S.

TABLE 4

SECTION	STRUT SIZE
TOP	5.5"
7TH	5.5"
6TH	5.5"
5TH	5.5"
4TH	5.5"
3RD	5.5"
2ND	5.5"
BOTTOM	5.5"

PRODUCT APPROVED
as complying with the Florida
Building Code

NOA-No. 22-0414.15

Approval Date 05/26/2022

By *[Signature]*
Miami-Dade Product Control

REV	DESCRIPTION OF REVISIONS	DATE	BY
	<p>MAX SIZE 16' WIDTH 14' HEIGHT (DOOR HEIGHT SUBJECT TO WEIGHT LIMITATIONS)</p> <p>DESIGN LOADS +37.0 PSF -45.0 PSF</p> <p>TEST LOADS +55.5 PSF -67.5 PSF</p>		
	<p>Thomas L. Shelmerdine, PE (FL PE #0048579) Structural Solutions, PA (FL Firm #29412)</p> <p>FL</p> <p>THOMAS L. SHELMERDINE LICENSE No. 48579 STATE OF FLORIDA PROFESSIONAL ENGINEER</p> <p>dba Structural Solutions of North Carolina, Inc. 5921-G W. Friendly Ave., Greensboro, NC 27410</p>		

Amarr
ENTREMATIC

MODEL #1200 AMARR HERITAGE 3000

SIZE	DRAWN BY	DRC	DATE	03/09/22	DRAWING NUMBER
B	CHECKED BY	RLR	DATE	03/14/22	IRC-1216-155-26-1
ENTREMATIC 165 CARRIAGE COURT WINSTON-SALEM, N.C. 27105					SHEET 3 OF 3